
Structure and Interpretation of Computer Programs

電腦程式ê結構kap解說



第二版　臺文翻譯版

原作：Harold Abelson, Gerald Jay Sussman & Julie Sussman
踏頭話：Alan J. Perlis
翻譯：Tân Kiàn-ting & Lîm Tsú-thuàn

©1996 by The Massachusetts Institute of Technology

Structure and Interpretation of Computer Programs,
second edition

原作：Harold Abelson、Gerald Jay Sussman kap Julie Sussman
踏頭話：Alan J. Perlis
翻譯：Tân Kiàn-ting、Lîm Tsú-thuàn

This work is licensed under a Creative Commons
Attribution-ShareAlike 4.0 International License
(CC BY-SA 4.0). Based on a work at mitpress.mit.edu.

The MIT Press
Cambridge, Massachusetts
London, England

McGraw-Hill Book Company
New York, St. Louis, San Francisco,
Montreal, Toronto

Unofficial Texinfo Format 2.andresraba5.6 (February 2, 2016),
based on 2.neilvandyke4 (January 10, 2007).

Contents

Unofficial Texinfo Format x

非正式臺語譯本 ê 踏頭話 xii

Dedication 獻詞 xiv

Foreword xvi

Preface to the Second Edition xxii

Preface to the First Edition xxiv

Acknowledgments xxviii

1 Building Abstractions with Procedures 用程序起造抽象 1

1.1 The Elements of Programming 程式設計 ê 要素 8

1.1.1 Expressions 表達式 11

1.1.2 Naming and the Environment 號名 kap 環境 15

1.1.3 Evaluating Combinations 算組合 ê 值 17

1.1.4 Compound Procedures 複合 ê 程序 22

1.1.5 The Substitution Model for Procedure Application 予程序應用 ê 取代模型 26
1.1.6 Conditional Expressions and Predicates 條件表達式 kap 謂詞 32
1.1.7 Example: Square Roots by Newton's Method 例：用 Newton 法算平方根 40
1.1.8 Procedures as Black-Box Abstractions 程序當做烏盒仔 ê 抽象 48
1.2 Procedures and the Processes They Generate 程序 kap In 產出ê 程序 57
1.2.1 Linear Recursion and Iteration 線性遞迴 kap 反覆 . 59
1.2.2 Tree Recursion 樹遞迴 68
1.2.3 Orders of Growth 成長率 78
1.2.4 Exponentiation 指數運算 82
1.2.5 Greatest Common Divisors 上大公約數 90
1.2.6 Example: Testing for Primality 例：判定質數 . . . 94
1.3 Formulating Abstractions with Higher-Order Procedures 用高階程序來形式化抽象 . . 109
1.3.1 Procedures as Arguments 程序當做引數 111
1.3.2 Constructing Procedures Using `lambda` 用 `lambda` 建構程序 120
1.3.3 Procedures as General Methods 準做一般方法 ê 程序 129
1.3.4 Procedures as Returned Values 程序當做傳轉 ê 值 . 140

2 Building Abstractions with Data 用資料起造抽象 155
2.1 Introduction to Data Abstraction 介紹資料抽象化 163
2.1.1 Example: Arithmetic Operations for Rational Numbers 例：有理數 ê 運算操作 164
2.1.2 Abstraction Barriers 抽象化障礙 172

2.1.3 What Is Meant by Data? 資料 ê 意思是 siáⁿ 物？ . . 177
2.1.4 Extended Exercise: Interval Arithmetic 擴展 ê 練習：區間運算 183
2.2 Hierarchical Data and the Closure Property 階層資料 kap 閉包性質 192
2.2.1 Representing Sequences 195
2.2.2 Hierarchical Structures 階層結構 212
2.2.3 Sequences as Conventional Interfaces 列當做慣例介面 223
2.2.4 Example: A Picture Language 例：圖片語言 248
2.3 Symbolic Data 符號資料 276
2.3.1 Quotation 引用 276
2.3.2 Example: Symbolic Differentiation 例：符號微分 . 283
2.3.3 Example: Representing Sets 291
2.3.4 Example: Huffman Encoding Trees 304
2.4 Multiple Representations for Abstract Data 314
2.4.1 Representations for Complex Numbers 317
2.4.2 Tagged data 322
2.4.3 Data-Directed Programming and Additivity 327
2.5 Systems with Generic Operations 339
2.5.1 Generic Arithmetic Operations 340
2.5.2 Combining Data of Different Types 347
2.5.3 Example: Symbolic Algebra 358

3 Modularity, Objects, and State 378
3.1 Assignment and Local State 380
3.1.1 Local State Variables 381
3.1.2 The Benefits of Introducing Assignment 389
3.1.3 The Costs of Introducing Assignment 395
3.2 The Environment Model of Evaluation 404

3.2.1 The Rules for Evaluation . . . 406
3.2.2 Applying Simple Procedures . . . 410
3.2.3 Frames as the Repository of Local State . . . 413
3.2.4 Internal Definitions . . . 419
3.3 Modeling with Mutable Data . . . 423
3.3.1 Mutable List Structure . . . 424
3.3.2 Representing Queues . . . 436
3.3.3 Representing Tables . . . 443
3.3.4 A Simulator for Digital Circuits . . . 451
3.3.5 Propagation of Constraints . . . 467
3.4 Concurrency: Time Is of the Essence . . . 482
3.4.1 The Nature of Time in Concurrent Systems . . . 484
3.4.2 Mechanisms for Controlling Concurrency . . . 491
3.5 Streams . . . 509
3.5.1 Streams Are Delayed Lists . . . 510
3.5.2 Infinite Streams . . . 521
3.5.3 Exploiting the Stream Paradigm . . . 532
3.5.4 Streams and Delayed Evaluation . . . 549
3.5.5 Modularity of Functional Programs and Modularity of Objects . . . 558

4 Metalinguistic Abstraction 566
4.1 The Metacircular Evaluator . . . 570
4.1.1 The Core of the Evaluator . . . 573
4.1.2 Representing Expressions . . . 579
4.1.3 Evaluator Data Structures . . . 590
4.1.4 Running the Evaluator as a Program . . . 596
4.1.5 Data as Programs . . . 600
4.1.6 Internal Definitions . . . 604

4.1.7 Separating Syntactic Analysis from Execution . . . 612
4.2 Variations on a Scheme — Lazy Evaluation 618
4.2.1 Normal Order and Applicative Order 619
4.2.2 An Interpreter with Lazy Evaluation 622
4.2.3 Streams as Lazy Lists 632
4.3 Variations on a Scheme — Nondeterministic Computing . . 636
4.3.1 Amb and Search 638
4.3.2 Examples of Nondeterministic Programs 644
4.3.3 Implementing the `amb` Evaluator 655
4.4 Logic Programming 670
4.4.1 Deductive Information Retrieval 675
4.4.2 How the Query System Works 690
4.4.3 Is Logic Programming Mathematical Logic? 702
4.4.4 Implementing the Query System 710
4.4.4.1 The Driver Loop and Instantiation 710
4.4.4.2 The Evaluator 713
4.4.4.3 Finding Assertions by Pattern Matching 717
4.4.4.4 Rules and Unification 720
4.4.4.5 Maintaining the Data Base 725
4.4.4.6 Stream Operations 729
4.4.4.7 Query Syntax Procedures 730
4.4.4.8 Frames and Bindings 734

5 Computing with Register Machines **740**
5.1 Designing Register Machines 742
5.1.1 A Language for Describing Register Machines . . . 746
5.1.2 Abstraction in Machine Design 751
5.1.3 Subroutines 754

5.1.4 Using a Stack to Implement Recursion 760
5.1.5 Instruction Summary 768
5.2 A Register-Machine Simulator 769
5.2.1 The Machine Model 771
5.2.2 The Assembler 777
5.2.3 Generating Execution Procedures for Instructions 781
5.2.4 Monitoring Machine Performance 791
5.3 Storage Allocation and Garbage Collection 795
5.3.1 Memory as Vectors 796
5.3.2 Maintaining the Illusion of Infinite Memory 804
5.4 The Explicit-Control Evaluator 813
5.4.1 The Core of the Explicit-Control Evaluator 815
5.4.2 Sequence Evaluation and Tail Recursion 823
5.4.3 Conditionals, Assignments, and Definitions 827
5.4.4 Running the Evaluator 831
5.5 Compilation 839
5.5.1 Structure of the Compiler 843
5.5.2 Compiling Expressions 850
5.5.3 Compiling Combinations 859
5.5.4 Combining Instruction Sequences 868
5.5.5 An Example of Compiled Code 873
5.5.6 Lexical Addressing 887
5.5.7 Interfacing Compiled Code to the Evaluator 893

References **904**

List of Exercises 練習 ê 列單 **914**

List of Figures 圖片 ê 列單 **917**

Index **919**

教會白話字 kap 教育部台羅拼音 ê 比較 **929**

Colophon 版權頁 **931**

Unofficial Texinfo Format

This is the second edition SICP book, from Unofficial Texinfo Format.

You are probably reading it in an Info hypertext browser, such as the Info mode of Emacs. You might alternatively be reading it TEX-formatted on your screen or printer, though that would be silly. And, if printed, expensive.

The freely-distributed official HTML-and-GIF format was first converted personally to Unofficial Texinfo Format (UTF) version 1 by Lytha Ayth during a long Emacs lovefest weekend in April, 2001.

The UTF is easier to search than the HTML format. It is also much more accessible to people running on modest computers, such as donated '386-based PCs. A 386 can, in theory, run Linux, Emacs, and a Scheme interpreter simultaneously, but most 386s probably can't also run both Netscape and the necessary X Window System without prematurely introducing budding young underfunded hackers to the concept of *thrashing*. UTF can also fit uncompressed on a 1.44MB floppy diskette, which may come in handy for installing UTF on PCs that do not have Internet or LAN access.

The Texinfo conversion has been a straight transliteration, to the extent possible. Like the TEX-to-HTML conversion, this was not without some introduction of breakage. In the case of Unofficial Texinfo Format, figures have suffered an amateurish resurrection of the lost art of ASCII. Also, it's quite possible that some errors of ambiguity were introduced during the conver-

sion of some of the copious superscripts ('^') and subscripts ('_'). Divining *which* has been left as an exercise to the reader. But at least we don't put our brave astronauts at risk by encoding the *greater-than-or-equal* symbol as `<u>></u>`.

If you modify `sicp.texi` to correct errors or improve the ASCII art, then update the `@set utfversion 2.andresraba5.6` line to reflect your delta. For example, if you started with Lytha's version `1`, and your name is Bob, then you could name your successive versions `1.bob1`, `1.bob2`, ... `1.bobn`. Also update `utfversiondate`. If you want to distribute your version on the Web, then embedding the string "sicp.texi" somewhere in the file or Web page will make it easier for people to find with Web search engines.

It is believed that the Unofficial Texinfo Format is in keeping with the spirit of the graciously freely-distributed HTML version. But you never know when someone's armada of lawyers might need something to do, and get their shorts all in a knot over some benign little thing, so think twice before you use your full name or distribute Info, DVI, PostScript, or PDF formats that might embed your account or machine name.

Peath, Lytha Ayth

Addendum: See also the SICP video lectures by Abelson and Sussman: at MIT CSAIL or MIT OCW.

Second Addendum: Above is the original introduction to the UTF from 2001. Ten years later, UTF has been transformed: mathematical symbols and formulas are properly typeset, and figures drawn in vector graphics. The original text formulas and ASCII art figures are still there in the Texinfo source, but will display only when compiled to Info output. At the dawn of e-book readers and tablets, reading a PDF on screen is officially not silly anymore. Enjoy!

A.R, May, 2011

非正式臺語譯本 ê 踏頭話

Che 是電腦科學出名 ê 教科書《電腦程式 ê 結果 kap 解說》(Structure and Interpretation of Computer Programs; SICP) ê 頭一本非正式 ê 臺語譯本，mā 應該是頭 chit 本臺語 ê 電腦科學長篇教科書。

現代雖 bóng 臺語是現此時臺灣上 chē lâng 講 ê 本土言語，但是真 chē lâng bōe 掠伊做時行、tòe ē 著科技 ê 語言，甚至除了少少本土語言課程以外，就無出現佇教學現場內底。敢講臺語真正是 chit 臺老 moh-moh，hō 時代棄 sak ê 老古董？應該毋是 án-ne。Chit 本冊是 beh 來證明，臺語 m̄-nā ē 當傳承古早 ê 智慧，mā 是 ē 當傳揚新科技 ê 思想 kap 智識。

這本冊是翻譯對 SICP ê 非正式 Texinfo 格式版，版本號碼 2.andresraba5.6（2016 年 2 月 2 日版），感謝整理 ê 團隊，予 goán 有一个好 ê 起頭點。另外 beh 予讀者對照原文，goán kā 英語原文留落來通參考。

為著推 sak 阿公阿媽 kap pē 母流傳落來 ê 話，真 chē lâng 開始用臺語寫世間 kap 社會 ê chē-chē 代誌，資訊領域 mā 是 kâng 款。向望 chit 本冊通幫 chān 逐 ê 想 beh 用臺語學程式 ê lâng。

關係書寫形式，本冊使用教會白話字 kap 漢字 lām 寫。另外 koh 附術語表予逐家參考。另外為著追求翻譯 ê 進度 kap 準確性，gún 使用本冊 ê 非官方日語版本、Rev. J. Macgowan ê *English and Chinese Dictionary of Amoy Dialect* 等辭典，做參考翻譯來源。因為 beh 予較 ē 曉教育部台羅拼音 ê 熟 sāi 白話字，冊 ê 後壁附白話字 kap 臺羅拼音對照說明提供參考。

代 seng 著感謝 goán ê pē 母，若是無 kā chit ê 傳統 ê 祖先語言續予 goán，

goán 無可能做 chit ê 計畫。感謝杜前部長正勝 ê 團隊對臺語書寫規範化 ê 試驗，雖 bóng 有一寡寫法 kap 政策 ê 方向主譯 kap in 有無 kâng 想法，但是無 in ê chhui-sak，主譯無得通對臺語書寫好玄，mā 無想 beh kā 臺語學轉來 koh hō͘ 精進。

感謝一位 ē 曉臺語 ê 朋友 A-sîn，雖然無參與 chit ê 計畫，nā 是無伊講著試翻譯看覓，chit ê 計畫 mā 無可能進行。

最後雖 bóng 團隊骨力追 jip 精確 kap 順 ê 程度，毋 kú 因為 che 是頭一改翻譯著作，若有無 toan-tiah，有 têng-tâⁿ ê 所在，koh 請讀者指教。Mā 多謝讀者願意讀 chit 本冊，入去程式設計 ê 領域。

Tân Kiàn-ting（主譯）
Lîm Tsú-thuàn（協譯、建議）

Dedication 獻詞

THIS BOOK IS DEDICATED, in respect and admiration, to the spirit that lives in the computer.

CHIT 本冊，用尊敬 KAP O-LÓ ê 心，獻予活佇 chit 臺電腦內底 ê 神魂。

> "I think that it's extraordinarily important that we in computer science keep fun in computing. When it started out, it was an awful lot of fun. Of course, the paying customers got shafted every now and then, and after a while we began to take their complaints seriously. We began to feel as if we really were responsible for the successful, error-free perfect use of these machines. I don't think we are. I think we're responsible for stretching them, setting them off in new directions, and keeping fun in the house. I hope the field of computer science never loses its sense of fun. Above all, I hope we don't become missionaries. Don't feel as if you're Bible salesmen. The world has too many of those already. What you know about computing other people will learn. Don't feel as if the key to successful computing is only in your hands. What's in your hands, I think and hope, is intelligence: the ability to see the machine as more than when you were first led up to it, that you can make it more."
>
> 「我認為 lán 佇電腦科學保持對計算 ê 趣味上蓋重要，當伊 tú 開

始，伊是夭壽趣味，當然納錢 ê lâng 客不管時 ē 予 lâng kòng，一 tiảp-á 久，lán 就認真處理 in 所投 ê。Lán 開始感覺 lán 親像 chiâⁿ 實對成功、無 thut-chhê、完美用 chiah ê 機器來負責。我無認為是 án-ne。我想 lán 是對 chhun in、予 in 對新 ê 方向開始，佇 chhù 內保持心適。我向望電腦科學 ê 領域 bōe 失去伊 ê 趣味。總是，我向望 lán mài 成做宣教師。毋通感覺家己是賣聖經 ê。世間已經有傷 chē 位 ah。別 lâng ē 學關係運算 lí 所知影 ê。毋通感覺計算成功 ê 鎖匙 kan-ta 佇 lí ê 手頭。我認為 kap 向望，佇 lí ê 手頭 ê，是靈通：看機器比 lí tú 開始看著伊 ê 時 koh 較 chē ê 能力，lí 就 ē 當做 koh 較 chē ah。」

—Alan J. Perlis (April 1, 1922 – February 7, 1990)

Foreword

EDUCATORS, GENERALS, DIETICIANS, psychologists, and parents program. Armies, students, and some societies are programmed. An assault on large problems employs a succession of programs, most of which spring into existence en route. These programs are rife with issues that appear to be particular to the problem at hand. To appreciate programming as an intellectual activity in its own right you must turn to computer programming; you must read and write computer programs—many of them. It doesn't matter much what the programs are about or what applications they serve. What does matter is how well they perform and how smoothly they fit with other programs in the creation of still greater programs. The programmer must seek both perfection of part and adequacy of collection. In this book the use of "program" is focused on the creation, execution, and study of programs written in a dialect of Lisp for execution on a digital computer. Using Lisp we restrict or limit not what we may program, but only the notation for our program descriptions.

教育者、將軍、營養師、心理學家、兩親設計計畫。[1]軍隊、學生、kap 一寡社會受規畫。大 ê 問題 ê 衝擊應用連 sòa ê 程式，in 大半 liâm-mī 佇路 nih 佇 leh。Chiah ê 程式充滿出現佇手頭 ê 特別 ê 問題。Beh 欣賞伊家 kī 準做智力活動 ê 程式設計，Lí 著 oat 轉來寫程式；lí 著讀 kap 寫電腦程式——

[1]英語 to program 除了有「程式設計」ê 意思以外，mā 有「規畫計畫 kap 程序等」ê 意思

chē-chē 篇。程式 ê 目的 kap 應用 lóng 無 siáⁿ 差別。有差 ê 是 in pháng gōa 好勢 kap in 有 gōa 合別个程序，佇創造 iah koh 較大 ê 程式。程式設計師愛 chhōe 求部份 ê 完美 kap kui 个 ê 夠額。佇 chit 本冊內，「程式」ê 使用，聚集佇程式建立、執行 kap 研究，用 Lisp ê 方言寫，佇數位 ê 電腦 pháng。用 Lisp，lán ē 當限制 ê，毋是 lán 通寫 ê 程式內容，卻是 lán ê 程式描述 ê 記號。

Our traffic with the subject matter of this book involves us with three foci of phenomena: the human mind, collections of computer programs, and the computer. Every computer program is a model, hatched in the mind, of a real or mental process. These processes, arising from human experience and thought, are huge in number, intricate in detail, and at any time only partially understood. They are modeled to our permanent satisfaction rarely by our computer programs. Thus even though our programs are carefully handcrafted discrete collections of symbols, mosaics of interlocking functions, they continually evolve: we change them as our perception of the model deepens, enlarges, generalizes until the model ultimately attains a metastable place within still another model with which we struggle. The source of the exhilaration associated with computer programming is the continual unfolding within the mind and on the computer of mechanisms expressed as programs and the explosion of perception they generate. If art interprets our dreams, the computer executes them in the guise of programs!

For all its power, the computer is a harsh taskmaster. Its programs must be correct, and what we wish to say must be said accurately in every detail. As in every other symbolic activity, we become convinced of program truth through argument. Lisp itself can be assigned a semantics (another model, by the way), and if a program's function can be specified, say, in the predicate calculus, the proof methods of logic can be used to make an acceptable correctness argument. Unfortunately, as programs get large and complicated, as they almost always do, the adequacy, consistency, and correctness of the specifications themselves become open to doubt, so that complete formal arguments

of correctness seldom accompany large programs. Since large programs grow from small ones, it is crucial that we develop an arsenal of standard program structures of whose correctness we have become sure—we call them idioms —and learn to combine them into larger structures using organizational techniques of proven value. These techniques are treated at length in this book, and understanding them is essential to participation in the Promethean enterprise called programming. More than anything else, the uncovering and mastery of powerful organizational techniques accelerates our ability to create large, significant programs. Conversely, since writing large programs is very taxing, we are stimulated to invent new methods of reducing the mass of function and detail to be fitted into large programs.

Unlike programs, computers must obey the laws of physics. If they wish to perform rapidly—a few nanoseconds per state change—they must transmit electrons only small distances (at most $1\frac{1}{2}$ feet). The heat generated by the huge number of devices so concentrated in space has to be removed. An exquisite engineering art has been developed balancing between multiplicity of function and density of devices. In any event, hardware always operates at a level more primitive than that at which we care to program. The processes that transform our Lisp programs to "machine" programs are themselves abstract models which we program. Their study and creation give a great deal of insight into the organizational programs associated with programming arbitrary models. Of course the computer itself can be so modeled. Think of it: the behavior of the smallest physical switching element is modeled by quantum mechanics described by differential equations whose detailed behavior is captured by numerical approximations represented in computer programs executing on computers composed of . . .!

It is not merely a matter of tactical convenience to separately identify the three foci. Even though, as they say, it's all in the head, this logical separation induces an acceleration of symbolic traffic between these foci whose richness,

vitality, and potential is exceeded in human experience only by the evolution of life itself. At best, relationships between the foci are metastable. The computers are never large enough or fast enough. Each breakthrough in hardware technology leads to more massive programming enterprises, new organizational principles, and an enrichment of abstract models. Every reader should ask himself periodically "Toward what end, toward what end?"—but do not ask it too often lest you pass up the fun of programming for the constipation of bittersweet philosophy.

Among the programs we write, some (but never enough) perform a precise mathematical function such as sorting or finding the maximum of a sequence of numbers, determining primality, or finding the square root. We call such programs algorithms, and a great deal is known of their optimal behavior, particularly with respect to the two important parameters of execution time and data storage requirements. A programmer should acquire good algorithms and idioms. Even though some programs resist precise specifications, it is the responsibility of the programmer to estimate, and always to attempt to improve, their performance.

Lisp is a survivor, having been in use for about a quarter of a century. Among the active programming languages only Fortran has had a longer life. Both languages have supported the programming needs of important areas of application, Fortran for scientific and engineering computation and Lisp for artificial intelligence. These two areas continue to be important, and their programmers are so devoted to these two languages that Lisp and Fortran may well continue in active use for at least another quarter-century.

Lisp changes. The Scheme dialect used in this text has evolved from the original Lisp and differs from the latter in several important ways, including static scoping for variable binding and permitting functions to yield functions as values. In its semantic structure Scheme is as closely akin to Algol 60 as to early Lisps. Algol 60, never to be an active language again, lives on in the

genes of Scheme and Pascal. It would be difficult to find two languages that are the communicating coin of two more different cultures than those gathered around these two languages. Pascal is for building pyramids—imposing, breathtaking, static structures built by armies pushing heavy blocks into place. Lisp is for building organisms—imposing, breathtaking, dynamic structures built by squads fitting fluctuating myriads of simpler organisms into place. The organizing principles used are the same in both cases, except for one extraordinarily important difference: The discretionary exportable functionality entrusted to the individual Lisp programmer is more than an order of magnitude greater than that to be found within Pascal enterprises. Lisp programs inflate libraries with functions whose utility transcends the application that produced them. The list, Lisp's native data structure, is largely responsible for such growth of utility. The simple structure and natural applicability of lists are reflected in functions that are amazingly nonidiosyncratic. In Pascal the plethora of declarable data structures induces a specialization within functions that inhibits and penalizes casual cooperation. It is better to have 100 functions operate on one data structure than to have 10 functions operate on 10 data structures. As a result the pyramid must stand unchanged for a millennium; the organism must evolve or perish.

To illustrate this difference, compare the treatment of material and exercises within this book with that in any first-course text using Pascal. Do not labor under the illusion that this is a text digestible at MIT only, peculiar to the breed found there. It is precisely what a serious book on programming Lisp must be, no matter who the student is or where it is used.

Note that this is a text about programming, unlike most Lisp books, which are used as a preparation for work in artificial intelligence. After all, the critical programming concerns of software engineering and artificial intelligence tend to coalesce as the systems under investigation become larger. This explains why there is such growing interest in Lisp outside of artificial intelli-

gence.

As one would expect from its goals, artificial intelligence research generates many significant programming problems. In other programming cultures this spate of problems spawns new languages. Indeed, in any very large programming task a useful organizing principle is to control and isolate traffic within the task modules via the invention of language. These languages tend to become less primitive as one approaches the boundaries of the system where we humans interact most often. As a result, such systems contain complex language-processing functions replicated many times. Lisp has such a simple syntax and semantics that parsing can be treated as an elementary task. Thus parsing technology plays almost no role in Lisp programs, and the construction of language processors is rarely an impediment to the rate of growth and change of large Lisp systems. Finally, it is this very simplicity of syntax and semantics that is responsible for the burden and freedom borne by all Lisp programmers. No Lisp program of any size beyond a few lines can be written without being saturated with discretionary functions. Invent and fit; have fits and reinvent! We toast the Lisp programmer who pens his thoughts within nests of parentheses.

Alan J. Perlis
New Haven, Connecticut

Preface to the Second Edition

> Is it possible that software is not like anything else, that it is meant to be discarded: that the whole point is to always see it as a soap bubble?
>
> —Alan J. Perlis

THE MATERIAL IN THIS BOOK has been the basis of MIT's entry-level computer science subject since 1980. We had been teaching this material for four years when the first edition was published, and twelve more years have elapsed until the appearance of this second edition. We are pleased that our work has been widely adopted and incorporated into other texts. We have seen our students take the ideas and programs in this book and build them in as the core of new computer systems and languages. In literal realization of an ancient Talmudic pun, our students have become our builders. We are lucky to have such capable students and such accomplished builders.

In preparing this edition, we have incorporated hundreds of clarifications suggested by our own teaching experience and the comments of colleagues at MIT and elsewhere. We have redesigned most of the major programming systems in the book, including the generic-arithmetic system, the interpreters, the register-machine simulator, and the compiler; and we have rewritten all the program examples to ensure that any Scheme implementation conforming to the IEEE Scheme standard (IEEE 1990) will be able to run the code.

This edition emphasizes several new themes. The most important of these is the central role played by different approaches to dealing with time in computational models: objects with state, concurrent programming, functional programming, lazy evaluation, and nondeterministic programming. We have included new sections on concurrency and nondeterminism, and we have tried to integrate this theme throughout the book.

The first edition of the book closely followed the syllabus of our MIT one-semester subject. With all the new material in the second edition, it will not be possible to cover everything in a single semester, so the instructor will have to pick and choose. In our own teaching, we sometimes skip the section on logic programming (Section 4.4), we have students use the register-machine simulator but we do not cover its implementation (Section 5.2), and we give only a cursory overview of the compiler (Section 5.5). Even so, this is still an intense course. Some instructors may wish to cover only the first three or four chapters, leaving the other material for subsequent courses.

The World-Wide-Web site http://mitpress.mit.edu/sicp provides support for users of this book. This includes programs from the book, sample programming assignments, supplementary materials, and downloadable implementations of the Scheme dialect of Lisp.

Preface to the First Edition

> A computer is like a violin. You can imagine a novice trying first a phonograph and then a violin. The latter, he says, sounds terrible. That is the argument we have heard from our humanists and most of our computer scientists. Computer programs are good, they say, for particular purposes, but they aren't flexible. Neither is a violin, or a typewriter, until you learn how to use it.
>
> —Marvin Minsky, "Why Programming Is a Good Medium for Expressing Poorly-Understood and Sloppily-Formulated Ideas"

"The Structure and Interpretation of Computer Programs" is the entry-level subject in computer science at the Massachusetts Institute of Technology. It is required of all students at MIT who major in electrical engineering or in computer science, as one-fourth of the "common core curriculum," which also includes two subjects on circuits and linear systems and a subject on the design of digital systems. We have been involved in the development of this subject since 1978, and we have taught this material in its present form since the fall of 1980 to between 600 and 700 students each year. Most of these students have had little or no prior formal training in computation, although many have played with computers a bit and a few have had extensive programming or hardware-design experience.

Our design of this introductory computer-science subject reflects two major concerns. First, we want to establish the idea that a computer language is not just a way of getting a computer to perform operations but rather that it is a novel formal medium for expressing ideas about methodology. Thus, programs must be written for people to read, and only incidentally for machines to execute. Second, we believe that the essential material to be addressed by a subject at this level is not the syntax of particular programming-language constructs, nor clever algorithms for computing particular functions efficiently, nor even the mathematical analysis of algorithms and the foundations of computing, but rather the techniques used to control the intellectual complexity of large software systems.

Our goal is that students who complete this subject should have a good feel for the elements of style and the aesthetics of programming. They should have command of the major techniques for controlling complexity in a large system. They should be capable of reading a 50-page-long program, if it is written in an exemplary style. They should know what not to read, and what they need not understand at any moment. They should feel secure about modifying a program, retaining the spirit and style of the original author.

These skills are by no means unique to computer programming. The techniques we teach and draw upon are common to all of engineering design. We control complexity by building abstractions that hide details when appropriate. We control complexity by establishing conventional interfaces that enable us to construct systems by combining standard, well-understood pieces in a "mix and match" way. We control complexity by establishing new languages for describing a design, each of which emphasizes particular aspects of the design and deemphasizes others.

Underlying our approach to this subject is our conviction that "computer science" is not a science and that its significance has little to do with computers. The computer revolution is a revolution in the way we think and in the

way we express what we think. The essence of this change is the emergence of what might best be called *procedural epistemology*—the study of the structure of knowledge from an imperative point of view, as opposed to the more declarative point of view taken by classical mathematical subjects. Mathematics provides a framework for dealing precisely with notions of "what is." Computation provides a framework for dealing precisely with notions of "how to."

In teaching our material we use a dialect of the programming language Lisp. We never formally teach the language, because we don't have to. We just use it, and students pick it up in a few days. This is one great advantage of Lisp-like languages: They have very few ways of forming compound expressions, and almost no syntactic structure. All of the formal properties can be covered in an hour, like the rules of chess. After a short time we forget about syntactic details of the language (because there are none) and get on with the real issues—figuring out what we want to compute, how we will decompose problems into manageable parts, and how we will work on the parts. Another advantage of Lisp is that it supports (but does not enforce) more of the large-scale strategies for modular decomposition of programs than any other language we know. We can make procedural and data abstractions, we can use higher-order functions to capture common patterns of usage, we can model local state using assignment and data mutation, we can link parts of a program with streams and delayed evaluation, and we can easily implement embedded languages. All of this is embedded in an interactive environment with excellent support for incremental program design, construction, testing, and debugging. We thank all the generations of Lisp wizards, starting with John McCarthy, who have fashioned a fine tool of unprecedented power and elegance.

Scheme, the dialect of Lisp that we use, is an attempt to bring together the power and elegance of Lisp and Algol. From Lisp we take the metalin-

guistic power that derives from the simple syntax, the uniform representation of programs as data objects, and the garbage-collected heap-allocated data. From Algol we take lexical scoping and block structure, which are gifts from the pioneers of programming-language design who were on the Algol committee. We wish to cite John Reynolds and Peter Landin for their insights into the relationship of Church's λ-calculus to the structure of programming languages. We also recognize our debt to the mathematicians who scouted out this territory decades before computers appeared on the scene. These pioneers include Alonzo Church, Barkley Rosser, Stephen Kleene, and Haskell Curry.

Acknowledgments

We would like to thank the many people who have helped us develop this book and this curriculum.

Our subject is a clear intellectual descendant of "6.231," a wonderful subject on programming linguistics and the λ-calculus taught at MIT in the late 1960s by Jack Wozencraft and Arthur Evans, Jr.

We owe a great debt to Robert Fano, who reorganized MIT's introductory curriculum in electrical engineering and computer science to emphasize the principles of engineering design. He led us in starting out on this enterprise and wrote the first set of subject notes from which this book evolved.

Much of the style and aesthetics of programming that we try to teach were developed in conjunction with Guy Lewis Steele Jr., who collaborated with Gerald Jay Sussman in the initial development of the Scheme language. In addition, David Turner, Peter Henderson, Dan Friedman, David Wise, and Will Clinger have taught us many of the techniques of the functional programming community that appear in this book.

Joel Moses taught us about structuring large systems. His experience with the Macsyma system for symbolic computation provided the insight that one should avoid complexities of control and concentrate on organizing the data to reflect the real structure of the world being modeled.

Marvin Minsky and Seymour Papert formed many of our attitudes about

programming and its place in our intellectual lives. To them we owe the understanding that computation provides a means of expression for exploring ideas that would otherwise be too complex to deal with precisely. They emphasize that a student's ability to write and modify programs provides a powerful medium in which exploring becomes a natural activity.

We also strongly agree with Alan Perlis that programming is lots of fun and we had better be careful to support the joy of programming. Part of this joy derives from observing great masters at work. We are fortunate to have been apprentice programmers at the feet of Bill Gosper and Richard Greenblatt.

It is difficult to identify all the people who have contributed to the development of our curriculum. We thank all the lecturers, recitation instructors, and tutors who have worked with us over the past fifteen years and put in many extra hours on our subject, especially Bill Siebert, Albert Meyer, Joe Stoy, Randy Davis, Louis Braida, Eric Grimson, Rod Brooks, Lynn Stein and Peter Szolovits. We would like to specially acknowledge the outstanding teaching contributions of Franklyn Turbak, now at Wellesley; his work in undergraduate instruction set a standard that we can all aspire to. We are grateful to Jerry Saltzer and Jim Miller for helping us grapple with the mysteries of concurrency, and to Peter Szolovits and David McAllester for their contributions to the exposition of nondeterministic evaluation in Chapter 4.

Many people have put in significant effort presenting this material at other universities. Some of the people we have worked closely with are Jacob Katzenelson at the Technion, Hardy Mayer at the University of California at Irvine, Joe Stoy at Oxford, Elisha Sacks at Purdue, and Jan Komorowski at the Norwegian University of Science and Technology. We are exceptionally proud of our colleagues who have received major teaching awards for their adaptations of this subject at other universities, including Kenneth Yip at Yale, Brian Harvey at the University of California at Berkeley, and Dan

Huttenlocher at Cornell.

Al Moyé arranged for us to teach this material to engineers at Hewlett-Packard, and for the production of videotapes of these lectures. We would like to thank the talented instructors—in particular Jim Miller, Bill Siebert, and Mike Eisenberg—who have designed continuing education courses incorporating these tapes and taught them at universities and industry all over the world.

Many educators in other countries have put in significant work translating the first edition. Michel Briand, Pierre Chamard, and André Pic produced a French edition; Susanne Daniels-Herold produced a German edition; and Fumio Motoyoshi produced a Japanese edition. We do not know who produced the Chinese edition, but we consider it an honor to have been selected as the subject of an "unauthorized" translation.

It is hard to enumerate all the people who have made technical contributions to the development of the Scheme systems we use for instructional purposes. In addition to Guy Steele, principal wizards have included Chris Hanson, Joe Bowbeer, Jim Miller, Guillermo Rozas, and Stephen Adams. Others who have put in significant time are Richard Stallman, Alan Bawden, Kent Pitman, Jon Taft, Neil Mayle, John Lamping, Gwyn Osnos, Tracy Larrabee, George Carrette, Soma Chaudhuri, Bill Chiarchiaro, Steven Kirsch, Leigh Klotz, Wayne Noss, Todd Cass, Patrick O'Donnell, Kevin Theobald, Daniel Weise, Kenneth Sinclair, Anthony Courtemanche, Henry M. Wu, Andrew Berlin, and Ruth Shyu.

Beyond the MIT implementation, we would like to thank the many people who worked on the IEEE Scheme standard, including William Clinger and Jonathan Rees, who edited the $\mathrm{R}^4\mathrm{RS}$, and Chris Haynes, David Bartley, Chris Hanson, and Jim Miller, who prepared the IEEE standard.

Dan Friedman has been a long-time leader of the Scheme community. The community's broader work goes beyond issues of language design to en-

compass significant educational innovations, such as the high-school curriculum based on EdScheme by Schemer's Inc., and the wonderful books by Mike Eisenberg and by Brian Harvey and Matthew Wright.

We appreciate the work of those who contributed to making this a real book, especially Terry Ehling, Larry Cohen, and Paul Bethge at the MIT Press. Ella Mazel found the wonderful cover image. For the second edition we are particularly grateful to Bernard and Ella Mazel for help with the book design, and to David Jones, TEX wizard extraordinaire. We also are indebted to those readers who made penetrating comments on the new draft: Jacob Katzenelson, Hardy Mayer, Jim Miller, and especially Brian Harvey, who did unto this book as Julie did unto his book *Simply Scheme*.

Finally, we would like to acknowledge the support of the organizations that have encouraged this work over the years, including support from Hewlett-Packard, made possible by Ira Goldstein and Joel Birnbaum, and support from DARPA, made possible by Bob Kahn.

1

Building Abstractions with Procedures 用程序起造抽象

> The acts of the mind, wherein it exerts its power over simple ideas, are chiefly these three: 1. Combining several simple ideas into one compound one, and thus all complex ideas are made. 2. The second is bringing two ideas, whether simple or complex, together, and setting them by one another so as to take a view of them at once, without uniting them into one, by which it gets all its ideas of relations. 3. The third is separating them from all other ideas that accompany them in their real existence: this is called abstraction, and thus all its general ideas are made.
>
> —John Locke, *An Essay Concerning Human Understanding* (1690)

心神 ê 行做，伊佇 hia 展伊 ê 能力佇簡單 ê 想法頂，主要有 chit 3 項：1. Kā 幾 ê 簡單 ê 想法組立做一 ê 複雜 ê，就 án-ne 產生

逐項複雜 ê 想法。2. 第二就是 kā 無論簡單 iah 是複雜 ê 2 項想法 tàu 做伙，互相設定，方便一 kái 觀察 in（毋免 kā in 合一），用 án-ne 得著所有 in ê 關係 ê 想法。第三是 kā in tùi 所有其他 kap in 佇 in ê 誠實存在內 tàu 陣 ê 想法拆開：che 號做抽象化，就 án-ne 產生伊所有一般 ê 想法。

—John Locke, 關係人類理解 *ê* 論文 *(An Essay Concerning Human Understanding)* (1690)

We are about to study the idea of a *computational process*. Computational processes are abstract beings that inhabit computers. As they evolve, processes manipulate other abstract things called *data*. The evolution of a process is directed by a pattern of rules called a *program*. People create programs to direct processes. In effect, we conjure the spirits of the computer with our spells.

Lán beh 研究計算過程 (compututational process) ê 概念。計算過程是電腦會當 pháng ê 抽象事物。過程進化 ê 時陣，ē 操作另一種號做資料 (data) ê 抽象 ê 概念。過程 ê 進行，是程式 (program) 所指引，伊是有模式 ê 一組規則。Lâng 建立程式來指引過程。其實 ùi 效果來看，lán 親像用咒語召喚電腦 ê 神魂。

A computational process is indeed much like a sorcerer's idea of a spirit. It cannot be seen or touched. It is not composed of matter at all. However, it is very real. It can perform intellectual work. It can answer questions. It can affect the world by disbursing money at a bank or by controlling a robot arm in a factory. The programs we use to conjure processes are like a sorcerer's spells. They are carefully composed from symbolic expressions in arcane and esoteric *programming languages* that prescribe the tasks we want our processes to perform.

計算過程確實 chiok 像西方術士講 ê 神魂。它看無 mā 摸無，根本毋是由物質所構成。不過它非常真實。它會當行智力 ê 工課，會當回答問題，亦會當

透過佇銀行提款抑是控制工廠內 ê 機械來影響世界。阮召喚過程 ê 程式著像西方術士 ê 咒語。由神秘深奧的程式語言 (programming languages) 中 ê 符號表達細膩編寫所成，chiah ê 言語規定 lán 希望過程執行 ê 任務。

A computational process, in a correctly working computer, executes programs precisely and accurately. Thus, like the sorcerer's apprentice, novice programmers must learn to understand and to anticipate the consequences of their conjuring. Even small errors (usually called *bugs* or *glitches*) in programs can have complex and unanticipated consequences.

佇正確運作 ê 電腦內底，計算過程進行精確無誤。親像西方術士 ê 半桶師仔，工程師嘛愛學按怎理解 kah ioh in ê 咒語 ê 後果。連足小 ê 錯誤（通常號做 *bugs* 抑是 *glitches*）攏會造成複雜又 koh phái^{n} ioh ê 結果。

Fortunately, learning to program is considerably less dangerous than learning sorcery, because the spirits we deal with are conveniently contained in a secure way. Real-world programming, however, requires care, expertise, and wisdom. A small bug in a computer-aided design program, for example, can lead to the catastrophic collapse of an airplane or a dam or the self-destruction of an industrial robot.

有幸，學程式設計予 lâng 掠做是比學魔法 khah 無危險，因為 lán 處理 ê 神靈是簡單包佇安全 ê 方法內底。但是真實世界 ê 程式設計需要注神、專精 kap 智慧。舉例，佇電腦幫 chān 設計 ê，細細 ê bug，可能致 kàu 機場 iah 是水壩 ê 崩去，或者是工業機器 lâng 家己毀滅。

Master software engineers have the ability to organize programs so that they can be reasonably sure that the resulting processes will perform the tasks intended. They can visualize the behavior of their systems in advance. They know how to structure programs so that unanticipated problems do not lead to catastrophic consequences, and when problems do arise, they can *debug* their programs. Well-designed computational systems, like well-designed automobiles or nuclear reactors, are designed in a modular manner, so that the parts can be constructed, replaced, and debugged separately.

出師 ê 軟體工程師 ē 曉組織程式，予伊 ē 當合理確定結果 ê 過程 ē 運作目標 ê 任務。In 知影 án-nóa 起做程式，予意外 ê 問題 bē 致 kàu 災難 ê 結果，起問題 ê 時陣，in 通 kā in ê 程式除去錯誤 (debug)。設計穩當 ê 運算系統，親像設計穩當 ê 汽車 iah 是核子反應爐，是 module（模組）化設計，chiah ê 部份通分開建築、取代 kap 除去錯誤。

Programming in Lisp 用 Lisp 設計程式

We need an appropriate language for describing processes, and we will use for this purpose the programming language Lisp. Just as our everyday thoughts are usually expressed in our natural language (such as English, French, or Japanese), and descriptions of quantitative phenomena are expressed with mathematical notations, our procedural thoughts will be expressed in Lisp. Lisp was invented in the late 1950s as a formalism for reasoning about the use of certain kinds of logical expressions, called *recursion equations*, as a model for computation. The language was conceived by John McCarthy and is based on his paper "Recursive Functions of Symbolic Expressions and Their Computation by Machine" (McCarthy 1960).

Lán 需要適當 ê 語言寫過程，為 chit ê 目的，ē 用 Lisp 程式設計語言。就親像 lán-lâng 逐工思考常常用 lán ê 自然語言表達（比如英語、法語、日語），寫量化現象 ē 用數學 ê 符號，lán ê 程序 ê 思考 ē 用 Lisp 表達。Lisp 佇 1950 年代後期發明，成做推論邏輯表達式 ê 一寡型式（叫做 遞迴方程式 (recursion equations)）ê 使用 ê 形式，當做運算 ê 模型。Chit ê 語言是由 John McCarthy 思想，khiā 佇伊 ê 論文 "Recursive Functions of Symbolic Expressions and Their Computation by Machine" (McCarthy 1960).

Despite its inception as a mathematical formalism, Lisp is a practical programming language. A Lisp *interpreter* is a machine that carries out processes described in the Lisp language. The first Lisp interpreter was implemented by McCarthy with the help of colleagues and students in the Artificial Intelligence Group of the MIT Research Laboratory of Electronics and in the MIT

Computation Center.[1] Lisp, whose name is an acronym for LISt Processing, was designed to provide symbol-manipulating capabilities for attacking programming problems such as the symbolic differentiation and integration of algebraic expressions. It included for this purpose new data objects known as atoms and lists, which most strikingly set it apart from all other languages of the period.

雖 bóng 伊 tú 開始是 tuì 數學 ê 形式主義，Lisp 是應用 ê 程式語言。Lisp ê 直譯器 (interpreter) 是機器，執行 lán 用 Lisp 語言寫 ê 過程。頭一 ê Lisp 直譯器是 MaCarthy kap MIT 電子研究實驗室以及運算中心 ê 人工智慧小組 ê 同事 kap 學生 ê 幫 chān 所實做。[2]Lisp 是「LISt Processing」（列單處理）ê 頭字母簡略，予 lâng 設計做提供符號操作能力來解決比如符號微分、代數表達式 ê 積分等等 ê 程式問題。為著 chit ê 目的，伊包含原子 (atom) kap 列單 (list) 等等新 ê 資料物件，大大 hām hit 陣 á 所有 ê 語言有差別。

Lisp was not the product of a concerted design effort. Instead, it evolved informally in an experimental manner in response to users' needs and to pragmatic implementation considerations. Lisp's informal evolution has continued through the years, and the community of Lisp users has traditionally resisted attempts to promulgate any "official" definition of the language. This evolution, together with the flexibility and elegance of the initial conception, has enabled Lisp, which is the second oldest language in widespread use today (only Fortran is older), to continually adapt to encompass the most modern ideas about program design. Thus, Lisp is by now a family of dialects, which, while sharing most of the original features, may differ from one another in significant ways. The dialect of Lisp used in this book is called Scheme.[3]

---

[1]The *Lisp 1 Programmer's Manual* appeared in 1960, and the *Lisp 1.5 Programmer's Manual* (McCarthy et al. 1965) was published in 1962. The early history of Lisp is described in McCarthy 1978.

[2]The *Lisp 1 Programmer's Manual* 佇 1960 年頭一改出，*Lisp 1.5 Programmer's Manual* (McCarthy et al. 1965) 佇 1962 年出版。Lisp 初期 ê 歷史佇 McCarthy 1978內底有說明。

[3]The two dialects in which most major Lisp programs of the 1970s were written are

Lisp 毋是設計 kah 好勢 á 好勢 ê 產物。反轉是用實驗方式非正式進化 ê，來回應用者 ê 需求 kap 應用上 ê 實做考慮。Lisp ê 非正式進化繼續幾 nā 年，Lisp 用者 ê 社群傳統上排斥任何公開 chit ê 語言「正式」定義 ê 意圖。Chit ê 進化，hām 初期概念 ê 靈活 kap 優雅 kâng 齊，予 Lisp chit ê 現 chú 時第二舊 ê 通用語言（kan-ta 比 Fortran 較 oàⁿ 出），有能力來繼續引用採用上現代 ê 程式設計 (program design) 思維。就 án-ne，Lisp kàu taⁿ 是方言 ê 家族，in 雖 bóng 分享大部份原底 ê 功能，毋 kú 有可能佇重要方面無 kâng。本冊所用 ê Lisp 方言是 Scheme。[4]

Because of its experimental character and its emphasis on symbol manip-

MacLisp (Moon 1978; Pitman 1983), developed at the MIT Project MAC, and Interlisp (Teitelman 1974), developed at Bolt Beranek and Newman Inc. and the Xerox Palo Alto Research Center. Portable Standard Lisp (Hearn 1969; Griss 1981) was a Lisp dialect designed to be easily portable between different machines. MacLisp spawned a number of subdialects, such as Franz Lisp, which was developed at the University of California at Berkeley, and Zetalisp (Moon and Weinreb 1981), which was based on a special-purpose processor designed at the MIT Artificial Intelligence Laboratory to run Lisp very efficiently. The Lisp dialect used in this book, called Scheme (Steele and Sussman 1975), was invented in 1975 by Guy Lewis Steele Jr. and Gerald Jay Sussman of the MIT Artificial Intelligence Laboratory and later reimplemented for instructional use at MIT. Scheme became an IEEE standard in 1990 (IEEE 1990). The Common Lisp dialect (Steele 1982, Steele 1990) was developed by the Lisp community to combine features from the earlier Lisp dialects to make an industrial standard for Lisp. Common Lisp became an ANSI standard in 1994 (ANSI 1994).

[4] 大部份 1970 年代 Lisp 程式所用 ê 2 款方言是 MacLisp (Moon 1978; Pitman 1983)，佇 MIT 計畫 MAC 開發，kap Interlisp (Teitelman 1974), 佇 Bolt Beranek and Newman Inc. and the Xerox Palo Alto 研究中心開發。Portable Standard Lisp (Hearn 1969; Griss 1981) 是一款 Lisp 方言，設計做 ē 當佇無 kâng ê 機器中間 suá 栽 (portable)。MacLisp thoàⁿ 出一寡次方言，比如 Franz Lisp，伊開發佇加州大學 Berkeley 分校，kap Zetalisp (Moon and Weinreb 1981)，伊 chhāi 佇由 MIT 人工智慧實驗室所設計，ē 當有效率 pháng Lisp ê 特殊目的 ê 處理器面頂。本冊用 ê Lisp 方言號做 Scheme (Steele and Sussman 1975)，佇 1975 年由 MIT 人工智慧實驗室 ê Guy Lewis Steele Jr. kap Gerald Jay Sussman 發明，了後為著佇 MIT ê 教育目的 koh 實做。Scheme 佇 1990 年變做是 IEEE 標準 (IEEE 1990)。Common Lisp 方言 (Steele 1982, Steele 1990)，是由 Lisp 社群開發，為著 kā 較早 ê Lisp 方言 ê 特點合做伙，成做 Lisp ê 工業標準。Common Lisp 佇 1994 年變做 ANSI 標準 (ANSI 1994).

ulation, Lisp was at first very inefficient for numerical computations, at least in comparison with Fortran. Over the years, however, Lisp compilers have been developed that translate programs into machine code that can perform numerical computations reasonably efficiently. And for special applications, Lisp has been used with great effectiveness.[5] Although Lisp has not yet overcome its old reputation as hopelessly inefficient, Lisp is now used in many applications where efficiency is not the central concern. For example, Lisp has become a language of choice for operating-system shell languages and for extension languages for editors and computer-aided design systems.

因為伊試驗 ê 特點兼強調符號操作，Lisp 原起頭佇數值運算真無效率，上無 kap Fortran 比。毋 kú 隨著年冬 leh 過，Lisp 編譯器有開發出 ē 當翻譯程式 kàu 機器碼，通合理有效率執行數值運算。針對特殊 ê 應用，有 lâng 使用伊，靠大大 ê 效能。[6] 雖 bóng Lisp iah bōe phah 破伊以早無效率 kàu 無向望 ê 名聲，Lisp chit-má 用佇真 chē 效率毋是中心考量 ê 應用。比如講，Lisp 已經變做通揀 ê 作業系統 ê shell ê 語言，以及予編輯器 kap 電腦輔助設計系統用 ê 擴充語言。

If Lisp is not a mainstream language, why are we using it as the framework for our discussion of programming? Because the language possesses unique features that make it an excellent medium for studying important programming constructs and data structures and for relating them to the linguistic features that support them. The most significant of these features is the fact that Lisp descriptions of processes, called *procedures*, can themselves be rep-

[5] One such special application was a breakthrough computation of scientific importance—an integration of the motion of the Solar System that extended previous results by nearly two orders of magnitude, and demonstrated that the dynamics of the Solar System is chaotic. This computation was made possible by new integration algorithms, a special-purpose compiler, and a special-purpose computer all implemented with the aid of software tools written in Lisp (Abelson et al. 1992; Sussman and Wisdom 1992).

[6] 一 ê 特殊運用 ê 例是科學重要性 ê 突破 ê 運算——太陽系運動 ê 積分，伊擴展進前 ê 結果 kàu beh 2 ê 數量級 (order of magnitude)，mā 展示太陽系 ê 動力學是混沌 ê。新 ê 積分演算法、特殊目的 ê 編譯器 kap 特殊目的 ê 電腦，in lóng 用 Lisp 寫 ê 家私來協助實做，予做 chit ê 運算會當成。(Abelson et al. 1992; Sussman and Wisdom 1992).

resented and manipulated as Lisp data. The importance of this is that there are powerful program-design techniques that rely on the ability to blur the traditional distinction between "passive" data and "active" processes. As we shall discover, Lisp's flexibility in handling procedures as data makes it one of the most convenient languages in existence for exploring these techniques. The ability to represent procedures as data also makes Lisp an excellent language for writing programs that must manipulate other programs as data, such as the interpreters and compilers that support computer languages. Above and beyond these considerations, programming in Lisp is great fun.

Nā 準 Lisp 毋是主流語言，lán 啥事用伊做 lán 程式討論 ê 框殼？因為 chit ê 語言有獨一 ê 特點，予伊變做 kài 好 ê 媒體，通學習重要 ê 程式起做 kap 資料結構，mā 通 kā in kap 支持 in ê 語言 ê 特點相關聯。Chiah ê 特點內底上明顯 ê，是 Lisp tùi 過程 ê 敘述（叫做程序 (procedure)），會當親像 Lisp 資料 kâng 款表達 kap 操作。伊 ê 重要是，有 ê 強大 ê 程式設計 ê 技術，倚靠 kā「被動」資料 kap「主動」過程 ê 傳統區別抹予霧霧。Lán 會發現，Lisp 佇 kā 程序當做資料 ê 靈活性，予伊變做一種佇 leh ê，上方便 ê 語言，來探查 chiah ê 技術。Kā 程序表達做資料 ê 能力，iā 予 Lisp 成做優秀 ê 語言，佇寫掠其他程式做資料操作 ê 程式，比如支持電腦語言 ê 直譯器 kap 編譯器。照頂懸 kap 下 kha ê 考量，用 Lisp 寫程序誠心適。

1.1 The Elements of Programming 程式設計 ê 要素

A powerful programming language is more than just a means for instructing a computer to perform tasks. The language also serves as a framework within which we organize our ideas about processes. Thus, when we describe a language, we should pay particular attention to the means that the language provides for combining simple ideas to form more complex ideas. Every powerful language has three mechanisms for accomplishing this:

有能力 ê 程式語言毋 nā 是教電腦做任務 ê 家私。語言 mā 是框殼，用

che，lán 組織 lán 所想 ê 程序 (process)。就 án-ne，伫 lán 描述語言 ê 時，需要加注意語言提供 ê 手段，來 kā 簡單 ê 想法結合，成做 koh 較複雜 ê 想法。任何有能力 ê 語言有 3 ê 機制完成目標：

- **primitive expressions**, which represent the simplest entities the language is concerned with,
- **means of combination**, by which compound elements are built from simpler ones, and
- **means of abstraction**, by which compound elements can be named and manipulated as units.
- **基礎表達式**，代表本語言關心 ê 上簡單 ê 實體，
- **組合方法**，用 che，複合 ê 要素通 tùi 簡單 ê 起做，kap
- **抽象方法**，用 che，複合 ê 要素通當做單元 (unit) 號名 kap 操作。

In programming, we deal with two kinds of elements: procedures and data. (Later we will discover that they are really not so distinct.) Informally, data is "stuff" that we want to manipulate, and procedures are descriptions of the rules for manipulating the data. Thus, any powerful programming language should be able to describe primitive data and primitive procedures and should have methods for combining and abstracting procedures and data.

伫寫程式 ê 時陣，lán 處理兩款要素：程序 kap 資料（以後 lán 會發現 in 實在無 hiah-nī 有差別）。無正式講，資料是 lán beh 操作 ê「物件」，程序是敘述操作資料 ê 規則。就 án-ne，任何有大功能 ê 程式語言應該會當描述基礎資料 kap 基礎程序，以及有方法組合 kap 抽象化程序 kap 資料。

In this chapter we will deal only with simple numerical data so that we can focus on the rules for building procedures.[7] In later chapters we will see that these same rules allow us to build procedures to manipulate compound data as well.

佇本章 lán kan-ta 會處理簡單 ê 數值資料，án-ne 會當集中佇起做程序。[8]落尾 ê 章 lán 會看見，chiah ê 規則 mā 允准 lán 起做程序，來操作複雜 ê 資料。

---

[7]The characterization of numbers as "simple data" is a barefaced bluff. In fact, the treatment of numbers is one of the trickiest and most confusing aspects of any programming language. Some typical issues involved are these: Some computer systems distinguish *integers*, such as 2, from *real numbers*, such as 2.71. Is the real number 2.00 different from the integer 2? Are the arithmetic operations used for integers the same as the operations used for real numbers? Does 6 divided by 2 produce 3, or 3.0? How large a number can we represent? How many decimal places of accuracy can we represent? Is the range of integers the same as the range of real numbers? Above and beyond these questions, of course, lies a collection of issues concerning roundoff and truncation errors—the entire science of numerical analysis. Since our focus in this book is on large-scale program design rather than on numerical techniques, we are going to ignore these problems. The numerical examples in this chapter will exhibit the usual roundoff behavior that one observes when using arithmetic operations that preserve a limited number of decimal places of accuracy in noninteger operations.

[8]Kā 數字特色化做「簡單資料」，是 bōe 見笑 ê hán-hông。其實處理數字是任何程式語言上 pháinn 剃頭兼上花 sà-sà ê 方面。下 kha 是一寡典型 ê 例：一寡電腦系統 kā整數 (integer)，比如 2，kap 實數 (real numbers)，比如 2.71 區別。實數 2.00 kám kap 整數 2 無 siâng 款？整數用 ê 算術操作 kap 實數用 ê kám kâng 款？6 用 2 除是 3，iah 是 3.0？Lán-lâng 通表示 ê 上大數字是 guā chē？整數 ê 範圍 kap 實數 ê 範圍 kám siâng 款？佇 chiah ê 問題 ê 頂懸 kap 下 kha，當然有有關捨入誤差 (roundoff error) kap 切斷誤差 (truncation error) ê 問題 ê 集合——屬佇 kui ê 數值分析 ê 技術。因為 lán 佇本冊 ê 焦點是佇大規模 ê 程式設計，毋是數值技術，lán 會忽略 chiah ê 問題。佇本章 ê 數值 ê 例會展示通常 ê 捨入行為，是照保留有限精準度 ê 十進位，毋是整數 ê 數位算術所操作 ê。

1.1.1 Expressions 表達式

One easy way to get started at programming is to examine some typical interactions with an interpreter for the Scheme dialect of Lisp. Imagine that you are sitting at a computer terminal. You type an *expression*, and the interpreter responds by displaying the result of its *evaluating* that expression.

Chit 款 khah 快來開始寫程式 ê 方法，是檢查一寡佮 Lisp ê Scheme 方言 ê 直譯器典型 ê 互動。想像汝坐佇電腦終端機 (terminal) 頭前，輸入表達式 (expression)，直譯器顯示表達式算值 (evaluating) ê 結果來回應。

One kind of primitive expression you might type is a number. (More precisely, the expression that you type consists of the numerals that represent the number in base 10.) If you present Lisp with a number

一款基礎 ê 表達式汝可能拍 ê 是數字。（講 koh 較準，是汝拍 ê 表達式，包含代表十進位 ê 數字 ê 數值。）Nā 汝予 Lisp 數字

```
486
```

the interpreter will respond by printing[9]
直譯器會印下 kha ê，來回應：[10]

```
486
```

Expressions representing numbers may be combined with an expression representing a primitive procedure (such as + or *) to form a compound expression that represents the application of the procedure to those numbers. For example:
代表數字 ê 表達式會當用代表基礎程序（比如 + iah 是 *）ê 表達式，來建立複合 ê 表達式，代表 chit ê 程序應用 kàu chiah ê 數字。比如：

[9] Throughout this book, when we wish to emphasize the distinction between the input typed by the user and the response printed by the interpreter, we will show the latter in slanted characters.

[10] 這本冊內底，佇 lán 想 beh 強調用者 ê 輸入，kap 編譯器 ê 回應 ê 差別 ê 時陣，lán 會用 *chhoàh* 體 (slanted) 字展示後壁 ê。

```
(+ 137 349)
486

(- 1000 334)
666

(* 5 99)
495

(/ 10 5)
2

(+ 2.7 10)
12.7
```

Expressions such as these, formed by delimiting a list of expressions within parentheses in order to denote procedure application, are called *combinations*. The leftmost element in the list is called the *operator*, and the other elements are called *operands*. The value of a combination is obtained by applying the procedure specified by the operator to the *arguments* that are the values of the operands.
表達式親像 chiah-ê ê，就是 kā 表達式 ê 列單隔開佇括弧 (koat-hô͘, parenthesis) 內底，來標記程序 ê 應用 ê，號做組合 (combinations)。上倒手 pêng ê 號做運算子 (operator)，其他 ê 元素號做運算數 (operand)。組合 ê 值是 tuì kā 運算子指定 ê 程序，應用 kàu 引數 (argument)，就是運算數 ê 值，求出來 ê。

The convention of placing the operator to the left of the operands is known as *prefix notation*, and it may be somewhat confusing at first because it departs significantly from the customary mathematical convention. Prefix notation has several advantages, however. One of them is that it can accommodate procedures that may take an arbitrary number of arguments, as in the following examples:

Kā 運算元 khìng 佇運算數倒 pêng ê 習慣，叫做前置表示法 (chiân-tì piáu-sī-hoat, prefix notation)，頭一改看，可能會點 á 霧 sà-sà，因為明顯離開慣勢 ê 數學傳統。但是前置表示法有幾項好處。其中一个是會當容允程序接受任何數量 ê 引數，親像下 kha ê 例：

```
(+ 21 35 12 7)
75

(* 25 4 12)
1200
```

No ambiguity can arise, because the operator is always the leftmost element and the entire combination is delimited by the parentheses.
程式 bōe 含糊，因為運算子不管時攏佇上倒爿，而且 kui ê 組合是用括弧隔開。

A second advantage of prefix notation is that it extends in a straightforward way to allow combinations to be *nested*, that is, to have combinations whose elements are themselves combinations:

第二項前置表示法 ê 優勢，是用直接 ê 方式擴展，允准組合 ē 當變做「siū-á 型」(nested)，就是有元素 mā 是組合 ê 組合：

```
(+ (* 3 5) (- 10 6))
19
```

There is no limit (in principle) to the depth of such nesting and to the overall complexity of the expressions that the Lisp interpreter can evaluate. It is we humans who get confused by still relatively simple expressions such as

（原則上）無限制 siū ê 深度，Lisp ê 直譯器通算出 ê，整個表達式 ê 複雜度，mā（原則上）無制限。毋過 lán lâng mā 是會予相對簡單 ê 表達式舞 bōe 清楚，比如

```
(+ (* 3 (+ (* 2 4) (+ 3 5))) (+ (- 10 7) 6))
```

which the interpreter would readily evaluate to be 57. We can help ourselves by writing such an expression in the form

編譯器會當 kā 緊緊算值，得著 57。Lán 通幫 chān 家己，kā chit ê 表達式寫做 tsit 號形式

```
(+ (* 3
      (+ (* 2 4)
         (+ 3 5)))
   (+ (- 10 7)
      6))
```

following a formatting convention known as *pretty-printing*, in which each long combination is written so that the operands are aligned vertically. The resulting indentations display clearly the structure of the expression.[11]
用號做 *súi* 氣輸出 (pretty-printing) ê 格式化慣例，逐 ê 長 ê 組合內底 ê 運算元調整做直 ê 排列。Kiu-chōa (indentation) ê 結果清楚展示表達式 ê 結構。[12]

Even with complex expressions, the interpreter always operates in the same basic cycle: It reads an expression from the terminal, evaluates the expression, and prints the result. This mode of operation is often expressed by saying that the interpreter runs in a *read-eval-print loop*. Observe in particular that it is not necessary to explicitly instruct the interpreter to print the value of the expression.[13]

[11] Lisp systems typically provide features to aid the user in formatting expressions. Two especially useful features are one that automatically indents to the proper pretty-print position whenever a new line is started and one that highlights the matching left parenthesis whenever a right parenthesis is typed.

[12] Lisp 系統一般會提供幫 chān 用者格式化表達式 ê 功能。兩 ê 特別好用 ê 特點，一 ê 是自動 kiu-chōa kàu 適當 ê súi 氣輸出 ê 位，無論底時開新 chōa，另外 ê 是佇正 pêng ê 括弧輸入 ê 時，會明顯標出 (highlight) 對應 ê 倒 pêng ê 括弧。

[13] Lisp obeys the convention that every expression has a value. This convention, together with the old reputation of Lisp as an inefficient language, is the source of the quip by Alan Perlis (paraphrasing Oscar Wilde) that "Lisp programmers know the value of everything but the cost of nothing."

就算有複雜 ê 表達式，直譯器一直操作佇 kâng 款 ê 基本循環：tùi 終端機讀表達式，算表達式 ê 值，印出結果。Chit 款操作模式通常表達做直譯器 pháng 佇讀算印 *loop*(read-eval-print loop)。著特別觀察，明確教直譯器來印表達式 ê 值，是無必要。[14]

1.1.2 Naming and the Environment 號名 kap 環境

A critical aspect of a programming language is the means it provides for using names to refer to computational objects. We say that the name identifies a *variable* whose *value* is the object.

程式語言一个重要 ê 特徵是，伊所提供來指示運算 ê 物件 ê 方法。Lán-lâng 講名指示變數 (variable)，伊 ê值 (value) 就是物件。

In the Scheme dialect of Lisp, we name things with `define`. Typing

用 Lisp ê Scheme 方言，lán 用 `define` 號名。輸入

```
(define size 2)
```

causes the interpreter to associate the value 2 with the name `size`.[15] Once the name `size` has been associated with the number 2, we can refer to the value 2 by name:

予直譯器 kā 值 2 kap 名 `size` 關係起來。[16]名 `size` 一下 kap 數字 2 有關聯，lán 通用名指 2 chit 个值：

```
size
2
```

[14] Lisp 遵趁任何表達式 lóng 有值 ê 慣例。Chit ê 慣例，kap 以早 Lisp 是無效率 ê 語言 ê 名聲，予 Alan Perlis 講 chit 句供體 ê 話（改 tuì Oscar Wilde）：「Lisp ê 程式設計師知影逐項物 ê 值，soah 毋知 in ê 成本。」

[15] In this book, we do not show the interpreter's response to evaluating definitions, since this is highly implementation-dependent.

[16] 本冊 lán bōe 展示直譯器算定義本身 ê 值 ê 回應，因為 che kap 實做非常有關聯。

```
(* 5 size)
10
```

Here are further examples of the use of `define`:
Koh 較 chē ê 使用 `define`ê 例佇 chia：

```
(define pi 3.14159)
(define radius 10)
(* pi (* radius radius))
314.159
(define circumference (* 2 pi radius))
circumference
62.8318
```

`define` is our language's simplest means of abstraction, for it allows us to use simple names to refer to the results of compound operations, such as the `circumference` computed above. In general, computational objects may have very complex structures, and it would be extremely inconvenient to have to remember and repeat their details each time we want to use them. Indeed, complex programs are constructed by building, step by step, computational objects of increasing complexity. The interpreter makes this step-by-step program construction particularly convenient because name-object associations can be created incrementally in successive interactions. This feature encourages the incremental development and testing of programs and is largely responsible for the fact that a Lisp program usually consists of a large number of relatively simple procedures.
`define` 是 lán 語言內底上簡單 ê 抽象方法，因為伊允准 lán 用簡單 ê 名指複合操作 ê 結果，比如頂懸所計算 ê `circumference`（圓周）。一般來講，運算 ê 物件 hoân-sè 有真複雜 ê 結構，背 in，kap 當 lán beh 用 ê 時，逐擺重寫 in ê 詳細，有可能極其無方便。實際上，複雜 ê 程式是由一步一步建立運算 ê 物件，siâng 時增加複雜度，所起做。直譯器予 chit ê 一步步 ê 起做程式變特別便利，因為名—物件 ê 關聯通漸漸 á 用連 sòa ê 互動建立。Chit ê 功

能鼓勵漸漸發展 kap 試程式，mā chiâⁿ 通信任，因為 Lisp 程式常常包含大量較簡單 ê 程序。

It should be clear that the possibility of associating values with symbols and later retrieving them means that the interpreter must maintain some sort of memory that keeps track of the name-object pairs. This memory is called the *environment* (more precisely the *global environment*, since we will see later that a computation may involve a number of different environments).[17]

通清楚知影 ê 是，關聯值 kap 符號 (symbol) 了後，koh kā in tshuē 出來 ê 機會，代表直譯器著維持一款記憶體，追蹤名—物件 ê 對。Chit ê 記憶體叫做環境 (environment)（講較準就是全域環境 (global environment)）機率，因為 lán 較停 á 會看見，運算可能干涉一寡無 kâng ê 環境。[18]

1.1.3 Evaluating Combinations 算組合 ê 值

One of our goals in this chapter is to isolate issues about thinking procedurally. As a case in point, let us consider that, in evaluating combinations, the interpreter is itself following a procedure.

Lán 佇本章 ê 一个目標就是照程序分離思考 ê 議題。舉一个相關 ê 例，佇算組合 ê 值，編譯器家己 tuè 一个程序。

To evaluate a combination, do the following:

Beh 算組合 ê 值，著做下 kha ê：

1. Evaluate the subexpressions of the combination.

2. Apply the procedure that is the value of the leftmost subexpression (the operator) to the arguments that are the values of the other subexpressions (the operands).

[17] Chapter 3 will show that this notion of environment is crucial, both for understanding how the interpreter works and for implementing interpreters.

[18] 第 3 章會展示 chit ê 觀念真關鍵，無論是了解直譯器運作 ê 方法 iah 是實做直譯器。

1. 算組合 ê kiáⁿ 表達式 ê 值。

2. Kā 程序，就是上倒 pêng ê kiáⁿ 表達式 ê 值（運算子），應用 kah 引數，就是其他 kiáⁿ 表達式 ê 值（運算數）。

Even this simple rule illustrates some important points about processes in general. First, observe that the first step dictates that in order to accomplish the evaluation process for a combination we must first perform the evaluation process on each element of the combination. Thus, the evaluation rule is *recursive* in nature; that is, it includes, as one of its steps, the need to invoke the rule itself.[19]
就算 chit ê 簡單 ê 規則 mā 展示一寡關係過程 ê 一般 ê 點。Tāi 先，觀察頭一步命令，為著完成算組合 ê 值 ê 過程，lán 著代先行算組合內底每一个要素 ê 值 ê 過程。就 án-ne，算值 ê 規則自然是遞迴 (recursive) ê。He 就是，伊需要（準做伊 ê 一个手續）呼叫 chit ê 規則家己。[20]

Notice how succinctly the idea of recursion can be used to express what, in the case of a deeply nested combination, would otherwise be viewed as a rather complicated process. For example, evaluating

注意遞迴 ê 想法是 gōa-nī 簡明，佇深 ê siū-á 型組合 ê 案例，nā 無用 che，會看做不止 á 複雜 ê 過程。舉例，算下 kha ê ê 值：

```
(* (+ 2 (* 4 6))
   (+ 3 5 7))
```

[19] It may seem strange that the evaluation rule says, as part of the first step, that we should evaluate the leftmost element of a combination, since at this point that can only be an operator such as + or * representing a built-in primitive procedure such as addition or multiplication. We will see later that it is useful to be able to work with combinations whose operators are themselves compound expressions.

[20] 求值規則所講，親像第一步 ê 部份，lán 著求組合上倒 pêng ê 要素 ê 值，chit 句可能看起來怪怪，因為 chit-má kan-ta+ iah 是 * 等，代表內底有 ê 基礎程序（比如加法 iah 是乘法）ê，chiah 通當做運算子。Lán 了後會看見，nā 會當操作伊 ê 運算子是複合表達式 ê 組合，是有路用 ê。

requires that the evaluation rule be applied to four different combinations. We can obtain a picture of this process by representing the combination in the form of a tree, as shown in Figure 1.1. Each combination is represented by a node with branches corresponding to the operator and the operands of the combination stemming from it. The terminal nodes (that is, nodes with no branches stemming from them) represent either operators or numbers. Viewing evaluation in terms of the tree, we can imagine that the values of the operands percolate upward, starting from the terminal nodes and then combining at higher and higher levels. In general, we shall see that recursion is a very powerful technique for dealing with hierarchical, treelike objects. In fact, the "percolate values upward" form of the evaluation rule is an example of a general kind of process known as *tree accumulation*.
愛 kā 算值 ê 規則用佇 4 ê 無 kâng ê 組合。Lán 通得著一幅圖，顯示 hit ê 過程，靠 kā 組合用樹 á 型表示，比如Figure 1.1。逐 ê 組合用有對 kàu 運算子 ê 樹 oe ê 節點代表，末端（就是無 pun-oe ê 節點）代表運算子 iah 是數。Kā 算值看做是樹，lán 通想像運算數 ê 值滲起去，ùi 末端 ê 節點，然後佇 ná 來 ná 懸 ê 所在相結合。一般來講，lán 會看見，遞迴是非常有力 ê 技術處理階層式兼樹仔型 ê 物件。實際上，算值規則 ê「滲透 ê 值 peh 起去」ê 形式，是一般號做樹累積 (tree accumulation) ê 處理種類 ê 例。

Next, observe that the repeated application of the first step brings us to the point where we need to evaluate, not combinations, but primitive expressions such as numerals, built-in operators, or other names. We take care of the primitive cases by stipulating that
Sòa 落來，觀察重複 ê 第一步 ê 應用，致使 lán kàu 需要算值 ê 重點，毋是組合，是基礎 ê 表達式，比如數值、內底有 ê 運算子，或者是其他 ê 名。Lán 關注基礎 ê 案例，靠下 kha ê 約束：

- the values of numerals are the numbers that they name,
- the values of built-in operators are the machine instruction sequences




Figure 1.1: Tree representation, showing the value of each subcombination. 樹 ê 表示，展示逐 ê kiáⁿ 組合 ê 值。

that carry out the corresponding operations, and

- the values of other names are the objects associated with those names in the environment.

- 數值 ê 值是 in 所號 ê 數字，

- 內底有 ê 運算子 ê 值，是機器 ê 指令列，帶出對應 ê 操作，以及

- 其他名 ê 值是佇環境內底，關聯 hia ê 名 ê 物件。

We may regard the second rule as a special case of the third one by stipulating that symbols such as + and * are also included in the global environment, and are associated with the sequences of machine instructions that are their "values." The key point to notice is the role of the environment in determining the meaning of the symbols in expressions. In an interactive language such as Lisp, it is meaningless to speak of the value of an expression such as `(+ x 1)` without specifying any information about the environment that would provide a meaning for the symbol `x` (or even for the symbol +). As we shall see in Chapter 3, the general notion of the environment as providing a context in

which evaluation takes place will play an important role in our understanding of program execution.

Lán 通 kā 規則二掠做規則三 ê 特例，nā 是規定 + kap * 等符號 lóng 包佇全域 ê 環境，而且 kap 機器指令列（當做 in ê 值）相關聯。著注意 ê 關鍵點是，佇決定表達式內底 ê 符號 ê 意義內底，環境 ê 角色。佇互動 ê 語言，比如 Lisp，講表達式親像 (+ x 1) ê 值，煞無指定任何關係可能會提供符號 x（甚至是符號 +）ê 環境 ê 資訊，是無意義。親像 lán 會佇第 3 章所看見，一般來講，環境 ê 概念，就是提供佇伊內底算值 ê 頂下文，tùi 知影程式執行來講，會真重要。

Notice that the evaluation rule given above does not handle definitions. For instance, evaluating `(define x 3)` does not apply `define` to two arguments, one of which is the value of the symbol `x` and the other of which is 3, since the purpose of the `define` is precisely to associate `x` with a value. (That is, `(define x 3)` is not a combination.)

注意面頂所列 ê 算值規則，無處理定義。比如講，kā `(define x 3)` 算值，毋是應用 `define` kàu 2 ê 引數，一 ê 是符號 `x` ê 值，一 ê 是 3，因為 `define` ê 目的是，準確講是 kā `x` kap 值關聯。(就是 `(define x 3)` 毋是組合。)

Such exceptions to the general evaluation rule are called *special forms*. `define` is the only example of a special form that we have seen so far, but we will meet others shortly. Each special form has its own evaluation rule. The various kinds of expressions (each with its associated evaluation rule) constitute the syntax of the programming language. In comparison with most other programming languages, Lisp has a very simple syntax; that is, the evaluation rule for expressions can be described by a simple general rule together with specialized rules for a small number of special forms.[21]

[21] Special syntactic forms that are simply convenient alternative surface structures for things that can be written in more uniform ways are sometimes called *syntactic sugar*, to use a phrase coined by Peter Landin. In comparison with users of other languages, Lisp programmers, as

Chit 號 tùi 一般 ê 算值規則 ê 特例，叫做專門形式 (special forms)。`define` 是 lán 所見著 ê 唯一 ê 專門形式，毋過無 gōa 久會看著別 ê。任何專門形式有家己 ê 算值規則。表達式 ê chē-chē 種類（kap 伊 ê 算值規則）造就程式語言 ê 句法。kap 大部份別 ê 程式語言比較，Lisp 有非常簡單 ê 句法，就是表達式 ê 算值規則通用簡單 ê 一般規則，kap 一寡專門形式用 ê 例外規則。[22]

1.1.4 Compound Procedures 複合 ê 程序

We have identified in Lisp some of the elements that must appear in any powerful programming language:

Lán 有佇 Lisp 辨別，一寡 ài 佇任何有能力 ê 程式語言出現 ê 要素：

- Numbers and arithmetic operations are primitive data and procedures. 數字 kap 算術運算是原始 ê 資料 kap 程序。
- Nesting of combinations provides a means of combining operations. 組合 ê 岫 á 型提供結合運算 ê 方法。
- Definitions that associate names with values provide a limited means of abstraction. 關聯名稱 kap 值 ê 定義提供有限制 ê 抽象方法。

a rule, are less concerned with matters of syntax. (By contrast, examine any Pascal manual and notice how much of it is devoted to descriptions of syntax.) This disdain for syntax is due partly to the flexibility of Lisp, which makes it easy to change surface syntax, and partly to the observation that many "convenient" syntactic constructs, which make the language less uniform, end up causing more trouble than they are worth when programs become large and complex. In the words of Alan Perlis, "Syntactic sugar causes cancer of the semicolon."

[22] 有簡單方便 ê，通揀 ê 表面結構，通用 koh 較統一寫 ê 方法 ê，語法 ê 形式，有時 á 號做語法糖 (syntactic sugar)，由 Peter Landin 所號。kap 其他語言 ê 用者比較，Lisp ê 程式設計師，一般來講，較少關心語法 ê 代誌。(顛倒，nā 是調查任何 Pascal ê 手冊，通注意語法 ê 描述佔 gōa 大 ê 部份)。Chit 款輕視句法，部份因為 Lisp ê 靈活性，予伊快改表面 ê 句法，予語言較無統一，落尾致 kàu 佇程式變大 koh 複雜 ê 時，產生比利益 koh 較 chē ê 麻煩。像 Alan Perlis 所講 ê，「語法糖 á 致 kàu 分號 ê 癌症。」

- 數字 kap 算術操作是基礎資料 kap 程序。
- 組合 ê siū-á 結果提供組合操作 ê 方法
- 關聯名 kap 值 ê 定義，提供有限 ê 抽象 ê 方法。

Now we will learn about *procedure definitions*, a much more powerful abstraction technique by which a compound operation can be given a name and then referred to as a unit.
這馬 lán 欲 o̍h 一寡程序定義 (procedure definitions)ê 代誌，這是一種足有力 ê 抽象技術，會使 kā 複合 ê 操作號名，了後就會當指做一个單位。

We begin by examining how to express the idea of "squaring." We might say, "To square something, multiply it by itself." This is expressed in our language as

Lán 先來看 án-nóa 表達 "平方" ê 觀念。lán 會當講，"欲 kā 啥物平方，就是 kā 伊 kah 家己相乘。" 這 tī lán ê 語言內底寫做

```
(define (square x) (* x x))
```

We can understand this in the following way:
Lán 會當按呢來理解：

```
(define (square     x)          (*       x          x))
  |       |         |            |       |          |
 To     square  something,   multiply   it   by   itself.
欲 kā    平 方      啥 物        相 乘       伊        家 己
```

We have here a *compound procedure*, which has been given the name `square`. The procedure represents the operation of multiplying something by itself. The thing to be multiplied is given a local name, `x`, which plays the same role that a pronoun plays in natural language. Evaluating the definition creates this compound procedure and associates it with the name `square`.[23]

[23] Observe that there are two different operations being combined here: we are creating the

遮 lán 有一个 複合程序，號做 `square`。這个程序代表 ê 是 kā 啥物 kah 家己相乘 ê 操作。欲予乘 ê 物件號一个區域名 `x`，這 kah 自然語言內底 ê 代名詞扮演仝款 ê 角色。這个定義 ê 值會建立這个複合程序，而且 kā 伊 kah `square` 這个名連起來。[24]

The general form of a procedure definition is

程序定義 ê 一般形式是

```
(define (⟨name⟩ ⟨formal parameters⟩)
  ⟨body⟩)
```

The ⟨*name*⟩ is a symbol to be associated with the procedure definition in the environment.[25] The ⟨*formal parameters*⟩ are the names used within the body of the procedure to refer to the corresponding arguments of the procedure. The ⟨*body*⟩ is an expression that will yield the value of the procedure application when the formal parameters are replaced by the actual arguments to which the procedure is applied.[26] The ⟨*name*⟩ and the ⟨*formal parameters*⟩ are grouped within parentheses, just as they would be in an actual call to the procedure being defined.

⟨*name*⟩ 是一个 tī 環境內底 kah 程序定義做伙連結 ê 符號。[27] ⟨*formal parameters*⟩

---

procedure, and we are giving it the name `square`. It is possible, indeed important, to be able to separate these two notions—to create procedures without naming them, and to give names to procedures that have already been created. We will see how to do this in Section 1.3.2.

[24]注意遮有兩个無仝 ê 操作予組合做伙：lán teh 建立程序，而且 teh kā 伊號名做 `square`。會使 kā 這兩个概念分開是足重要 ê—建立一个程序無 kā 伊號名，kah kā 已建立 ê 程序號名。lán 會 tī Section 1.3.2 看著按怎做這件代誌。

[25]Throughout this book, we will describe the general syntax of expressions by using italic symbols delimited by angle brackets—e.g., ⟨*name*⟩—to denote the "slots" in the expression to be filled in when such an expression is actually used.

[26]More generally, the body of the procedure can be a sequence of expressions. In this case, the interpreter evaluates each expression in the sequence in turn and returns the value of the final expression as the value of the procedure application.

[27]Tī 這本冊內底，lán 會用予角括弧框-起來 ê chhoán 體符號—比論講 ⟨*name*⟩—來表示表達式內底 ê「空位」，會 tī 實際使用這款表達式 ê 時陣予添入。

是 tī 程序 ê 本體內底使用 ê 名，用來參考程序 ê 對應引數。⟨*body*⟩ 是一个表達式，當形式參數予實際引數替換 ê 時陣，會產生程序應用 ê 值。[28] ⟨*name*⟩ kah ⟨*formal parameters*⟩ 用括弧組做伙 ê 方式，著親像 tī 實際呼叫這个程序 ê 寫法。

Having defined `square`, we can now use it:

定義好 `square` 了後，lán 這馬會當用伊：

```
(square 21)
441
(square (+ 2 5))
49
(square (square 3))
81
```

We can also use `square` as a building block in defining other procedures. For example, $x^2 + y^2$ can be expressed as

Lán mā 會當 kā `square` 當做建構區塊來定義其他程序。比論講，$x^2 + y^2$ 會當寫做

```
(+ (square x) (square y))
```

We can easily define a procedure `sum-of-squares` that, given any two numbers as arguments, produces the sum of their squares:

Lán 會當輕鬆定義一个程序 `sum-of-squares`，予兩个數做引數 ê 時陣，會產生 in ê 平方 ê 和：

```
(define (sum-of-squares x y)
  (+ (square x) (square y)))
(sum-of-squares 3 4)
25
```

[28] 較一般來講，程序 ê 本體會當是表達式 ê 序列。Tī 這種情形，直譯器會 àn 順序算每一个表達式 ê 值，而且 kā 上尾 ê 表達式 ê 值當做程序應用 ê 值 thèh 來。

Now we can use `sum-of-squares` as a building block in constructing further procedures:

Chit-má lán 會當 kā `sum-of-squares` 當做建構區塊，來建構別項程序：

```
(define (f a)
  (sum-of-squares (+ a 1) (* a 2)))
(f 5)
136
```

Compound procedures are used in exactly the same way as primitive procedures. Indeed, one could not tell by looking at the definition of `sum-of-squares` given above whether `square` was built into the interpreter, like `+` and `*`, or defined as a compound procedure.

複合程序 kah 原始程序 ê 用法完全仝款。實際上，看頂懸寫 ê `sum-of-squares` ê 定義，講袂出 `square` 是像 `+` kah `*` 按呢寫 tī 直譯器內底，抑是一个複合程序定義。

1.1.5 The Substitution Model for Procedure Application 予程序應用 ê 取代模型

To evaluate a combination whose operator names a compound procedure, the interpreter follows much the same process as for combinations whose operators name primitive procedures, which we described in Section 1.1.3. That is, the interpreter evaluates the elements of the combination and applies the procedure (which is the value of the operator of the combination) to the arguments (which are the values of the operands of the combination).

Beh kā 運算子 ê 名表示複合程序 ê 組合算值，編譯器差不多跟 tòe lán 佇Section 1.1.3說明 ê，kā 運算子 ê 名是基礎運算符號 ê 組合算值 ê 過程 kâng 款。就是編譯器算值組合 ê 要素，應用程序（組合 ê 運算元）kàu 引數（組合 ê 運算數）。

We can assume that the mechanism for applying primitive procedures to arguments is built into the interpreter. For compound procedures, the application process is as follows:

Lán 會當想像 chit 款應用基礎程序 kàu 引數 ê 機制佇直譯器內底有收 khǹg。針對複合程序，應用 ê 過程 ná 下 kha：

> To apply a compound procedure to arguments, evaluate the body of the procedure with each formal parameter replaced by the corresponding argument.
>
> Beh 引用複合 ê 程序 kàu 因素，先 kā 程序 ê 任何正式 ê 參數用對應 ê 引數取代了後，kā 程序 ê 本體 (body) 算值。

To illustrate this process, let's evaluate the combination
為著描述 chit ê 過程，lán 做伙算值 chit ê 組合

```
(f 5)
```

where `f` is the procedure defined in Section 1.1.4. We begin by retrieving the body of `f`:
其中 `f` 是佇Section 1.1.4定義 ê 程序。Lán 開始用取得 `f`ê 本體：

```
(sum-of-squares (+ a 1) (* a 2))
```

Then we replace the formal parameter `a` by the argument 5:
Sòa 落來 lán kā 正式參數 `a` 用引數 5 替代：

```
(sum-of-squares (+ 5 1) (* 5 2))
```

Thus the problem reduces to the evaluation of a combination with two operands and an operator `sum-of-squares`. Evaluating this combination involves three subproblems. We must evaluate the operator to get the procedure to be applied, and we must evaluate the operands to get the arguments. Now `(+ 5 1)` produces 6 and `(* 5 2)` produces 10, so we must apply the `sum-`

of-squares procedure to 6 and 10. These values are substituted for the formal parameters x and y in the body of sum-of-squares, reducing the expression to
就 án-ne，問題縮小 kàu kā 有 2 ê 運算數 kap 一 ê 運算子 sum-of-squares ê 組合算值。算值 chit ê 組合干涉三 ê kiáⁿ 問題。Lán 愛算值來 thèh 著引數。Taⁿ (+ 5 1) 產出 6，(* 5 2) 產出 10，lán 一定愛應用 sum-of-squares 程序 kàu 6 kap 10。Chiah ê 值 thèh 來取代 sum-of-squares ê 本體內底 ê 正式參數 x kap y，表達式縮小 kàu

```
(+ (square 6) (square 10))
```

If we use the definition of square, this reduces to
Nā 是 lán 用 square ê 定義，che ē 縮小 kàu

```
(+ (* 6 6) (* 10 10))
```

which reduces by multiplication to
用乘法 ē 當 koh 縮小 kàu

```
(+ 36 100)
```

and finally to
落尾得著

```
136
```

The process we have just described is called the *substitution model* for procedure application. It can be taken as a model that determines the "meaning" of procedure application, insofar as the procedures in this chapter are concerned. However, there are two points that should be stressed:
Lán 所描述 ê chit ê 過程號做取代模型 (substitution model)，予程式應用使用。伊會當準做模型，決定程序應用 ê「意義」，kàu 目前 lán 所關心 ê 本章 ê 程序。毋過，chia 有兩點愛注意 ê：

- The purpose of the substitution is to help us think about procedure application, not to provide a description of how the interpreter really

works. Typical interpreters do not evaluate procedure applications by manipulating the text of a procedure to substitute values for the formal parameters. In practice, the "substitution" is accomplished by using a local environment for the formal parameters. We will discuss this more fully in Chapter 3 and Chapter 4 when we examine the implementation of an interpreter in detail.

- Over the course of this book, we will present a sequence of increasingly elaborate models of how interpreters work, culminating with a complete implementation of an interpreter and compiler in Chapter 5. The substitution model is only the first of these models—a way to get started thinking formally about the evaluation process. In general, when modeling phenomena in science and engineering, we begin with simplified, incomplete models. As we examine things in greater detail, these simple models become inadequate and must be replaced by more refined models. The substitution model is no exception. In particular, when we address in Chapter 3 the use of procedures with "mutable data," we will see that the substitution model breaks down and must be replaced by a more complicated model of procedure application.[29]

- 取代 ê 目的是幫 chān lán 想有關程序應用，毋是提供直譯器實際運作 ê 方法 ê 描述。一般 ê 直譯器無用操作程序 ê 文字來 kā 形式參數用值替代 ê 方法，kā 程序應用算值。實際上，「取代」是用表示正式 ê 參數 ê 本地環境達成。Lán 會佇第 3 章 kap 第 4 章全面討論，當 lán 詳細考察直譯器 ê 實做 ê 時。

[29] Despite the simplicity of the substitution idea, it turns out to be surprisingly complicated to give a rigorous mathematical definition of the substitution process. The problem arises from the possibility of confusion between the names used for the formal parameters of a procedure and the (possibly identical) names used in the expressions to which the procedure may be applied. Indeed, there is a long history of erroneous definitions of *substitution* in the literature of logic and programming semantics. See Stoy 1977 for a careful discussion of substitution.

- 通過本冊 ê 課程，lán 會展示增加 koh 詳細 ê，講直譯器運作方法 ê 模型，上尾 kàu 完全實做出來 ê 直譯器 kap 編譯器，佇 第 5 章。替代模型 kan-ta 是 chiah ê 模型 ê 頭一 ê——開始正式想算值過程 ê 一 ê 方法。一般來講，nā beh kā 科學 kap 工程 ê 現象起做模型，lán ê 先用簡略 ê，無完全 ê 模型開始。隨著 lán 考察代誌 koh khah 幼路，chiah ê 簡單模型變無夠用，tioh 用 khah 精巧 ê 模型取代。取代模型 mā kâng 款。特別是，若是 lán 佇第 3 章提起程序 kap「可變資料」ê 使用，lán 會看見取代模型會崩去，需要 koh khah 複雜 ê 程序應用 ê 模型。[30]

Applicative order versus normal order 應用序 vs. 正規序

According to the description of evaluation given in Section 1.1.3, the interpreter first evaluates the operator and operands and then applies the resulting procedure to the resulting arguments. This is not the only way to perform evaluation. An alternative evaluation model would not evaluate the operands until their values were needed. Instead it would first substitute operand expressions for parameters until it obtained an expression involving only primitive operators, and would then perform the evaluation. If we used this method, the evaluation of `(f 5)` would proceed according to the sequence of expansions

根據佇 Section 1.1.3 tùi 算值 ê 描述，直譯器代先算運算子 kap 運算數，了後引用結果 ê 程序 kàu 結果 ê 引數。Che 毋是算值 ê 唯一方法。另外 ê 方法是 mài 算運算數，直 kàu 有需要。伊會代先用運算數替代參數，直 kàu thèh 著 kan-ta 基礎運算子參與 ê 表達式，然後 chiah 算值。Nā 準 lán 用 chit ê 方法，`(f 5)` ê 算值，會照下 kha ê 擴展順序進行：

```
(sum-of-squares (+ 5 1) (* 5 2))
(+   (square (+ 5 1))      (square (* 5 2))  )
```

[30] 雖然取代 ê 想法 khah 簡單，提供取代過程 ê 嚴密 ê 數學定義反轉複雜 kah 予 lâng 驚。有可能因為程序 ê 正式參數 ê 名 kap（可能 chhiăng-póng ê）程序所應用 ê 表達式 ê 名分 bōe 清，chiah 會出問題。論真，佇邏輯 kap 程式語義 ê 文獻內底，出現 tuì 取代 ê 毋著 ê 定義，歷史真長。有關取代 ê 詳細討論，請看Stoy 1977。

```
(+    (* (+ 5 1) (+ 5 1))    (* (* 5 2) (* 5 2)))
```

followed by the reductions
然後 án-ne 縮小

```
(+       (* 6 6)       (* 10 10))
(+          36            100)
                136
```

This gives the same answer as our previous evaluation model, but the process is different. In particular, the evaluations of `(+ 5 1)` and `(* 5 2)` are each performed twice here, corresponding to the reduction of the expression `(* x x)` with `x` replaced respectively by `(+ 5 1)` and `(* 5 2)`.

Che mā 提供 kap 進前 ê 算值模型 kâng 款 ê 答案，但是過程無 kâng。特別是，`(+ 5 1)` kap `(* 5 2)` ê 算值佇 chia lóng 行 2 改，對應 kàu kā `(* x x)` 分別用 `(+ 5 1)` kap `(* 5 2)` 取代。

This alternative "fully expand and then reduce" evaluation method is known as *normal-order evaluation*, in contrast to the "evaluate the arguments and then apply" method that the interpreter actually uses, which is called *applicative-order evaluation*. It can be shown that, for procedure applications that can be modeled using substitution (including all the procedures in the first two chapters of this book) and that yield legitimate values, normal-order and applicative-order evaluation produce the same value. (See Exercise 1.5 for an instance of an "illegitimate" value where normal-order and applicative-order evaluation do not give the same result.)

Chit 款另外 ê「lóng thián 開 koh 縮小」ê 算值方法號做正規序算值 (normal-order evaluation)，kap「先算引數 ê 值然後應用」，chit 號直譯器實際用 ê，號做應用序算值 (applicative-order evaluation) 方法相對比。會當顯示，tùi 通用取代建立模型 ê 程序應用（包含本冊頂 2 章 ê 所有程序），kap thèh 著正當 ê 值 ê，正規序 kap 應用序 ê 算值產出 kâng 款 ê 值。（看 Exercise 1.5，內底展示「無正當」ê 值 ê 案例，用正規序 kap 應用序 ê 算值得著 ê 值無 kâng。）

Lisp uses applicative-order evaluation, partly because of the additional efficiency obtained from avoiding multiple evaluations of expressions such as those illustrated with `(+ 5 1)` and `(* 5 2)` above and, more significantly, because normal-order evaluation becomes much more complicated to deal with when we leave the realm of procedures that can be modeled by substitution. On the other hand, normal-order evaluation can be an extremely valuable tool, and we will investigate some of its implications in Chapter 3 and Chapter 4.[31]

Lisp 用應用序算值，部份因為毋免重複算比如頂懸所寫 ê `(+ 5 1)` kap `(* 5 2)` ê 表達式所加添 ê 效率，koh khah 明顯 ê 是，因為當 lán 離開通用替代建立模型 ê 程序 ê 領域 ê 時，正規序算值變做傷過複雜 oh 處理。另外一面，正規序算值會當是極其有價值 ê 家私，lán 會佇第 3 章 kap 第 4 章調查伊可能 ê 結果。[32]

1.1.6 Conditional Expressions and Predicates 條件表達式 kap 謂詞

The expressive power of the class of procedures that we can define at this point is very limited, because we have no way to make tests and to perform different operations depending on the result of a test. For instance, we cannot define a procedure that computes the absolute value of a number by testing whether the number is positive, negative, or zero and taking different actions in the different cases according to the rule Kàu 這馬為止，lán 會當定義 ê 程序種類，表達力真有限，因為 lán 無法度做測試，也無法度照試驗結果來執行無仝 ê 運算。比論講，lán 無法度定義一个程序，憑數是正數、負數抑是零，

[31] In Chapter 3 we will introduce *stream processing*, which is a way of handling apparently "infinite" data structures by incorporating a limited form of normal-order evaluation. In Section 4.2 we will modify the Scheme interpreter to produce a normal-order variant of Scheme.

[32] 佇第 3 章 lán 會紹介 流處理 (stream processing)，是一種用 kā 有限形式 ê 正規序算值 ê 包入去，處理明顯是「無限」ê 資料結構 ê 方法。佇Section 4.2，lán 會改 Scheme ê 直譯器，來做出 Scheme ê 正規序變種。

做無仝 ê 反應，算出絕對值。

$$|x| = \begin{cases} x & \text{if} \quad x > 0, \\ 0 & \text{if} \quad x = 0, \\ -x & \text{if} \quad x < 0. \end{cases}$$

This construct is called a *case analysis*, and there is a special form in Lisp for notating such a case analysis. It is called `cond` (which stands for "conditional"), and it is used as follows: 這个構造號做 案例分析，Lisp 有一个專門形式來表示這個功能。伊號做 `cond`（是 "conditional" 條件 ê 意思），用法如下：

```
(define (abs x)
  (cond ((> x 0) x)
        ((= x 0) 0)
        ((< x 0) (- x))))
```

The general form of a conditional expression is 條件表達式 ê 一般形式如下：

```
(cond (⟨p1⟩ ⟨e1⟩)
      (⟨p2⟩ ⟨e2⟩)
      ...
      (⟨pn⟩ ⟨en⟩))
```

consisting of the symbol `cond` followed by parenthesized pairs of expressions 由符號 `cond` kah 幾若 ê 用一對括弧箍起來 ê 表達式組成

```
(⟨p⟩ ⟨e⟩)
```

called *clauses*. The first expression in each pair is a *predicate*—that is, an expression whose value is interpreted as either true or false.[33] 號做 子句

[33] "Interpreted as either true or false" means this: In Scheme, there are two distinguished values that are denoted by the constants `#t` and `#f`. When the interpreter checks a predicate's value, it interprets `#f` as false. Any other value is treated as true. (Thus, providing `#t` is logically unnecessary, but it is convenient.) In this book we will use names `true` and `false`, which are associated with the values `#t` and `#f` respectively.

(clause)。逐个子句內底第一 ê 表達式號做 謂詞 (predicate)—也就是講，表達式 ê 值 ê 解釋若毋是真就是假。[34]

Conditional expressions are evaluated as follows. The predicate $\langle p_1 \rangle$ is evaluated first. If its value is false, then $\langle p_2 \rangle$ is evaluated. If $\langle p_2 \rangle$'s value is also false, then $\langle p_3 \rangle$ is evaluated. This process continues until a predicate is found whose value is true, in which case the interpreter returns the value of the corresponding *consequent expression* $\langle e \rangle$ of the clause as the value of the conditional expression. If none of the $\langle p \rangle$'s is found to be true, the value of the `cond` is undefined. 條件表達式 ê 算值方式如下。先算謂詞 $\langle p_1 \rangle$。若伊 ê 值是假，就算 $\langle p_2 \rangle$。若 $\langle p_2 \rangle$ ê 值 mā 是假，就算 $\langle p_3 \rangle$。這个過程會試到謂詞 ê 值是真為止，這个時陣，直譯器會 kā 對應 ê 子句內底 ê 結果表達式 (consequent expression) $\langle e \rangle$ ê 值當做條件表達式 ê 值 thèh 來。若逐个 $\langle p \rangle$ lóng 是假，`cond` ê 值就無定義。

The word *predicate* is used for procedures that return true or false, as well as for expressions that evaluate to true or false. The absolute-value procedure `abs` makes use of the primitive predicates >, <, and =.[35] These take two numbers as arguments and test whether the first number is, respectively, greater than, less than, or equal to the second number, returning true or false accordingly. 謂詞 (predicate) chit 个詞，用來指結果是真抑是假 ê 程序，mā 用來指算值是真抑是假 ê 表達式。絕對值程序 `abs` 有使用原始謂詞 >、< kah =。[36] 伊接受兩个數字做引數，測試頭一个數字是毋是分別大過、小過抑是等於第二个數字，照值 thèh 來。

---

[34]"若毋是真就是假" ê 意思是：Scheme 有兩个無仝款 ê 值，予常數 `#t` kah `#f` 代表。當直譯器檢查謂詞 ê 值 ê 時陣，`#f` 解釋做假，其他 lóng 解釋做真。(所以，提供 `#t` 佇邏輯上是無必要 ê，但是較方便。) 佇這本冊內底，lán 會用名 `true` kah `false`，分別表示值 `#t` kah `#f`。

[35] `abs` also uses the "minus" operator −, which, when used with a single operand, as in `(- x)`, indicates negation.

[36] `abs` mā 有使用「減」運算子 −，當伊只用一个運算數 ê 時陣，像 `(- x)`，表示「0 - x」。

Another way to write the absolute-value procedure is 絕對值程序 ê 另外一種寫法是

```
(define (abs x)
  (cond ((< x 0) (- x))
        (else x)))
```

which could be expressed in English as "If x is less than zero return $-x$; otherwise return x." `else` is a special symbol that can be used in place of the ⟨p⟩ in the final clause of a `cond`. This causes the `cond` to return as its value the value of the corresponding ⟨e⟩ whenever all previous clauses have been bypassed. In fact, any expression that always evaluates to a true value could be used as the ⟨p⟩ here. 口頭會使講做「若 x 小過零就 kā $-x$ thèh 來；無就 kā x thèh 來。」`else` 是專門符號，用佇 `cond` ê 上尾子句內底來代替 ⟨p⟩。這會予 `cond` 佇頭前逐个子句 lóng 無滿足 ê 時陣，kā 後項 ê ⟨e⟩ ê 值 thèh 來。實際上，任何值是真 ê 表達式 lóng 會使用做遮 ê ⟨p⟩。

Here is yet another way to write the absolute-value procedure: 這是絕對值程序 ê 又閣一種寫法是

```
(define (abs x)
  (if (< x 0)
      (- x)
      x))
```

This uses the special form `if`, a restricted type of conditional that can be used when there are precisely two cases in the case analysis. The general form of an `if` expression is Chit ê 有使用專門形式 `if`，是有限制 ê 案例分析，只有兩个案例 ê 時陣會使使用。`if` 表達式 ê 一般形式是

(**if** ⟨*predicate*⟩ ⟨*consequent*⟩ ⟨*alternative*⟩)

To evaluate an `if` expression, the interpreter starts by evaluating the ⟨*predicate*⟩ part of the expression. If the ⟨*predicate*⟩ evaluates to a true value, the interpreter then evaluates the ⟨*consequent*⟩ and returns its value. Otherwise it

evaluates the ⟨*alternative*⟩ and returns its value.[37] 算 `if` 表達式，直譯器先算表達式內底 ê ⟨*predicate*⟩ 部分。若 ⟨*predicate*⟩ ê 值是真，直譯器就算 ⟨*consequent*⟩ kah kā 伊 ê 值 thèh 來。無，就算 ⟨*alternative*⟩ kah kā 伊 ê 值 thèh 來。[38]

In addition to primitive predicates such as <, =, and >, there are logical composition operations, which enable us to construct compound predicates. The three most frequently used are these: <、=、kah > 這款原始謂詞掠外，嘛有邏輯組合運算，予 lán 會當建構複合謂詞。上定用 ê 三个是:

- `(and` ⟨e_1⟩ `...` ⟨e_n⟩`)`

  The interpreter evaluates the expressions ⟨e⟩ one at a time, in left-to-right order. If any ⟨e⟩ evaluates to false, the value of the `and` expression is false, and the rest of the ⟨e⟩'s are not evaluated. If all ⟨e⟩'s evaluate to true values, the value of the `and` expression is the value of the last one. 直譯器會一个一个算遮 ê 表達式 ⟨e⟩ ê 值，照倒爿到正爿 ê 排列。若有任何一个 ⟨e⟩ 算值是假，`and` 表達式 ê 值就是假，而且賭 ê ⟨e⟩ 就袂 koh 算啊。若所有 ê ⟨e⟩ lóng 算值是真，`and` 表達式 ê 值就是上尾彼个表達式 ê 值。

- `(or` ⟨e_1⟩ `...` ⟨e_n⟩`)`

  The interpreter evaluates the expressions ⟨e⟩ one at a time, in left-to-right order. If any ⟨e⟩ evaluates to a true value, that value is returned

[37] A minor difference between `if` and `cond` is that the ⟨e⟩ part of each `cond` clause may be a sequence of expressions. If the corresponding ⟨p⟩ is found to be true, the expressions ⟨e⟩ are evaluated in sequence and the value of the final expression in the sequence is returned as the value of the `cond`. In an `if` expression, however, the ⟨*consequent*⟩ and ⟨*alternative*⟩ must be single expressions.

[38] `if` kah `cond` ê 小差別是，逐个 `cond` 子句內底 ê ⟨e⟩ 部分會使是表達式 ê 序列。若對應 ê ⟨p⟩ 是真，表達式 ⟨e⟩ 會照排列算值，kā 上尾 hit 个表達式 ê 值當做 `cond` ê 值 thèh 來。但是佇 `if` 表達式內底，⟨*consequent*⟩ kah ⟨*alternative*⟩ 一定愛是一个表達式。

as the value of the `or` expression, and the rest of the $\langle e \rangle$'s are not evaluated. If all $\langle e \rangle$'s evaluate to false, the value of the `or` expression is false. 直譯器會一个一个算遮 ê 表達式 $\langle e \rangle$ ê 值，照倒爿到正爿 ê 排列。若有任何一个 $\langle e \rangle$ 算值是真，就 kah 伊 ê 值 thèh 來，賭 ê $\langle e \rangle$ 就袂 koh 算啊。若所有 ê $\langle e \rangle$ lóng 算值是假，`or` 表達式 ê 值就是假。

- `(not` $\langle e \rangle$`)`

  The value of a `not` expression is true when the expression $\langle e \rangle$ evaluates to false, and false otherwise. `not` 表達式 ê 值，當表達式 $\langle e \rangle$ 算值是假 ê 時是真，若無就是假。

Notice that `and` and `or` are special forms, not procedures, because the subexpressions are not necessarily all evaluated. `not` is an ordinary procedure. 注意 `and` kah `or` 是專門形式，毋是程序，因為囝表達式無一定愛全部算出來。`not` 是一般 ê 程序。

As an example of how these are used, the condition that a number x be in the range $5 < x < 10$ may be expressed as 舉例來講，數字 x tī 範圍 $5 < x < 10$ 內 ê 條件會當表達做

```
(and (> x 5) (< x 10))
```

As another example, we can define a predicate to test whether one number is greater than or equal to another as 又閣有，lán 會當定義一个謂詞來試一个數字是毋是大於抑是等於別个數字

```
(define (>= x y) (or (> x y) (= x y)))
```

or alternatively as 抑是

```
(define (>= x y) (not (< x y)))
```

Exercise 1.1: Below is a sequence of expressions. What is the result printed by the interpreter in response to each expression?

Assume that the sequence is to be evaluated in the order in which it is presented. 下底是一寡表達式。逐个表達式 ê 直譯器印出結果是啥物？準做這个序列照呈現 ê 排列來算值。

```
10
(+ 5 3 4)
(- 9 1)
(/ 6 2)
(+ (* 2 4) (- 4 6))
(define a 3)
(define b (+ a 1))
(+ a b (* a b))
(= a b)
(if (and (> b a) (< b (* a b)))
    b
    a)

(cond ((= a 4) 6)
      ((= b 4) (+ 6 7 a))
      (else 25))

(+ 2 (if (> b a) b a))

(* (cond ((> a b) a)
         ((< a b) b)
         (else -1))
   (+ a 1))
```

Exercise 1.2: Translate the following expression into prefix form: Kā 下底 ê 表達式寫做前置形式：

$$\frac{5+4+(2-(3-(6+\frac{4}{5})))}{3(6-2)(2-7)}.$$

Exercise 1.3: Define a procedure that takes three numbers as arguments and returns the sum of the squares of the two larger numbers. 定義一个程序，接受三个數字做引數，kah 較大 ê 兩个數 ê 平方和傳轉來。

Exercise 1.4: Observe that our model of evaluation allows for combinations whose operators are compound expressions. Use this observation to describe the behavior of the following procedure: 注意 lán ê 算值模型允許運算子是複合表達式 ê 組合。用這个觀察來描述下底 ê 程序 ê 行為：

```
(define (a-plus-abs-b a b)
  ((if (> b 0) + -) a b))
```

Exercise 1.5: Ben Bitdiddle has invented a test to determine whether the interpreter he is faced with is using applicative-order evaluation or normal-order evaluation. He defines the following two procedures: 阿班 (Ben Bitdiddle) 發明一个測試來判斷伊用 ê 直譯器是用應用序（applicative-order）算值抑是正規序（normal-order）算值。伊定義下底兩个程序：

```
(define (p) (p))
(define (test x y)
  (if (= x 0) 0 y))
```

Then he evaluates the expression

```
(test 0 (p))
```

What behavior will Ben observe with an interpreter that uses applicative-order evaluation? What behavior will he observe with an interpreter that uses normal-order evaluation? Explain your answer. (Assume that the evaluation rule for the special

form `if` is the same whether the interpreter is using normal or applicative order: The predicate expression is evaluated first, and the result determines whether to evaluate the consequent or the alternative expression.) 阿班用一个應用序算值 ê 直譯器會看著啥物行為？若是用一个正規序算值 ê 直譯器會看著啥物行為？解說汝 ê 答案。(準做專門形式 `if` ê 規則，無論直譯器是用正規序抑是應用序 lóng 仝款：謂詞表達式先算，閣有伊 ê 結果決定是 ài 算後件抑是算替代表達式。)

1.1.7 Example: Square Roots by Newton's Method 例：用 Newton 法算平方根

Procedures, as introduced above, are much like ordinary mathematical functions. They specify a value that is determined by one or more parameters. But there is an important difference between mathematical functions and computer procedures. Procedures must be effective.

程序親像頂懸紹介 ê，足 sêng 一般 ê 數學函數。In 指定一个值，由一个以上 ê 參數決定。毋過數學 ê 函數 kap 電腦 ê 程序有重要 ê 無 kâng。程序愛有效率。

As a case in point, consider the problem of computing square roots. We can define the square-root function as

舉一个例，考慮算平方根 ê 問題。Lán 通定義平方根函數做

$$\sqrt{x} \;=\; \text{the } y \text{ such that } y \geq 0 \text{ and } y^2 = x.$$

This describes a perfectly legitimate mathematical function. We could use it to recognize whether one number is the square root of another, or to derive facts about square roots in general. On the other hand, the definition does not describe a procedure. Indeed, it tells us almost nothing about how to actually find the square root of a given number. It will not help matters to

rephrase this definition in pseudo-Lisp:

Che 定義完美 koh 有效 ê 數學函數。Lán 會當用 che 辨別一个數敢是別个數 ê 平方根，á 是推論關係平方根 ê 一般事實。另外方面，定義 bōe 當描述程序。確實，伊強強無講任何 chhōe 一个數 ê 平方根 ê 方法。共定義用假 Lisp 碼寫 mā 無幫 chān：

```
(define (sqrt x)
  (the y (and (>= y 0)
              (= (square y) x))))
```

This only begs the question.

Che kan-ta 求乞問題。

The contrast between function and procedure is a reflection of the general distinction between describing properties of things and describing how to do things, or, as it is sometimes referred to, the distinction between declarative knowledge and imperative knowledge. In mathematics we are usually concerned with declarative (what is) descriptions, whereas in computer science we are usually concerned with imperative (how to) descriptions.[39]

函數 kap 程序 ê 對比是一般佇描述代誌 ê 性質 kap 按怎做 ê 方法之間 ê 區別 ê 反映。或者親像有時 á 所指 ê，宣告式智識 kap 命令式智識之間 ê 區別。

[39] Declarative and imperative descriptions are intimately related, as indeed are mathematics and computer science. For instance, to say that the answer produced by a program is "correct" is to make a declarative statement about the program. There is a large amount of research aimed at establishing techniques for proving that programs are correct, and much of the technical difficulty of this subject has to do with negotiating the transition between imperative statements (from which programs are constructed) and declarative statements (which can be used to deduce things). In a related vein, an important current area in programming-language design is the exploration of so-called very high-level languages, in which one actually programs in terms of declarative statements. The idea is to make interpreters sophisticated enough so that, given "what is" knowledge specified by the programmer, they can generate "how to" knowledge automatically. This cannot be done in general, but there are important areas where progress has been made. We shall revisit this idea in Chapter 4.

佇數學 lán 定定關注有宣告式（是啥物）描述 ê 智識，毋過佇電腦科學 lán 定定關心命令式（按 nóa 做）ê 描述。[40]

How does one compute square roots? The most common way is to use Newton's method of successive approximations, which says that whenever we have a guess y for the value of the square root of a number x, we can perform a simple manipulation to get a better guess (one closer to the actual square root) by averaging y with x/y.[41] For example, we can compute the square root of 2 as follows. Suppose our initial guess is 1:

按 nóa 算平方根？上 chiàp 用 ê 方法是，用相連 sòa 近似 ê Newton 法，講不管時 lán ioh x ê 平方根是 y，lán 通行基本操作，來 thèh 著較好 ê ioh ê 值（較近倚實際 ê 平方根），就是算 y kap x/y ê 平均。[42] 比如，lán 通計算 2 ê 平方根 ná 下 kha。設使 lán 原起頭所 ioh ê 是 1:

```
所 ioh          商 數                          平 均
1               (2/1) = 2                      ((2 + 1)/2) = 1.5
1.5             (2/1.5) = 1.3333               ((1.3333 + 1.5)/2) = 1.4167
1.4167          (2/1.4167) = 1.4118            ((1.4167 + 1.4118)/2) = 1.414
1.4142          ...                            ...
```

[40]宣告式 kap 命令式描述 ê 關係密密密，親像數學 kap 電腦科學 ê，確實仝款。比如講，講程式產出 ê 答案「正確」，就是寫一个關係程式 ê 宣告式 ê 陳述。有有夠 chē 研究協助佇成立證明程式正確 ê 技術，chit ê 主題 ê 技術困難，chē-chē 是佇應對命令式陳述（程式 tùi che 建構）kap 宣告式陳述（會當演繹物件）中間 ê 變換。Mā siâng 款，一个現 chú 時佇程式語言設計內底重要 ê 所在是，所謂 ê 蓋懸階 ê 語言 ê 研究，用 chit 款語言，lâng 實際用描述式 ê 陳述寫程式。Chit ê 想法是予直譯器有夠額 ê 經驗，佇 thèh 著程式設計師指定 ê「是啥物」ê 智識了後，會當自動產出「按 nóa 做」ê 智識。一般 bōe 當完成，但是有重要 ê 有進步 ê 所在。Lán 會佇第 4 章 koh 探討 chit ê 想法。

[41]This square-root algorithm is actually a special case of Newton's method, which is a general technique for finding roots of equations. The square-root algorithm itself was developed by Heron of Alexandria in the first century A.D. We will see how to express the general Newton's method as a Lisp procedure in Section 1.3.4.

[42]Chit ê 平方根演算法實際上是 Newton 法 ê 特例，he 是用來 chhōe 方程式 ê 根 ê 一般技術。Chit ê 平方根演算法是由亞歷山大城 ê Heron 佇西元一世紀所發展。Lán 會佇Section 1.3.4 看著按 nóa kā 一般 ê Newton 法表達做 Lisp 程序。

Continuing this process, we obtain better and better approximations to the square root.
繼續 chit ê 過程，lán 得著愈來愈好 ê 平方根 ê 近似。

Now let's formalize the process in terms of procedures. We start with a value for the radicand (the number whose square root we are trying to compute) and a value for the guess. If the guess is good enough for our purposes, we are done; if not, we must repeat the process with an improved guess. We write this basic strategy as a procedure:

Chit-má lán 著用程序形式化 chit ê 過程。Lán 開始用一个值當做受平方數（radicand，lán beh 算 chit ê 數 ê 平方根），kap 一个當做所 ioh ê 值。若是所 ioh ê 好 kah 合 lán ê 目的，就完成；ah 無，lán 愛用改進 ê 所 ioh，來重複 chit ê 過程。Lán kā chit ê 基礎策略寫做程序：

```
(define (sqrt-iter guess x)
  (if (good-enough? guess x)
      guess
      (sqrt-iter (improve guess x) x)))
```

A guess is improved by averaging it with the quotient of the radicand and the old guess:
所 ioh 是由平均伊以及「受平方數 kap 早前 ioh ê」ê 商數所改善：

```
(define (improve guess x)
  (average guess (/ x guess)))
```

where
其中

```
(define (average x y)
  (/ (+ x y) 2))
```

We also have to say what we mean by "good enough." The following will do for illustration, but it is not really a very good test. (See Exercise 1.7.) The

idea is to improve the answer until it is close enough so that its square differs from the radicand by less than a predetermined tolerance (here 0.001):[43]
Lán mā 定著愛講「有夠好」指 ê 是 siáⁿ。下 kha 會做說明，但是毋是真正 ê 好試驗（請看Exercise 1.7。）Chit ê 想法是改善答案，直到伊有夠接近，致 kàu 伊 ê 平方 kap 受平方數 ê 差，無夠進前指定 ê 誤差（chia 是 0.001）：[44]

```
(define (good-enough? guess x)
  (< (abs (- (square guess) x)) 0.001))
```

Finally, we need a way to get started. For instance, we can always guess that the square root of any number is 1:[45]
尾 á，lán 需要一个開始 ê 方法。比如，lán 通一直 ioh 講任何數 ê 平方根是 1：[46]

[43] We will usually give predicates names ending with question marks, to help us remember that they are predicates. This is just a stylistic convention. As far as the interpreter is concerned, the question mark is just an ordinary character.

[44] Lán 會定定 kā 謂詞 ê 名用問號? 收 soah，來幫 chān lán 記得 in 是謂詞。Tùi 直譯器來講，問號是一般 ê 字元 nā 定。

[45] Observe that we express our initial guess as 1.0 rather than 1. This would not make any difference in many Lisp implementations. MIT Scheme, however, distinguishes between exact integers and decimal values, and dividing two integers produces a rational number rather than a decimal. For example, dividing 10 by 6 yields 5/3, while dividing 10.0 by 6.0 yields 1.6666666666666667. (We will learn how to implement arithmetic on rational numbers in Section 2.1.1.) If we start with an initial guess of 1 in our square-root program, and x is an exact integer, all subsequent values produced in the square-root computation will be rational numbers rather than decimals. Mixed operations on rational numbers and decimals always yield decimals, so starting with an initial guess of 1.0 forces all subsequent values to be decimals.

[46] 請觀察 lán 表達 lán 原起頭所 ioh ê 是 1.0 毋是 1，che 佇 chē-chē Lisp ê 實做內底 lóng 無差。但是 MIT Scheme 區別準確 ê 整數 kap 十進位小數 ê 值，兩 ê 整數相除產出有理數，毋是十進位小數。比如講，10 用 6 除 thèh 著 5/3，毋過 10.0 用 6.0 除 thèh 著 1.6666666666666667（Lán ê 佇Section 2.1.1學按 nóa 實做有理數 ê 算術）Nā lán 開始佇 lán ê 平方根程式，用 1 做起頭所 ioh ê 值，x 是精確 ê 整數，所有佇平方根演算所出 ê 相 sòa ê 值會是有理數毋是小數。因為 kā 有理數 kap 十進位小數濫 leh 運算會一直得著十進位小數，所以開始 kā 1.0 掠做起頭所 ioh ê 值，會強制予相 sòa ê 值變做十進位小數。

```
(define (sqrt x)
  (sqrt-iter 1.0 x))
```

If we type these definitions to the interpreter, we can use `sqrt` just as we can use any procedure:
Nā 是 lán phah chiah-ê 定義 kàu 直譯器，lán 通用 `sqrt` 親像 lán 用任何程序：

```
(sqrt 9)
3.00009155413138

(sqrt (+ 100 37))
11.704699917758145

(sqrt (+ (sqrt 2) (sqrt 3)))
1.7739279023207892

(square (sqrt 1000))
1000.000369924366
```

The `sqrt` program also illustrates that the simple procedural language we have introduced so far is sufficient for writing any purely numerical program that one could write in, say, C or Pascal. This might seem surprising, since we have not included in our language any iterative (looping) constructs that direct the computer to do something over and over again. `sqrt-iter`, on the other hand, demonstrates how iteration can be accomplished using no special construct other than the ordinary ability to call a procedure.[47]
`sqrt` 程式 mā 解說 lán 目前為止所紹介 ê 簡單 ê 程序式語言，tùi 寫任何會當佇 C iah 是 Pascal 寫 ê 純 ê 數值程式是真夠額。Che 可能通驚著儂，因為 lán 無佇 lán ê 語言包含任何直接指導電腦做代誌幾 nā 擺 ê 反覆 (loop) 建構。

[47] Readers who are worried about the efficiency issues involved in using procedure calls to implement iteration should note the remarks on "tail recursion" in Section 1.2.1.

另外方面，`sqrt-iter`，展示反覆通按 nóa kan-ta 用叫函數 ê 一般能力，無用其他特殊 ê 構造，來完成。[48]

Exercise 1.6: Alyssa P. Hacker doesn't see why `if` needs to be provided as a special form. "Why can't I just define it as an ordinary procedure in terms of `cond`?" she asks. Alyssa's friend Eva Lu Ator claims this can indeed be done, and she defines a new version of `if`:

Exercise 1.6: Alyssa P. Hacker 看無 siáⁿ 事 `if` 需要用專門形式提供。伊問：「是按 nóa 我 bōe 當 kan-ta 用 `cond`，親像一般 ê 程序 kā 定義？」In 朋友 Eva Lu Ator 主張 che 當然會當做，koh 定義新版 ê `if`：

```
(define (new-if predicate then-clause else-clause)
  (cond (predicate then-clause)
        (else else-clause)))
```

Eva demonstrates the program for Alyssa:

Eva kā Elyssa 展示 chit ê 程序：

```
(new-if (= 2 3) 0 5)
5
(new-if (= 1 1) 0 5)
0
```

Delighted, Alyssa uses `new-if` to rewrite the square-root program:

Alyssa 真歡喜，就用 `new-if` 重寫平方根 ê 程式：

[48] 煩惱用叫程序來實做反覆，會有效率問題 ê 讀者，應該佇Section 1.2.1注意「尾遞迴」ê 重點。

```
(define (sqrt-iter guess x)
  (new-if (good-enough? guess x)
          guess
          (sqrt-iter (improve guess x) x)))
```

What happens when Alyssa attempts to use this to compute square roots? Explain.

若是 Alyssa 用 che 算平方根，會出 siáⁿ 代誌？請解說。

Exercise 1.7: The `good-enough?` test used in computing square roots will not be very effective for finding the square roots of very small numbers. Also, in real computers, arithmetic operations are almost always performed with limited precision. This makes our test inadequate for very large numbers. Explain these statements, with examples showing how the test fails for small and large numbers. An alternative strategy for implementing `good-enough?` is to watch how `guess` changes from one iteration to the next and to stop when the change is a very small fraction of the guess. Design a square-root procedure that uses this kind of end test. Does this work better for small and large numbers?

Exercise 1.7: `good-enough?` 測試用佇算平方根，tùi 算蓋細 ê 數字 ê 來講，無真有效率。而且，佇真實 ê 電腦，算術運算差不多攏佇有限精度進行。Che 予 lán ê 測試 tùi 非常大 ê 數字來講無適合。解說 chiah ê 陳述，用例展示是按 nóa 數字傷大 iah 是傷細 ê 時測試會失敗。別款實作 `good-enough?` 策略，是觀察所 ioh ê 值 tuì 頂一个 kàu 下一个反覆之間 ê 差，nā 是差 kap 所 ioh ê 值 ê 比例誠細，就停止反覆。設計一款用 che 測試 ê 平方根程序。Che kám kā 細 ê 數字 kap 大 ê，處理 kah koh khah 好？

Exercise 1.8: Newton's method for cube roots is based on the fact that if y is an approximation to the cube root of x, then a better approximation is given by the value

Exercise 1.8: 立方根 ê Newton 法是 chhāi 佇 chit ê 事實：nā 準 y 是 x ê 立方根 ê 近似值，較好 ê 近似當用 che the̍h 著：

$$\frac{x/y^2 + 2y}{3}.$$

Use this formula to implement a cube-root procedure analogous to the square-root procedure. (In Section 1.3.4 we will see how to implement Newton's method in general as an abstraction of these square-root and cube-root procedures.)

用 chit ê 公式實做立方根程序，kap 平方根程序相 siâng。(佇 Section 1.3.4 lán 會看著按 nóa 實做 Newton 法 ê 一般化 ê 形式，當做 chiah-ê 平方根 kap 立方根程序 ê 抽象化。)

1.1.8 Procedures as Black-Box Abstractions 程序當做烏盒仔 ê 抽象

`sqrt` is our first example of a process defined by a set of mutually defined procedures. Notice that the definition of `sqrt-iter` is *recursive*; that is, the procedure is defined in terms of itself. The idea of being able to define a procedure in terms of itself may be disturbing; it may seem unclear how such a "circular" definition could make sense at all, much less specify a well-defined process to be carried out by a computer. This will be addressed more carefully in Section 1.2. But first let's consider some other important points illustrated by the `sqrt` example.

`sqrt` 是 lán ê 頭一个用相定義 ê 程序 ê 集合定義 ê 過程 ê 例。注意 `sqrt-iter` ê 定義是遞迴 (recursive) ê；就是，程序用伊家己定義。通用程序家己定義程序 chit ê 想法可能真煩；Hit 款「圓箍型 ê」定義會當合理 ê 方




Figure 1.2: Procedural decomposition of the `sqrt` program.
`sqrt` 程式 ê 程序分解

法可能霧霧無明，mā 毋免講電腦所運轉 ê 好好定義 ê 過程。Che 會佇 Section 1.2 斟酌提起。但是代先 lán 看一寡其他 `sqrt` 案例說明 ê 重點。

Observe that the problem of computing square roots breaks up naturally into a number of subproblems: how to tell whether a guess is good enough, how to improve a guess, and so on. Each of these tasks is accomplished by a separate procedure. The entire `sqrt` program can be viewed as a cluster of procedures (shown in Figure 1.2) that mirrors the decomposition of the problem into subproblems.

觀察計算平方根 ê 問題自然拆做一寡 kiáⁿ 問題：按 nóa 講一个所 ioh ê 有夠好，按 nóa 改善所 ioh ê，等等。其中 ê 逐 ê 任務是由分離 ê 程序完成（展示佇Figure 1.2）反映問題拆做 kiáⁿ 問題：

The importance of this decomposition strategy is not simply that one is dividing the program into parts. After all, we could take any large program and divide it into parts—the first ten lines, the next ten lines, the next ten lines, and so on. Rather, it is crucial that each procedure accomplishes an identifiable task that can be used as a module in defining other procedures. For example, when we define the `good-enough?` procedure in terms of `square`, we are able to regard the `square` procedure as a "black box." We are not at that moment concerned with *how* the procedure computes its result, only with the fact that it computes the square. The details of how the square

is computed can be suppressed, to be considered at a later time. Indeed, as far as the `good-enough?` procedure is concerned, `square` is not quite a procedure but rather an abstraction of a procedure, a so-called *procedural abstraction*. At this level of abstraction, any procedure that computes the square is equally good.

分解策略 ê 重要 m̄-nā 是 kā 程式簡單分做部份。總是，lán 會當 kā 任何 sài-suh ê 程式切做幾 nā 部份—頭前 10 chōa、後 10 chōa、後 10 chōa 等等。顛倒上重要是，逐 ê 程序完成唯一 ê，ē 當佇定義其他 ê 程序 ê 內底，準做 module ê 任務。舉例，當 lán 用 `square` 定義 `good-enough?` ê 時陣，lán 通 kā `square` 掠做「烏盒 á」。佇 chit 時 lán 無關心 chit ê 程序「按 nóa」算結果，kan-ta 關心伊算平方 ê 事實。平方按 nóa 算 ê 詳細通 khàm 掉，以後 koh 考慮。確實，tùi `good-enough?` 程序來講，`square` 毋是程序，反轉是程序 ê 抽象，所謂 ê 程序抽象化 (procedural abstraction)。佇 chit 層抽象，任何算平方 ê 程序 lóng 平好。

Thus, considering only the values they return, the following two procedures for squaring a number should be indistinguishable. Each takes a numerical argument and produces the square of that number as the value.[49]

就 án-ne，kan-ta 考慮傳轉來 ê 值，下 kha ê 兩 ê kā 一个數平方 ê 程序應該無差別。逐 ê thèh 一个數值引數，產出 ê 值是 chit ê 數 ê 平方。[50]

```
(define (square x) (* x x))
(define (square x) (exp (double (log x))))
(define (double x) (+ x x))
```

[49] It is not even clear which of these procedures is a more efficient implementation. This depends upon the hardware available. There are machines for which the "obvious" implementation is the less efficient one. Consider a machine that has extensive tables of logarithms and antilogarithms stored in a very efficient manner.

[50] 甚至 iah 無清楚佗一个是 khah 有效率 ê。Che 倚靠會當用 ê 硬體。有對伊來講，上「明顯」ê 實做是 khah 無效率 ê 機器。想像 chit 臺機器，伊有大張 ê 對數表 kap 反對數表，用誠有效率 ê 方法儲存。

So a procedure definition should be able to suppress detail. The users of the procedure may not have written the procedure themselves, but may have obtained it from another programmer as a black box. A user should not need to know how the procedure is implemented in order to use it.

所以，程序 ê 定義應該通 kā 詳細 teh 牢。程序用者可能無家己寫，毋過通 tùi 別 ê 程式設計師收著 che，當做烏盒 á。用者無應該需要知影程序按怎實做，chiah 通用。

Local names 區域變數

One detail of a procedure's implementation that should not matter to the user of the procedure is the implementer's choice of names for the procedure's formal parameters. Thus, the following procedures should not be distinguishable:

程序有一个無應該 kap 伊 ê 用者有交插 ê 實做詳細，是實做 ê kā 程序 ê 正式參數按 nóa 號名。就 án-ne，下 kha 兩 ê 程序無應該有差別：

```
(define (square x) (* x x))
(define (square y) (* y y))
```

This principle—that the meaning of a procedure should be independent of the parameter names used by its author—seems on the surface to be self-evident, but its consequences are profound. The simplest consequence is that the parameter names of a procedure must be local to the body of the procedure. For example, we used `square` in the definition of `good-enough?` in our square-root procedure:

Chit ê 原則——程序 ê 意義應該 kap 伊 ê 作者所號 ê 名獨立——假若佇外表上，通家己做證，毋過伊 ê 結果，影響誠深。上簡單 ê 結果是，參數定著是程序本體 ê 區域變數。比如講，lán 佇 lán ê 平方根內底 ê，`good-enough?` ê 定義，用 `square`：

```
(define (good-enough? guess x)
```

```
(< (abs (- (square guess) x))
   0.001))
```

The intention of the author of `good-enough?` is to determine if the square of the first argument is within a given tolerance of the second argument. We see that the author of `good-enough?` used the name `guess` to refer to the first argument and `x` to refer to the second argument. The argument of `square` is `guess`. If the author of `square` used `x` (as above) to refer to that argument, we see that the `x` in `good-enough?` must be a different `x` than the one in `square`. Running the procedure `square` must not affect the value of `x` that is used by `good-enough?`, because that value of `x` may be needed by `good-enough?` after `square` is done computing.

作者佇 `good-enough?` ê 強調，是決定第一个引數 ê 平方 kap 第二个引數 ê 差，kám 是佇誤差內底。Lán 看出 `good-enough?` ê 作者用 `guess` chit ê 名，來指頭一个引數，koh 用 `x` chit ê 名，來指第二个引數。Nā `square` ê 作者用 `x`（像面頂）指 chit ê 引數，lán 通看著佇 `good-enough?` ê `x` kap `square` ê 無 kâng。Pháng chit ê 程序 `square` 無應該影響 `good-enough?` 所用 ê `x` ê 值，因為佇 `square` 算出了後，`good-enough?` 可能需要 `x` ê 值。

If the parameters were not local to the bodies of their respective procedures, then the parameter `x` in `square` could be confused with the parameter `x` in `good-enough?`, and the behavior of `good-enough?` would depend upon which version of `square` we used. Thus, `square` would not be the black box we desired.

Nā 參數毋是對 in 家己 ê 程序本體是區域 ê，`square` ê 參數 `x` 會 kap `good-enough?` ê 參數 `x` 舞亂去，`good-enough?` ê 行為會予 lán 所用 ê `square` ê 版本所影響。就 án-ne，`square` 毋是 lán 所意愛 ê 烏盒 á。

A formal parameter of a procedure has a very special role in the procedure definition, in that it doesn't matter what name the formal parameter has. Such a name is called a *bound variable*, and we say that the procedure defi-

nition *binds* its formal parameters. The meaning of a procedure definition is unchanged if a bound variable is consistently renamed throughout the definition.[51] If a variable is not bound, we say that it is *free*. The set of expressions for which a binding defines a name is called the *scope* of that name. In a procedure definition, the bound variables declared as the formal parameters of the procedure have the body of the procedure as their scope.

程序 ê 正式參數有佇程序定義內底非常特別 ê 角色，佇內底正式參數號 siánn 物名 lóng 無要緊。Chit 款 ê 名號做束縛變數 (bound variable)，lán 講 chit ê 程序 ê 定義束縛 (bind) 伊 ê 正式參數。程序 ê 意義無改變，nā 是束縛變數佇定義內底重號名，而且 lóng 一致。[52]Nā 是變數無束縛，lán 講伊是自由 *ê* (free)。表達式 ê 集合，佇 chia 束縛定義 chit ê 變數 ê 名，號做 chit ê 名 ê作用範圍 (scope)。束縛變數佇程序 ê 定義宣告做程序 ê 形式參數，in ê 作用範圍就是 chit ê 程序 ê 本體。

In the definition of `good-enough?` above, `guess` and `x` are bound variables but `<`, `-`, `abs`, and `square` are free. The meaning of `good-enough?` should be independent of the names we choose for `guess` and `x` so long as they are distinct and different from `<`, `-`, `abs`, and `square`. (If we renamed `guess` to `abs` we would have introduced a bug by *capturing* the variable `abs`. It would have changed from free to bound.) The meaning of `good-enough?` is not independent of the names of its free variables, however. It surely depends upon the fact (external to this definition) that the symbol `abs` names a procedure for computing the absolute value of a number. `good-enough?` will compute a different function if we substitute `cos` for `abs` in its definition.

佇面頂 ê `good-enough?` ê 定義，`guess` kap `x` 是束縛變數，但是 `<`、`-`、`abs`kap `square` 是自由 ê。`good-enough?` ê 意義應該 kap lán

[51]The concept of consistent renaming is actually subtle and difficult to define formally. Famous logicians have made embarrassing errors here.

[52]一致重號名實際上誠微妙 koh oh 得形式定義。出名 ê 邏輯學家佇 chia 有創礙虐 ê 錯誤。

所揀予 guess kap x ê 名獨立，只要 in hām <、−、abs kap square 有區別 koh kap in 無 kâng。(Nā 是 lán 重 kā guess 號做 abs，會加添 bug，因為會掠 (capturing) 變數 abs。Che 會 kā 自由 ê 束縛)。毋過，good-enough? ê 意義無 hām 伊 ê 自由變數 ê 名獨立。伊誠實倚靠 chit ê 事實，就是符號 abs thèh 來 kā 算數字 ê 絕對值 ê 程序號名 (佇 chit ê 定義外面)。Nā lán kāgood-enough? ê 定義內底 ê abs 改做 cos，伊會計算無 kâng ê 函數。

Internal definitions and block structure 內部 ê 定義 kap 塊 ê 結構

We have one kind of name isolation available to us so far: The formal parameters of a procedure are local to the body of the procedure. The square-root program illustrates another way in which we would like to control the use of names. The existing program consists of separate procedures:

目前 Lán 有一款 kā 名孤立 ê 方法通用：程序 ê 正式參數對程序 ê 本體是區域 ê。平方根程式說明別款方法佇 hia lán beh 愛控制名 ê 使用。Chit ê 佇 leh ê 程式包含分開 ê 程序：

```
(define (sqrt x)
  (sqrt-iter 1.0 x))
(define (sqrt-iter guess x)
  (if (good-enough? guess x)
      guess
      (sqrt-iter (improve guess x) x)))
(define (good-enough? guess x)
  (< (abs (- (square guess) x)) 0.001))
(define (improve guess x)
  (average guess (/ x guess)))
```

The problem with this program is that the only procedure that is important to users of sqrt is sqrt. The other procedures (sqrt-iter, good-enough?, and improve) only clutter up their minds. They may not define

any other procedure called `good-enough?` as part of another program to work together with the square-root program, because `sqrt` needs it. The problem is especially severe in the construction of large systems by many separate programmers. For example, in the construction of a large library of numerical procedures, many numerical functions are computed as successive approximations and thus might have procedures named `good-enough?` and `improve` as auxiliary procedures. We would like to localize the subprocedures, hiding them inside `sqrt` so that `sqrt` could coexist with other successive approximations, each having its own private `good-enough?` procedure. To make this possible, we allow a procedure to have internal definitions that are local to that procedure. For example, in the square-root problem we can write

程式 ê 問題是，對 `sqrt` ê 用者來講，kan-ta `sqrt` chiah 重要。其他 ê 程序(`sqrt-iter`、`good-enough?` kap `improve`)kan-ta kā 用者 ê 心舞予亂。In bē 當定義任何其他號做 `good-enough?` 程式，因為 `sqrt` 需要 che。Chit ê 問題佇起做 chē-chē 個別 ê 程式設計師所寫 ê 大 ê 系統 ê 時，特別嚴重。比如講，佇起做大 ê 數值程序 ê 函式庫 ê 時，真 chē 數值函數用一步一步近似 ê 方式計算，可能有號做 `good-enough?` kap `improve` ê 程序，當做輔助程序。Beh 予 che 可能，lán 允准一个程序內底有定義，對 chit ê 程序是區域 ê。舉例，佇平方根問題，lán 通寫：

```
(define (sqrt x)
  (define (good-enough? guess x)
    (< (abs (- (square guess) x)) 0.001))
  (define (improve guess x) (average guess (/ x guess)))
  (define (sqrt-iter guess x)
    (if (good-enough? guess x)
        guess
        (sqrt-iter (improve guess x) x)))
  (sqrt-iter 1.0 x))
```

Such nesting of definitions, called *block structure*, is basically the right so-

lution to the simplest name-packaging problem. But there is a better idea lurking here. In addition to internalizing the definitions of the auxiliary procedures, we can simplify them. Since `x` is bound in the definition of `sqrt`, the procedures `good-enough?`, `improve`, and `sqrt-iter`, which are defined internally to `sqrt`, are in the scope of `x`. Thus, it is not necessary to pass `x` explicitly to each of these procedures. Instead, we allow `x` to be a free variable in the internal definitions, as shown below. Then `x` gets its value from the argument with which the enclosing procedure `sqrt` is called. This discipline is called *lexical scoping*.[53]

Chit 款 ê siū-á 型定義，叫做塊結構 (tè-kiat-kò, block structure)，基本上是包裹名 ê 問題 ê 正確解法。但是 chia chhàng koh 較好 ê 想法。除了 kā 輔助程序 ê 定義 sóa kàu 內部，lán 會當予 khah 簡單。因為 `x` 束縛佇 `sqrt` ê 定義內底，程序 `good-enough?`、`improve` kap `sqrt-iter`，in lóng 定義佇 `sqrt` 內底，mā 佇 `x` ê 作用範圍內底。就 án-ne，無必要 kā `x` 明白 sòa 予 chia ê 所有程序。Lán 反轉允准 `x` 成做佇 chiah ê 內部定義 ê 自由變數，ná 下 kha 所展示。了後，`x` tùi 引數得著伊 ê 值，kā 所有總包 ê 程序 `sqrt` 用 chit ê 引數叫。Chit ê 約束號做詞法使用範圍。[54]

```
(define (sqrt x)
  (define (good-enough? guess)
    (< (abs (- (square guess) x)) 0.001))
  (define (improve guess)
    (average guess (/ x guess)))
  (define (sqrt-iter guess)
    (if (good-enough? guess)
```

[53] Lexical scoping dictates that free variables in a procedure are taken to refer to bindings made by enclosing procedure definitions; that is, they are looked up in the environment in which the procedure was defined. We will see how this works in detail in chapter 3 when we study environments and the detailed behavior of the interpreter.

[54] 詞法使用範圍決定程序內底 ê 自由變數，予 lâng thèh 來指包 ê 程序定義所做 ê 束縛；就是，in 佇程序佇內底定義 ê 環境，受 chhiau-chhōe。當 lán 學環境 kap 直譯器 ê 詳細行為 ê 時，會佇第 3 章看見 che 詳細 ê 運作方法。

```
        guess
        (sqrt-iter (improve guess))))
  (sqrt-iter 1.0))
```

We will use block structure extensively to help us break up large programs into tractable pieces.[55] The idea of block structure originated with the programming language Algol 60. It appears in most advanced programming languages and is an important tool for helping to organize the construction of large programs.

Lán 會用擴展塊結構來幫 chān lán kā 大 ê 程式拆做好處理 ê koe̍h。[56] 塊結構 ê 想法 kap 程式語言 Algol 60 做伙開始。伊出現佇大部份 ê 進階語言，mā 是重要 ê 家私，幫 chān 組織起做大 ê 程式。

1.2 Procedures and the Processes They Generate 程序 kap In 產出ê 程序

We have now considered the elements of programming: We have used primitive arithmetic operations, we have combined these operations, and we have abstracted these composite operations by defining them as compound procedures. But that is not enough to enable us to say that we know how to program. Our situation is analogous to that of someone who has learned the rules for how the pieces move in chess but knows nothing of typical openings, tactics, or strategy. Like the novice chess player, we don't yet know the common patterns of usage in the domain. We lack the knowledge of which moves are worth making (which procedures are worth defining). We lack the experience to predict the consequences of making a move (executing a procedure).

[55] Embedded definitions must come first in a procedure body. The management is not responsible for the consequences of running programs that intertwine definition and use.

[56] 門入去 ê 程序著愛佇程序本體代先來。管理無對定義 kap 使用相 tī^{n} ê，所 pháng ê 程式 ê 結果負責。

Lán chit-má 有考慮程式設計 ê 要素：Lán 用基礎 ê 運算操作、組合 chiah ê 操作，koh 用定義 in 成做複合程序來抽象 chiah ê 複合操作。毋過 iah 無夠予 lán 講 lán 知影 án-nóa 寫程式。Lán ê 狀況足 sêng 已經學 án-nóa sóa 棋 á ê 規則 ê 人，但是毋知開局、撇步 á 是策略。親像行棋 ê 新儂，lán iah 毋知 chit ê 範圍內底，通常 ê 使用規則。Lán 欠棋 á án-nóa 行較有價值（siánn 物程式 khah 值著定義）ê 智識，kap 預測行棋 á 了後 ê 結果（執行程式）ê 經驗。

The ability to visualize the consequences of the actions under consideration is crucial to becoming an expert programmer, just as it is in any synthetic, creative activity. In becoming an expert photographer, for example, one must learn how to look at a scene and know how dark each region will appear on a print for each possible choice of exposure and development conditions. Only then can one reason backward, planning framing, lighting, exposure, and development to obtain the desired effects. So it is with programming, where we are planning the course of action to be taken by a process and where we control the process by means of a program. To become experts, we must learn to visualize the processes generated by various types of procedures. Only after we have developed such a skill can we learn to reliably construct programs that exhibit the desired behavior.

Kā 考慮 ê 動作 ê 結果視覺化 ê 能力，對成做程式設計 ê 專家真要緊，就親像佇任何合成 ê、創造性 ê 活動內底。舉例，愛變做專業 ê 攝影師，著愛學按怎觀察場面，koh 愛知對逐 ê 可能 ê 曝光 kap 處理情況 ê 選擇，逐 ê 區會佇相片紙呈現 kah 有 gōa 暗。Kan-ta án-ne chiah 通推理倒轉，計畫構圖、照明、曝光 kap 處理，來得著 beh 愛 ê 效果。程序 mā kâng 款，佇 hia lán 計畫程序 beh 行 ê 行動 ê 順序，koh 用程式 ê 法度來控制程序。Beh 成做專家，lán 定著學 kā chē-chē 款 ê 程序所生成 ê 過程視覺化。Kan-ta 佇 lán 有發展 chit-ê 技術以後，lán chiah 通學可靠起做程式，伊展出所 beh 愛 ê 行為。

A procedure is a pattern for the *local evolution* of a computational process. It specifies how each stage of the process is built upon the previous stage. We would like to be able to make statements about the overall, or *global*, be-

havior of a process whose local evolution has been specified by a procedure. This is very difficult to do in general, but we can at least try to describe some typical patterns of process evolution.

程序是予計算過程 ê 區域展開 (local evolution) 用 ê 模樣 (pattern)。伊指定過程 ê 逐階段 án-nóa 起做佇進前 ê 階段面頂。Lán 想 beh 會當對過程全體 ê，或者是全域 *ê* (global) 行為表達想法，其中 chit ê 過程 ê 區域展開予程序指定。Che 一般非常困難，毋過 lán 上無通試描述一寡典型 ê 過程，所展開 ê 模樣。

In this section we will examine some common "shapes" for processes generated by simple procedures. We will also investigate the rates at which these processes consume the important computational resources of time and space. The procedures we will consider are very simple. Their role is like that played by test patterns in photography: as oversimplified prototypical patterns, rather than practical examples in their own right.

佇 chit 段 lán 會考察一寡 chiảp-chiảp 看著 ê，簡單過程所生成 ê 程序 ê「形」。Lán mā 會調查 chiah-ê 過程所開時間 kap 空間 ê 重要運算資源 ê 比率。Lán beh 考慮 ê 程序非常簡單。In ê 角色像攝影 ê 測試模樣所演 ê：假若過度簡化 ê 原形 ê 模樣，毋是靠本身 ê 應用案例。

1.2.1 Linear Recursion and Iteration 線性遞迴 kap 反覆

We begin by considering the factorial function, defined by

Lán tùi 考慮階乘函數開始，伊 án-ne 定義：

$$n! = n \cdot (n-1) \cdot (n-2) \cdots 3 \cdot 2 \cdot 1.$$

There are many ways to compute factorials. One way is to make use of the observation that $n!$ is equal to n times $(n-1)!$ for any positive integer n:

有 chē-chē 方法算階乘。一款方法是用觀察對所有正整數 n，$n!$ 等於 n 乘以 $(n-1)!$：

$$n! = n \cdot [(n-1) \cdot (n-2) \cdots 3 \cdot 2 \cdot 1] = n \cdot (n-1)!.$$

Thus, we can compute $n!$ by computing $(n-1)!$ and multiplying the result by n. If we add the stipulation that $1!$ is equal to 1, this observation translates directly into a procedure:

就 án-ne，lán 會當用 kā $(n-1)!$ 算出來 ê 結果乘以 n 來算 $n!$。Nā 是 lán 加添 $1!$ 等於 1 規定，chit ê 觀察直接翻譯做程序會是：

```
(define (factorial n)
  (if (= n 1)
      1
      (* n (factorial (- n 1)))))
```

We can use the substitution model of Section 1.1.5 to watch this procedure in action computing 6!, as shown in Figure 1.3.

Lán 通用Section 1.1.5 ê 替代模型來觀察 chit ê 程序佇計算 6! ê 行動，顯示佇Figure 1.3。

Now let's take a different perspective on computing factorials. We could describe a rule for computing $n!$ by specifying that we first multiply 1 by 2, then multiply the result by 3, then by 4, and so on until we reach n. More formally, we maintain a running product, together with a counter that counts from 1 up to n. We can describe the computation by saying that the counter and the product simultaneously change from one step to the next according to the rule

Chit-má lán 用別款角度看算階乘。Lán 通用指定 lán 先 kā 1 乘以 2，了後乘以 3，乘以 4，等等，直到 lán 拄著 n，來描述算 $n!$ 規則。Koh 較正式 ê 方法是，lán 維持 pháng ê 乘積 (product)，kap 一个 ùi 1 siàu kah n ê siàu 數器 (counter)。Lán 通用講 siàu 數器 kap 乘積對一步 kàu 下一步仝時改變，根據下 kha ê 規則，描述 chit ê 運算：

```
product ← counter * product
counter ← counter + 1
```




Figure 1.3: A linear recursive process for computing 6!. 算 6! ê 線性遞迴過程

and stipulating that $n!$ is the value of the product when the counter exceeds n.

Koh 規定 $n!$ 是當 siàu 數器超過 n ê 時，乘積 ê 值。

Once again, we can recast our description as a procedure for computing factorials:[57]

Koh 來，lán 通重寫 lán ê 算階乘 ê 描述，用程序 ê 方式：[58]

[57] In a real program we would probably use the block structure introduced in the last section to hide the definition of `fact-iter`:

```
(define (factorial n)
  (define (iter product counter)
    (if (> counter n)
        product
        (iter (* counter product)
              (+ counter 1))))
  (iter 1 1))
```

We avoided doing this here so as to minimize the number of things to think about at once.

[58] 佇真 ê 程式內底，lán hoân-sè 用頂節紹介 ê 塊結構，來 khàm 掉 `fact-iter` ê 定義：




Figure 1.4: A linear iterative process for computing 6!. 算 6! ê 線性反覆過程

```
(define (factorial n)
  (fact-iter 1 1 n))
(define (fact-iter product counter max-count)
  (if (> counter max-count)
      product
      (fact-iter (* counter product)
                 (+ counter 1)
                 max-count)))
```

As before, we can use the substitution model to visualize the process of computing 6!, as shown in Figure 1.4.

```
(define (factorial n)
  (define (iter product counter)
    (if (> counter n)
        product
        (iter (* counter product)
              (+ counter 1))))
  (iter 1 1))
```

Lán 避免佇 chia 做 che，為著 beh kā 一改愛想 ê 代誌 ê 量，降 kah 上 kē。

親像進前 ê，lán 通用替代模型來視覺化算 6! ê 過程，展示佇 Figure 1.4。

Compare the two processes. From one point of view, they seem hardly different at all. Both compute the same mathematical function on the same domain, and each requires a number of steps proportional to n to compute $n!$. Indeed, both processes even carry out the same sequence of multiplications, obtaining the same sequence of partial products. On the other hand, when we consider the "shapes" of the two processes, we find that they evolve quite differently.

比較 chit 兩个程序。對一方面看，in 差不多仝款。兩个佇仝款 ê 定義域算仝款 ê 函數，而且 lóng 需要 kap n 仝比例 ê 步數，來算 $n!$。兩个過程誠實 lóng 行仝款 ê 乘法 ê 列，得著仝款 ê 部份乘積 ê 列。另外方面，lán 考慮兩个過程 ê「形」ê 時陣，發現 in 展開 ê 方式非常無仝。

Consider the first process. The substitution model reveals a shape of expansion followed by contraction, indicated by the arrow in Figure 1.3. The expansion occurs as the process builds up a chain of *deferred operations* (in this case, a chain of multiplications). The contraction occurs as the operations are actually performed. This type of process, characterized by a chain of deferred operations, is called a *recursive process*. Carrying out this process requires that the interpreter keep track of the operations to be performed later on. In the computation of $n!$, the length of the chain of deferred multiplications, and hence the amount of information needed to keep track of it, grows linearly with n (is proportional to n), just like the number of steps. Such a process is called a *linear recursive process*.

考慮頭一个過程。替代模型顯露擴展了後收縮 ê 形，佇 Figure 1.3 ê 箭頭有指示。當過程建立 延遲運算 (deferred operations)（Chit ê 例指乘法 ê 鏈）ê 鍊 ê 時，擴展就會出現。行 chit ê 過程需要直譯器追蹤了後 chiah 做 ê 操作。佇算 $n!$ ê 時，延遲乘法 ê 鏈 ê 長度，kap 就 án-ne 所愛追蹤 ê 資訊量，tòe n 線性成長（hām n 仝比例），親像步數仝款。Chit 款程序號做 線性遞迴過程 (linear recursive process)。

By contrast, the second process does not grow and shrink. At each step, all we need to keep track of, for any n, are the current values of the variables `product`, `counter`, and `max-count`. We call this an *iterative process*. In general, an iterative process is one whose state can be summarized by a fixed number of *state variables*, together with a fixed rule that describes how the state variables should be updated as the process moves from state to state and an (optional) end test that specifies conditions under which the process should terminate. In computing $n!$, the number of steps required grows linearly with n. Such a process is called a *linear iterative process*.

對反 ê 是，第二 ê 過程無成長 koh kiu 水。對所有 n，逐步 lán 所 beh 追蹤 ê，是變數 `product`、`counter`、`max-count` chit-má ê 值。Lán kā che 號做 反覆過程 (iterative process)。一般來講，反覆過程是一个過程，伊 ê 狀態會當用固定數量 ê 狀態變數 (state variables) 摘要，koh 有固定 ê 規矩，描述狀態變數 án-nóa tòe 過程轉移 ê 狀態更新，kap（無必要 ê）結尾測試，指定佇 siáⁿ 物狀況過程應該結束。佇算 $n!$ ê 時，步數需要 kap n 線性成長。Chit 款程序號做線性反覆過程 (linear iterative process)。

The contrast between the two processes can be seen in another way. In the iterative case, the program variables provide a complete description of the state of the process at any point. If we stopped the computation between steps, all we would need to do to resume the computation is to supply the interpreter with the values of the three program variables. Not so with the recursive process. In this case there is some additional "hidden" information, maintained by the interpreter and not contained in the program variables, which indicates "where the process is" in negotiating the chain of deferred operations. The longer the chain, the more information must be maintained.[59]

[59] When we discuss the implementation of procedures on register machines in Chapter 5, we will see that any iterative process can be realized "in hardware" as a machine that has a fixed set of registers and no auxiliary memory. In contrast, realizing a recursive process requires a machine that uses an auxiliary data structure known as a *stack*.

Chit 兩个過程 ê 比較會當對別面來看。佇反覆 ê，程式變數佇逐位提供過程 ê 完全 ê 狀態描述。Nā lán 停止階段之間 ê 計算，所有 lán 著做來恢復運算 ê 方法，是供應直譯器 chit 3 ê 程式 ê 變數。但是對遞迴過程毋是 án-ne。佇 chit ê 例，有一寡所附 ê「隱藏」ê 資訊，由直譯器維護，無包佇程式變數，伊指示佇處理延遲運算 ê 鏈內底，「過程佇 toeh」。鍊愈長，著維護愈 chē 資訊。[60]

In contrasting iteration and recursion, we must be careful not to confuse the notion of a recursive *process* with the notion of a recursive *procedure*. When we describe a procedure as recursive, we are referring to the syntactic fact that the procedure definition refers (either directly or indirectly) to the procedure itself. But when we describe a process as following a pattern that is, say, linearly recursive, we are speaking about how the process evolves, not about the syntax of how a procedure is written. It may seem disturbing that we refer to a recursive procedure such as `fact-iter` as generating an iterative process. However, the process really is iterative: Its state is captured completely by its three state variables, and an interpreter need keep track of only three variables in order to execute the process.

佇比較反覆 kap 遞迴 ê 時陣，lán 定著愛注意 mài kā 遞迴 ê 過程 (process) ê 觀念 kap 遞迴 ê 程序 (procedure) ê 觀念舞花去。當 lán 描述一个程序是遞迴 ê 時，是 leh 指程序 ê 定義（無論有無直接）包含 chit ê 程序家己 ê 語法 ê 事實。毋過當 lán 描述一个過程跟 tòe 線性遞迴 ê 模樣，lán teh 講關係過程 án-nóa 展開，毋是程序 án-nóa 寫 ê 語法。Lán 指像 `fact-iter` ê 遞迴過程生成反覆過程，可能會予 lâng 花去。但是，過程的確是反覆：伊 ê 狀態完全予伊 ê 三 ê 狀態變數掠起來，而且直譯器 beh 執行 chit ê 過程，kan-ta 需要追蹤三 ê 變數。

One reason that the distinction between process and procedure may be confusing is that most implementations of common languages (including Ada,

[60] 佇 lán 佇第 5 章討論程序佇暫存器機器實做 ê 時陣，lán 會看見任何反覆過程會當「佇硬體」實現，成做一臺有有限暫存器集合，無輔助記憶體 ê 機器，實現遞迴過程顛倒需要用號做 *stack* (su-tá-khuh) ê 輔助資料結構 ê 機器。

Pascal, and C) are designed in such a way that the interpretation of any recursive procedure consumes an amount of memory that grows with the number of procedure calls, even when the process described is, in principle, iterative. As a consequence, these languages can describe iterative processes only by resorting to special-purpose "looping constructs" such as `do`, `repeat`, `until`, `for`, and `while`. The implementation of Scheme we shall consider in Chapter 5 does not share this defect. It will execute an iterative process in constant space, even if the iterative process is described by a recursive procedure. An implementation with this property is called *tail-recursive*. With a tail-recursive implementation, iteration can be expressed using the ordinary procedure call mechanism, so that special iteration constructs are useful only as syntactic sugar.[61]

區別過程 kap 程序可能 ê 舞花 ê 原因之一，是大部份 ê chiảp 用 ê 語言（包含 Ada、Pascal kap C）實做，是用 chit ê 方式設計，就是任何遞迴 ê 過程 ê 直譯器開記憶體 ê 量，是對程序呼叫 ê 額成長，就算程序 ê 描述原則上是反覆 ê。結果，chiah ê 語言 kan-ta 當去用特殊目的 ê「loop 結構」，比如 `do`、`repeat`、`until`、`for` kap `while`，chiah 通描述反覆過程。Lán 佇第 5 章考慮 ê Scheme ê 實做無 chit ê 缺點。伊會佇固定空間執行反覆過程，就算反覆過程予遞迴程序描述。有 chit ê 特點 ê 實做號做尾遞迴 (tail-recursive)。有尾遞迴實做，反覆會當用一般 ê 程序呼叫 ê 機制表達，致 kàu 特殊 ê 反覆建構 kan-ta 佇做語法糖 ê 時 chiah 有路用。[62]

[61] Tail recursion has long been known as a compiler optimization trick. A coherent semantic basis for tail recursion was provided by Carl Hewitt (1977), who explained it in terms of the "message-passing" model of computation that we shall discuss in Chapter 3. Inspired by this, Gerald Jay Sussman and Guy Lewis Steele Jr. (see Steele and Sussman 1975) constructed a tail-recursive interpreter for Scheme. Steele later showed how tail recursion is a consequence of the natural way to compile procedure calls (Steele 1977). The IEEE standard for Scheme requires that Scheme implementations be tail-recursive.

[62] 尾遞迴長久予 lâng 掠做是編譯器最佳化 ê 手路。尾遞迴整個 ê 語義基礎，是由 Carl 提供Hewitt (1977)，伊用「sòa 訊息」(message-passing)ê 計算模型（Lán 會佇第 3 章討論）解說。Gerald Jay Sussman kap Guy Lewis Steele Jr. （看Steele and Sussman 1975）予伊啟發，

Exercise 1.9: Each of the following two procedures defines a method for adding two positive integers in terms of the procedures `inc`, which increments its argument by 1, and `dec`, which decrements its argument by 1.

下 kha ê 兩 ê 程序定義用程序 `inc`（kā 引數加 1）kap `dec`（kā 引數減 1），來 kā 兩 ê 正整數加起來 ê 方法。

```
(define (+ a b)
  (if (= a 0) b (inc (+ (dec a) b))))
(define (+ a b)
  (if (= a 0) b (+ (dec a) (inc b))))
```

Using the substitution model, illustrate the process generated by each procedure in evaluating `(+ 4 5)`. Are these processes iterative or recursive?

請用替換模型說明兩 ê 程序佇算 `(+ 4 5)` 所生成 ê 過程。Chiah ê 過程是反覆 á 是遞迴？

Exercise 1.10: The following procedure computes a mathematical function called Ackermann's function.

下 kha ê 程序計算號做 Ackermann 函數 (Ackermann's function) ê 數學函數。

```
(define (A x y)
  (cond ((= y 0) 0)
        ((= x 0) (* 2 y))
        ((= y 1) 2)
        (else (A (- x 1) (A x (- y 1))))))
```

建立一个尾遞迴 ê Scheme 直譯器。Steele 以後展示尾遞迴 an-nóa 是自然 ê 方法，來編譯程序呼叫 ê 結果（Steele 1977）。佇 Scheme ê IEEE 標準內底，實做需要尾遞迴。

What are the values of the following expressions?

下 kha ê 表達式 ê 值是 siánn 物？

```
(A 1 10)
(A 2 4)
(A 3 3)
```

Consider the following procedures, where `A` is the procedure defined above:

考慮下 kha ê 過程，佇 chia `A` 是頂懸定義 ê 程序：

```
(define (f n) (A 0 n))
(define (g n) (A 1 n))
(define (h n) (A 2 n))
(define (k n) (* 5 n n))
```

Give concise mathematical definitions for the functions computed by the procedures `f`, `g`, and `h` for positive integer values of n. For example, `(k n)` computes $5n^2$.

提供一致 ê 由程序 `f`、`g` kap `h`（引數 n lóng 是正整數）所算 ê，函數 ê 數學定義。舉例，`(k n)` 是算 $5n^2$。

1.2.2 Tree Recursion 樹遞迴

Another common pattern of computation is called *tree recursion*. As an example, consider computing the sequence of Fibonacci numbers, in which each number is the sum of the preceding two:

另外一款運算 ê 模樣號做樹遞迴 (tree recursion)。比如講，考慮算 Fibonacci 數 ê 列，佇 chia，逐个數是伊進前兩个數 ê 和：

$$0,\ 1,\ 1,\ 2,\ 3,\ 5,\ 8,\ 13,\ 21,\ \ldots.$$

In general, the Fibonacci numbers can be defined by the rule
一般來講，Fibonacci 數會當用下 kha ê 規則定義

$$\mathrm{Fib}(n) = \begin{cases} 0 & \text{if } n = 0, \\ 1 & \text{if } n = 1, \\ \mathrm{Fib}(n-1) + \mathrm{Fib}(n-2) & \text{otherwise.} \end{cases}$$

We can immediately translate this definition into a recursive procedure for computing Fibonacci numbers:
Lán 通連鞭翻譯 chit ê 定義做遞迴 ê 程序，來算 Fibonacci 數：

```
(define (fib n)
  (cond ((= n 0) 0)
        ((= n 1) 1)
        (else (+ (fib (- n 1))
                 (fib (- n 2))))))
```

Consider the pattern of this computation. To compute `(fib 5)`, we compute `(fib 4)` and `(fib 3)`. To compute `(fib 4)`, we compute `(fib 3)` and `(fib 2)`. In general, the evolved process looks like a tree, as shown in Figure 1.5. Notice that the branches split into two at each level (except at the bottom); this reflects the fact that the `fib` procedure calls itself twice each time it is invoked.
考慮 chit ê 運算 ê 模樣。Beh 算 `(fib 5)`，lán 著算 `(fib 4)` kap `(fib 3)`。Beh 算 `(fib 4)`，lán 著算 `(fib 3)` kap `(fib 2)`。Lán 一般講，擴展過程看起來像一欉樹 á，若Figure 1.5。注意分支佇逐層分做兩 oe（除了上下底 ê）；Che 反應 `fib` 程序當 leh 呼叫 ê 時，伊呼叫家己兩改 ê 事實。

This procedure is instructive as a prototypical tree recursion, but it is a terrible way to compute Fibonacci numbers because it does so much redundant computation. Notice in Figure 1.5 that the entire computation of `(fib`

`3)` —almost half the work—is duplicated. In fact, it is not hard to show that the number of times the procedure will compute `(fib 1)` or `(fib 0)` (the number of leaves in the above tree, in general) is precisely Fib($n+1$). To get an idea of how bad this is, one can show that the value of Fib(n) grows exponentially with n. More precisely (see Exercise 1.13), Fib(n) is the closest integer to $\varphi^n/\sqrt{5}$, where

Chit ê 程序當做原形 ê 樹遞迴有教育性，但是對算 Fibonacci 數來講，非常害，因為伊做傷 chōe 加做 ê 運算。注意佇 Figure 1.5，`(fib 3)` 規个運算（強欲佔一半）是重複 ê。實際上，展示 chit ê 程序會算 `(fib 1)` á 是 `(fib 0)` ê 次數（一般來講是頂懸樹 á ê 葉 á 數）無困難。Beh 得著 che 有 gōa bái ê 概念，lâng 會當展示 Fib(n) ê 值 tòe n 用指數方式成長。較準確來講（看 Exercise 1.13），Fib(n) 是 $\varphi^n/\sqrt{5}$ ê 上近 ê 整數，其中

$$\varphi = \frac{1+\sqrt{5}}{2} \approx 1.6180$$

is the *golden ratio*, which satisfies the equation
是黃金比例 (golden ratio)，滿足方程式

$$\varphi^2 = \varphi + 1.$$

Thus, the process uses a number of steps that grows exponentially with the input. On the other hand, the space required grows only linearly with the input, because we need keep track only of which nodes are above us in the tree at any point in the computation. In general, the number of steps required by a tree-recursive process will be proportional to the number of nodes in the tree, while the space required will be proportional to the maximum depth of the tree.

就 án-ne，chit ê 過程用 ê 手續數是 tòe 輸入用指數形式成長。另外方面，空間 kan-ta 需要 tòe 輸入用線性成長，因為 lán kan-ta 需要追蹤佇樹 á 內底，siáⁿ 物節 (node) 佇 lán 頂懸，佇運算 ê 任何點。一般來講，樹遞迴需要 ê 手續數




Figure 1.5: The tree-recursive process generated in computing `(fib 5)`.算 `(fib 5)` 生成 ê 樹遞迴過程

會 kap 樹 á ê 節數成比例關係，iā hit 時需要 ê 空間會 kap 樹 á ê 上大 ê 深度成比例關係。

We can also formulate an iterative process for computing the Fibonacci numbers. The idea is to use a pair of integers a and b, initialized to Fib(1) = 1 and Fib(0) = 0, and to repeatedly apply the simultaneous transformations

Lán mā 通制定反覆 ê 過程來算 Fibonacci 數。Chit ê 想法是用一對整數 a kap b，開始設做 Fib(1) = 1 kap Fib(0) = 0，而且重覆仝齊應用轉換

$$\begin{aligned} a &\leftarrow a + b, \\ b &\leftarrow a. \end{aligned}$$

It is not hard to show that, after applying this transformation n times, a and b will be equal, respectively, to Fib($n + 1$) and Fib(n). Thus, we can compute Fibonacci numbers iteratively using the procedure

展示佇應用 chit ê 轉換 n 改以後，a kap b 會個別等於 Fib$(n+1)$ kap Fib(n)，無困難。就 án-ne，lán 會當反覆用下 kha ê 程序計算 Fibonacci 數

```
(define (fib n)
  (fib-iter 1 0 n))
(define (fib-iter a b count)
  (if (= count 0)
      b
      (fib-iter (+ a b) a (- count 1))))
```

This second method for computing Fib(n) is a linear iteration. The difference in number of steps required by the two methods—one linear in n, one growing as fast as Fib(n) itself—is enormous, even for small inputs.
第二个計算 Fib(n) ê 方法是線性反覆。佇 chit 兩个方法需要 ê 手續數 ê 無仝——一个是 kap n 成線性，一个 kap Fib(n) 家己成長平緊——差別蓋大，就算用較細 ê 輸入。

One should not conclude from this that tree-recursive processes are useless. When we consider processes that operate on hierarchically structured data rather than numbers, we will find that tree recursion is a natural and powerful tool.[63] But even in numerical operations, tree-recursive processes can be useful in helping us to understand and design programs. For instance, although the first `fib` procedure is much less efficient than the second one, it is more straightforward, being little more than a translation into Lisp of the definition of the Fibonacci sequence. To formulate the iterative algorithm required noticing that the computation could be recast as an iteration with three state variables.

Lâng 無應該 ùi chia 落結論講，樹遞迴無路用。Lán 考慮操作階層 ê，結構資料，毋是數 ê 過程 ê 時，會發現樹遞迴是自然 kap 有力 ê 家私[64]毋過就

[63] An example of this was hinted at in Section 1.1.3. The interpreter itself evaluates expressions using a tree-recursive process.

[64] Che ê 例佇 Section 1.1.3 受提示。直譯器家己算表達式是用樹遞迴 ê 過程。

算仔數值操作，樹遞迴過程會當仔幫贊 lán 了解 kap 設計程序，有路用。舉例，雖罔頭一个 `fib` 程序比第二个 koh 較無效率，但是較直覺，kan-ta 比 Fibonacci 數列 ê 定義翻做 Lisp koh 加一屑 á。Beh 規範反覆演算法，需要注意計算會當重換做有三 ê 狀態變數 ê 反覆。

Example: Counting change 例：計算找 ê 錢

It takes only a bit of cleverness to come up with the iterative Fibonacci algorithm. In contrast, consider the following problem: How many different ways can we make change of $1.00, given half-dollars, quarters, dimes, nickels, and pennies? More generally, can we write a procedure to compute the number of ways to change any given amount of money?

想出反覆 ê Fibonacci 演算法，kan-ta 需要一寡巧路。對比來講，考慮下 kha ê 問題：beh 找 $1.00（譯註：美金）有幾種方法，準講有 5 角 (half-dollar)、2.5 角 (quarter)、1 角 (dime)、5 sián (nickel) kap 1 sián (penny)？較一般來講，lán 敢會當寫程序，算找任何數額 ê 錢方法數？

This problem has a simple solution as a recursive procedure. Suppose we think of the types of coins available as arranged in some order. Then the following relation holds:

Chit ê 問題有簡單 ê 遞迴程序解。假使 lán 想會當用 ê 銀角 á ê 款有順序 leh 排。然後就保持下 kha ê 關係：

The number of ways to change amount a using n kinds of coins equals

- the number of ways to change amount a using all but the first kind of coin, plus
- the number of ways to change amount $a - d$ using all n kinds of coins, where d is the denomination of the first kind of coin.

Kā 數額 a 用 n 款銀角 á 找 ê 方法數等於

- Kā 數額 a 用所有（除了頭一款）ê 銀角 á 找 ê 方法數，加
- Kā 數額 $a - d$ 用所有 n 款 ê 銀角 á 找 ê 方法數，其中 d 是頭一款銀角 ê 面額。

To see why this is true, observe that the ways to make change can be divided into two groups: those that do not use any of the first kind of coin, and those that do. Therefore, the total number of ways to make change for some amount is equal to the number of ways to make change for the amount without using any of the first kind of coin, plus the number of ways to make change assuming that we do use the first kind of coin. But the latter number is equal to the number of ways to make change for the amount that remains after using a coin of the first kind.
Nā beh 看出這是真 ê ê 原因，觀察找錢 ê 方法會當分做 2 種：無用頭一款銀角 á ê，kap 有用 ê。所以，找一寡數額 ê 方法總數，是無用頭一款銀角 á 找 chit ê 數額 ê 方法數，加添假使 lán 用頭一款銀角 á 找錢 ê 方法數。但是後壁 ê 數等於假使 lán 用了一个頭一款 ê 銀角以後，chhun ê 數額找錢 ê 方法數。

Thus, we can recursively reduce the problem of changing a given amount to the problem of changing smaller amounts using fewer kinds of coins. Consider this reduction rule carefully, and convince yourself that we can use it to describe an algorithm if we specify the following degenerate cases:[65]

就 án-ne，lán 會當遞迴減少 chit ê 找所予 ê 數額問題，kàu 用較少 ê 種類 ê 銀角，找較細 ê 數額 ê 問題。斟酌考慮 chit ê 規則，說服家己 lán 會當用這描述演算法，Nā lán 指定下 kha ê 退化 ê 例：[66]

- If a is exactly 0, we should count that as 1 way to make change.
- If a is less than 0, we should count that as 0 ways to make change.

[65] For example, work through in detail how the reduction rule applies to the problem of making change for 10 cents using pennies and nickels.

[66] 舉例，詳細解決減少 ê 規則應用 kàu 用 1 sián kap 5 sián 找 10 sián ê 問題。

- If n is 0, we should count that as 0 ways to make change.
- Nā a 的確是 0，lán 應該當做有 1 種方法來找錢。
- Nā a 較少 0，lán 應該當做有 0 種方法來找錢。
- Nā n 是 0，lán 應該當做有 0 種方法來找錢。

We can easily translate this description into a recursive procedure:
Lán 通容易 kā chit ê 描述翻譯做遞迴程序：

```
(define (count-change amount) (cc amount 5))
(define (cc amount kinds-of-coins)
  (cond ((= amount 0) 1)
        ((or (< amount 0) (= kinds-of-coins 0)) 0)
        (else (+ (cc amount
                     (- kinds-of-coins 1))
                 (cc (- amount
                        (first-denomination
                         kinds-of-coins))
                     kinds-of-coins)))))
(define (first-denomination kinds-of-coins)
  (cond ((= kinds-of-coins 1) 1)
        ((= kinds-of-coins 2) 5)
        ((= kinds-of-coins 3) 10)
        ((= kinds-of-coins 4) 25)
        ((= kinds-of-coins 5) 50)))
```

(The `first-denomination` procedure takes as input the number of kinds of coins available and returns the denomination of the first kind. Here we are thinking of the coins as arranged in order from largest to smallest, but any order would do as well.) We can now answer our original question about changing a dollar:

(`first-denomination` 程序 thèh 會當用 ê 銀角種類，傳轉頭一種 ê 面額。佇 chia lán 想銀角 á 是對大 kàu 細排列，但是任何排列 mā 會使。) Lán chit-má 通回答 lán 原本 ê 找錢 ê 問題：

```
(count-change 100)
292
```

`count-change` generates a tree-recursive process with redundancies similar to those in our first implementation of `fib`. (It will take quite a while for that 292 to be computed.) On the other hand, it is not obvious how to design a better algorithm for computing the result, and we leave this problem as a challenge. The observation that a tree-recursive process may be highly inefficient but often easy to specify and understand has led people to propose that one could get the best of both worlds by designing a "smart compiler" that could transform tree-recursive procedures into more efficient procedures that compute the same result.[67]

`count-change` 生成有重頭算 ê 樹遞迴，像 lán 頭一改實做 ê `fib`。(Che 會開一段時間來算 292)。另外方面，設計較好 ê 演算法算結果 ê 方法無明顯，lán 留 che 做挑戰。樹遞迴 ê 過程可能真無效率，但是定定較快指定 kap 了解 ê 觀察，致 kàu lâng 提議，倚靠設計「巧 ê 編譯器」有可能得著一兼二顧 ê 結果。[68]

---

[67] One approach to coping with redundant computations is to arrange matters so that we automatically construct a table of values as they are computed. Each time we are asked to apply the procedure to some argument, we first look to see if the value is already stored in the table, in which case we avoid performing the redundant computation. This strategy, known as *tabulation* or *memoization*, can be implemented in a straightforward way. Tabulation can sometimes be used to transform processes that require an exponential number of steps (such as `count-change`) into processes whose space and time requirements grow linearly with the input. See Exercise 3.27.

[68] 一个方法來應對重頭算，是安排代誌，予 lán 會當主動佇值算出 ê 時建立 in ê 表。逐改 lán 予 lâng 問著愛應用程序 kàu 一寡值 ê 時陣，lán 先看值敢有 tiông 佇表內底，避免行重覆 ê 運算。Chit ê 策略號做表化 (tabulation) á 是記持化 (memoization)，會當用直接 ê 方法實做。表

Exercise 1.11: A function f is defined by the rule that

函數 f 用下 kha ê 規則定義

$$f(n) = \begin{cases} n & \text{if } n < 3, \\ f(n-1) + 2f(n-2) + 3f(n-3) & \text{if } n \geq 3. \end{cases}$$

Write a procedure that computes f by means of a recursive process. Write a procedure that computes f by means of an iterative process.

寫一个程序，用遞迴過程計算 f。寫一个程序，用反覆過程計算 f。

Exercise 1.12: The following pattern of numbers is called *Pascal's triangle*.

下 kha ê 數 ê 模樣號做 *Pascal* 三角形 (Pascal's triangle)。

```
          1
        1   1
      1   2   1
    1   3   3   1
  1   4   6   4   1
        . . .
```

The numbers at the edge of the triangle are all 1, and each number inside the triangle is the sum of the two numbers above it.[69]

化有時陣通用來變換手續需要指數時間 ê 過程（比如 `count-change`）變做時間 kap 空間需要 kap 輸入線性成長 ê 過程。看Exercise 3.27。

[69]The elements of Pascal's triangle are called the *binomial coefficients*, because the nth row

Write a procedure that computes elements of Pascal's triangle by means of a recursive process.

三角形 ê 邊 á ê 角攏總是 1，逐个佇三角形內底 ê 數，是伊頂懸 ê 兩个數 ê 和。[70]

Exercise 1.13: Prove that Fib(n) is the closest integer to $\varphi^n/\sqrt{5}$, where $\varphi = (1+\sqrt{5})/2$. Hint: Let $\psi = (1-\sqrt{5})/2$. Use induction and the definition of the Fibonacci numbers (see Section 1.2.2) to prove that Fib$(n) = (\varphi^n - \psi^n)/\sqrt{5}$.

證明 Fib(n) 是上接近 $\varphi^n/\sqrt{5}$ ê 整數，其中 $\varphi = (1+\sqrt{5})/2$。提示：予 $\psi = (1-\sqrt{5})/2$。用歸納 kap Fibonacci 數 ê 定義（看Section 1.2.2）來證明 Fib$(n) = (\varphi^n - \psi^n)/\sqrt{5}$。

1.2.3 Orders of Growth 成長率

The previous examples illustrate that processes can differ considerably in the rates at which they consume computational resources. One convenient way to describe this difference is to use the notion of *order of growth* to obtain

consists of the coefficients of the terms in the expansion of $(x+y)^n$. This pattern for computing the coefficients appeared in Blaise Pascal's 1653 seminal work on probability theory, *Traité du triangle arithmétique*. According to Knuth (1973), the same pattern appears in the *Szu-yuen Yü-chien* ("The Precious Mirror of the Four Elements"), published by the Chinese mathematician Chu Shih-chieh in 1303, in the works of the twelfth-century Persian poet and mathematician Omar Khayyam, and in the works of the twelfth-century Hindu mathematician Bháscara Áchárya.

[70] Pascal 三角形內底 ê 元素號做 二項係數 (binomial coefficients)，因為第 n ê 列包含 $(x+y)^n$ ê 擴展式 ê 項 ê 係數。Chit ê 計算係數模樣出現佇 Blaise Pascal 1653 年佇機率理論方面 ê 深遠著作，就是 *Traité du triangle arithmétique*，根據 Knuth (1973)，全款 ê 模樣出現佇由中國數學家朱世傑 (Chu Shih-chieh) 佇 1303 年出版 ê《四元玉鑑》(*Szu-yuen Yü-chien*)，12 世紀波斯詩人 kap 數學家 Omar Khayyam ê 作品，kap ê 12 世紀 ê 印度數學家 Bháscara Áchárya ê 作品內底。寫一个程序，用遞迴方法算 Pascal 三角形。

a gross measure of the resources required by a process as the inputs become larger.

頂懸 ê 例說明過程會當佇 in 開運算計算資源 ê 使用率有 gōa 無仝。一个方便描述 chit ê 無仝 ê 方法，是用 成長率 ê 概念，來 thèh 當輸入變大 ê 時陣，大概所需要 ê 資源 ê 測量。

Let n be a parameter that measures the size of the problem, and let $R(n)$ be the amount of resources the process requires for a problem of size n. In our previous examples we took n to be the number for which a given function is to be computed, but there are other possibilities. For instance, if our goal is to compute an approximation to the square root of a number, we might take n to be the number of digits accuracy required. For matrix multiplication we might take n to be the number of rows in the matrices. In general there are a number of properties of the problem with respect to which it will be desirable to analyze a given process. Similarly, $R(n)$ might measure the number of internal storage registers used, the number of elementary machine operations performed, and so on. In computers that do only a fixed number of operations at a time, the time required will be proportional to the number of elementary machine operations performed.

予 n 當做量問題 sài-suh ê 參數，$R(n)$ 當做過程處理 sài-suh 是 n 問題需要 ê 資源量。佇 lán 進前 ê 例，lán thèh n 當做是函數所算 ê 次數，但是 koh 有其他可能。比如講，若是 lán ê 目標是算一个數 ê 平方根 ê 近似值，lán 可能掠 n 做需要 ê 精確數位。對矩陣 (matrix) 乘法，lán 可能掠 n 做矩陣 ê 列數。一般來講，有關係問題特性 ê 數，分析過程用 che 真理想。仝款，$R(n)$ 可能 thèh 來量內部儲存暫存器所用 ê 量、基本機器操作次數，等等。佇一改 kan-ta 做固定操作量 ê 電腦，需要 ê 時間會 hām 所行 ê 基本機器操作量成比例關係。

We say that $R(n)$ has order of growth $\Theta(f(n))$, written $R(n) = \Theta(f(n))$ (pronounced "theta of $f(n)$"), if there are positive constants k_1 and k_2 independent of n such that $k_1 f(n) \leq R(n) \leq k_2 f(n)$ for any sufficiently large value of n. (In other words, for large n, the value $R(n)$ is sandwiched

between $k_1 f(n)$ and $k_2 f(n)$.)

Lán 講 $R(n)$ 有成長率 $\Theta(f(n))$，寫做 $R(n) = \Theta(f(n))$（讀做「theta of $f(n)$」），若是有正數 k_1 kap k_2，kap n 獨立，滿足 $k_1 f(n) \leq R(n) \leq k_2 f(n)$，對任何夠大 ê n 值（別个方法講，對大 ê n，$R(n)$ ê 值予 lâng giap 佇 $k_1 f(n)$ kap $k_2 f(n)$ 中間。）

For instance, with the linear recursive process for computing factorial described in Section 1.2.1 the number of steps grows proportionally to the input n. Thus, the steps required for this process grows as $\Theta(n)$. We also saw that the space required grows as $\Theta(n)$. For the iterative factorial, the number of steps is still $\Theta(n)$ but the space is $\Theta(1)$—that is, constant.[71] The tree-recursive Fibonacci computation requires $\Theta(\varphi^n)$ steps and space $\Theta(n)$, where φ is the golden ratio described in Section 1.2.2.

舉例，佇 Section 1.2.1 提起 ê 算階乘 ê 線性遞迴過程，手續數 kap 輸入 n 成比例成長。就 án-ne，chit ê 過程需要 ê 手續，成長若 $\Theta(n)$。Lá mā 看著需要 ê 空間成長若 $\Theta(n)$。佇反覆 ê 階乘，手續數 iáu 是 $\Theta(n)$，但是空間是 $\Theta(1)$，就是常數。[72]樹遞迴 ê Fibonacci 計算，需要 $\Theta(\varphi^n)$ 步手續 kap 空間 $\Theta(n)$，其中 φ 是佇 Section 1.2.2描述 ê 黃金比例。

Orders of growth provide only a crude description of the behavior of a process. For example, a process requiring n^2 steps and a process requiring $1000n^2$ steps and a process requiring $3n^2 + 10n + 17$ steps all have $\Theta(n^2)$ order of growth. On the other hand, order of growth provides a useful indication of how we may expect the behavior of the process to change as we

[71] These statements mask a great deal of oversimplification. For instance, if we count process steps as "machine operations" we are making the assumption that the number of machine operations needed to perform, say, a multiplication is independent of the size of the numbers to be multiplied, which is false if the numbers are sufficiently large. Similar remarks hold for the estimates of space. Like the design and description of a process, the analysis of a process can be carried out at various levels of abstraction.

[72] Chiah ê 句 khàm 掉真 chē 過度簡化 ê 所在。比如講，若是 lán 用「機器操作」算過程手續，lán teh 設使需要行 ê 機器操作數，比如乘法，hām 受乘數獨立，毋過若是數字足大就毋著。佇空間 ê 估計 mā 相 siâng。親像過程 ê 設計 kap 描述，分析過程會當佇 chē-chē 款 ê 抽象層級行。

change the size of the problem. For a $\Theta(n)$ (linear) process, doubling the size will roughly double the amount of resources used. For an exponential process, each increment in problem size will multiply the resource utilization by a constant factor. In the remainder of Section 1.2 we will examine two algorithms whose order of growth is logarithmic, so that doubling the problem size increases the resource requirement by a constant amount.

成長率 kan-ta 提供粗 ê 過程行為 ê 描述。舉例，需要 n^2 ê 手續 ê 過程、需要 $1000n^2$ ê 手續 ê kap 需要 $3n^2 + 10n + 17$ ê 程序，成長率 lóng 是 $\Theta(n^2)$。另外方面，成長率提供有路用 ê 指示，對若準講 lán 改變問題 ê sài-suh，lán ê 期待過程 ê 行為 án-nóa 改變。對 $\Theta(n)$ (線性) ê 過程，sài-suh 加一倍，資源大約會加一倍。對指數 ê 過程，問題 sài-suh ê 增加會 kā 資源使用率乘以常數因子。佇Section 1.2 ê chhun ê 部份，lán ê 檢查兩个演算法，in ê 成長率是對數 ê，致 kàu kā 問題 sài-suh 加一倍，增加常數 ê 量 ê 資源需求。

Exercise 1.14: Draw the tree illustrating the process generated by the `count-change` procedure of Section 1.2.2 in making change for 11 cents. What are the orders of growth of the space and number of steps used by this process as the amount to be changed increases?

畫說明佇Section 1.2.2內底，程序 `count-change` 佇找 11 sián 所生成 ê 過程樹 á。若是找 ê 錢增加，chit ê 過程所用 ê 空間 kap 手續數 ê 成長率是 siáⁿ 物？

Exercise 1.15: The sine of an angle (specified in radians) can be computed by making use of the approximation $\sin x \approx x$ if x is sufficiently small, and the trigonometric identity

角 ê 正弦（用弧度表示）會當用$\sin x \approx x$ ê 近似來算，nā 準 x 有夠細

而且三角函數等式 (trigonometric identity)

$$\sin x = 3 \sin \frac{x}{3} - 4 \sin^3 \frac{x}{3}$$

to reduce the size of the argument of sin. (For purposes of this exercise an angle is considered "sufficiently small" if its magnitude is not greater than 0.1 radians.) These ideas are incorporated in the following procedures:

會當減少 sin ê 引數 ê sài-suh。(本練習 ê 目的內底，nā 是角 ê 角度無比 0.1 弧度較大，chit ê 角就掠做有夠細)。Chiah ê 想法包含佇下 kha ê 程序：

```
(define (cube x) (* x x x))
(define (p x) (- (* 3 x) (* 4 (cube x))))
(define (sine angle)
   (if (not (> (abs angle) 0.1))
       angle
       (p (sine (/ angle 3.0)))))
```

a. How many times is the procedure `p` applied when `(sine 12.15)` is evaluated? 若是算 `(sine 12.15)` ê 值，程序 `p` 受應用幾改？

b. What is the order of growth in space and number of steps (as a function of a) used by the process generated by the `sine` procedure when `(sine a)` is evaluated? 若算 `(sine a)` ê 值，chit ê `sine` 所生成 ê 過程（當做 a ê 函數）所用 ê 空間 kap 手續數 ê 成長率是 siáⁿ 物？

1.2.4 Exponentiation 指數運算

Consider the problem of computing the exponential of a given number. We would like a procedure that takes as arguments a base b and a positive integer

exponent n and computes b^n. One way to do this is via the recursive definition

考慮計算數 ê 指數函數 ê 問題。Lán beh 愛一个程序，thèh 底數 b kap 正整數指數 n，算出 b^n。一个方法是用遞迴定義

$$b^n = b \cdot b^{n-1},$$
$$b^0 = 1,$$

which translates readily into the procedure

緊緊翻譯做程序就是

```
(define (expt b n)
  (if (= n 0)
      1
      (* b (expt b (- n 1)))))
```

This is a linear recursive process, which requires $\Theta(n)$ steps and $\Theta(n)$ space. Just as with factorial, we can readily formulate an equivalent linear iteration:

Che 是線性遞迴過程，需要 $\Theta(n)$ ê 手續 kap $\Theta(n)$ ê 空間。親像函數，lán 通容易規範做等價 ê 線性反覆：

```
(define (expt b n)
  (expt-iter b n 1))
(define (expt-iter b counter product)
  (if (= counter 0)
      product
      (expt-iter b
                 (- counter 1)
                 (* b product))))
```

This version requires $\Theta(n)$ steps and $\Theta(1)$ space.

Chit ê 版本需要 $\Theta(n)$ 手續 kap $\Theta(1)$ 空間。

We can compute exponentials in fewer steps by using successive squaring. For instance, rather than computing b^8 as

倚靠連 sòa 平方 ê 方法，lán 會當用較少 ê 手續計算指數。比如講，無 kā b^8 án-ne 算

$$b \cdot (b \cdot (b \cdot (b \cdot (b \cdot (b \cdot b))))),$$

we can compute it using three multiplications:

Lán 顛倒會當用三个乘法計算：

$$\begin{aligned} b^2 &= b \cdot b, \\ b^4 &= b^2 \cdot b^2, \\ b^8 &= b^4 \cdot b^4. \end{aligned}$$

This method works fine for exponents that are powers of 2. We can also take advantage of successive squaring in computing exponentials in general if we use the rule

Chit ê 方法佇指數是 2 ê 冪 (bėk) ê 時陣運作誠好。Nā 是用下 kha ê 規則，lán mā 通利用連 sòa 平方 ê 方法佇一般算指數 ê 過程：

$$\begin{aligned} b^n &= (b^{n/2})^2 \quad \text{if } n \text{ is even (nā n 是雙數),} \\ b^n &= b \cdot b^{n-1} \quad \text{if } n \text{ is odd (nā n 是單數).} \end{aligned}$$

We can express this method as a procedure:

Lán 通用程序方式，表達 chit ê 方法：

```
(define (fast-expt b n)
  (cond ((= n 0) 1)
        ((even? n) (square (fast-expt b (/ n 2))))
        (else (* b (fast-expt b (- n 1))))))
```

where the predicate to test whether an integer is even is defined in terms of the primitive procedure `remainder` by

其中測試一个整數敢是雙數 ê 謂詞，是用基礎程序 `remainder` 所定義，ná 下 kha：

```
(define (even? n)
  (= (remainder n 2) 0))
```

The process evolved by `fast-expt` grows logarithmically with n in both space and number of steps. To see this, observe that computing b^{2n} using `fast-expt` requires only one more multiplication than computing b^n. The size of the exponent we can compute therefore doubles (approximately) with every new multiplication we are allowed. Thus, the number of multiplications required for an exponent of n grows about as fast as the logarithm of n to the base 2. The process has $\Theta(\log n)$ growth.[73]

`fast-expt` 所擴展 ê 過程佇空間 kap 手續數方面,kap n 成對數方式成長。Beh 看 che，觀察用 `fast-expt` 計算 b^{2n}，比 b^n，kan-ta 需要加一改乘法。所以若是 lán 會當加用乘法，lán 通算 ê 指數 ê sài-suh 會變雙倍。就 án-ne，n ê 指數所需要 ê 乘法數成長大約 kap n ê 以 2 為底 ê 對數平緊。Chit ê 過程 ê 成長率是 $\Theta(\log n)$。[74]

The difference between $\Theta(\log n)$ growth and $\Theta(n)$ growth becomes striking as n becomes large. For example, `fast-expt` for n = 1000 requires only 14 multiplications.[75] It is also possible to use the idea of successive squaring to devise an iterative algorithm that computes exponentials with a logarithmic number of steps (see Exercise 1.16), although, as is often the case with iterative algorithms, this is not written down so straightforwardly as the

[73] More precisely, the number of multiplications required is equal to 1 less than the log base 2 of n plus the number of ones in the binary representation of n. This total is always less than twice the log base 2 of n. The arbitrary constants k_1 and k_2 in the definition of order notation imply that, for a logarithmic process, the base to which logarithms are taken does not matter, so all such processes are described as $\Theta(\log n)$.

[74] 較準確來講，需要 ê 乘法數等於 n ê 以 2 為底 ê 對數減 1，koh 加 n ê 二進位表示 ê 1 ê 數量。總計定著較少 n ê 2 為底 ê 對數 ê 2 倍。任何佇成長率定義 ê 表示法 ê 常數 k_1 kap k_2 chhàng 著對對數過程，對數 ê 底無要緊 ê 意思，所以任何 chit 款 ê 過程 lóng 用 $\Theta(\log n)$ 描述。

[75] You may wonder why anyone would care about raising numbers to the 1000th power. See Section 1.2.6.

recursive algorithm.[76]

$\Theta(\log n)$ ê 成長 kap $\Theta(n)$ ê 成長 ê 差別佇 n 變 koh 較大 ê 時陣會誠明顯。舉例，若是 $n = 1000$，`fast-expt` kan-ta 需要 14 ê 乘法。[77] Mā 是有可能用相 sòa ê 平方 ê 想法來設計反覆 ê，用對數 ê 手續數算指數 ê 演算法。(看Exercise 1.16)，雖 bóng 就親像反覆 ê 演算法 ê 例，寫 che 無像遞迴演算法 hiah 直接。[78]

> **Exercise 1.16:** Design a procedure that evolves an iterative exponentiation process that uses successive squaring and uses a logarithmic number of steps, as does `fast-expt`. (Hint: Using the observation that $(b^{n/2})^2 = (b^2)^{n/2}$, keep, along with the exponent n and the base b, an additional state variable a, and define the state transformation in such a way that the product ab^n is unchanged from state to state. At the beginning of the process a is taken to be 1, and the answer is given by the value of a at the end of the process. In general, the technique of defining an *invariant quantity* that remains unchanged from state to state is a powerful way to think about the design of iterative algorithms.)
>
> 設計一个程序，擴展反覆 ê 指數過程，伊使用相連 sòa ê 平方 kap 用對數 ê 手續數，親像 `fast-expt` 所行 ê。(提示：用觀察 $(b^{n/2})^2 = (b^2)^{n/2}$，kap 保持指數 n、底數 b，以及加添 ê

[76] This iterative algorithm is ancient. It appears in the *Chandah-sutra* by Áchárya Pingala, written before 200 B.C. See Knuth 1981, section 4.6.3, for a full discussion and analysis of this and other methods of exponentiation.

[77] Lí 可能好奇，是 án-nóa 有 lâng 會關心 kā 數字 giâ kàu 伊 ê 1000 次方。看Section 1.2.6。

[78] Chit ê 反覆演算法誠古早。伊出現佇 Áchárya Pingala 佇西元前 200 年進前寫 ê *Chandah-sutra*。看Knuth 1981，第 4.6.3 節，來得著 chit ê kap 其他指數運算 ê 方法 ê 全面討論 kap 分析。

狀態變數 a ，而且定義狀態變換，致使狀態變換中間，ab^n ê 乘積 lóng 無變。佇過程起頭，a 設做 1，佇過程 soah ê 時陣，a ê 值就是答案。一般來講，定義佇狀態變換之內維持不變 ê 不變量 (invariant quantity) 是有力 ê 方法，來考慮反覆演算法 ê 設計。

Exercise 1.17: The exponentiation algorithms in this section are based on performing exponentiation by means of repeated multiplication. In a similar way, one can perform integer multiplication by means of repeated addition. The following multiplication procedure (in which it is assumed that our language can only add, not multiply) is analogous to the `expt` procedure:

本節 ê 指數演算法是用重覆乘法運算。用相 siâng ê 方法，會當用重覆加法來行整數乘法。下 kha ê 乘法程序（佇 chia 假設 lán ê 語言會當加，bē 當乘），kap `expt` 程序比並：

```
(define (* a b)
  (if (= b 0)
      0
      (+ a (* a (- b 1)))))
```

This algorithm takes a number of steps that is linear in `b`. Now suppose we include, together with addition, operations `double`, which doubles an integer, and `halve`, which divides an (even) integer by 2. Using these, design a multiplication procedure analogous to `fast-expt` that uses a logarithmic number of steps.

Chit ê 程序 thèh 線性 ê 手續數佇 `b`。Chit-má 假設 lán 包含加法、操作 `double`（kā 整數乘以 2 倍），kap `halve`（kā 雙數除以 2）。用 chiah-ê，設計一个乘法程序，kap `fast-expt` 比並，而且使用對數 ê 手續數。

Exercise 1.18: Using the results of Exercise 1.16 and Exercise 1.17, devise a procedure that generates an iterative process for multiplying two integers in terms of adding, doubling, and halving and uses a logarithmic number of steps.[79]

使用Exercise 1.16 kap Exercise 1.17 ê 結果，想出一个程序，生成反覆 ê，kā 兩个整數相乘 ê 過程，使用加、kā 整數乘以 2 倍 kap kā 雙數除以 2 ê 方式，而且用對數 ê 手續數。[80]

Exercise 1.19: There is a clever algorithm for computing the Fibonacci numbers in a logarithmic number of steps. Recall the transformation of the state variables a and b in the `fib-iter` process of Section 1.2.2: $a \leftarrow a + b$ and $b \leftarrow a$. Call this transformation T, and observe that applying T over and over again n times, starting with 1 and 0, produces the pair Fib$(n+1)$ and Fib(n). In other words, the Fibonacci numbers are produced by applying T^n, the nth power of the transformation T, starting with the pair (1, 0). Now consider T to be the special case of $p = 0$ and $q = 1$ in a family of transformations T_{pq}, where T_{pq} transforms the pair (a, b) according to $a \leftarrow bq + aq + ap$ and $b \leftarrow bp + aq$. Show that if we apply such a transformation T_{pq} twice, the effect is the same as using a single transformation $T_{p'q'}$ of the same form, and compute p' and q' in terms of p and q. This gives us an explicit way to square these transformations,

[79] This algorithm, which is sometimes known as the "Russian peasant method" of multiplication, is ancient. Examples of its use are found in the Rhind Papyrus, one of the two oldest mathematical documents in existence, written about 1700 B.C. (and copied from an even older document) by an Egyptian scribe named A'h-mose.

[80] Chit ê 演算法，有時仔號做乘法 ê「露西亞 choh-sit-lâng 方法」(Russian peasant method)，是古早 ê 方法。Chit ê 方法 ê 例會當佇 Rhind 紙草紙 (Papyrus) 揣著，伊是兩篇佇 leh ê 上古早 ê 數學文件之一，由埃及書記 A'h-mose 寫佇大約西元前 1700 年（伊家己 mā 是較早 ê 文件 ê 抄本）。

and thus we can compute T^n using successive squaring, as in the `fast-expt` procedure. Put this all together to complete the following procedure, which runs in a logarithmic number of steps:[81]

有巧 ê 演算法來用對數 ê 手續數算 Fibonacci 數。回想佇 Section 1.2.2內底，`fib-iter` 程序內底 ê 狀態變數 a kap b ê 變換：$a \leftarrow a + b$ kap $b \leftarrow a$。Kā chit ê 變換號做 T，觀察直直應用 T n 改，用 1 kap 0 開始，產生數對 Fib$(n+1)$ kap Fib(n)。換別句話講，Fibonacci 數是 kā 開始 ê 數列 (1,0) 應用 T^n，就是變換 T ê n^{th} 次方來生成。Chit-má kā T 掠做 $p = 0$ kap $q = 1$ ê 時 ê 變換 T_{pq} ê 特殊形式，其中 T_{pq} 根據 $a \leftarrow bq + aq + ap$ kap $b \leftarrow bp + aq$ 變換數對 (a, b)。展示若是 lán 應用 chit 款變換 T_{pq} 2 改，效果 kap 用一个 kâng 形 ê 變換 $T_{p'q'}$ kâng 款。用 p kap q ê 形式算出 p' kap q'。Che 予 lán 明顯 ê 方法來平方 chiah ê 變換，lán 就 án-ne 會當用相連 sòa ê 平方計算 T^n，親像佇 `fast-expt` 程序。請 kā 逐个門做伙完成下 kha ê 程序，伊用對數 ê 手續數 pháng：[82]

```
(define (fib n)
  (fib-iter 1 0 0 1 n))
(define (fib-iter a b p q count)
  (cond ((= count 0) b)
        ((even? count)
         (fib-iter a
                   b
                   ⟨??⟩    ; compute p′
                   ⟨??⟩    ; compute q′
                   (/ count 2)))
        (else (fib-iter (+ (* b q) (* a q) (* a p))
```

[81] This exercise was suggested to us by Joe Stoy, based on an example in Kaldewaij 1990.

[82] Chit ê 練習是 Joe Stoy 由推薦予 lán，根據佇 Kaldewaij 1990 ê 例。

```
(+ (* b p) (* a q))
p
q
(- count 1)))))
```

1.2.5 Greatest Common Divisors 上大公約數

The greatest common divisor (GCD) of two integers a and b is defined to be the largest integer that divides both a and b with no remainder. For example, the GCD of 16 and 28 is 4. In Chapter 2, when we investigate how to implement rational-number arithmetic, we will need to be able to compute GCDs in order to reduce rational numbers to lowest terms. (To reduce a rational number to lowest terms, we must divide both the numerator and the denominator by their GCD. For example, 16/28 reduces to 4/7.) One way to find the GCD of two integers is to factor them and search for common factors, but there is a famous algorithm that is much more efficient.
整數 a kap b ê 上大公約數 (GCD) ê 定義是，上大 ê 整數 kā a kap b 除，lóng 無餘數。比如講，16 kap 28 ê 上大公約數是 4。佇Chapter 2，當 lán 調查按怎實做有理數運算，lán 會需要會曉計算上大公約數，為著欲約分 (reduce) 有理數 kàu 上短 ê 形式 (lowest terms)（欲約分有理數 kàu 上短 ê 形式，lán tiòh kā 分子 kap 分母 lóng 予上大公約數除，比如 16/28 約分變做 4/7。）一款 chhiau 兩个整數 ê 上大公約數 ê 方法是 kā in 因數分解了後，chhōe in ê 公約數。但是有出名 ê 演算法，koh 較有效率。

The idea of the algorithm is based on the observation that, if r is the remainder when a is divided by b, then the common divisors of a and b are precisely the same as the common divisors of b and r. Thus, we can use the equation

Chit ê 演算法 ê 想法徛起佇 chit ê 觀察，就是 nā r 是 a 予 b 除 ê 餘數，a kap b ê 公約數就準確是 b kap r ê 公約數。就 án-ne，lán 通用方程式

```
GCD(a,b) = GCD(b,r)
```

to successively reduce the problem of computing a GCD to the problem of computing the GCD of smaller and smaller pairs of integers. For example,
來相連 sòa 縮小計算上大公約數 ê 問題，kàu 別个愈來愈細 ê 數對 ê 上大公約數 ê 問題。比如，

```
GCD(206,40) = GCD(40,6)
            = GCD(6,4)
            = GCD(4,2)
            = GCD(2,0)
            = 2
```

reduces GCD(206, 40) to GCD(2, 0), which is 2. It is possible to show that starting with any two positive integers and performing repeated reductions will always eventually produce a pair where the second number is 0. Then the GCD is the other number in the pair. This method for computing the GCD is known as *Euclid's Algorithm*.[83]

GCD(206, 40) 就縮小 kàu GCD(2, 0)，就是 2。有可能展示用 2 ê 正整數開始，而且行重覆縮小就定著落尾會產生一个數對，其中第二个數是 0。上大公因數就是數對 ê 另外一个數。Chit ê 計算上大公因數 ê 方法號做*Euclid ê* 演算法 (Euclid's Algorithm)。[84]

It is easy to express Euclid's Algorithm as a procedure:

[83] Euclid's Algorithm is so called because it appears in Euclid's *Elements* (Book 7, ca. 300 B.C.). According to Knuth (1973), it can be considered the oldest known nontrivial algorithm. The ancient Egyptian method of multiplication (Exercise 1.18) is surely older, but, as Knuth explains, Euclid's algorithm is the oldest known to have been presented as a general algorithm, rather than as a set of illustrative examples.

[84] 號做 Euclid ê 演算法是因為伊出現佇 Euclid ê *Elements* (Book 7, ca. 300 B.C.). 根據 Knuth (1973)，伊通掠做是上早 ê 非自明 (nontrivial) 演算法。乘法 ê 古早 ê 埃及方法 (Exercise 1.18) 當然較早，但是，像 Knuth 所解說，Euclid ê 演算法是上早用一般演算法 ê 形式所展示 ê，毋是說明性 ê 案例 ê 集合。

Euclid ê 演算法用程序來表示，是真快：

```
(define (gcd a b)
  (if (= b 0)
      a
      (gcd b (remainder a b))))
```

This generates an iterative process, whose number of steps grows as the logarithm of the numbers involved.

Che 生成反覆 ê 過程，伊 ê 手續數照輸入 ê 數字 ê 對數成長。

The fact that the number of steps required by Euclid's Algorithm has logarithmic growth bears an interesting relation to the Fibonacci numbers:

Euclid ê 演算法成對數成長 ê 事實，送出一个 kap Fibonacci 數 ê 趣味 ê 關係：

> **Lamé's Theorem:** If Euclid's Algorithm requires k steps to compute the GCD of some pair, then the smaller number in the pair must be greater than or equal to the kth Fibonacci number.[85]

[85] This theorem was proved in 1845 by Gabriel Lamé, a French mathematician and engineer known chiefly for his contributions to mathematical physics. To prove the theorem, we consider pairs (a_k, b_k), where $a_k \geq b_k$, for which Euclid's Algorithm terminates in k steps. The proof is based on the claim that, if $(a_{k+1}, b_{k+1}) \rightarrow (a_k, b_k) \rightarrow (a_{k-1}, b_{k-1})$ are three successive pairs in the reduction process, then we must have $b_{k+1} \geq b_k + b_{k-1}$. To verify the claim, consider that a reduction step is defined by applying the transformation $a_{k-1} = b_k, b_{k-1} =$ remainder of a_k divided by b_k. The second equation means that $a_k = qb_k + b_{k-1}$ for some positive integer q. And since q must be at least 1 we have $a_k = qb_k + b_{k-1} \geq b_k + b_{k-1}$. But in the previous reduction step we have $b_{k+1} = a_k$. Therefore, $b_{k+1} = a_k \geq b_k + b_{k-1}$. This verifies the claim. Now we can prove the theorem by induction on k, the number of steps that the algorithm requires to terminate. The result is true for $k = 1$, since this merely requires that b be at least as large as Fib(1) = 1. Now, assume that the result is true for all integers less than or equal to k and establish the result for $k + 1$. Let $(a_{k+1}, b_{k+1}) \rightarrow (a_k, b_k) \rightarrow (a_{k-1}, b_{k-1})$ be successive pairs in the reduction process. By our induction hypotheses, we have $b_{k-1} \geq \text{Fib}(k-1)$ and $b_k \geq \text{Fib}(k)$. Thus, applying the claim we

Lamé ê 定理 若是 Euclid ê 演算法需要 k 步來算一个數對 ê 上大公約數，數對內底上細 ê 數一定無比第 k ê Fibonacci 數較細。[86]

We can use this theorem to get an order-of-growth estimate for Euclid's Algorithm. Let n be the smaller of the two inputs to the procedure. If the process takes k steps, then we must have $n \geq \mathrm{Fib}(k) \approx \varphi^k/\sqrt{5}$. Therefore the number of steps k grows as the logarithm (to the base φ) of n. Hence, the order of growth is $\Theta(\log n)$.

Lán 通用 chit ê 定理來 thèh 著 Euclid ê 演算法 ê 成長級 ê 估計。Kā n 設做 2 ê 輸入值 ê 上細 ê。準講程序行 k 步，lán 著有 $n \geq \mathrm{Fib}(k) \approx \varphi^k/\sqrt{5}$。就 án-ne 手續數 k，用 n ê 掠 φ 做底數 ê 對數 ê 方式成長。所以，成長級是 $\Theta(\log n)$。

Exercise 1.20: The process that a procedure generates is of course dependent on the rules used by the interpreter. As an exam-

---

just proved together with the definition of the Fibonacci numbers gives $b_{k+1} \geq b_k + b_{k-1} \geq \mathrm{Fib}(k) + \mathrm{Fib}(k-1) = \mathrm{Fib}(k+1)$, which completes the proof of Lamé's Theorem.

[86] Chit ê 定理由 Gabriel Lamé 佇 1845 年證明，伊是法國數學家 kap 工程師，主要因為伊對數學物理 ê 貢獻出名。Beh 證明 chit ê 定理，lán 考慮數對 (a_k, b_k)，其中 $a_k \geq b_k$，對 che，Euclid ê 演算法佇 k 步內中止。證明是 chhāi 佇若 $(a_{k+1}, b_{k+1}) \to (a_k, b_k) \to (a_{k-1}, b_{k-1})$ 是 3 ê 佇縮小 ê 過程相 sòa ê 數對，lán 定著有 $b_{k+1} \geq b_k + b_{k-1}$ ê 主張。Beh 驗證 chit ê 主張，考慮減少 ê 手續是由應用轉換「$a_{k-1} = b_k, b_{k-1} = a_k$ 予 b_k 除 ê 餘數」所定義。第二 ê 程式意思是 $a_k = qb_k + b_{k-1}$ 對正整數 q。而且因為 q 上少一定是 1，lán 有 $a_k = qb_k + b_{k-1} \geq b_k + b_{k-1}$。毋過佇頂一 ê 縮小 ê 手續 lán 有 $b_{k+1} = a_k$。因此，$b_{k+1} = a_k \geq b_k + b_{k-1}$。Che 驗證 chit ê 主張。Chit-má lán 通用佇 k （演算法 beh 停止所愛 ê 手續數）ê 歸納，來證明 chit ê 定理。對 $k = 1$，結果是真 ê，因為這 kan-ta 需要 b 上少 kap Fib(1)（伊 ê 值是 1）平大。Chit-má，設使對所有無超過 k ê 整數是真 ê，而且成立對 $k+1$ ê 結果。Lán kā $(a_{k+1}, b_{k+1}) \to (a_k, b_k) \to (a_{k-1}, b_{k-1})$ 準做佇縮小過程內底相連 sòa ê 數對。靠 lán ê 歸納假設，lán 有 $b_{k-1} \geq \mathrm{Fib}(k-1)$ kap $b_k \geq \mathrm{Fib}(k)$。就 án-ne，應用 chit ê 頭拄 á 證明 ê 主張 kap Fibonacci 數 ê 定義，得著 $b_{k+1} \geq b_k + b_{k-1} \geq \mathrm{Fib}(k) + \mathrm{Fib}(k-1) = \mathrm{Fib}(k+1)$，完成證明 Lamé ê 定理。

ple, consider the iterative `gcd` procedure given above. Suppose we were to interpret this procedure using normal-order evaluation, as discussed in Section 1.1.5. (The normal-order-evaluation rule for `if` is described in Exercise 1.5.) Using the substitution method (for normal order), illustrate the process generated in evaluating `(gcd 206 40)` and indicate the `remainder` operations that are actually performed. How many `remainder` operations are actually performed in the normal-order evaluation of `(gcd 206 40)`? In the applicative-order evaluation?

Exercise 1.20: 程序生成 ê 過程當然倚佇直譯器所用 ê 規則。比如講，考慮面頂 ê 反覆 ê `gcd` 程序。設使 lán beh 用正規序直譯 chit ê 程序，親像佇Section 1.1.5所討論 ê。（`if` ê 正規序算值佇 Exercise 1.5有描述）用替代法（正規序），請說明佇算 `(gcd 206 40)` ê 值生出來 ê 過程，koh 標示實際行 ê `remainder` 操作。佇用正規序算 `(gcd 206 40)` ê 值中，`remainder` 實際行 gōa chē 改？佇應用序算值是 gōa chē 改？

1.2.6 Example: Testing for Primality 例：判定質數

This section describes two methods for checking the primality of an integer n, one with order of growth $\Theta(\sqrt{n})$, and a "probabilistic" algorithm with order of growth $\Theta(\log n)$. The exercises at the end of this section suggest programming projects based on these algorithms.

Chit 節描述兩个檢查整數 n 敢是指數 ê 方法，一个 ê 成長率是 $\Theta(\sqrt{n})$，kap 另外一个「機率性 ê」演算法，伊 ê 成長率是 $\Theta(\log n)$。本節尾 á ê 練習提出 chhāi 佇 chiah ê 演算法 ê 程式設計專案。

Searching for divisors Chhiau 約數

Since ancient times, mathematicians have been fascinated by problems concerning prime numbers, and many people have worked on the problem of determining ways to test if numbers are prime. One way to test if a number is prime is to find the number's divisors. The following program finds the smallest integral divisor (greater than 1) of a given number n. It does this in a straightforward way, by testing n for divisibility by successive integers starting with 2.
對古早時代，數學家就痴迷佇關係質數 ê 問題，chē-chē lâng 骨力佇決定判定數字敢是質數 ê 方法 ê 問題。Chit ê 判定數敢是質數 ê 方法，是 chhōe 著數字 ê 因數。下 kha ê 程式 chhōe 數字 n ê 上細 ê 整除 ê 除數（超過 1）。伊行佇直接 ê 方式，用對 2 開始相 sòa ê 整數，試伊對 n ê 整除性。

```
(define (smallest-divisor n) (find-divisor n 2))
(define (find-divisor n test-divisor)
  (cond ((> (square test-divisor) n) n)
        ((divides? test-divisor n) test-divisor)
        (else (find-divisor n (+ test-divisor 1)))))
(define (divides? a b) (= (remainder b a) 0))
```

We can test whether a number is prime as follows: n is prime if and only if n is its own smallest divisor.
Lán 會當用下 kha ê 方法測試一个數敢是質數：n 是質數，若而且 kan-ta 若 n 是伊家己上細 ê 約數（譯註：而且超過 1）。

```
(define (prime? n)
  (= n (smallest-divisor n)))
```

The end test for `find-divisor` is based on the fact that if n is not prime it must have a divisor less than or equal to $\sqrt{n}$.[87] This means that the algorithm

[87] If d is a divisor of n, then so is n/d. But d and n/d cannot both be greater than $\sqrt{n}$.

need only test divisors between 1 and $\sqrt{n}$. Consequently, the number of steps required to identify n as prime will have order of growth $\Theta(\sqrt{n})$.
`find-divisor` 上尾 ê 測試是 chhāi 佇 chit ê 事實，就是若 n 毋是質數，定著有約數無超過 $\sqrt{n}$。[88] Che 意思是 chit ê 演算法 kan-ta 需要試 1 kàu $\sqrt{n}$ 之間 ê 約數。結果，判定 n 是質數需要 ê 手續數 ē 有成長率 $\Theta(\sqrt{n})$。

The Fermat test Fermat 測試

The $\Theta(\log n)$ primality test is based on a result from number theory known as Fermat's Little Theorem.[89]
$\Theta(\log n)$ ê 質數測試是 chhāi 佇對號做 Fermat ê 小定理 ê 數論 ê 結果來 ê。[90]

Fermat's Little Theorem: If n is a prime number and a is any

[88] 若是 d 是 n ê 約數，n/d mā 是。但是 d kap n/d bōe 當同時超過 $\sqrt{n}$。

[89] Pierre de Fermat (1601-1665) is considered to be the founder of modern number theory. He obtained many important number-theoretic results, but he usually announced just the results, without providing his proofs. Fermat's Little Theorem was stated in a letter he wrote in 1640. The first published proof was given by Euler in 1736 (and an earlier, identical proof was discovered in the unpublished manuscripts of Leibniz). The most famous of Fermat's results—known as Fermat's Last Theorem—was jotted down in 1637 in his copy of the book *Arithmetic* (by the third-century Greek mathematician Diophantus) with the remark "I have discovered a truly remarkable proof, but this margin is too small to contain it." Finding a proof of Fermat's Last Theorem became one of the most famous challenges in number theory. A complete solution was finally given in 1995 by Andrew Wiles of Princeton University.

[90] Pierre de Fermat (1601-1665) 受掠做現代數論 ê 創立者。伊 thèh 著 chē-chē 重要 ê 數論結果，但是伊定定 kan-ta 宣佈結果，無提供伊 ê 證明。Fermat ê 小定理是寫佇伊佇 1640 年寫 ê phoe。頭一个出版 ê 證明是由 Euler 佇 1736 年推出。(較早 ê，siâng 款 ê 證明 mā 佇 Leibniz 無出版 ê 手稿內發現)。上出名 ê Fermat ê 結果——號做 Fermat 上尾 ê 定理是佇 1637 年緊緊記佇伊 ê *Arithmetic* (第三世紀 ê 希臘數學家 Diophantus 寫 ê) chit 本冊 ê khó-pih，koh 寫註：「我有發現真 ê 無四常 ê 記錄，但是邊 á 傷細，beh 當總寫。」chhiau-chhōe Fermat ê 上尾 ê 定理成做數論內底上出名 ê 挑戰之一。全面 ê 解落尾由 Princeton 大學 ê Andrew Wiles 佇 1995 年提出。

positive integer less than n, then a raised to the nth power is congruent to a modulo n.

Fermat ê 小定理：若 n 是質數，而且 a 是任何比 n 較細 ê 正整數，án-ne a ê n 次方 hām a，予 n 除 ê 時，就有 kâng 款 ê 餘數 (a raised to the nth power is congruent to a modulo n)。

(Two numbers are said to be *congruent modulo* n if they both have the same remainder when divided by n. The remainder of a number a when divided by n is also referred to as the *remainder of* a *modulo* n, or simply as a *modulo* n.)

(若準兩 ê 數兩 ê 予 n 除 ê 時，有平大 ê 餘數 (remainder)，就通講 in 予 n 除，有 *kâng* 款 *ê* 餘數 (congruent modulo)。數 a 予 n 除 ê 餘數，ē 當講是 a modulo n ê 餘數，á 是簡略做 a modulo n。)

If n is not prime, then, in general, most of the numbers $a < n$ will not satisfy the above relation. This leads to the following algorithm for testing primality: Given a number n, pick a random number $a < n$ and compute the remainder of a^n modulo n. If the result is not equal to a, then n is certainly not prime. If it is a, then chances are good that n is prime. Now pick another random number a and test it with the same method. If it also satisfies the equation, then we can be even more confident that n is prime. By trying more and more values of a, we can increase our confidence in the result. This algorithm is known as the Fermat test.

若是 n 毋是質數，一般來講，大部份 ê 數 $a < n$ 就 bōe 滿足頂懸 ê 關係。這致 kàu 下 kha 判定質數 ê 演算法：有數字 n，揀隨機 ê 數 $a < n$，而且算 a^n 予 n 除 ê 餘數。若是結果無等於 a，n 當然毋是質數。若是是 a，就有可能是質數。Chit-má 揀別 ê 隨機數 a，用 kâng 款 ê 方法測試。靠試愈來愈 chē ê a，lán 通增加對結果 ê 信心。Chit ê 演算法號做 Fermat 測試。

To implement the Fermat test, we need a procedure that computes the exponential of a number modulo another number:

Beh 實做 Fermat 測試，lán 需要一个程序，來計算一个數予另外一个數除 ê 餘數 ê 指數：

```
(define (expmod base exp m)
  (cond ((= exp 0) 1)
        ((even? exp)
         (remainder
          (square (expmod base (/ exp 2) m))
          m))
        (else
         (remainder
          (* base (expmod base (- exp 1) m))
          m))))
```

This is very similar to the `fast-expt` procedure of Section 1.2.4. It uses successive squaring, so that the number of steps grows logarithmically with the exponent.[91]

Che kap Section 1.2.4 ê `fast-expt` 程序真 sêng。伊用相 sòa ê 平方，致 kàu 手續數綴指數照對數成長。[92]

The Fermat test is performed by choosing at random a number a between 1 and $n - 1$ inclusive and checking whether the remainder modulo n of the nth power of a is equal to a. The random number a is chosen using the

[91] The reduction steps in the cases where the exponent e is greater than 1 are based on the fact that, for any integers x, y, and m, we can find the remainder of x times y modulo m by computing separately the remainders of x modulo m and y modulo m, multiplying these, and then taking the remainder of the result modulo m. For instance, in the case where e is even, we compute the remainder of $b^{e/2}$ modulo m, square this, and take the remainder modulo m. This technique is useful because it means we can perform our computation without ever having to deal with numbers much larger than m. (Compare Exercise 1.25.)

[92] 佇指數 e 超過 1 ê 例內底，縮小 ê 手續是根據 chit ê 事實，就是對任何整數 x、y kap m，lán 通用分別算 x 予 m 除 ê 餘數 kap y 予 m 除 ê 餘數，然後 kā chit 兩个餘數相乘，koh 算伊予 m 除 ê 餘數，來 chhōe 著 $(x \times y)$ 予 m 除 ê 餘數。比論，佇 e 是雙數 ê 時陣，lán 算 $b^{e/2}$ 予 m 除 ê 餘數，koh kā 平方，koh 算出伊予 m 除 ê 餘數。Chit ê 技術 chiâⁿ 有路用，因為伊代表 lán 毋免 tāi 先處理比 m 較大 ê 數，chiah 通行 lán ê 運算。(比較 Exerxise 1.25)

procedure `random`, which we assume is included as a primitive in Scheme. `random` returns a nonnegative integer less than its integer input. Hence, to obtain a random number between 1 and $n - 1$, we call `random` with an input of $n - 1$ and add 1 to the result:

Fermat ê 測試 ê 行法，是對 1 kàu $n - 1$（包含）之間 chhìn-chhái 揀一个整數，檢查 a ê n 次方予 n 除 ê 餘數敢等於 a。隨機數 a 用程序 `random` 揀，設使伊是佇 Scheme 內底 ê 基礎運算。`random` 傳轉去比輸入 ê 整數較細 ê，毋是負數 ê 整數。就 án-ne，beh chhìn-chhái thèh 著佇 1 kap $n - 1$ 之間 ê 數，lán kā $n - 1$ 傳入去 `random`，koh kā 輸出 ê 結果加 1：

```
(define (fermat-test n)
  (define (try-it a)
    (= (expmod a n n) a))
  (try-it (+ 1 (random (- n 1)))))
```

The following procedure runs the test a given number of times, as specified by a parameter. Its value is true if the test succeeds every time, and false otherwise.

下 kha ê 程序行測試幾 lo̍h 改（由參數決定）。若是測試逐擺 lóng 成功，伊 ê 值就是真 ê，ah 無就是假 ê。

```
(define (fast-prime? n times)
  (cond ((= times 0) true)
        ((fermat-test n) (fast-prime? n (- times 1)))
        (else false)))
```

Probabilistic methods 機率法

The Fermat test differs in character from most familiar algorithms, in which one computes an answer that is guaranteed to be correct. Here, the answer obtained is only probably correct. More precisely, if n ever fails the Fermat test, we can be certain that n is not prime. But the fact that n passes the test,

while an extremely strong indication, is still not a guarantee that n is prime. What we would like to say is that for any number n, if we perform the test enough times and find that n always passes the test, then the probability of error in our primality test can be made as small as we like.
Fermat ê 測試 kap 大部份熟似 ê，算出來 ê 答案保證精確 ê 演算法無 kâng 款。佇 chia，所得著 ê 答案 kan-ta 是可能正確 ê。Koh 較準確來講，若是 n 捌佇 Fermat ê 測試失敗，lán 會當有把握 n 毋是質數。但是 n 通過測試，而且有極其強 ê 標示（譯註：就是測試 ê 數真 chē，致 kàu lán 有蓋大 ê 信心來信）是事實，mā 無保證 n 是質數。Lán 想 beh 講 ê 是，對所有 ê 數字 n，若 lán 行測試有夠 chē 改，而且發現 n lóng 通過 chit ê 測試，佇 lán ê 質數判定 ê 錯誤機率會當細 kah lán 意愛 ê 標準。

Unfortunately, this assertion is not quite correct. There do exist numbers that fool the Fermat test: numbers n that are not prime and yet have the property that a^n is congruent to a modulo n for all integers $a < n$. Such numbers are extremely rare, so the Fermat test is quite reliable in practice.[93]

這个宣稱不幸無精確。Chia 就有數字 ē 騙過 Fermat ê 測試：數字 n 毋是質數，毋 koh 有 chit ê 性質，就是對逐个整數 $a < n$，a^n kap a 予 n 除，有 kâng 款 ê 餘數。Chit 款數極其少，Fermat 測試佇應用內底 chiah ē 真通倚靠。[94]

[93] Numbers that fool the Fermat test are called *Carmichael numbers*, and little is known about them other than that they are extremely rare. There are 255 Carmichael numbers below 100,000,000. The smallest few are 561, 1105, 1729, 2465, 2821, and 6601. In testing primality of very large numbers chosen at random, the chance of stumbling upon a value that fools the Fermat test is less than the chance that cosmic radiation will cause the computer to make an error in carrying out a "correct" algorithm. Considering an algorithm to be inadequate for the first reason but not for the second illustrates the difference between mathematics and engineering.

[94] Ē 騙過 Fermat ê 數號做 *Carmichael* 數 (Carmichael numbers)，除了 in chiânⁿ 罕得有以外，lán 所知 ê chiânⁿ 有限。比 1 億較細 ê Carmichael 數有 255 ê。上細 ê 幾个有 561、1105、1729、2465、2821 kap 6601。佇測誠 chhìn-chhái 揀 ê 大 ê 整數敢是質數 ê 過程，tú 好 tú 著一个騙過 Fermat ê 測試 ê 數 ê 機率，比宇宙輻射予電腦佇行「正確」ê 演算法 ê 時 thut-chhê ê

There are variations of the Fermat test that cannot be fooled. In these tests, as with the Fermat method, one tests the primality of an integer n by choosing a random integer $a < n$ and checking some condition that depends upon n and a. (See Exercise 1.28 for an example of such a test.) On the other hand, in contrast to the Fermat test, one can prove that, for any n, the condition does not hold for most of the integers $a < n$ unless n is prime. Thus, if n passes the test for some random choice of a, the chances are better than even that n is prime. If n passes the test for two random choices of a, the chances are better than 3 out of 4 that n is prime. By running the test with more and more randomly chosen values of a we can make the probability of error as small as we like.

有其他 Fermat 測試 ê 變形，bōe 予伊騙。佇 chiah ê 測試，kap Fermat ê 方法 kâng 款，lâng 用隨機揀一个數 $a < n$，koh 檢查一寡倚靠 n kap a ê 狀況，來測試數 n 敢是質數（看 Exercise 1.28，內底有 chit 號測試 ê 例。）另外方面，kap Fermat ê 測試相對 ê，ē 當證明對所有 n，而且對大多數整數 $a < n$，條件無成立，除非 n 是質數。就 án-ne，若是對一寡 chhìn-chhái 揀 ê a，n 通過測試，n 是質數 ê 機會 ē 過半。若準講 n 對兩 ê 隨機選擇 ê a 通過測試，n 是質數 ê 機會 ē 超過四分三。若是用愈來愈 chē chhìn-chhái 揀 ê a 來 pháng chit ê 測試，lán 通予 thut-chhê ê 機率 kiu 水 kàu lán 所意愛 ê 程度。

The existence of tests for which one can prove that the chance of error becomes arbitrarily small has sparked interest in algorithms of this type, which have come to be known as *probabilistic algorithms*. There is a great deal of research activity in this area, and probabilistic algorithms have been fruitfully applied to many fields.[95]

機率較細。Kā 演算法因為頭一 ê，毋是第二 ê 原因，掠做無蓋好，說明數學 kap 工程無 kâng。

[95] One of the most striking applications of probabilistic prime testing has been to the field of cryptography. Although it is now computationally infeasible to factor an arbitrary 200-digit number, the primality of such a number can be checked in a few seconds with the Fermat test.

予人會當證明 têng-tâⁿ 出現 ê 機會變做任意細 ê 測試 ê 存在，致使對 chit 款演算法 ê 興趣，in 號做機率演算法 (probabilistic algorithms)。Chit ê 領域不止仔 chē ê 研究活動，機率演算法 mā 昌盛應用 kàu 真 chē 範圍。[96]

Exercise 1.21: Use the `smallest-divisor` procedure to find the smallest divisor of each of the following numbers: 199, 1999, 19999.

Exercise 1.21: 用 `smallest-divisor` 程序，來 chhōe 下 kha ê 數 ê 上細 ê 約數：199、1999、19999。

Exercise 1.22: Most Lisp implementations include a primitive called `runtime` that returns an integer that specifies the amount of time the system has been running (measured, for example, in microseconds). The following `timed-prime-test` procedure, when called with an integer n, prints n and checks to see if n is prime. If n is prime, the procedure prints three asterisks followed by the amount of time used in performing the test.

This fact forms the basis of a technique for constructing "unbreakable codes" suggested by Rivest et al. (1977). The resulting *RSA algorithm* has become a widely used technique for enhancing the security of electronic communications. Because of this and related developments, the study of prime numbers, once considered the epitome of a topic in "pure" mathematics to be studied only for its own sake, now turns out to have important practical applications to cryptography, electronic funds transfer, and information retrieval.

[96] 上得 lâng 注意 ê 機率質數測試應用，其中一个就是暗碼學 (cryptography)。雖 bóng chit-má 計算中 bōe 當 kā 任何 200 位 ê 數因數分解，毋 koh 一个數敢是質數 ê 問題，會當佇幾秒鐘內底用 Fermat ê 測試來判斷。Chit ê 事實形成起造「bōe 破得 ê 碼」ê 技術基礎，由Rivest et al. (1977)所提議。結果 ê *RSA* 演算法 (RSA algorithm)，變做使用真闊 ê 技術，來加強電子通信 ê 安全。因為 che hām 關聯 ê 發展，質數 ê 研究對捌掠做是「純」數學 ê 主題 ê 典範，kan-ta 為著家 kī ê 目的來研究，chit-má 成做一个暗碼學、電子轉 siàu kap 資訊檢索 ê 重要 ê 實際應用。

Exercise 1.22: 大部份 Lisp ê 實做 kâⁿ 一个號做 `runtime` ê 基礎函數，通傳轉去指示 pháng 系統所開 ê 時間量（比論，用微秒 (1/1000 秒) 量）ê 整數。下 kha ê `timed-prime-test` 程序，若是用 n 呼叫，ē 印出 n，koh 檢查 n 敢是質數。若 n 是質數，程序印三粒星號 (***)，了後印行測試所開 ê 時間量。

```
(define (timed-prime-test n)
  (newline)
  (display n)
  (start-prime-test n (runtime)))
(define (start-prime-test n start-time)
  (if (prime? n)
      (report-prime (- (runtime) start-time))))
(define (report-prime elapsed-time)
  (display " *** ")
  (display elapsed-time))
```

Using this procedure, write a procedure `search-for-primes` that checks the primality of consecutive odd integers in a specified range. Use your procedure to find the three smallest primes larger than 1000; larger than 10,000; larger than 100,000; larger than 1,000,000. Note the time needed to test each prime. Since the testing algorithm has order of growth of $\Theta(\sqrt{n})$, you should expect that testing for primes around 10,000 should take about $\sqrt{10}$ times as long as testing for primes around 1000. Do your timing data bear this out? How well do the data for 100,000 and 1,000,000 support the $\Theta(\sqrt{n})$ prediction? Is your result compatible with the notion that programs on your machine run in time proportional to the number of steps required for the computation?

用 chit ê 程序，寫 `search-for-primes` 程序，來檢查指

定 ê 範圍內底，連 sòa ê 奇數敢是質數。用汝 ê 程序 chhiau 超過 1,000 ê 上細 ê 三 ê 質數；然後是超過 10,000 ê 上細 ê 三 ê、超過 100,000 ê kap 超過 1,000,000 ê。注意試逐个質數著開 ê 時間。因為測試 ê 演算法 ê 成長率是 $\Theta(\sqrt{n})$，所以汝應該期待測試 sài-suh 10,000 左右 ê 質數所開 ê 時間，大概是測試 sài-suh 1,000 左右 ê 質數 ê ê $\sqrt{10}$ 倍。汝 ê 時間資料敢會當 kā 做干證？若資料對 100,000 變 kàu 1,000,000，敢有真支持 $\Theta(\sqrt{n})$ chit ê 預測？汝 ê 結果敢符合 chit ê 主張，就是汝 ê 機器所 páng ê 程所開 ê 時間，是對計算所愛 ê 手續數，有比例關係？

Exercise 1.23: The `smallest-divisor` procedure shown at the start of this section does lots of needless testing: After it checks to see if the number is divisible by 2 there is no point in checking to see if it is divisible by any larger even numbers. This suggests that the values used for `test-divisor` should not be 2, 3, 4, 5, 6, ..., but rather 2, 3, 5, 7, 9, ... To implement this change, define a procedure `next` that returns 3 if its input is equal to 2 and otherwise returns its input plus 2. Modify the `smallest-divisor` procedure to use `(next test-divisor)` instead of `(+ test-divisor 1)`. With `timed-prime-test` incorporating this modified version of `smallest-divisor`, run the test for each of the 12 primes found in Exercise 1.22. Since this modification halves the number of test steps, you should expect it to run about twice as fast. Is this expectation confirmed? If not, what is the observed ratio of the speeds of the two algorithms, and how do you explain the fact that it is different from 2?

Exercise 1.23: 本節頂展示 ê `smallest-divisor` 程序做真 chē 無需要 ê 測試：佇伊檢查 chit ê 數敢會當予 2 除了後，

就毋免檢查 che 敢會當予較大 ê 雙數除。Che 建議 `test-divisor` 所用 ê 數無應該是 2, 3, 4, 5, 6，顛倒是, 3, 5, 7, 9, ...。Beh 實做 chit ê 改變，定義程序 `next` 若是伊 ê 輸入等於 2，ah 無就傳轉去「輸入 +2」。改 `smallest-divisor` 程序，mài 用 `(+ test-divisor 1)`，顛倒改用 `(next test-divisor)`。用 `timed-prime-test` hām `smallest-divisor` ê chit ê 修改版本，pháng chit ê 測試佇 Exercise 1.22 所講 ê 12 ê 質數。因為 chit ê 改變 kā 試 ê 手續數減半，所以汝應該期待伊 pháng koh 較緊一倍。Chit ê 期待敢有確認？若無，所觀察 ê chit 兩个演算法 ê 速度 ê 比例是 gōa chē？比例 kap 2 無 kâng，汝 beh án-nóa 解說？

Exercise 1.24: Modify the `timed-prime-test` procedure of Exercise 1.22 to use `fast-prime?` (the Fermat method), and test each of the 12 primes you found in that exercise. Since the Fermat test has $\Theta(\log n)$ growth, how would you expect the time to test primes near 1,000,000 to compare with the time needed to test primes near 1000? Do your data bear this out? Can you explain any discrepancy you find?

Exercise 1.24: 改 Exercise 1.22 ê `timed-prime-test` 程序，來用 `fast-prime?`（Fermat 方法），koh 試汝佇 chit ê 測試發現 ê 12 ê 質數。因為 Fermat ê 測試 ê 成長率是 $\Theta(\log n)$，kap 試接近 1000 ê 質數所開 ê 時間相比，汝 án-nóa 期待試接近 1,000,000 ê 質數所開 ê 時間？汝 ê 資料敢 kā 做干證？汝敢 ē 當解說所 chhōe 著 ê 出入？

Exercise 1.25: Alyssa P. Hacker complains that we went to a lot of extra work in writing `expmod`. After all, she says, since we already know how to compute exponentials, we could have simply written

Exercise 1.25: Alyssa P. Hacker 怨講 lán 佇寫 `expmod` ê 時，做真 chē 額外 ê khang-khòe。伊講，總是因為 lán 已經知 án-nóa 算指數，lán 通簡單寫做

```
(define (expmod base exp m)
  (remainder (fast-expt base exp) m))
```

Is she correct? Would this procedure serve as well for our fast prime tester? Explain.

伊敢正確？Chit ê 程序敢 ē 當 kap 起頭 ê 質數測試程序 kâng 款有路用？請解說。

Exercise 1.26: Louis Reasoner is having great difficulty doing Exercise 1.24. His `fast-prime?` test seems to run more slowly than his `prime?` test. Louis calls his friend Eva Lu Ator over to help. When they examine Louis's code, they find that he has rewritten the `expmod` procedure to use an explicit multiplication, rather than calling `square`:

Exercise 1.26: Louis Reasoner 做 Exercise 1.24 ê 時陣拄著蓋大 ê 困難。伊 ê `fast-prime?` 測試假若比伊 ê `prime?` 測試明顯 pháng koh 較慢。Louis khà 予 in 朋友 Eva Lu Ator 來 tàu 相 kang。當 in 檢查 Louis ê 程式碼 ê 時，揣著伊重寫 `expmod` 程序，用明顯 ê 乘法，顛倒毋是呼叫 `square`：

```
(define (expmod base exp m)
  (cond ((= exp 0) 1)
        ((even? exp)
         (remainder (* (expmod base (/ exp 2) m)
                       (expmod base (/ exp 2) m))
                    m))
        (else
         (remainder (* base
```

```
                (expmod base (- exp 1) m))
            m))))
```

"I don't see what difference that could make," says Louis. "I do." says Eva. "By writing the procedure like that, you have transformed the $\Theta(\log n)$ process into a $\Theta(n)$ process." Explain.

Louis 講：「我看無 in 兩个有 siáⁿ 物無仝」。

「我看有，」Eva 講：「Kā 程序 án-ne 寫，汝著 kā $\Theta(\log n)$ ê 過程，變做 $\Theta(n)$ ê 過程。」請解說。

Exercise 1.27: Demonstrate that the Carmichael numbers listed in Footnote 1.47 really do fool the Fermat test. That is, write a procedure that takes an integer n and tests whether a^n is congruent to a modulo n for every $a < n$, and try your procedure on the given Carmichael numbers.

Exercise 1.27: 展示佇 Footnote 1.47 所列 ê Carmichael 數，chiâⁿ 實 ē 當騙過 Fermat ê 測試。就是，寫一个程序，輸入整數 n，測試對所有 ê $a < n$，a^n kap a 予 n 除，敢 lóng 有 kâng 款 ê 餘數，koh 用所列 ê Carmichael 數試汝 ê 程序。

Exercise 1.28: One variant of the Fermat test that cannot be fooled is called the *Miller-Rabin test* (Miller 1976; Rabin 1980). This starts from an alternate form of Fermat's Little Theorem, which states that if n is a prime number and a is any positive integer less than n, then a raised to the $(n-1)$-st power is congruent to 1 modulo n. To test the primality of a number n by the Miller-Rabin test, we pick a random number $a < n$ and raise a to the $(n-1)$-st power modulo n using the `expmod`

procedure. However, whenever we perform the squaring step in `expmod`, we check to see if we have discovered a "nontrivial square root of 1 modulo n," that is, a number not equal to 1 or $n-1$ whose square is equal to 1 modulo n. It is possible to prove that if such a nontrivial square root of 1 exists, then n is not prime. It is also possible to prove that if n is an odd number that is not prime, then, for at least half the numbers $a < n$, computing a^{n-1} in this way will reveal a nontrivial square root of 1 modulo n. (This is why the Miller-Rabin test cannot be fooled.) Modify the `expmod` procedure to signal if it discovers a nontrivial square root of 1, and use this to implement the Miller-Rabin test with a procedure analogous to `fermat-test`. Check your procedure by testing various known primes and non-primes. Hint: One convenient way to make `expmod` signal is to have it return 0.

Exercise 1.28: 一个 bōe 騙得 ê Fermat ê 測試 ê 變形，號做*Miller-Rabin ê* 測試 (Miller-Rabin test)(Miller 1976; Rabin 1980)。Che 對 Fermat 小定理 ê 別个形式開始，伊陳述，若是 n 是質數，而且 a 是比 n 較細 ê 正整數，a ê $n-1$ 次方 kap 1 予 n 除，就有 kâng 款 ê 餘數。Beh 用 Miller-Rabin ê 測試，試數 n 敢是質數，lán chhìn-chhái 揀一个數 $a < n$，koh 用 `expmod` 程序算出 a ê $n-1$ 次方予 n 除 ê 餘數。毋 koh，lán lóng ē 佇 `expmod` 行平方 ê 手續 ê 時陣，檢查敢有發現「1 予 n 除 ê 餘數 ê，非自明 ê 平方根」。就是，毋是 1 iah 是 $n-1$ ê 數字，伊 ê 平方等於 1 予 n 除 ê 餘數。有可能證明若非自明 ê 1 ê 平方根佇 leh，n 就毋是質數。Mā 有可能證明若 n 是毋是質數 ê 奇數，對上無一半 ê 數字 $a < n$，用 chit ê 方法計算 a^{n-1}，就 ē 展示非自明 ê，1 予 n 除 ê 餘數 ê 平方根。(Che 是 Miller-Rabin ê 測試 bōe 予 lâng 騙 ê 原因。) 改 `expmod` 程序來指示伊敢有

發現非自明 ê 1 ê 平方根，koh 用 che 來實做 Miller-Rabin ê 測試，用 kap `fermat-test` 相 siâng ê 程式。Thèh chē-chē 款所知 ê 質數 kap 非質數，來檢查汝 ê 程序。提示：一个便利 ê 方法來創造 `expmod` ê 訊號，是予伊 kā 0 傳倒轉。

1.3 Formulating Abstractions with Higher-Order Procedures 用高階程序來形式化抽象

We have seen that procedures are, in effect, abstractions that describe compound operations on numbers independent of the particular numbers. For example, when we declare

Lán 已經看著，程序其實是描述對數字 ê 複合運算 ê 抽象，而且毋管特定 ê 數字是 siáⁿ。比論，lán 若寫

```
(define (cube x) (* x x x))
```

we are not talking about the cube of a particular number, but rather about a method for obtaining the cube of any number. Of course we could get along without ever defining this procedure, by always writing expressions such as
Lán 毋是 teh 講 tó 一个數字 ê 立方，煞是 teh 講，求任何數字 ê 立方 ê 方法。當然，lán 亦會當 mài 定義 chit-ê 程序，逐擺 tiō 寫出來

```
(* 3 3 3)
(* x x x)
(* y y y)
```

and never mentioning `cube` explicitly. This would place us at a serious disadvantage, forcing us to work always at the level of the particular operations that happen to be primitives in the language (multiplication, in this case) rather than in terms of higher-level operations. Our programs would be able to compute cubes, but our language would lack the ability to express the concept of

cubing. One of the things we should demand from a powerful programming language is the ability to build abstractions by assigning names to common patterns and then to work in terms of the abstractions directly. Procedures provide this ability. This is why all but the most primitive programming languages include mechanisms for defining procedures.
而且毋捌明確提起 `cube` chit ê 程序。Che ē 予 lán 陷入嚴重不便 ê 狀況，逼 lán 一直著處理屬佇 chit ê 語言 ê 基礎運算 ê 操作（佇 chit ê 例指乘法），soah 無用 koân 階 ê 操作。Lán ê 程式 ē 當算立方，但是 lán ê 語言欠表達立方概念 ê 能力。Lán 應該要求有 chē-chē 路用 ê 程式語言 ê 代誌，其中一个就是用 kā 名分配 kàu 一般 ê 模式來建立抽象，koh 直接用 chiah ê 抽象工作 ê 能力。程序提供 chit ê 能力。Che 是除了上基礎 ê 以外，程式語言 lóng 提供定義程序 ê 機制 ê 原因。

Yet even in numerical processing we will be severely limited in our ability to create abstractions if we are restricted to procedures whose parameters must be numbers. Often the same programming pattern will be used with a number of different procedures. To express such patterns as concepts, we will need to construct procedures that can accept procedures as arguments or return procedures as values. Procedures that manipulate procedures are called *higher-order procedures*. This section shows how higher-order procedures can serve as powerful abstraction mechanisms, vastly increasing the expressive power of our language.

但是就算是數值處理，若是 lán 寫程序 ê 時，參數受限制著愛用數字，lí ê 能力佇建立抽象 ē 非常受限制。Kâng 款 ê 程式設計模式定定 ē 用佇一寡無 kâng ê 程序。Beh kā chit 款 ê 模式表達做觀念，lán 著愛建構程序，會當接受程序當做參數，或者是 kā 程序準做值傳轉來。操作程序 ê 程序號做高階程序 (higher-order procedures)。Chit 節展示高階程序 án-nóa 通當做有大能力 ê 抽象機制，非常增加 lán ê 語言 ê 表現力。

1.3.1 Procedures as Arguments 程序當做引數

Consider the following three procedures. The first computes the sum of the integers from a through b:
考慮下 kha 三 ê 程序。頭一个算 a kàu b ê 整數 ê 和：

```
(define (sum-integers a b)
  (if (> a b)
      0
      (+ a (sum-integers (+ a 1) b))))
```

The second computes the sum of the cubes of the integers in the given range:
第二个算指定 ê 範圍內 ê 數 ê 立方和：

```
(define (sum-cubes a b)
  (if (> a b)
      0
      (+ (cube a)
         (sum-cubes (+ a 1) b))))
```

The third computes the sum of a sequence of terms in the series
第三个算下 kha ê 級數，逐項 ê 列 ê 和：

$$\frac{1}{1\cdot 3}+\frac{1}{5\cdot 7}+\frac{1}{9\cdot 11}+\cdots,$$

which converges to $\pi/8$ (very slowly):[97]
伊 ē 收斂 kàu $\pi/8$ （chiâⁿ 實慢）:[98]

```
(define (pi-sum a b)
  (if (> a b)
```

[97] This series, usually written in the equivalent form $\frac{\pi}{4}=1-\frac{1}{3}+\frac{1}{5}-\frac{1}{7}+\ldots$, is due to Leibniz. We'll see how to use this as the basis for some fancy numerical tricks in Section 3.5.3.

[98] Chit ê 級數，常常寫做等式形式 $\frac{\pi}{4}=1-\frac{1}{3}+\frac{1}{5}-\frac{1}{7}+\ldots$，是因為 Leibniz。Lán ē 佇 Section 3.5.3看見 beh án-nóa 用 che，當做一寡奇巧 ê 數值把戲 ê 基礎。

```
    0
    (+ (/ 1.0 (* a (+ a 2)))
       (pi-sum (+ a 4) b))))
```

These three procedures clearly share a common underlying pattern. They are for the most part identical, differing only in the name of the procedure, the function of `a` used to compute the term to be added, and the function that provides the next value of `a`. We could generate each of the procedures by filling in slots in the same template:

Chit 3 ê 程序清楚分享隱藏 ê 模式。In 大部份 lóng kâng 款，kan-ta 無 kâng 佇程序 ê 名、thèh 來算 beh 加起來 ê 項 ê `a` ê 函數，kap 提供 `a` ê 後一个值 ê 函數。Lán 通用添 kâng 形 ê 枋模 (template)ê 框 á，來生成個別 ê 程序：

```
(define (⟨name⟩ a b)
  (if (> a b)
      0
      (+ (⟨term⟩ a)
         (⟨name⟩ (⟨next⟩ a) b))))
```

The presence of such a common pattern is strong evidence that there is a useful abstraction waiting to be brought to the surface. Indeed, mathematicians long ago identified the abstraction of *summation of a series* and invented "sigma notation," for example

Chit 款一般 ê 模式出現，是真強 ê 證據，反映有有路用 ê 抽象，等待予 lâng chhōa kàu 表面。數學家的確佇足久以前辨別級數和 (summation of a series) ê 抽象，發明「Σ 標記」（譯註：Σ 讀做 /'sɪgmə/ ），比如：

$$\sum_{n=a}^{b} f(n) = f(a) + \cdots + f(b),$$

to express this concept. The power of sigma notation is that it allows mathematicians to deal with the concept of summation itself rather than only with

particular sums—for example, to formulate general results about sums that are independent of the particular series being summed.
來表達 chit 个概念。Σ 標記 ê 能力是允准數學家處理總和 ê 概念家 kī，毋是干焦部份 ê 和——舉例，形式化和 ê 一般結果，chit ê 和 kap 受總計 ê 特定級數獨立。

Similarly, as program designers, we would like our language to be powerful enough so that we can write a procedure that expresses the concept of summation itself rather than only procedures that compute particular sums. We can do so readily in our procedural language by taking the common template shown above and transforming the "slots" into formal parameters:

做著一个程式設計者，lán siâng 款 kah 意 lán ê 語言有夠額 ê 能力，來予 lán 寫一个程序，表達總計 ê 概念伊家 kī，毋是算特定 ê 和 ê 程序 niâ-niâ。Lán ē 當佇 lán ê 程序語言，用 thèh 頂 koân ê 枋模，kā 框 á 變換做正式 ê 參數，來緊緊做 che：

```
(define (sum term a next b)
  (if (> a b)
      0
      (+ (term a)
         (sum term (next a) next b))))
```

Notice that `sum` takes as its arguments the lower and upper bounds `a` and `b` together with the procedures `term` and `next`. We can use `sum` just as we would any procedure. For example, we can use it (along with a procedure `inc` that increments its argument by 1) to define `sum-cubes`:
注意 `sum` 除了 thèh ē 界 `a` kap 頂界 `b` 做引數以外，koh 有程序 `term` kap `next`。Lán ē 當用 `sum`，像用程序。比如講，lán 通用伊（kap `inc` 程序，伊 kā 伊 ê 引數加 1）來定義 `sum-cubes`：

```
(define (inc n) (+ n 1))
(define (sum-cubes a b)
  (sum cube a inc b))
```

Using this, we can compute the sum of the cubes of the integers from 1 to 10:
用 che，lán ē 當算 1 kàu 10 之間 ê 整數 ê 立方和：

```
(sum-cubes 1 10)
3025
```

With the aid of an identity procedure to compute the term, we can define `sum-integers` in terms of `sum`:
有「相 kâng」(identity) 函數幫 chān 算項，lán ē 當用 `sum` 定義 `sum-integers`：

```
(define (identity x) x)
(define (sum-integers a b)
  (sum identity a inc b))
```

Then we can add up the integers from 1 to 10:
Soah 落來 lán 通總計 1 kàu 10 之間 ê 整數：

```
(sum-integers 1 10)
55
```

We can also define `pi-sum` in the same way:[99]
Lán mā ē 當照 kâng 款 ê 方式定義 `pi-sum`：[100]

```
(define (pi-sum a b)
  (define (pi-term x)
    (/ 1.0 (* x (+ x 2))))
  (define (pi-next x)
    (+ x 4))
  (sum pi-term a pi-next b))
```

[99] Notice that we have used block structure (Section 1.1.8) to embed the definitions of `pi-next` and `pi-term` within `pi-sum`, since these procedures are unlikely to be useful for any other purpose. We will see how to get rid of them altogether in Section 1.3.2.

[100] 注意 lán 有用塊結構 (Section 1.1.8) 來 kā `pi-next` kap `pi-term` ê 定義 tàu 入去 `pi-sum`，因為 chiah ê 程序無可能對其他 ê 目的有路用。Lán ē 佇 Section 1.3.2 看見 án-nóa 做伙 kā in piàⁿ 掉。

Using these procedures, we can compute an approximation to π:
用 chiah ê 程序，lán ē 當算 π 大概 ê 值：

```
(* 8 (pi-sum 1 1000))
3.139592655589783
```

Once we have `sum`, we can use it as a building block in formulating further concepts. For instance, the definite integral of a function f between the limits a and b can be approximated numerically using the formula
Lán 一下有 `sum`，lán ē 當 kā 伊佇形式化較遠 ê 概念內，準做起造 ê 塊。舉例，函數 f 佇極限 a kap b 之間 ê 定積分 ē 當用下底 ê 公式，數值算出大概 ê 值（近似）：

$$\int_a^b f = \left[f\left(a + \frac{dx}{2}\right) + f\left(a + dx + \frac{dx}{2}\right) + f\left(a + 2dx + \frac{dx}{2}\right) + \ldots \right] dx$$

for small values of dx. We can express this directly as a procedure:
若是 dx ê 值真細。Lán ē 當直接用程序表達 che：

```
(define (integral f a b dx)
  (define (add-dx x)
    (+ x dx))
  (* (sum f (+ a (/ dx 2.0)) add-dx b)
     dx))

(integral cube 0 1 0.01)
.24998750000000042

(integral cube 0 1 0.001)
.249999875000001
```

(The exact value of the integral of `cube` between 0 and 1 is 1/4.)
（`cube` 佇 0 kap 1 之間 ê 積分 ê 精確值是 1/4）。

Exercise 1.29: Simpson's Rule is a more accurate method of numerical integration than the method illustrated above. Using Simpson's Rule, the integral of a function f between a and b is approximated as

Exercise 1.29: Simpson ê 法則是比頂懸說明 ê 較準 ê 數值積分方法。用 Simpson ê 法則，函數 f 佇 a kap b 之間 ê 積分 ê 近似 ē 當是

$$\frac{h}{3}(y_0 + 4y_1 + 2y_2 + 4y_3 + 2y_4 + \cdots + 2y_{n-2} + 4y_{n-1} + y_n),$$

where $h = (b - a)/n$, for some even integer n, and $y_k = f(a + kh)$. (Increasing n increases the accuracy of the approximation.) Define a procedure that takes as arguments f, a, b, and n and returns the value of the integral, computed using Simpson's Rule. Use your procedure to integrate `cube` between 0 and 1 (with $n = 100$ and $n = 1000$), and compare the results to those of the `integral` procedure shown above.

其中 $h = (b - a)/n$，n 是雙數，而且 $y_k = f(a + kh)$（加添 n 增加近似 ê 精度。）定義一个程序，引數是 f、a、b kap n，用 Simpson ê 法則計算積分，傳轉伊 ê 值。用 lí ê 程序算 `cube` 佇 0 kap 1 之間 ê 值（用 $n = 100$ kap $n = 1000$），koh kap 頂懸 ê $intergal$ 算出 ê 結果相比。

Exercise 1.30: The `sum` procedure above generates a linear recursion. The procedure can be rewritten so that the sum is performed iteratively. Show how to do this by filling in the missing expressions in the following definition:

Exercise 1.30: 頂懸 ê `sum` 程序生出線性遞迴。程序 ē 當重寫予總和 ē 當照反覆行。佇下 kha ê 程序添失去 ê 表達式，來展示 án-nóa 做：

```
(define (sum term a next b)
  (define (iter a result)
    (if ⟨??⟩
        ⟨??⟩
        (iter ⟨??⟩ ⟨??⟩))))
  (iter ⟨??⟩ ⟨??⟩))
```

Exercise 1.31:

a. The `sum` procedure is only the simplest of a vast number of similar abstractions that can be captured as higher-order procedures.[101] Write an analogous procedure called `product` that returns the product of the values of a function at points over a given range. Show how to define `factorial` in terms of `product`. Also use `product` to compute approximations to π using the formula[102]

   `sum` 程序 kan-ta 是巨額相 siâng ê，ē 當掠做 kôan 階程序 ê 抽象內底，上簡單 ê。[103]寫相 siâng ê 程序，號做

[101] The intent of Exercise 1.31 through Exercise 1.33 is to demonstrate the expressive power that is attained by using an appropriate abstraction to consolidate many seemingly disparate operations. However, though accumulation and filtering are elegant ideas, our hands are somewhat tied in using them at this point since we do not yet have data structures to provide suitable means of combination for these abstractions. We will return to these ideas in Section 2.2.3 when we show how to use *sequences* as interfaces for combining filters and accumulators to build even more powerful abstractions. We will see there how these methods really come into their own as a powerful and elegant approach to designing programs.

[102] This formula was discovered by the seventeenth-century English mathematician John Wallis.

[103] Exercise 1.31 kàu Exercise 1.33 強調 ê 是，通用適當 ê 抽象，kā 看起來無關聯 ê 操作

`product`，kā 函數佇指定範圍內底 ê 所有點 ê 值 ê 積傳轉。展示用 `product` 定義 `factorial` ê 方法。Mā 用 `product` kap 下 kha ê 公式算 π ê 近似 [104]

$$\frac{\pi}{4} = \frac{2 \cdot 4 \cdot 4 \cdot 6 \cdot 6 \cdot 8 \cdots}{3 \cdot 3 \cdot 5 \cdot 5 \cdot 7 \cdot 7 \cdots}.$$

b. If your `product` procedure generates a recursive process, write one that generates an iterative process. If it generates an iterative process, write one that generates a recursive process.

若是 lí ê `product` 程序生成遞迴 ê 過程，寫出一个生成反覆 ê 過程 ê。若是伊生成反覆 ê 過程，寫一个生成遞迴 ê 過程 ê。

Exercise 1.32:

a. Show that `sum` and `product` (Exercise 1.31) are both special cases of a still more general notion called `accumulate` that combines a collection of terms, using some general accumulation function:

展示 `sum` kap `product`（Exercise 1.31）兩个 lóng 是 koh 較一般 ê，號做 `accumulate`（譯註：累積）ê 概念 ê 特例。`accumulate` 合併項 ê 集合，用一般 ê 累積函數：

---

khōng 起來，來表現。毋 kú，雖 bóng 累積 kap 過濾是優美 ê 想法，chit 時使用 in，ē 小 kóa 縛牢 lán ê 手，因為 lán iáu koh 無資料結構來 kā 適當 ê 組合方法續予 in。Lán ē 佇 Section 2.2.3 轉去 chiah ê 想法，當 lán 展示 án-nóa 掠列 (sequence) 做介面，來組合過濾器 kap 累積器，起造 koh 較有能力 ê 抽象。Lán ē 佇 hia 看，chiah ê 方法 án-nóa 確實顯明路用，成做有能力 kap 優美 ê，設計程式 ê 方法。

[104] Chit ê 公式是由十七世紀 ê 英國數學家 John Wallis 發現 ê。

```
(accumulate combiner null-value term a next b)
```

`accumulate` takes as arguments the same term and range specifications as `sum` and `product`, together with a `combiner` procedure (of two arguments) that specifies how the current term is to be combined with the accumulation of the preceding terms and a `null-value` that specifies what base value to use when the terms run out. Write `accumulate` and show how `sum` and `product` can both be defined as simple calls to `accumulate`.

`accumulate` thèh kâng 款 ê 指定項 kap 範圍當做引數（像 `sum` kap `product`），kap `combiner`（有兩个引數）程序，指定 chit-má ê 項 kap 進前 ê 項 ê 累積 án-nóa 合併，koh 有 `null-value`，指定若是項 lóng 算了 ê 時 ê 基準值。寫 `accumulate`，展示 `sum` kap `product` án-nóa 兩个 ē 當定義做 `accumulate` ê 簡單呼叫。

b. If your `accumulate` procedure generates a recursive process, write one that generates an iterative process. If it generates an iterative process, write one that generates a recursive process.

若是 lí ê `accumulate` 程序生成遞迴 ê 過程，寫出一个生成反覆 ê 過程 ê。若是伊生成反覆 ê 過程，寫一个生成遞迴 ê 過程 ê。

Exercise 1.33: You can obtain an even more general version of `accumulate` (Exercise 1.32) by introducing the notion of a *filter* on the terms to be combined. That is, combine only those terms derived from values in the range that satisfy a specified condition. The resulting `filtered-accumulate`

abstraction takes the same arguments as accumulate, together with an additional predicate of one argument that specifies the filter. Write `filtered-accumulate` as a procedure. Show how to express the following using `filtered-accumulate`:

Exercise 1.33: Lí ē 當用引入佇 beh 組合 ê 項應用過濾器 (fliter) ê 概念，來 thèh 著閣較一般 ê `accumulate` ê 版本 (Exercise 1.32)。就是，kan-ta 組合對滿足指定條件 ê 範圍內 ê 值來 ê 項。結果 ê `filtered-accumulate` 抽象 thèh kap accumulate kâng 款 ê 引數，koh 有加一个單引數謂詞，伊指定過濾器。展示 án-nóa 用 `filtered-accumulate` 表示下 kha ê：

a. the sum of the squares of the prime numbers in the interval a to b (assuming that you have a `prime?` predicate already written)

   區間 a kàu b 中間 ê 質數 ê 平方和（假使 lí 已經有寫 `prime?` 謂詞）

b. the product of all the positive integers less than n that are relatively prime to n (i.e., all positive integers $i < n$ such that $\text{GCD}(i, n) = 1$).

   逐 ê 比 n 較細 ê，kap n 互質 ê 正整數（就是逐 ê 正整數 $i < n$ 滿足 $\text{GCD}(i, n) = 1$）ê 乘積

1.3.2 Constructing Procedures Using `lambda` 用 `lambda` 建構程序

In using `sum` as in Section 1.3.1, it seems terribly awkward to have to define trivial procedures such as `pi-term` and `pi-next` just so we can use them as arguments to our higher-order procedure. Rather than define `pi-next` and `pi-term`, it would be more convenient to have a way to directly specify "the procedure that returns its input incremented by 4" and "the procedure

that returns the reciprocal of its input times its input plus 2." We can do this by introducing the special form `lambda`, which creates procedures. Using `lambda` we can describe what we want as
佇 Section 1.3.1 用 `sum` ê 時陣，因為 án-ne chiah 通 kā 自明 ê 程序像 `pi-term` kap `pi-next`，當做 lán ê koân 階函數 ê 引數，所以 bōe 使無定義 in，án-ne 真 gāi-giòh。若有方法來直接指定「傳轉輸入 ê 值加 4 ê 程序」kap「傳轉『$x \times (x+2)$』ê 倒數 (reciprocal) ê 程序」，毋免定義 `pi-next` kap `pi-term`，ē 真方便。Lán ē 當引入建立程序 ê 特別形式 `lambda` 來行。用 `lambda` lán 通描述所意愛 ê 若

```
(lambda (x) (+ x 4))
```

and

```
(lambda (x) (/ 1.0 (* x (+ x 2))))
```

Then our `pi-sum` procedure can be expressed without defining any auxiliary procedures as
了後，lán ê `pi-sum` ē 當無用定義任何助程序 (auxiliary procedure)，表達做

```
(define (pi-sum a b)
  (sum (lambda (x) (/ 1.0 (* x (+ x 2))))
       a
       (lambda (x) (+ x 4))
       b))
```

Again using `lambda`, we can write the `integral` procedure without having to define the auxiliary procedure `add-dx`:
Koh 用 `lambda`，lán 通毋免定義助程序 `add-dx`，來寫 `integral` 程序：

```
(define (integral f a b dx)
  (* (sum f
          (+ a (/ dx 2.0))
```

```
          (lambda (x) (+ x dx))
          b)
    dx))
```

In general, `lambda` is used to create procedures in the same way as `define`, except that no name is specified for the procedure:
一般來講，`lambda` thèh 來用 kap `define` kâng 款 ê 方式建立程序，除了程序毋免指名：

```
(lambda (⟨formal-parameters⟩) ⟨body⟩)
```

The resulting procedure is just as much a procedure as one that is created using `define`. The only difference is that it has not been associated with any name in the environment. In fact,
結果 ê 程序就干焦親像用 `define` 定義 ê 程序。只有一个無 kâng，就是伊無縛佇環境內任何 ê 名。實際上，

```
(define (plus4 x) (+ x 4))
```

is equivalent to

```
(define plus4 (lambda (x) (+ x 4)))
```

We can read a `lambda` expression as follows:
Lán ē 當照下 kha ê 方法讀 `lambda` ê 表達式：

```
(lambda                    (x)      (+   x     4))
    |                       |        |   |     |
the procedure of an argument x that adds x and 4

程 序                      有 一 个 引 數 x ， kā  x  kap  4   加 起 來
```

Like any expression that has a procedure as its value, a `lambda` expression can be used as the operator in a combination such as
像任何有程序準做伊 ê 值 ê 表達式，`lambda` 表達式 ē 當 thèh 來做組合 ê 運算子，比如

```
((lambda (x y z) (+ x y (square z)))
 1 2 3)
12
```

or, more generally, in any context where we would normally use a procedure name.[105]
或者是，koh 較一般來講，佇任何頂下文，其中 lán 可能 ē 正常用程序 ê 名。[106] z

Using `let` to create local variables 用 `let` 建立區域變數

Another use of `lambda` is in creating local variables. We often need local variables in our procedures other than those that have been bound as formal parameters. For example, suppose we wish to compute the function
`lambda`ê 別款路用是佇建立區域變數。Lán 定定佇 lán ê 程序需要區域變數，除了已經縛做正式參數 ê。舉例，假使 lán 想 beh 算 chit ê 函數

$$f(x, y) = x(1 + xy)^2 + y(1 - y) + (1 + xy)(1 - y),$$

which we could also express as
Lán mā ē 當寫做

[105] It would be clearer and less intimidating to people learning Lisp if a name more obvious than `lambda`, such as `make-procedure`, were used. But the convention is firmly entrenched. The notation is adopted from the λ-calculus, a mathematical formalism introduced by the mathematical logician Alonzo Church (1941). Church developed the λ-calculus to provide a rigorous foundation for studying the notions of function and function application. The λ-calculus has become a basic tool for mathematical investigations of the semantics of programming languages.

[106] 若是用一个比 `lambda` koh 較明顯 ê 名，比如 `make-procedure`，ē 對學 Lisp ê lâng koh 較清楚，而且較 bōe 予 in 著驚。但是 chit ê 傳統 ê 根已經釘牢牢 ah。Chit ê 概念是對λ 運算 (λ-calculus) 引來 ê，伊是由數理邏輯學家 Alonzo Church (1941) 紹介 ê 數學形式方法。Church 開發 λ 運算來提供嚴 ê 基礎，來學習函數 kap 應用函數 ê 概念。λ 運算已經變做基礎 ê 家私，來數學調查程式語言 ê 語義。

$$a = 1 + xy,$$
$$b = 1 - y,$$
$$f(x, y) = xa^2 + yb + ab.$$

In writing a procedure to compute f, we would like to include as local variables not only x and y but also the names of intermediate quantities like a and b. One way to accomplish this is to use an auxiliary procedure to bind the local variables:

佇寫算 f ê 程序 ê 時，lán beh 包括做區域變數 ê，毋但是 x kap y，mā 有中途 ê 量像 a kap b。一个達成 che ê 方法是用助程序來束縛區域變數：

```
(define (f x y)
  (define (f-helper a b)
    (+ (* x (square a))
       (* y b)
       (* a b)))
  (f-helper (+ 1 (* x y))
            (- 1 y)))
```

Of course, we could use a `lambda` expression to specify an anonymous procedure for binding our local variables. The body of `f` then becomes a single call to that procedure:

當然，lán 通用 `lambda` 表達式來指定無落名 ê 程序，縛 lán ê 區域變數。`f` ê 本體就變做 hit ê 程序 ê 簡單 ê 呼叫：

```
(define (f x y)
  ((lambda (a b)
     (+ (* x (square a))
        (* y b)
        (* a b)))
   (+ 1 (* x y))
   (- 1 y)))
```

This construct is so useful that there is a special form called `let` to make its use more convenient. Using `let`, the `f` procedure could be written as
Chit ê 結構真有路用，所以有特殊形式號做 `let` 來予伊 ê 使用 koh 較利便。用 `let`，`f` 程序 ē 當寫做

```
(define (f x y)
  (let ((a (+ 1 (* x y)))
        (b (- 1 y)))
    (+ (* x (square a))
       (* y b)
       (* a b))))
```

The general form of a `let` expression is
`let` 表達式 ê 一般形式是

```
(let ((⟨var1⟩ ⟨exp1⟩)
      (⟨var2⟩ ⟨exp2⟩)
      ...
      (⟨varn⟩ ⟨expn⟩))
  ⟨body⟩)
```

which can be thought of as saying

```
let ⟨var1⟩ have the value ⟨exp1⟩ and
    ⟨var2⟩ have the value ⟨exp2⟩ and
    ...
    ⟨varn⟩ have the value ⟨expn⟩
in  ⟨body⟩
```

Ē 當掠做是 án-ne 講：

```
Kā ⟨var1⟩ 設做 ⟨exp1⟩ 而且
   ⟨var2⟩ 設做 ⟨exp2⟩ 而且
   ...
   ⟨varn⟩ 設做 ⟨expn⟩
佇 ⟨body⟩
```

The first part of the `let` expression is a list of name-expression pairs. When the `let` is evaluated, each name is associated with the value of the corresponding expression. The body of the `let` is evaluated with these names bound as local variables. The way this happens is that the `let` expression is interpreted as an alternate syntax for

`let` 表達式頭一个部份是名—表達式 ê 對 ê 列單。當 `let` teh 算值 ê 時，逐 ê 名 kap 對應 ê 表達式 ê 值有關聯。`let` ê 本體 kap chiah ê 縛做區域變數 ê 做伙算值。發生 ê 機制是，`let` 表達式會解釋做下 kha ê 表達式 ê 別 ê 句法形式：

```
((lambda (⟨var1⟩ ... ⟨varn⟩)
    ⟨body⟩)
 ⟨exp1⟩
 ...
 ⟨expn⟩)
```

No new mechanism is required in the interpreter in order to provide local variables. A `let` expression is simply syntactic sugar for the underlying `lambda` application.

佇 chit ê 解釋器無需要新 ê 機制來提供區域變數。`let` 表達式簡單是下層 ê `lambda` ê 應用 ê 語法糖。

We can see from this equivalence that the scope of a variable specified by a `let` expression is the body of the `let`. This implies that:

Lán 通對 chit ê 對 tâng 發現，`let` 表達式指定 ê 變數 ê 作用範圍是 `let` ê 主體。Che mā 代表

- `let` allows one to bind variables as locally as possible to where they are to be used. For example, if the value of `x` is 5, the value of the expression

  `let` 允准 lâng 對 in 所用 ê 所在，kā 變數縛 kah 愈區域愈好。舉例，`x` ê 值若是 5，下 kha ê 表達式 ê 值

```
(+ (let ((x 3))
     (+ x (* x 10)))
   x)
```

is 38. Here, the `x` in the body of the `let` is 3, so the value of the `let` expression is 33. On the other hand, the `x` that is the second argument to the outermost + is still 5.

就是 38。佇 chia，因為 `let` 本體 ê `x` 是 3，`let` 表達式 ê 值 chiah 是 33。另外方面，上外面 ê + ê 第二个 `x` ê 值 iáu 是 5。

- The variables' values are computed outside the `let`. This matters when the expressions that provide the values for the local variables depend upon variables having the same names as the local variables themselves. For example, if the value of `x` is 2, the expression

  變數 ê 值是佇 `let` ê 外口算出來 ê。若是提供予區域變數 ê 值 ê 表達式，倚靠 kap 區域變數 ê 名 chhiăng-póng ê 變數，就有要緊。舉例，`x` ê 值若是 2，表達式

  ```
  (let ((x 3)
        (y (+ x 2)))
    (* x y))
  ```

  will have the value 12 because, inside the body of the `let`, `x` will be 3 and `y` will be 4 (which is the outer `x` plus 2).

  ê 值是 12，因為佇 `let` ê 本體，`x` 是 3，`y` 是 4（伊是外口 ê `x` 加 2）。

Sometimes we can use internal definitions to get the same effect as with `let`. For example, we could have defined the procedure `f` above as
有時 á lán ē 當用內部定義來 thèh 著 kap 用 `let` kâng 款 ê 效果。舉例，lán ē 當 kā 頂懸 `f` 程序定義做

```
(define (f x y)
  (define a (+ 1 (* x y)))
  (define b (- 1 y))
  (+ (* x (square a))
     (* y b)
     (* a b)))
```

We prefer, however, to use `let` in situations like this and to use internal `define` only for internal procedures.[107]
但是 lán 較意愛，佇 chit 號情形用 `let`，kan-ta 佇內部程序用內部 `define`。[108]

Exercise 1.34: Suppose we define the procedure

Exercise 1.34: 設使 lán 定義 chit ê 程序

```
(define (f g) (g 2))
```

Then we have

Lán koh 有

```
(f square)
4
(f (lambda (z) (* z (+ z 1))))
6
```

What happens if we (perversely) ask the interpreter to evaluate the combination `(f f)`? Explain.

[107] Understanding internal definitions well enough to be sure a program means what we intend it to mean requires a more elaborate model of the evaluation process than we have presented in this chapter. The subtleties do not arise with internal definitions of procedures, however. We will return to this issue in Section 4.1.6, after we learn more about evaluation.

[108] 知 bat 內部定義 kah 確定程式所指 ê 是 lán 所愛伊指 ê，需要比 lán 佇本章所展示 ê，koh khah 用工做 ê 算值過程 ê 模型。但是程序 ê 內部定義無起微妙 ê 所在。Lán ē 佇Section 4.1.6 學習 koh 較 chē 算值 ê 智識了後，轉去看 chit ê 議題。

若是 lán（失常）叫直譯器算組合（`f f`）ê 值，ē 發生 siánn 物 tāi 誌？請解說。

1.3.3 Procedures as General Methods 準做一般方法 ê 程序

We introduced compound procedures in Section 1.1.4 as a mechanism for abstracting patterns of numerical operations so as to make them independent of the particular numbers involved. With higher-order procedures, such as the `integral` procedure of Section 1.3.1, we began to see a more powerful kind of abstraction: procedures used to express general methods of computation, independent of the particular functions involved. In this section we discuss two more elaborate examples—general methods for finding zeros and fixed points of functions—and show how these methods can be expressed directly as procedures.

Lán 佇Section 1.1.4紹介合成程序當做數值操作 ê 抽象模式 ê 機制，來予 in kap 干涉 ê 特定數字獨立。有 koân 階程序，比如 Section 1.3.1 ê `integral` 程序，lán 開始看 koh 較有路用 ê 抽象 ê 款：程序 thèh 來表達計算 ê 一般方法，kap 干涉 ê 特定程序獨立。佇 chit 節，lán 討論兩个閣較用工做 ê 例——揣 0 kap 函數 ê 不動點 ê 一般方法，koh 展示 chit 兩个方法 án-nóa ē 當直接表達做程序。

Finding roots of equations by the half-interval method 用半區間法 chhōe 方程式 ê 根

The *half-interval method* is a simple but powerful technique for finding roots of an equation $f(x) = 0$, where f is a continuous function. The idea is that, if we are given points a and b such that $f(a) < 0 < f(b)$, then f must have at least one zero between a and b. To locate a zero, let x be the average of a and b, and compute $f(x)$. If $f(x) > 0$, then f must have a zero between a and x. If $f(x) < 0$, then f must have a zero between x and b. Continuing

in this way, we can identify smaller and smaller intervals on which f must have a zero. When we reach a point where the interval is small enough, the process stops. Since the interval of uncertainty is reduced by half at each step of the process, the number of steps required grows as $\Theta(\log(L/T))$, where L is the length of the original interval and T is the error tolerance (that is, the size of the interval we will consider "small enough"). Here is a procedure that implements this strategy:
半區間法 (half-interval method) 是簡單但是有能力 ê 技術，來 chhōe 方程式 $f(x) = 0$ ê 根，其中 f 是連續函數。想法是，lán 若有 a kap b，滿足 $f(a) < 0 < f(b)$，佇 a kap b 中間，f 會有上少一个 0。Beh chhōe 0 對 ê 位置，就 kā x 設做 a kap b ê 平均，算出 $f(x)$。若是 $f(x) > 0$，a kap x 之間，f ê 值定著有 0；若是 $f(x) < 0$，x kap b 之間，f ê 值定著有 0。若是 án-ne 繼續，lán ē 當 kā f 定著有 0 ê 區間 kiu kah 愈來愈細。若是 lán kàu 區間有夠細 ê 點，程序就 soah。因為佇過程 ê 逐步，區間 ê 無確定範圍 ē kiu 半，所以需要 ê 手續數 tòe $\Theta(\log(L/T))$ 成長，其中 L 是開始 ê 區間長度，T 是錯誤 ê 公差（就是 lán 掠做「有夠細」ê 區間 sài-suh）。Che 是實做 chit ê 策略 ê 程序：

```
(define (search f neg-point pos-point)
  (let ((midpoint (average neg-point pos-point)))
    (if (close-enough? neg-point pos-point)
        midpoint
        (let ((test-value (f midpoint)))
          (cond ((positive? test-value)
                 (search f neg-point midpoint))
                ((negative? test-value)
                 (search f midpoint pos-point))
                (else midpoint))))))
```

We assume that we are initially given the function f together with points at which its values are negative and positive. We first compute the midpoint of the two given points. Next we check to see if the given interval is small

enough, and if so we simply return the midpoint as our answer. Otherwise, we compute as a test value the value of f at the midpoint. If the test value is positive, then we continue the process with a new interval running from the original negative point to the midpoint. If the test value is negative, we continue with the interval from the midpoint to the positive point. Finally, there is the possibility that the test value is 0, in which case the midpoint is itself the root we are searching for.

Lán 設使 tú 開始有函數 f kap 予函數值是負 kap 正 ê 點。Lán tāi 先計算 chit 兩點 ê 中點。續落來 lán 檢查區間敢有夠細，若是，就傳倒中點成做 lán ê 答案。Ah 無，lán 算 f 佇中點 ê 值，掠做測試 ê 值。若是試 ê 值是正 ê，lán 繼續過程，毋 koh 用 ê 新 ê 區間是對原來負 ê 點 kàu 中點；若是負 ê，lán 繼續，用 ê 新 ê 區間是對中點 kàu 正 ê 點。落尾，試 ê 值 mā 有可能是 0，chit 時中點就是 lán beh chhiau ê 根。

To test whether the endpoints are "close enough" we can use a procedure similar to the one used in Section 1.1.7 for computing square roots:[109]

Beh 試端點之間敢「有夠倚」，lán 通用 kap Section 1.1.7 ê 相 siâng ê 程序來算平方根：[110]

```
(define (close-enough? x y) (< (abs (- x y)) 0.001))
```

`search` is awkward to use directly, because we can accidentally give it points at which f's values do not have the required sign, in which case we get a wrong answer. Instead we will use `search` via the following procedure, which checks to see which of the endpoints has a negative function value and

[109] We have used 0.001 as a representative "small" number to indicate a tolerance for the acceptable error in a calculation. The appropriate tolerance for a real calculation depends upon the problem to be solved and the limitations of the computer and the algorithm. This is often a very subtle consideration, requiring help from a numerical analyst or some other kind of magician.

[110] Lán 有用 0.001 當做代表 ê「細」ê 數字來指示佇計算內允准 ê 公差。實際運算 ê 適當 ê 公差受決定佇 beh 解決 ê 問題 kap 電腦 hām 演算法 ê 限制。Che 定定是微妙 ê 考慮，需要數值分析師 á 是一寡別款 ê 魔術師。

which has a positive value, and calls the `search` procedure accordingly. If the function has the same sign on the two given points, the half-interval method cannot be used, in which case the procedure signals an error.[111]
直接用 `search` ē 真 gāi-giòh，因為 lán 可能無細膩予伊 f ê 值 ê 正負號無符合 ê 點，án-ne ē thèh 著無精確 ê 答案。Lán soah 通過下 kha ê 程序用 `search`，伊檢查 tó 一个端點有負 ê 函數值，tó 一个是正 ê，chiah 適當呼叫 `search`。若是函數佇 chit 兩个點 lóng kâng 正負號，半區間法就 bōe 當用，chit 時程序送錯誤訊號。[112]

```
(define (half-interval-method f a b)
  (let ((a-value (f a))
        (b-value (f b)))
    (cond ((and (negative? a-value) (positive? b-value))
           (search f a b))
          ((and (negative? b-value) (positive? a-value))
           (search f b a))
          (else
           (error "Values are not of opposite sign" a b)))))
```

The following example uses the half-interval method to approximate π as the root between 2 and 4 of $\sin x = 0$:
下 kha ê 例用半區間法來近似 π，當做 $\sin x = 0$ 佇 2 kap 4 之間 ê 值：

```
(half-interval-method sin 2.0 4.0)
3.14111328125
```

Here is another example, using the half-interval method to search for a root of the equation $x^3 - 2x - 3 = 0$ between 1 and 2:
Che 是別 ê 例，用半區間法 chhōe 方程式 $x^3 - 2x - 3 = 0$ 佇 1 kap 2 之間 ê 根：

[111] This can be accomplished using `error`, which takes as arguments a number of items that are printed as error messages.

[112] Che 通用 `error` 完成，伊 thèh 一寡 ē 印佇錯誤訊息 ê 項目做引數。

```
(half-interval-method (lambda (x) (- (* x x x) (* 2 x) 3))
                      1.0
                      2.0)
1.89306640625
```

Finding fixed points of functions Chhōe 函數 ê 不動點

A number x is called a *fixed point* of a function f if x satisfies the equation $f(x) = x$. For some functions f we can locate a fixed point by beginning with an initial guess and applying f repeatedly,
若是 x 滿足方程式 $f(x) = x$，x 就號做函數 f ê不動點 (fixed point)。對函數 f lán ē 當用起頭所 ioh ê，koh kā 重覆應用 kàu f，來定位不動點，

$$f(x), \quad f(f(x)), \quad f(f(f(x))), \quad \ldots,$$

until the value does not change very much. Using this idea, we can devise a procedure `fixed-point` that takes as inputs a function and an initial guess and produces an approximation to a fixed point of the function. We apply the function repeatedly until we find two successive values whose difference is less than some prescribed tolerance:
直 kàu 值無改變傷 chē。用 chit ê 概念，lán ē 當設計程序 `fixed-point`，kā 函數當做輸入，輸出函數 ê 不動點 ê 近似。Lán 重覆應用 chit ê 函數，直 kàu lán chhiau 著兩个連 sòa ê 值，伊 ê 差比規定 ê 公差較細：

```
(define tolerance 0.00001)
(define (fixed-point f first-guess)
  (define (close-enough? v1 v2)
    (< (abs (- v1 v2))
       tolerance))
  (define (try guess)
    (let ((next (f guess)))
      (if (close-enough? guess next)
```

```
          next
          (try next))))
  (try first-guess))
```

For example, we can use this method to approximate the fixed point of the cosine function, starting with 1 as an initial approximation:[113]
舉例，lán ē 當用 chit ê 方法來近似 cosine 函數 ê 不動點，kā 1 準做起頭 ê 近似：[114]

```
(fixed-point cos 1.0)
.7390822985224023
```

Similarly, we can find a solution to the equation
lán siâng 款 ē 當揣著 chit ê 方程式 ê 一个解
$y = \sin y + \cos y$:

```
(fixed-point (lambda (y) (+ (sin y) (cos y)))
             1.0)
1.2587315962971173
```

The fixed-point process is reminiscent of the process we used for finding square roots in Section 1.1.7. Both are based on the idea of repeatedly improving a guess until the result satisfies some criterion. In fact, we can readily formulate the square-root computation as a fixed-point search. Computing the square root of some number x requires finding a y such that $y^2 = x$. Putting this equation into the equivalent form $y = x/y$, we recognize that we are looking for a fixed point of the function[115] $y \mapsto x/y$, and we can therefore try to compute square roots as

[113] Try this during a boring lecture: Set your calculator to radians mode and then repeatedly press the `cos` button until you obtain the fixed point.

[114] 佇無聊 ê 課程中試 che：kā lí ê 計算機設做弧度 (radian) 模式，koh 直直 jih `cos` khí，直 kàu lí thèh 著不動點。

[115] $\mapsto$ (pronounced "maps to") is the mathematician's way of writing `lambda`. $y \mapsto x/y$ means `(lambda (y) (/ x y))`, that is, the function whose value at y is x/y.

不動點過程引 lâng 想起 lán 佇 Section 1.1.7 thèh 來 chhōe 平方根 ê 過程。兩个 lóng 起造佇重覆改進所 ioh ê，直 kàu 結果滿足一寡標準 ê 想法。實際上，Lán ē 當緊緊 kā 平方根 ê 計算形式化做不動點 ê chhiau-chhōe。計算數字 x ê 平方根需要 chhōe y，滿足 $y^2 = x$。Kā chit 个方程式改寫做 $y = x/y$，lán 辨別出 lán leh chhōe chit ê 函數[116] $y \mapsto x/y$ ê 不動點，lán 就 án-ne ē 當試用下 kha ê 方法算平方根：

```
(define (sqrt x)
  (fixed-point (lambda (y) (/ x y))
               1.0))
```

Unfortunately, this fixed-point search does not converge. Consider an initial guess y_1. The next guess is $y_2 = x/y_1$ and the next guess is $y_3 = x/y_2 = x/(x/y_1) = y_1$. This results in an infinite loop in which the two guesses y_1 and y_2 repeat over and over, oscillating about the answer.

Chit ê 不動點 chhiau-chhōe 方法不幸 bōe 收斂。考慮起頭所 ioh ê y_1。後一个所 ioh ê 是 $y_2 = x/y_1$，koh 後一个所 ioh ê 是 $y_3 = x/y_2 = x/(x/y_1) = y_1$。Chit ê 結果是佇無限 loop，其中 2 ê 所 ioh ê 值 y_1 kap y_2 一直重覆，答案 hài^{n} 來 hài^{n} 去。

One way to control such oscillations is to prevent the guesses from changing so much. Since the answer is always between our guess y and x/y, we can make a new guess that is not as far from y as x/y by averaging y with x/y, so that the next guess after y is $\frac{1}{2}(y+x/y)$ instead of x/y. The process of making such a sequence of guesses is simply the process of looking for a fixed point of $y \mapsto \frac{1}{2}(y + x/y)$:

Chit 款控制 hài^{n} 振動 ê 方法是避免所 ioh ê 改傷過大。因為答案一直佇所 ioh ê y kap x/y 中間，lán ē 當 kā x kap x/y 平均，製造新 ê 所 ioh ê，予伊 kàu y ê 距離無像 x/y hiah 遠，致 kàu y 以後後一个所 ioh ê，毋

[116] $\mapsto$（讀做「對應 kàu」）是數學家寫 `lambda` ê 方式。$y \mapsto x/y$ 意思是 `(lambda (y) (/ x y))`，就是佇 y ê 值是 x/y ê 函數。

是 x/y，是 $\frac{1}{2}(y + x/y)$。製造 chit 款所 ioh ê 列 ê 過程，就簡單是 chhōe $y \mapsto \frac{1}{2}(y + x/y)$ ê 不動點 ê 過程。

```
(define (sqrt x)
  (fixed-point (lambda (y) (average y (/ x y)))
               1.0))
```

(Note that $y = \frac{1}{2}(y + x/y)$ is a simple transformation of the equation $y = x/y$; to derive it, add y to both sides of the equation and divide by 2.)
(注意 $y = \frac{1}{2}(y + x/y)$ 干焦是方程式 $y = x/y$ ê 簡單轉換。Beh kā 推出，著 kā chit ê 方程式 ê 雙 pêng 邊加 y，koh 用 2 除)

With this modification, the square-root procedure works. In fact, if we unravel the definitions, we can see that the sequence of approximations to the square root generated here is precisely the same as the one generated by our original square-root procedure of Section 1.1.7. This approach of averaging successive approximations to a solution, a technique that we call *average damping*, often aids the convergence of fixed-point searches.

用 chit ê 修改，平方根程序通運作。實際上，若是 lán 解破 chiah ê 定義，lán 通看見所生成 ê 近似 kàu 平方根 ê 列 kap lán 佇 Section 1.1.7 原來 ê 平方根程序所生成 ê，完全 kâng 款。解 ê 平均相連 sòa ê 近似方法，就是 lán 所講 ê 平均減衰 (average damping)，定定幫 chān 不動點 chhiau-chhōe ê 收斂。

Exercise 1.35: Show that the golden ratio φ (Section 1.2.2) is a fixed point of the transformation $x \mapsto 1 + 1/x$, and use this fact to compute φ by means of the `fixed-point` procedure.

Exercise 1.35: 展示黃金比例 φ (Section 1.2.2) 是轉換 (transformation) $x \mapsto 1 + 1/x$ ê 一个不動點，koh 用 chit ê 事實 kap `fixed-point` 程序計算 φ。

Exercise 1.36: Modify `fixed-point` so that it prints the sequence of approximations it generates, using the `newline`

and `display` primitives shown in Exercise 1.22. Then find a solution to $x^x = 1000$ by finding a fixed point of $x \mapsto \log(1000)/\log(x)$. (Use Scheme's primitive `log` procedure, which computes natural logarithms.) Compare the number of steps this takes with and without average damping. (Note that you cannot start `fixed-point` with a guess of 1, as this would cause division by $\log(1) = 0$.)

Exercise 1.36: 用展示佇 Exercise 1.22 ê 基礎函數 `newline` kap `display`，改 `fixed-point` 予伊印所生成 ê 近似 ê 列。Koh chhōe $x \mapsto \log(1000)/\log(x)$ ê 不動點，來 chhōe $x^x = 1000$ ê 一个解。(用 Scheme ê 基礎 `log` 程序，伊計算自然對數。) 比較需要 kap 無需要平均減衰所需要 ê 手續數（注意，lí bōe 當用 1 準做所 ioh ê 來開始 `fixed-point`，che 會發生予 $\log(1) = 0$ 除。

Exercise 1.37:

a. An infinite *continued fraction* is an expression of the form 無限 ê 連分數 (continued fraction) 是下 kha 形式 ê 表達式：

$$f = \cfrac{N_1}{D_1 + \cfrac{N_2}{D_2 + \cfrac{N_3}{D_3 + \ldots}}}.$$

As an example, one can show that the infinite continued fraction expansion with the N_i and the D_i all equal to 1 produces $1/\varphi$, where φ is the golden ratio (described in

Section 1.2.2). One way to approximate an infinite continued fraction is to truncate the expansion after a given number of terms. Such a truncation—a so-called *k-term finite continued fraction*—has the form

舉例：lâng ē 當展示無限連分數 ê N_i kap D_i lóng 是 1 ê 時陣，ē 得著 $1/\varphi$，其中 φ 就是黃金比例（敘述佇 Section 1.2.2）。一个近似無限連分數 ê 方法，就是佇特定量 ê 項以後，kā 表達式切斷。Chit 款切斷——所謂 ê k 項有限連分數 (k-term finite continued fraction)，有下 kha ê 型：

$$\cfrac{N_1}{D_1 + \cfrac{N_2}{\ddots + \cfrac{N_k}{D_k}}}.$$

Suppose that `n` and `d` are procedures of one argument (the term index i) that return the N_i and D_i of the terms of the continued fraction. Define a procedure `cont-frac` such that evaluating `(cont-frac n d k)` computes the value of the k-term finite continued fraction. Check your procedure by approximating $1/\varphi$ using

假使 `n` kap `d` 是單引數程序（引數是項 ê 指數 i），傳轉去連分數 ê 項 N_i kap D_i。定義程序 `cont-frac`，滿足計算 `(cont-frac n d k)` ê 值，就 ē 計算 k 項有限連分數 ê 值。用近似 $1/\varphi$ kap 下 kha ê 程序，檢查 lí ê 程序：

```
(cont-frac (lambda (i) 1.0)
           (lambda (i) 1.0)
           k)
```

for successive values of `k`. How large must you make `k` in order to get an approximation that is accurate to 4 decimal places?

對 `k` ê 相連 sòa ê 值。為著 beh thèh 著準確 kah 小數點第 4 位 ê 近似，`k` 需要有 gōa 大？

b. If your `cont-frac` procedure generates a recursive process, write one that generates an iterative process. If it generates an iterative process, write one that generates a recursive process.

若是 lí ê `cont-frac` 程序生成遞迴 ê 過程，寫出一个生成反覆 ê 過程 ê。若是伊生成反覆 ê 過程，寫一个生成遞迴 ê 過程 ê。

Exercise 1.38: In 1737, the Swiss mathematician Leonhard Euler published a memoir *De Fractionibus Continuis*, which included a continued fraction expansion for $e - 2$, where e is the base of the natural logarithms. In this fraction, the N_i are all 1, and the D_i are successively 1, 2, 1, 1, 4, 1, 1, 6, 1, 1, 8, ... Write a program that uses your `cont-frac` procedure from Exercise 1.37 to approximate e, based on Euler's expansion.

Exercise 1.38: 佇 1737 年，瑞士 ê 數學家 Leonhard Euler 出版回憶錄 *De Fractionibus Continuis*，包含 $e - 2$ ê 連分數 ê 展開，其中 e 是自然對數 ê 底。佇 chit ê 分數，N_i lóng 是 1，D_i 是相連 sòa ê 1, 2, 1, 1, 4, 1, 1, 6, 1, 1, 8, ...。寫一个程式，用 lí 佇 Exercise 1.37 ê `cont-frac` 程序，來近似 e，chhāi 佇 Euler ê 展開式。

Exercise 1.39: A continued fraction representation of the tangent function was published in 1770 by the German mathematician J.H. Lambert:

Exercise 1.39: 正切 (tangent) 函數 ê 連分數表示法是佇 1770 年由德國數學家 J.H. Lambert 提出：

$$\tan x = \cfrac{x}{1 - \cfrac{x^2}{3 - \cfrac{x^2}{5 - \ldots}}},$$

where x is in radians. Define a procedure `(tan-cf x k)` that computes an approximation to the tangent function based on Lambert's formula. `k` specifies the number of terms to compute, as in Exercise 1.37.

其中 x ê 單位是弧度。定義程序 `(tan-cf x k)`，chhāi 佇 Lambert ê 公式，來算正切函數 ê 近似。`k` 指定 beh 算 ê 項 ê 數量，親像佇 Exercise 1.37。

1.3.4 Procedures as Returned Values 程序當做傳轉 ê 值

The above examples demonstrate how the ability to pass procedures as arguments significantly enhances the expressive power of our programming language. We can achieve even more expressive power by creating procedures whose returned values are themselves procedures.
頂 koân ê 例展示 kā 程序當做引數傳入去 ê 能力，ē án-nóa 明顯加強 lán ê 程式語言 ê 表達力。Lán 通創造傳轉來 ê 值是程序 ê 程序，及至 koh 較大 ê 表現力。

We can illustrate this idea by looking again at the fixed-point example described at the end of Section 1.3.3. We formulated a new version of the square-root procedure as a fixed-point search, starting with the observation that $\sqrt{x}$ is a fixed-point of the function $y \mapsto x/y$. Then we used average

damping to make the approximations converge. Average damping is a useful general technique in itself. Namely, given a function f, we consider the function whose value at x is equal to the average of x and $f(x)$.

Lán ē 當 koh 看佇 Section 1.3.3 落尾 ê 不動點 ê 例，來說明 chit ê 想法。Lán 形式化平方根程序 ê 新版，當做不動點 ê chhiau-chhōe，對觀察 $\sqrt{x}$ 是函數 $y \mapsto x/y$ ê 不動點開始，了後 lán 用平均減衰來予近似收斂。平均減衰家 kī 是有路用 ê 一般技術。就是，有函數 f，lán 考慮函數，伊佇 x ê 值等於 x kap $f(x)$ ê 平均。

We can express the idea of average damping by means of the following procedure:

Lán ē 當用下 kha ê 程序，表達平均減衰 ê 想法：

```
(define (average-damp f)
  (lambda (x) (average x (f x))))
```

`average-damp` is a procedure that takes as its argument a procedure `f` and returns as its value a procedure (produced by the `lambda`) that, when applied to a number `x`, produces the average of `x` and `(f x)`. For example, applying `average-damp` to the `square` procedure produces a procedure whose value at some number x is the average of x and x^2. Applying this resulting procedure to 10 returns the average of 10 and 100, or 55:[117]

`average-damp` 是程序，thèh 程序 f 成做引數，傳轉一个程序（由 `lambda` 所生成），若是 chit ê 程序應用一个數 `x`，產出 `x` kap `(f x)` ê 平均。舉例，應用 `average-damp` kàu `square` 程序，產出程序，伊佇 x ê 值是 x kap x^2 ê 平均。應用 chit ê 結果程序 kàu 10，ē 傳倒轉 10 kap 100 ê 平均，就是 55：[118]

[117] Observe that this is a combination whose operator is itself a combination. Exercise 1.4 already demonstrated the ability to form such combinations, but that was only a toy example. Here we begin to see the real need for such combinations—when applying a procedure that is obtained as the value returned by a higher-order procedure.

[118] 觀察 che 是伊 ê 運算子家 kī mā 是組合 ê 組合。Exercise 1.4 已經展示予這號組合成形 ê

```
((average-damp square) 10)
55
```

Using `average-damp`, we can reformulate the square-root procedure as follows:
用 `average-damp`，lán ē 當 koh 形式化平方根 ê 程序，若下 kha：

```
(define (sqrt x)
  (fixed-point (average-damp (lambda (y) (/ x y)))
               1.0))
```

Notice how this formulation makes explicit the three ideas in the method: fixed-point search, average damping, and the function $y \mapsto x/y$. It is instructive to compare this formulation of the square-root method with the original version given in Section 1.1.7. Bear in mind that these procedures express the same process, and notice how much clearer the idea becomes when we express the process in terms of these abstractions. In general, there are many ways to formulate a process as a procedure. Experienced programmers know how to choose procedural formulations that are particularly perspicuous, and where useful elements of the process are exposed as separate entities that can be reused in other applications. As a simple example of reuse, notice that the cube root of x is a fixed point of the function $y \mapsto x/y^2$, so we can immediately generalize our square-root procedure to one that extracts cube roots:[119]
注意 chit ê 形式化佇本方法，予 chit 三个想法顯明：chhōe 不動點、平均減衰 kap 函數 $y \mapsto x/y$。Kā chit ê 平方根法 ê 形式化 kap 佇 Section 1.1.7 ê 原版相比，通啟發 lâng。著記得 chiah ê 程序表達 kâng 款 ê 過程，mā 注意當 lán 用 chiah ê 抽象，想法 ē 變做 gǒa-nī-á 清楚。一般來講，有 chē-chē 方法 kā 過程形式化做程序。老經驗 ê 程式設計師知 án-nóa 揀程序 ê 特別清楚 ê 形式

能力，毋過 he kan-ta 是 chhit-thô 物 á ê 例。Lán 佇 chia 開始看見 chit 款組合 ê 真 ê 需求——佇應用所 thèh 著 ê，是由懸階函數傳轉 ê 值 ê 程序。

[119] See Exercise 1.45 for a further generalization.

化，以及過程有路用 ê 要素，佇 tó 位 ē 當拆做分開 ê 實體，ē 當佇別 ê 應用內重使用。做著重使用 ê 簡單 ê 例，注意 x ê 立方根是函數 $y \mapsto x/y^2$ ê 不動點，án-ne lán ē 當 liâm-mi kā lán ê 平方根程序一般化 kàu 求立方根 ê：[120]

```
(define (cube-root x)
  (fixed-point (average-damp (lambda (y) (/ x (square y))))
               1.0))
```

Newton's method Newton ê 方法

When we first introduced the square-root procedure, in Section 1.1.7, we mentioned that this was a special case of *Newton's method*. If $x \mapsto g(x)$ is a differentiable function, then a solution of the equation $g(x) = 0$ is a fixed point of the function $x \mapsto f(x)$, where

當 lán 佇 Section 1.1.7 代先介紹平方根 ê 程序，bat 提起 che 是*Newton ê* 方法 (Newton's method)ê 特例。若準講 $x \mapsto g(x)$ 是通微分 ê 函數，方程式 $g(x) = 0$ ê 解，是函數 $x \mapsto f(x)$ ê 不動點，其中

$$f(x) = x - \frac{g(x)}{Dg(x)}$$

and $Dg(x)$ is the derivative of g evaluated at x. Newton's method is the use of the fixed-point method we saw above to approximate a solution of the equation by finding a fixed point of the function f.[121]
而且 $Dg(x)$ 是 g 佇 x ê 導函數 (derivative)。Newton ê 方法是用 lán 進前看 ê 不動點方法，來用 chhōe 函數 f ê 不動點，近似方程式 ê 解。[122]

[120] 看 Exercise 1.45，了解 koh 較深 ê 一般化。

[121] Elementary calculus books usually describe Newton's method in terms of the sequence of approximations $x_{n+1} = x_n - g(x_n)/Dg(x_n)$. Having language for talking about processes and using the idea of fixed points simplifies the description of the method.

[122] 基礎微積分 ê 冊通常用近似 ê 列 $x_{n+1} = x_n - g(x_n)/Dg(x_n)$，來描述 Newton ê 方法。有通討論過程 kap 用不動點 ê 想法 ê 語言，ē 簡單化 chit ê 方法 ê 描述。

For many functions g and for sufficiently good initial guesses for x, Newton's method converges very rapidly to a solution of $g(x) = 0$.[123]

對 chē-chē 函數 g kap 有夠好 ê 起頭所 ioh ê x，Newton ê 方法快速收斂 kàu $g(x) = 0$ ê 解。[124]

In order to implement Newton's method as a procedure, we must first express the idea of derivative. Note that "derivative," like average damping, is something that transforms a function into another function. For instance, the derivative of the function $x \mapsto x^3$ is the function $x \mapsto 3x^2$. In general, if g is a function and dx is a small number, then the derivative Dg of g is the function whose value at any number x is given (in the limit of small dx) by

Beh kā Newton ê 方法實做成做程序，lán 定著先表達導函數 ê 概念。注意「導函數」，像平均減衰，是 kā 函數轉換做別 ê 函數 ê。比如講，函數 ê 導函數 $x \mapsto x^3$ 是函數 $x \mapsto 3x^2$。一般來講，若是 g 是函數，dx 是較細 ê 數字，g ê 導函數 Dg，是伊佇任何數 x ê 值，由下 kha ê 式求（dx 著愛足細）ê 函數：

$$Dg(x) = \frac{g(x + dx) - g(x)}{dx}.$$

Thus, we can express the idea of derivative (taking dx to be, say, 0.00001) as the procedure

就 án-ne，lán 通表達導數 ê 概念（kā dx 準做 0.00001），用程序

```
(define (deriv g)
  (lambda (x) (/ (- (g (+ x dx)) (g x)) dx)))
```

[123] Newton's method does not always converge to an answer, but it can be shown that in favorable cases each iteration doubles the number-of-digits accuracy of the approximation to the solution. In such cases, Newton's method will converge much more rapidly than the half-interval method.

[124] Newton ê 方法無一定 ē 收斂 kàu 答案，毋 koh ē 當展示，佇較好 ê 例內底，逐擺反覆 kā 解 ê 近似值 ê 精度 ê 數位加一倍。佇 chit 號案例，Newton ê 方法 ē 比半區間法收斂 koh 較緊。

along with the definition
kap chit ê 定義

```
(define dx 0.00001)
```

Like `average-damp`, `deriv` is a procedure that takes a procedure as argument and returns a procedure as value. For example, to approximate the derivative of $x \mapsto x^3$ at 5 (whose exact value is 75) we can evaluate
像 `average-damp`，`deriv` 是一个程序，thèh 一个程序當做引數，傳轉程序當做值。舉例，beh 近似 $x \mapsto x^3$ ê 引數佇 5 ê 值（伊精確 ê 值是 75），lán ē 當算

```
(define (cube x) (* x x x))
((deriv cube) 5)
75.00014999664018
```

With the aid of `deriv`, we can express Newton's method as a fixed-point process:
有 `deriv` ê 幫 chān，lán ē 當 kā Newton ê 方法表達做不動點 ê 過程：

```
(define (newton-transform g)
  (lambda (x) (- x (/ (g x) ((deriv g) x)))))
(define (newtons-method g guess)
  (fixed-point (newton-transform g) guess))
```

The `newton-transform` procedure expresses the formula at the beginning of this section, and `newtons-method` is readily defined in terms of this. It takes as arguments a procedure that computes the function for which we want to find a zero, together with an initial guess. For instance, to find the square root of x, we can use Newton's method to find a zero of the function $y \mapsto y^2 - x$ starting with an initial guess of 1.[125]

[125] For finding square roots, Newton's method converges rapidly to the correct solution from any starting point.

`newton-transform` 程序表達佇本節起頭 ê 公式，`newtons-method` 是用 che 緊緊定義。伊 ê 引數是一个程序（chit ê 程序是 thèh 來計算 lán 想 beh chhōe 伊佇 0 ê 值 ê 函數用 ê），kap 起頭所 ioh ê 值。舉例，beh chhōe x ê 平方根，lán 通用 Newton ê 方法來 chhōe 函數 $y \mapsto y^2 - x$ 佇 0 ê 值，起頭所 ioh ê 值是 1。[126]

This provides yet another form of the square-root procedure:
Che 提供另外一个平方根程序 ê 形式：

```
(define (sqrt x)
  (newtons-method
   (lambda (y) (- (square y) x)) 1.0))
```

Abstractions and first-class procedures 抽象 kap 第一級程序

We've seen two ways to express the square-root computation as an instance of a more general method, once as a fixed-point search and once using Newton's method. Since Newton's method was itself expressed as a fixed-point process, we actually saw two ways to compute square roots as fixed points. Each method begins with a function and finds a fixed point of some transformation of the function. We can express this general idea itself as a procedure:
Lán 有看見 2 種表達平方根計算 ê 方法當做 koh 較一般 ê 方法，一个是 chhiau-chhōe 不動點，一个用 Newton ê 方法。因為 Newton ê 方法家 kī 予 lâng 表達做不動點過程，lán 實際上看見 kā 平方根當做不動點來算 ê 兩款方法。逐 ê 方法 kap 函數做伙開始，然後 chhōe 函數 ê 變形 ê 不動點。Lán ē 當 kā chit ê 一般 ê 概念家 kī 當做程序表達：

```
(define (fixed-point-of-transform g transform guess)
  (fixed-point (transform g) guess))
```

[126] 對 chhōe 平方根來講，Newton ê 方法 ē 對任何起頭 ê 點，緊緊收斂 kàu 正確 ê 解。

This very general procedure takes as its arguments a procedure g that computes some function, a procedure that transforms g, and an initial guess. The returned result is a fixed point of the transformed function.
Chit ê 非常一般 ê 程序所 thèh ê 引數，有程序 g（伊計算函數）、變換 g ê 程序 kap 起頭所 ioh ê。傳轉 ê 結果是轉換 ê 函數 ê 不動點。

Using this abstraction, we can recast the first square-root computation from this section (where we look for a fixed point of the average-damped version of $y \mapsto x/y$) as an instance of this general method:

用 chit ê 抽象，lán 通 kā 本節 ê 頭一个平方根計算（lán 佇其中 chhōe $y \mapsto x/y$ 平均減衰版 ê 不動點）重改做 chit ê 一般方法 ê 實例：

```
(define (sqrt x)
  (fixed-point-of-transform
   (lambda (y) (/ x y)) average-damp 1.0))
```

Similarly, we can express the second square-root computation from this section (an instance of Newton's method that finds a fixed point of the Newton transform of $y \mapsto y^2 - x$) as
Lán kâng 款 ē 當表達本節第二个平方根計算（Newton ê 方法 ê 實例，伊 chhōe $y \mapsto y^2 - x$ ê Newton 變換 ê 不動點）做

```
(define (sqrt x)
  (fixed-point-of-transform
   (lambda (y) (- (square y) x)) newton-transform 1.0))
```

We began Section 1.3 with the observation that compound procedures are a crucial abstraction mechanism, because they permit us to express general methods of computing as explicit elements in our programming language. Now we've seen how higher-order procedures permit us to manipulate these general methods to create further abstractions.
Lán 用觀察複合程序是蓋重要 ê 抽象機制來開始 Section 1.3，因為 in 允准 lán 佇 lán ê 程式語言 kā 一般計算概念當做顯明 ê 要素來表達。Ta^{n} lán 有看著 koân 階程序允准 lán 操作 chiah ê 一般方法，來創造 koh 較進階 ê 抽象。

As programmers, we should be alert to opportunities to identify the underlying abstractions in our programs and to build upon them and generalize them to create more powerful abstractions. This is not to say that one should always write programs in the most abstract way possible; expert programmers know how to choose the level of abstraction appropriate to their task. But it is important to be able to think in terms of these abstractions, so that we can be ready to apply them in new contexts. The significance of higher-order procedures is that they enable us to represent these abstractions explicitly as elements in our programming language, so that they can be handled just like other computational elements.

做著程式設計師，lán 著對辨別程序內底隱藏 ê 抽象 ê 機會警醒，起造 in，koh kā in 一般化來創造 koh 較有路用 ê 抽象。Che 毋是講 lán 著一直用上抽象 ê 可能方式寫程式；出師 ê 程式設計師知 án-nóa 揀適合 in ê 工課 ê 抽象水準。但是 ē 當用 chiah ê 抽象思考是真重要，致使 lán ē 當備辦好勢，佇後文用 che。Koân 階程序 ê 意義是通予 lán kā chiah ê 抽象顯明表示做 lán ê 語言 ê 要素，致 kàu in ē 當像別 ê 計算要素 kâng 款予 lâng 處理。

In general, programming languages impose restrictions on the ways in which computational elements can be manipulated. Elements with the fewest restrictions are said to have *first-class* status. Some of the "rights and privileges" of first-class elements are:[127]

一般來講，程式語言 ē kā 計算要素 ē 當操作 ê 方法捒限制。要素有上少 ê 限制 ē 當講是有頭等 (first-class) ê 狀態。一寡頭等要素 ê「權利 kap 特權」是[128]

- They may be named by variables.

  In ē 當用變數號名

[127] The notion of first-class status of programming-language elements is due to the British computer scientist Christopher Strachey (1916-1975).

[128] 程式語言要素 ê 頭等狀態，是由不列顛 ê 電腦科學家 Christopher Strachey (1916-1975) 所推出。

- They may be passed as arguments to procedures.

  In ē 當當做引數傳入去程序

- They may be returned as the results of procedures.

  In ē 當當做程序傳轉去 ê 結果

- They may be included in data structures.[129]

  In ē 當包佇資料結構。[130]

Lisp, unlike other common programming languages, awards procedures full first-class status. This poses challenges for efficient implementation, but the resulting gain in expressive power is enormous.[131]
Lisp 無 sêng 其他通常 ê 程式語言，程序 lóng 有頭等地位。Che ē 加添有效率實做 ê 挑戰，毋 koh 結果 ē thèh 著極大 ê 表現力。[132]

> **Exercise 1.40:** Define a procedure `cubic` that can be used together with the `newtons-method` procedure in expressions of the form
>
> **Exercise 1.40:** 定義程序 `cubic`，伊著照下 kha ê 形式 ê 表達式，hām `newtons-method` 做伙用
>
> ```
> (newtons-method (cubic a b c) 1)
> ```

[129] We'll see examples of this after we introduce data structures in Chapter 2.

[130] Lán 佇Chapter 2紹介資料結果了後，ē 看著 chit ê ê 例。

[131] The major implementation cost of first-class procedures is that allowing procedures to be returned as values requires reserving storage for a procedure's free variables even while the procedure is not executing. In the Scheme implementation we will study in Section 4.1, these variables are stored in the procedure's environment.

[132] 頭等程序 ê 主要 ê 實做成本，是允准程序當做值傳轉，就算程序無 teh pháng，mā 需要保留程序 ê 自由變數 ê 儲存空間。佇 lán beh 佇 Section 4.1學習 ê Scheme 實做，chiah ê 變數 ē tiông 佇程序 ê 環境。

to approximate zeros of the cubic $x^3 + ax^2 + bx + c$.

來 chhōe 三次方程式 $x^3 + ax^2 + bx + c$ ê 近似解。

Exercise 1.41: Define a procedure `double` that takes a procedure of one argument as argument and returns a procedure that applies the original procedure twice. For example, if `inc` is a procedure that adds 1 to its argument, then `(double inc)` should be a procedure that adds 2. What value is returned by

Exercise 1.41: 定義程序 `double`，伊 thèh 一个單引數程序當做引數，傳轉應用原底 ê 程序兩改 ê 程序。比如講，若 `inc` 是一个 kā 引數加 1 ê 程序，`(double inc)` 就應該是 kā 引數加 2 ê 程序。下 kha ê 表達式 ê 值是 siáⁿ？

```
(((double (double double)) inc) 5)
```

Exercise 1.42: Let f and g be two one-argument functions. The *composition* f after g is defined to be the function $x \mapsto f(g(x))$. Define a procedure `compose` that implements composition. For example, if `inc` is a procedure that adds 1 to its argument,

Exercise 1.42: Chia 有 f kap g 兩 ê 單引數程序。f kap g ê 合成 (composition) 定義做函數 $x \mapsto f(g(x))$。請定義實做合成 ê 程序 `compose`。比如講，若 `inc` 是一个 kā 引數加 1 ê 程序，就有

```
((compose square inc) 6)
49
```

Exercise 1.43: If f is a numerical function and n is a positive integer, then we can form the nth repeated application of f, which is defined to be the function whose value at x is

$f(f(\ldots(f(x))\ldots))$. For example, if f is the function $x \mapsto x + 1$, then the nth repeated application of f is the function $x \mapsto x + n$. If f is the operation of squaring a number, then the nth repeated application of f is the function that raises its argument to the 2^n-th power. Write a procedure that takes as inputs a procedure that computes f and a positive integer n and returns the procedure that computes the nth repeated application of f. Your procedure should be able to be used as follows:

Exercise 1.43: 若 f 是數值函數，n 是正整數，lán ē 當 kā f 重覆應用 n 改，伊 ē 當定義做，伊佇 x ê 值就是 $f(f(\ldots(f(x))\ldots))$。舉例，若 f 是函數 $x \mapsto x + 1$，f 重覆應用 n 改就是函數 $x \mapsto x + n$。若 f 是平方一个數 ê 運算子，f 重覆應用 n 改就是傳轉引數 ê 2^n 次方 ê 函數。寫一个程序，伊 ê 引數是算 f ê 程序 kap 正整數 n，傳轉 kā f 重覆應用 n 改 ê 程序。Lí ê 程序應該 ē 當 án-ne 用：

```
((repeated square 2) 5)
625
```

Hint: You may find it convenient to use `compose` from Exercise 1.42.

提示：Lí 可能發現用 Exercise 1.42 ê `compose` 較利便。

Exercise 1.44: The idea of *smoothing* a function is an important concept in signal processing. If f is a function and dx is some small number, then the smoothed version of f is the function whose value at a point x is the average of $f(x - dx)$, $f(x)$, and $f(x + dx)$. Write a procedure `smooth` that takes as input a procedure that computes f and returns a procedure that computes the smoothed f. It is sometimes valuable to repeatedly smooth a function (that is, smooth the smoothed function,

and so on) to obtain the *n-fold smoothed function*. Show how to generate the *n*-fold smoothed function of any given function using `smooth` and `repeated` from Exercise 1.43.

Exercise 1.44: Kā 函數平滑化 (smoothing) 是佇訊號處理內 ê 重要概念。若準講 f 是函數，dx 是足細 ê 數，f ê 平滑化 ê 版本就是一个函數，伊佇 x 點 ê 值是 $f(x-dx)$、$f(x)$ kap $f(x+dx)$ ê 平均。寫一个程序 `smooth`，伊 thèh 算 f 函數 ê 程序做引數，傳轉算平滑化 ê f 函數 ê 程序。有時仔重覆平滑化一个函數 ē 有價值（就是，kā 平滑化了後 ê 函數 koh 一直平滑化），來 thèh 著第 *n* 改平滑化 *ê* 函數 (*n*-fold smoothed function)。展示 án-nóa 用 Exercise 1.43 內底 ê `smooth` kap `repeated`，生成函數 ê 第 *n* 改平滑化 ê 函數。

Exercise 1.45: We saw in Section 1.3.3 that attempting to compute square roots by naively finding a fixed point of $y \mapsto x/y$ does not converge, and that this can be fixed by average damping. The same method works for finding cube roots as fixed points of the average-damped $y \mapsto x/y^2$. Unfortunately, the process does not work for fourth roots—a single average damp is not enough to make a fixed-point search for $y \mapsto x/y^3$ converge. On the other hand, if we average damp twice (i.e., use the average damp of the average damp of $y \mapsto x/y^3$) the fixed-point search does converge. Do some experiments to determine how many average damps are required to compute n^{th} roots as a fixed-point search based upon repeated average damping of $y \mapsto x/y^{n-1}$. Use this to implement a simple procedure for computing n^{th} roots using `fixed-point`, `average-damp`, and the `repeated` procedure of Exercise 1.43. Assume that any arithmetic operations you need are available as primitives.

Exercise 1.45: Lán 佇 Section 1.3.3 看見用 chhōe $y \mapsto x/y$ ê 不動點來試計算平方根 bōe 收斂，而且 ē 當用平均減衰解決。Kâng 款方法 mā ē 當用佇 chhōe 立方根，只要求出 $y \mapsto x/y^2$ ê 平均減衰 ê 不動點。但是 chit ê 過程佇 chhōe 四次方根 ê 時無效——一个平均減衰無夠予 $y \mapsto x/y^3$ ê 不動點 chhiau-chhōe 收斂。另外方面，若是 lán 平均減衰兩改（就是用 $y \mapsto x/y^3$ ê 平均減衰 ê 平均減衰），不動點 chhiau-chhōe ē 收斂。做一寡試驗來確定，beh 用重覆平均減衰 kap chhiau-chhōe $y \mapsto x/y^{n-1}$ ê 不動點 ê 方法，來算 n 次平方根 ê 過程，平均減衰著愛幾改？用 che 來實做簡單 ê 程序，thèh 佇 Exercise 1.43 內底 ê `fixed-point`、`average-damp` kap `repeated` ê 程序，來算 n 次平方根。假使任何 lí 需要 ê 任何運算操作 lóng 是 ē 當用 ê 基礎函數。

Exercise 1.46: Several of the numerical methods described in this chapter are instances of an extremely general computational strategy known as *iterative improvement*. Iterative improvement says that, to compute something, we start with an initial guess for the answer, test if the guess is good enough, and otherwise improve the guess and continue the process using the improved guess as the new guess. Write a procedure `iterative-improve` that takes two procedures as arguments: a method for telling whether a guess is good enough and a method for improving a guess. `iterative-improve` should return as its value a procedure that takes a guess as argument and keeps improving the guess until it is good enough. Rewrite the `sqrt` procedure of Section 1.1.7 and the `fixed-point` procedure of Section 1.3.3 in terms of `iterative-improve`.

Exercise 1.46: 幾个佇本章描述 ê 數值方法是極其一般 ê，號做反覆改善 (iterative improvement) ê 運算策略 ê 實例。反覆改善是

講，beh 算物件，lán 先為答案 ioh 起頭 ê 值，試所 ioh ê 敢有夠好，若無，改善所 ioh ê，koh 用改善過 ê 值準做新 ê 所 ioh ê，來繼續過程。寫程序 `iterative-improve`，伊 ê 引數是兩个程序：一个判定所 ioh ê 敢有夠好，kap 一个改善所 ioh ê。`iterative-improve` 應該傳轉 ê 值是程序，伊 thèh 所 ioh ê 當做引數，繼續改善，直到伊有夠好。用 `iterative-improve` 重寫 Section 1.1.7 ê `sqrt` 程序 kap Section 1.3.3 ê `fixed-point` 程序。

2

Building Abstractions with Data 用資料起造抽象

> We now come to the decisive step of mathematical abstraction: we forget about what the symbols stand for. . . .[The mathematician] need not be idle; there are many operations which he may carry out with these symbols, without ever having to look at the things they stand for.
>
> Lán chit-má 來 kàu 數學抽象上要緊 ê 階段：lán kā 符號所指 ê 放 bē 記。[數學家] 無需要無代誌；chia 有真 chē 伊可能需要用 chiah ê 符號執行 ê 操作，無需要看 in 所指 ê 物件。
>
> —Hermann Weyl, *The Mathematical Way of Thinking*

We concentrated in Chapter 1 on computational processes and on the role of procedures in program design. We saw how to use primitive data (numbers) and primitive operations (arithmetic operations), how to combine procedures to form compound procedures through composition, conditionals, and the use of parameters, and how to abstract procedures by using `define`. We saw that a procedure can be regarded as a pattern for the local evolution

of a process, and we classified, reasoned about, and performed simple algorithmic analyses of some common patterns for processes as embodied in procedures. We also saw that higher-order procedures enhance the power of our language by enabling us to manipulate, and thereby to reason in terms of, general methods of computation. This is much of the essence of programming.

Lán 佇 Chapter 1 注意計算過程，kap 佇程式設計內底，程序 ê 角色。Lán 看見基礎資料（數）kap 基礎操作（運算操作）、án-nóa 用合成來組合程序來成做複合程序、條件、參數 ê 使用，以及 án-nóa 用 `define` 抽象程序。Lán 看見程序 ē 當看做是過程 ê 區域展開 ê 模式，而且分類、推理 kap 行簡單 ê 一寡 chiảp 看 ê，收佇程序 ê 過程 ê，模式 ê 演算法分析。Mā 看見 koân 階函數倚靠予 lán ē 當操作，就 án-ne 用一般計算 ê 方法來推理，來 giâ-koân lán ê 語言 ê 能力。Che 是程式設計 ê 大部份精華。

In this chapter we are going to look at more complex data. All the procedures in chapter 1 operate on simple numerical data, and simple data are not sufficient for many of the problems we wish to address using computation. Programs are typically designed to model complex phenomena, and more often than not one must construct computational objects that have several parts in order to model real-world phenomena that have several aspects. Thus, whereas our focus in chapter 1 was on building abstractions by combining procedures to form compound procedures, we turn in this chapter to another key aspect of any programming language: the means it provides for building abstractions by combining data objects to form *compound data*.

佇 chit 章 lán beh 來看較複雜 ê 資料，所有佇第一章 ê 程式 lóng 操作數值資料，簡單 ê 資料無夠 thèh 來予 lán beh 用計算處理 ê 問題用，lâng 定定著建構有幾个部份運算 ê 物件，來模型有幾个層面 ê 現實世界 ê 現象。因此，雖bóng lán 佇第一章聚集佇用組合程序成做複合程序，來起造抽象，lán 佇 chit 章 oat 過來看逐 ê 程式語言另外 ê 關鍵層面：提供用組合資料物件組成複合資料 (compound data)，來起造抽象 ê 方法。

Why do we want compound data in a programming language? For the same reasons that we want compound procedures: to elevate the conceptual level at which we can design our programs, to increase the modularity of our designs, and to enhance the expressive power of our language. Just as the ability to define procedures enables us to deal with processes at a higher conceptual level than that of the primitive operations of the language, the ability to construct compound data objects enables us to deal with data at a higher conceptual level than that of the primitive data objects of the language.

是 án-nóa lán 佇程式語言內底 beh 愛複合資料？Kap lán beh 愛複合程序 ê 原因 kâng 款：來提升 lán ē 當設計程式 ê 觀念層，lán 增加 lán ê 設計 ê *module* 化 (modularity) kap giâ-koân lán ê 語言 ê 表達力。就親像定義程序 ê 能力予 lán ē 當佇比語言 ê 基礎運算 ê，koh 較 koân 觀念層來處理過程，建構複合資料物件予 lán ē 當佇比語言 ê 基礎資料物件 ê，koh 較 koân 觀念層處理資料。

Consider the task of designing a system to perform arithmetic with rational numbers. We could imagine an operation `add-rat` that takes two rational numbers and produces their sum. In terms of simple data, a rational number can be thought of as two integers: a numerator and a denominator. Thus, we could design a program in which each rational number would be represented by two integers (a numerator and a denominator) and where `add-rat` would be implemented by two procedures (one producing the numerator of the sum and one producing the denominator). But this would be awkward, because we would then need to explicitly keep track of which numerators corresponded to which denominators. In a system intended to perform many operations on many rational numbers, such bookkeeping details would clutter the programs substantially, to say nothing of what they would do to our minds. It would be much better if we could "glue together" a numerator and denominator to form a pair—a *compound data object*—that our programs could manipulate in a way that would be consistent with regarding a rational number as a single conceptual unit.

考慮設計系統，來行運算有理數 ê 任務。Lán 通想像一个操作 `add-rat` thèh 兩个有理數，產出 in ê 和。用簡單資料，有理數 ē 當掠做兩个整數：一个分子，一个分母。就 án-ne，lán 通設計程式，內底 ê 有理數由兩个整數代表（分子 kap 分母），`add-rat` 由兩个程序實做（一个生成和 ê 分子，一个生成分母）。毋 kú che 真 gāi-giòh，因為 lán 就著愛顯明追蹤 tó 一个分母對應 kàu tó 一个分子。佇強調 kā chē-chē 有理數行真 chē 操作 ê 系統，án-ne 所詳細記 ê，實際上 ē 舞花程式，koh 免講 in 對 lán ê 心神 ê 影響。若準 lán ē 當 kā 分子 kap 分母「黏做伙」，成做數對——一个複合資料物件 (compound data object)，lán ê 程式就通操作佇 kā 有理數當做一个概念單位 ê 方式。

The use of compound data also enables us to increase the modularity of our programs. If we can manipulate rational numbers directly as objects in their own right, then we can separate the part of our program that deals with rational numbers per se from the details of how rational numbers may be represented as pairs of integers. The general technique of isolating the parts of a program that deal with how data objects are represented from the parts of a program that deal with how data objects are used is a powerful design methodology called *data abstraction*. We will see how data abstraction makes programs much easier to design, maintain, and modify.

使用複合資料 mā 予 lán 增加 lán ê 程式 ê module 化。若是 lán 家 kī ē 當直接 kā 有理數當做物件操作，就 ē 當 kā 處理有理數家 kī ê 部份程式，對有理數代表做整數對 ê，可能 ê 詳細方法分開。有一个號做資料抽象化 (data abstraction) 一般技術，伊 kā 處理資料物件表示方式 ê 程式部份，對處理資料物件使用方法 ê 程式部份孤立起來，mā 是有大路用 ê 設計方法論。Lán ē 看見資料抽象化 án-nóa 予程式較快設計、維持 kap 修改。

The use of compound data leads to a real increase in the expressive power of our programming language. Consider the idea of forming a "linear combination" $ax + by$. We might like to write a procedure that would accept a, b, x, and y as arguments and return the value of $ax + by$. This presents no difficulty if the arguments are to be numbers, because we can readily define

the procedure

使用複合資料會予 lán ê 程式語言 ê 表現力增加。考慮組一个「線性組合」$ax + by$，lán 可能想 beh 寫程序，引數有 a、b、x kap y，傳轉 $ax + by$ ê 值。若是引數 lóng 是數，che 無問題，因為 lán 通緊緊定義 chit ê 程序

```
(define (linear-combination a b x y)
  (+ (* a x) (* b y)))
```

But suppose we are not concerned only with numbers. Suppose we would like to express, in procedural terms, the idea that one can form linear combinations whenever addition and multiplication are defined—for rational numbers, complex numbers, polynomials, or whatever. We could express this as a procedure of the form

毋 koh 假使 lán beh 處理 ê 毋但是數。設使 lán 想 beh 用程序 ê 元素表達，無論是啥物款（有理數、複數、多項式，等等）ê 加法 kap 乘法，lóng 通組線性組合 ê 想法。Lán ē 當用下 kha ê 程序形式表達 che：

```
(define (linear-combination a b x y)
  (add (mul a x) (mul b y)))
```

where `add` and `mul` are not the primitive procedures `+` and `*` but rather more complex things that will perform the appropriate operations for whatever kinds of data we pass in as the arguments `a`, `b`, `x`, and `y`. The key point is that the only thing `linear-combination` should need to know about `a`, `b`, `x`, and `y` is that the procedures `add` and `mul` will perform the appropriate manipulations. From the perspective of the procedure `linear-combination`, it is irrelevant what `a`, `b`, `x`, and `y` are and even more irrelevant how they might happen to be represented in terms of more primitive data. This same example shows why it is important that our programming language provide the ability to manipulate compound objects directly: Without this, there is no way for a procedure such as `linear-combination` to pass its arguments along to `add` and `mul` without having to know their

detailed structure.[1]
其中 add kap mul 毋是基礎程序 + kap *，毋過是 koh 較複雜 ê 物，不管 lán 傳入 ê 參數 a、b、x kap y ê 型別是 siáⁿ 物，lóng ē 行適當 ê 操作。關鍵就是，關係 a、b、x kap y ，linear-combination 應該 kan-ta 知影 ê，是程序 add kap mul ē 行適當 ê 操作。對程序 linear-combination 來講，kap a、b、x kap y 無 tī-taī，koh 較無 tī-taī ê 就是，in 可能拄仔好由 koh 較基礎 ê 資料所表示。Chit ê kâng 款 ê 例，展示是 án-nóa lán ê 程式語言提供直接操作複合物件能力真重要：無 che，像 linear-combination ê 程序無法度毋免知 in ê 詳細結構，就 kā 伊 ê 引數送 kah add kap mul。[2]

We begin this chapter by implementing the rational-number arithmetic system mentioned above. This will form the background for our discussion of compound data and data abstraction. As with compound procedures, the main issue to be addressed is that of abstraction as a technique for coping with complexity, and we will see how data abstraction enables us to erect suitable *abstraction barriers* between different parts of a program.

Lán 對頂懸數提起 ê，實做有理數 ê 運算系統開始 chit 章。伊 ē 形成予 lán 討論複合資料 kap 資料抽象化 ê 背景。Kap 複合程序 kâng 款，beh 處理 ê

[1]The ability to directly manipulate procedures provides an analogous increase in the expressive power of a programming language. For example, in Section 1.3.1 we introduced the sum procedure, which takes a procedure term as an argument and computes the sum of the values of term over some specified interval. In order to define sum, it is crucial that we be able to speak of a procedure such as term as an entity in its own right, without regard for how term might be expressed with more primitive operations. Indeed, if we did not have the notion of "a procedure," it is doubtful that we would ever even think of the possibility of defining an operation such as sum. Moreover, insofar as performing the summation is concerned, the details of how term may be constructed from more primitive operations are irrelevant.

[2]直接操作程序 ê 能力，siâng 款 ē 增加程式語言 ê 表現力。舉例，lán 佇Section 1.3.1 kā sum 程序引入，伊 thèh 程序 term 當做引數，計算 term 佇指定區間 ê 和 ê 值。Beh 定義 sum，lán 毋免掛慮 term án-nóa ē 當用 koh 較基礎 ê 操作表示，就通講程序家 kī 當做實體，是蓋重要。若是 lán 無「程序」ê 概念，lán 敢有可能想著定義親像 sum ê 操作，chiâⁿ 實予 lâng giâu 疑。此外，對行總和來講，term 表示做 koh 較基礎 ê 操作 ê，可能 ê 詳細方法，kap 伊無 tī-taī。

主要問題就是抽象當做應對複雜性 ê 技術 ê 抽象化，lán ē 看見資料抽象化按怎予 lán kā 佇程式無 kâng 部份中間 ê，適當 ê 抽象化障礙 (abstraction barriers) chhāi 起來。

We will see that the key to forming compound data is that a programming language should provide some kind of "glue" so that data objects can be combined to form more complex data objects. There are many possible kinds of glue. Indeed, we will discover how to form compound data using no special "data" operations at all, only procedures. This will further blur the distinction between "procedure" and "data," which was already becoming tenuous toward the end of chapter 1. We will also explore some conventional techniques for representing sequences and trees. One key idea in dealing with compound data is the notion of *closure*—that the glue we use for combining data objects should allow us to combine not only primitive data objects, but compound data objects as well. Another key idea is that compound data objects can serve as *conventional interfaces* for combining program modules in mix-and-match ways. We illustrate some of these ideas by presenting a simple graphics language that exploits closure.

Lán ē 看見形成複合資料 ê 關鍵是程式語言應該提供一寡「膠」，來予資料組合組合做 koh 較複雜 ê 資料物件。膠 ê 可能 ê 款式有真 chē。Lán ē 確實發現 án-nóa 用無特別 ê「資料」操作，干焦用程序，來成形複合資料。這 ē 予「程序」kap「資料」ê 區別霧霧無明，kàu 第一章落尾伊已經真無明顯 ah。Lán ē 探索一寡傳統 ê 技術來標示列 kap 樹。處理複合資料 ê 一个關鍵概念是閉包 (closure) ——lán thèh 來組合資料物件 ê，除了允准 lán 組合基礎資料物件以外，koh 應該允准複合資料物件。另外一个關鍵 ê 想法就是複合資料物件 ē 當當做慣例介面 (conventional interfaces) ，來組合烏白鬥 ê 程式 module。

We will then augment the representational power of our language by introducing *symbolic expressions*—data whose elementary parts can be arbitrary symbols rather than only numbers. We explore various alternatives for representing sets of objects. We will find that, just as a given numerical function can be computed by many different computational processes, there are many

ways in which a given data structure can be represented in terms of simpler objects, and the choice of representation can have significant impact on the time and space requirements of processes that manipulate the data. We will investigate these ideas in the context of symbolic differentiation, the representation of sets, and the encoding of information.

了後 lán ē 引入符號表達式 (symbolic expression)——伊 ê 基本 ê 部份 ē 當是任意 ê 符號，毋但是數 ê 資料，來加強 lán ê 語言 ê 寫實力。Lán 探索 chē-chē 項表示物件 ê 集合 ê 選擇。Lán ē 發現，親像數值函數 ē 當用真 chē 無 kâng ê 計算過程計算，有真 chē 方法，其中資料結構 ē 當用較簡單 ê 物件表示，表示 ê 選擇通顯明影響操作資料 ê 過程所需要 ê 時間 kap 空間。Lán ē 調查 chiah ê 想法佇符號差異 ê 頂下文、集合 ê 表示，kap 資訊 ê 編碼。

Next we will take up the problem of working with data that may be represented differently by different parts of a program. This leads to the need to implement *generic operations*, which must handle many different types of data. Maintaining modularity in the presence of generic operations requires more powerful abstraction barriers than can be erected with simple data abstraction alone. In particular, we introduce *data-directed programming* as a technique that allows individual data representations to be designed in isolation and then combined *additively* (i.e., without modification). To illustrate the power of this approach to system design, we close the chapter by applying what we have learned to the implementation of a package for performing symbolic arithmetic on polynomials, in which the coefficients of the polynomials can be integers, rational numbers, complex numbers, and even other polynomials.

Sòa 落來 lán ē 討論操作資料 ê 問題，其中 ê 資料 ē 當用程式 ê 無 kâng 部份，做無 kâng ê 表示。Che 致使需要通用操作 (generic operations)，伊著愛處理真 chē 無 kâng 種類 ê 資料。佇通用操作 ê 頭前，beh 維持 module 化，需要比簡單 ê 資料抽象化所 ē 當 chhāi ê，koh 較有能力 ê 抽象化障礙，特別是，lán 引入資料引 *chhōa* 程式設計 (data-directed programming) 當做一个

技術，允准個別 ê 資料表示 ē 當分離設計，了後 ē 當附加 (additively)（就是免修改）組合。Beh 說明 chit ê 系統設計 ê 方法 ê 能力，lán ē 應用學著 ê，來實做行運算 ê 多項式 ê 符號運算 ê 包裹 (package)，來收 soah 本章。佇包裹內底，多項式 ê 係數 ē 當是整數、有理數、複數，甚至是別 ê 多項式。

2.1 Introduction to Data Abstraction 介紹資料抽象化

In Section 1.1.8, we noted that a procedure used as an element in creating a more complex procedure could be regarded not only as a collection of particular operations but also as a procedural abstraction. That is, the details of how the procedure was implemented could be suppressed, and the particular procedure itself could be replaced by any other procedure with the same overall behavior. In other words, we could make an abstraction that would separate the way the procedure would be used from the details of how the procedure would be implemented in terms of more primitive procedures. The analogous notion for compound data is called *data abstraction*. Data abstraction is a methodology that enables us to isolate how a compound data object is used from the details of how it is constructed from more primitive data objects.
佇 Section 1.1.8，lán 注意著 thèh 來當做要素，來建立 koh 較複雜 ê 程序 ê 程序，毋但 ē 當掠做特定 ê 操作 ê 集合，mā 通當做程序 ê 抽象化。就是，程序 ê 實做方法 ê 詳細 ē 當 khàm 掉，特定 ê 程序家己 ē 當予任何有 kâng 款 ê 整 kô 行為 ê 程序替換。就是講，lán 通用抽象化，kā 程序 ê 使用方法，對程序 án-nóa 用 koh 較基礎 ê 程序起造 ê 詳細分開。複合資料 ê 相 siâng ê 概念號做資料抽象化 (data abstraction)。伊是一个方法論，予 lán kā 複合資料 ê 使用方法，對伊是 án-nóa 用 koh 較基礎 ê 資料物件起造起來 ê 詳細分離。

The basic idea of data abstraction is to structure the programs that are to use compound data objects so that they operate on “abstract data.” That is, our programs should use data in such a way as to make no assumptions about the data that are not strictly necessary for performing the task at hand.

At the same time, a "concrete" data representation is defined independent of the programs that use the data. The interface between these two parts of our system will be a set of procedures, called *selectors* and *constructors*, that implement the abstract data in terms of the concrete representation. To illustrate this technique, we will consider how to design a set of procedures for manipulating rational numbers.

資料抽象化 ê 基本概念是使用複合資料物件建構程式，致使 in 佇「抽象資料」頂操作。就是，lán ê 程式應該 án-ne 用資料，致使 lán 毋免對毋是行手頭 ê 工課所必要 ê 資料提出假設。Siâng 時，「具體」(concrete) ê 資料表示 ê 定義，kap 用 chit ê 資料 ê 程式無 tī-tāi。佇 chit 兩个部份中間 ê 介面是程序 ê 集合，號做 揀選器 (selectors) kap 建構器 (constructors)，in 用具體表示來實做抽象資料。Beh 說明 chit ê 技術，lán ē 考慮按怎設計操作有理數 ê 程序 ê 集合。

2.1.1 Example: Arithmetic Operations for Rational Numbers 例：有理數 ê 運算操作

Suppose we want to do arithmetic with rational numbers. We want to be able to add, subtract, multiply, and divide them and to test whether two rational numbers are equal.

假使 lán 想 beh 行有理數運算。Lán 想 beh ē 當 kā in 加、減、乘 kap 除，以及試兩个有理數敢相 kâng。

Let us begin by assuming that we already have a way of constructing a rational number from a numerator and a denominator. We also assume that, given a rational number, we have a way of extracting (or selecting) its numerator and its denominator. Let us further assume that the constructor and selectors are available as procedures:

Lán 做伙假設 lán 有對分子 kap 分母建構有理數 ê 方法來開始。Lán koh 設使，有一个有理數，lán 有法度抽出（iah 是揀）伊 ê 分子 kap 分母。Lán koh 進一步設使建構器 kap 揀選器攏是 ē 當用 ê 程序：

- `(make-rat` $\langle n \rangle$ $\langle d \rangle$`)` returns the rational number whose numerator is the integer $\langle n \rangle$ and whose denominator is the integer $\langle d \rangle$.

  `(make-rat` $\langle n \rangle$ $\langle d \rangle$`)` 傳轉分子是整數 $\langle n \rangle$、分母是整數 $\langle d \rangle$ ê 有理數。.

- `(numer` $\langle x \rangle$`)` returns the numerator of the rational number $\langle x \rangle$.

  `(numer` $\langle x \rangle$`)` 傳轉有理數 $\langle x \rangle$ ê 分子。

- `(denom` $\langle x \rangle$`)` returns the denominator of the rational number $\langle x \rangle$.

  `(denom` $\langle x \rangle$`)` 傳轉有理數 $\langle x \rangle$ ê 分母。

We are using here a powerful strategy of synthesis: *wishful thinking*. We haven't yet said how a rational number is represented, or how the procedures `numer`, `denom`, and `make-rat` should be implemented. Even so, if we did have these three procedures, we could then add, subtract, multiply, divide, and test equality by using the following relations:
Lán 佇 chia leh 用一个有能力 ê 合成策略：向望 *ê* 觀察 (wishful thinking)。Lán iáu bōe 講有理數 án-nóa 實做，á 是程序 `numer`、`denom` kap `make-rat` 應該 án-nóa 實做。就算 án-ne，若是 lán 有 chit 三个程序，lán 通用下 kha ê 關係，來加、減、乘、除 kap 試敢有相 kâng：

$$\frac{n_1}{d_1} + \frac{n_2}{d_2} = \frac{n_1 d_2 + n_2 d_1}{d_1 d_2},$$
$$\frac{n_1}{d_1} - \frac{n_2}{d_2} = \frac{n_1 d_2 - n_2 d_1}{d_1 d_2},$$
$$\frac{n_1}{d_1} \cdot \frac{n_2}{d_2} = \frac{n_1 n_2}{d_1 d_2},$$
$$\frac{n_1/d_1}{n_2/d_2} = \frac{n_1 d_2}{d_1 n_2},$$
$$\frac{n_1}{d_1} = \frac{n_2}{d_2} \quad \text{if and only if} \quad n_1 d_2 = n_2 d_1.$$

We can express these rules as procedures:
Lán 通用程序表達 chiah ê 規則：

```
(define (add-rat x y)
  (make-rat (+ (* (numer x) (denom y))
               (* (numer y) (denom x)))
            (* (denom x) (denom y))))
(define (sub-rat x y)
  (make-rat (- (* (numer x) (denom y))
               (* (numer y) (denom x)))
            (* (denom x) (denom y))))
(define (mul-rat x y)
  (make-rat (* (numer x) (numer y))
            (* (denom x) (denom y))))
(define (div-rat x y)
  (make-rat (* (numer x) (denom y))
            (* (denom x) (numer y))))

(define (equal-rat? x y)
  (= (* (numer x) (denom y))
     (* (numer y) (denom x))))
```

Now we have the operations on rational numbers defined in terms of the selector and constructor procedures `numer`, `denom`, and `make-rat`. But we haven't yet defined these. What we need is some way to glue together a numerator and a denominator to form a rational number.

Ta^{n} lán 有用揀選器 kap 建構器程序 `numer`、`denom` kap `make-rat` 定義 ê 有理數操作。毋 kú lán iáu bōe kā in 定義。Lán 所需要 ê 是一个 ē 當 kā 分子 kap 分母相黏，組成有理數 ê 方法。

Pairs 對

To enable us to implement the concrete level of our data abstraction, our language provides a compound structure called a *pair*, which can be constructed with the primitive procedure `cons`. This procedure takes two arguments and returns a compound data object that contains the two arguments as parts. Given a pair, we can extract the parts using the primitive procedures `car` and `cdr`.[3] Thus, we can use `cons`, `car`, and `cdr` as follows:

Beh 予 lán 實做 lán ê 資料抽象化 ê 具體層，lán ê 語言提供號做對 (pair) ê 複合結構，ē 當用基礎程序 `cons` 建構。Chit ê 程序 thèh 兩 ê 引數，傳轉一个複合資料物件，伊包含兩个引數，lóng 準做伊 ê 部份。Lán ē 當用基礎程序 `car` kap `cdr` kā 伊 ê 部份抽出來。[4]就 án-ne，lán 通用 `cons`、`car` kap `cdr`，若下 kha：

[3]The name `cons` stands for "construct." The names `car` and `cdr` derive from the original implementation of Lisp on the IBM 704. That machine had an addressing scheme that allowed one to reference the "address" and "decrement" parts of a memory location. `car` stands for "Contents of Address part of Register" and `cdr` (pronounced "could-er") stands for "Contents of Decrement part of Register."

[4]`cons` chit ê 名意思是「建構」(construct)。`car` kap `cdr` ê 名，是對原底佇 IBM 704 機器實做 ê Lisp sòa 來 ê。Hit 臺機器有確定地址 (addressing) ê 機制，允准 lán 指一个記憶體位置 ê 本地地址 (address) ê 部份 kap 遞減 (decrement) ê 部份。`car` 是「暫存器 ê 本地地址部份 ê 內容」(Contents of Address part of Register) ê 簡略；`cdr`（讀做 "could-er"）是「暫存器 ê 遞減部份 ê 內容」(Contents of Decrement part of Register) ê 簡略。

```
(define x (cons 1 2))
(car x)
1
(cdr x)
2
```

Notice that a pair is a data object that can be given a name and manipulated, just like a primitive data object. Moreover, `cons` can be used to form pairs whose elements are pairs, and so on:
注意對是一个 ē 當號名 kap 操作 ê 資料物件，親像基礎 ê 資料物件。另外，`cons` ē 當 thèh 來組成要素是對 ê 對，等等：

```
(define x (cons 1 2))
(define y (cons 3 4))
(define z (cons x y))
(car (car z))
1
(car (cdr z))
3
```

In Section 2.2 we will see how this ability to combine pairs means that pairs can be used as general-purpose building blocks to create all sorts of complex data structures. The single compound-data primitive *pair*, implemented by the procedures `cons`, `car`, and `cdr`, is the only glue we need. Data objects constructed from pairs are called *list-structured* data.
Lán ē 佇 Section 2.2 看見組合對 ê 能力代表對 ē 當 thèh 來做通用目的 (general-purpose) ê 建構 ê 塊，來建立逐款 ê 複雜 ê 資料結構。由程序 `cons`、`car` kap `cdr` 實做 ê，孤 ê 複合資料基礎對 (pair)，是 lán 獨獨需要 ê 膠。對對建構 ê 資料物件號做列單結構 (list-structured) ê 資料。

Representing rational numbers 表示有理數

Pairs offer a natural way to complete the rational-number system. Simply represent a rational number as a pair of two integers: a numerator and a denomi-

nator. Then `make-rat`, `numer`, and `denom` are readily implemented as follows:[5]

對提供自然 ê 方法來完成有理數系統。Kā 有理數簡單表示做一對整數：分子 kap 分母。Sòa 落來 `make-rat`、`numer` kap `denom` ē 當緊緊用下 kha ê 方式實做：[6]

```
(define (make-rat n d) (cons n d))
(define (numer x) (car x))
```

[5] Another way to define the selectors and constructor is

```
(define make-rat cons)
(define numer car)
(define denom cdr)
```

The first definition associates the name `make-rat` with the value of the expression `cons`, which is the primitive procedure that constructs pairs. Thus `make-rat` and `cons` are names for the same primitive constructor.

Defining selectors and constructors in this way is efficient: Instead of `make-rat` *calling* `cons`, `make-rat` *is* `cons`, so there is only one procedure called, not two, when `make-rat` is called. On the other hand, doing this defeats debugging aids that trace procedure calls or put breakpoints on procedure calls: You may want to watch `make-rat` being called, but you certainly don't want to watch every call to `cons`.

We have chosen not to use this style of definition in this book.

[6] 別款定義揀選器 kap 建構器 ê 方法是

```
(define make-rat cons)
(define numer car)
(define denom cdr)
```

頭一个定義 kā 名 `make-rat` kap 表達式 `cons` ê 值關聯，伊是建構對 ê 基礎程序。因此 `make-rat` kap `cons` 是 kâng 款 ê 基礎建構器 ê 無 kâng ê 名。

Án-ne 定義揀選器 kap 建構器 chiâⁿ 有效率：毋免予 `make-rat`「呼叫」`cons`，`make-rat`「就是」`cons`，所以當 `make-rat` 呼叫 ê 時陣，kan-ta 呼叫一个程序，毋是兩个。另外方面，án-ne 做 ē 予協助除去錯誤 ê 功能，就是追蹤程序呼叫 kap 佇程序呼叫內 khǹg 中斷點，失效。Lí hoân-sè 想欲看受呼叫 ê `make-rat`，毋 koh lí 當然無想 beh 看逐擺呼叫 `cons`。

Lán 已經選擇 mài 佇 chit 本冊用 chit 款風格定義。

```
(define (denom x) (cdr x))
```

Also, in order to display the results of our computations, we can print rational numbers by printing the numerator, a slash, and the denominator:[7]
而且，為著佇展示 lán 運算 ê 結果，lán 通印有理數做分子、chhoàh 線 kap 分子：[8]

```
(define (print-rat x)
  (newline)
  (display (numer x))
  (display "/")
  (display (denom x)))
```

Now we can try our rational-number procedures:
Chit-má lán ē 當試 lán ê 有理數程序：

```
(define one-half (make-rat 1 2))
(print-rat one-half)
1/2
(define one-third (make-rat 1 3))
(print-rat (add-rat one-half one-third))
5/6
(print-rat (mul-rat one-half one-third))
1/6
(print-rat (add-rat one-third one-third))
6/9
```

[7] `display` is the Scheme primitive for printing data. The Scheme primitive `newline` starts a new line for printing. Neither of these procedures returns a useful value, so in the uses of `print-rat` below, we show only what `print-rat` prints, not what the interpreter prints as the value returned by `print-rat`.

[8] `display` 是 Scheme 印資料 ê 基礎函數。Scheme ê 基礎函數 `newline` 開新 ê 一 chōa 來印。兩个程序 lóng bōe 傳轉有路用 ê 值，所以佇使用下底 ê `print-rat`，lán kan-ta 展示 `print-rat` 印 siáⁿ 物，直譯器無展示 `print-rat` 傳轉去 ê 值。

As the final example shows, our rational-number implementation does not reduce rational numbers to lowest terms. We can remedy this by changing `make-rat`. If we have a `gcd` procedure like the one in Section 1.2.5 that produces the greatest common divisor of two integers, we can use `gcd` to reduce the numerator and the denominator to lowest terms before constructing the pair:
像落尾 ê 例所展示，lán ê 有理數實做無 kā 有理數變做既約分數（譯註：華語 koh 號做最簡分數，ta^{n} 參考華日韓共通詞翻）。Lán ē 當改 `make-rat` 來修正。若是 lán 有像佇 Section 1.2.5 ê `gcd` 程序，lán 通用 `gcd` lán 約分分子 kap 分母 kàu 既約 ê，chiah 建構對：

```
(define (make-rat n d)
  (let ((g (gcd n d)))
    (cons (/ n g) (/ d g))))
```

Now we have
Ta^{n} lán 有

```
(print-rat (add-rat one-third one-third))
2/3
```

as desired. This modification was accomplished by changing the constructor `make-rat` without changing any of the procedures (such as `add-rat` and `mul-rat`) that implement the actual operations.
是 lán 所意愛 ê。Chit ê 修改是用改建構器 `make-rat`，免改任何 `add-rat`、`mul-rat` 等實做實際操作 ê 程序，就達成 ah。

> **Exercise 2.1:** Define a better version of `make-rat` that handles both positive and negative arguments. `make-rat` should normalize the sign so that if the rational number is positive, both the numerator and denominator are positive, and if the rational number is negative, only the numerator is negative.

Exercise 2.1: 定義 koh 較好 ê `make-rat` 版本，伊處理正 kap 負 ê 引數。`make-rat` 應該 kā 正負號規範，致使若有理數是正 ê，分子分母攏是正 ê；若是有理數是負 ê，kan-ta 分子是負 ê。

2.1.2 Abstraction Barriers 抽象化障礙

Before continuing with more examples of compound data and data abstraction, let us consider some of the issues raised by the rational-number example. We defined the rational-number operations in terms of a constructor `make-rat` and selectors `numer` and `denom`. In general, the underlying idea of data abstraction is to identify for each type of data object a basic set of operations in terms of which all manipulations of data objects of that type will be expressed, and then to use only those operations in manipulating the data. 佇用 koh 較 chē ê 複合資料 kap 資料抽象化 ê 例繼續進前，lán 做伙考慮有理數 ê 例 chah 來 ê 一寡問題。Lán 用建構器 `make-rat` 以及揀選器 `numer` kap `denom` 定義有理數操作。一般來講，chhàng 佇資料抽象化下 kha ê 概念是針對逐款 ê 資料物件，用表達 chit 款 ê 資料物件 ê 逐 ê 操作 (manipulations) ê 命令 (operations)（譯註：翻做 che 是 beh hām "manipulation" 區別），來確定命令 ê 基本集合，了後 kan-ta 用 chiah ê 命令來操作資料。

We can envision the structure of the rational-number system as shown in Figure 2.1. The horizontal lines represent *abstraction barriers* that isolate different "levels" of the system. At each level, the barrier separates the programs (above) that use the data abstraction from the programs (below) that implement the data abstraction. Programs that use rational numbers manipulate them solely in terms of the procedures supplied "for public use" by the rational-number package: `add-rat`, `sub-rat`, `mul-rat`, `div-rat`, and `equal-rat?`. These, in turn, are implemented solely in terms of the constructor and selectors `make-rat`, `numer`, and `denom`, which themselves are implemented in terms of pairs. The details of how pairs are




Figure 2.1: Data-abstraction barriers in the rational-number package. 佇有理數包裹內底 ê 資料抽象化障礙。

implemented are irrelevant to the rest of the rational-number package so long as pairs can be manipulated by the use of `cons`, `car`, and `cdr`. In effect, procedures at each level are the interfaces that define the abstraction barriers and connect the different levels.

Lán 通設想有理數系統 ê 結構，像Figure 2.1所展示。水平線代表抽象化障礙，伊 kā 系統 ê 無 kâng ê「層」分離。佇逐層，障礙分開（頂 koân）用資料抽象化 ê 程式 kap（下底）實做資料抽象化 ê 程式。用有理數 ê 程式 kan-ta 用有理數包裹提供 ê「公用」程序：`add-rat`、`sub-rat`、`mul-rat`、`div-rat` kap `equal-rat?` 等操作 in。Chiah ê 程序，sòa 落來，kan-ta 用建構器 kap 揀選器（`make-rat`、`numer` kap `denom`）實做，chit 三个程序用對實做。對 ê 詳細實做方法 kap 有理數包裹 chhun ê 無 tī-taī，只要對 ē 當用 `cons`、`car` kap `cdr` 操作。實際上，佇逐層，程序攏是定義抽象化障礙 kap 聯絡無 kâng 層 ê 介面。

This simple idea has many advantages. One advantage is that it makes programs much easier to maintain and to modify. Any complex data structure can be represented in a variety of ways with the primitive data structures provided by a programming language. Of course, the choice of representation influences the programs that operate on it; thus, if the representation were to be changed at some later time, all such programs might have to be modified accordingly. This task could be time-consuming and expensive in the case of large programs unless the dependence on the representation were to be confined by design to a very few program modules.

Chit ê 簡單 ê 想法有真 chē 好處。一个是伊予程式較好維持 kap 修改。任何複雜 ê 資料結構 ē 當用程式語言提供 ê 基礎資料結構，表達做 chē-chē 款形式。當然，表示 ê 選擇影響操作伊 ê 程式；就 án-ne，若是表示佇以後有修改，所有 chiah ê 程式可能著配合修改。佇大程式內底，chit ê 工課 ē 開真 chē 時間，代價 mā 真 koân，除非表示 ê 依賴予設計限制 kah 真少 ê 程式 module。

For example, an alternate way to address the problem of reducing rational numbers to lowest terms is to perform the reduction whenever we access the parts of a rational number, rather than when we construct it. This leads to different constructor and selector procedures:

舉例，處理 kā 有理數約分做既約分數 ê 別款方法是，lán 佇接近使用 (access) 有理數 ê 部份，毋是佇 lán 建構伊 ê 時，chiah kā 約分。Che 產生無 kâng ê 建構器 kap 揀選器程序：

```
(define (make-rat n d) (cons n d))
(define (numer x)
  (let ((g (gcd (car x) (cdr x))))
    (/ (car x) g)))
(define (denom x)
  (let ((g (gcd (car x) (cdr x))))
    (/ (cdr x) g)))
```

The difference between this implementation and the previous one lies in when

we compute the `gcd`. If in our typical use of rational numbers we access the numerators and denominators of the same rational numbers many times, it would be preferable to compute the `gcd` when the rational numbers are constructed. If not, we may be better off waiting until access time to compute the `gcd`. In any case, when we change from one representation to the other, the procedures `add-rat`, `sub-rat`, and so on do not have to be modified at all.

Chit ê 實做 kap 進前 ê ê 無 kâng 佇當 lán 算 `gcd` ê 時陣。若是佇 lán 典型使用有理數 ê 時陣，lán 接近使用仝款 ê 有理數 ê 分子 kap 分母足 chē 改，佇建構有理數 ê 時算 `gcd` ē 較好。Ȧh 無，若準講 lán 改變表示 kàu 別款，程序 `add-rat`、`sub-rat` 等等毋免 tòe 咧修改。

Constraining the dependence on the representation to a few interface procedures helps us design programs as well as modify them, because it allows us to maintain the flexibility to consider alternate implementations. To continue with our simple example, suppose we are designing a rational-number package and we can't decide initially whether to perform the `gcd` at construction time or at selection time. The data-abstraction methodology gives us a way to defer that decision without losing the ability to make progress on the rest of the system.

限制表示 ê 依賴 kàu 真少 ê 介面程序，幫 chān lán 設計 kap 修改程式，因為伊予 lán 保持考慮別款實做 ê 靈活性。Beh 用 lán ê 簡單 ê 例繼續，假使 lán leh 設計有理數包裹，koh lán tú 開始 bōe 當決定行 `gcd` 佇建構 ê 時 iah 是選擇 ê 時。資料抽象化 ê 方法論予 lán 有方法，毋免停止寫別位 ê 程式，mā 會使延 chhiân 決定。

> **Exercise 2.2:** Consider the problem of representing line segments in a plane. Each segment is represented as a pair of points: a starting point and an ending point. Define a constructor `make-segment` and selectors `start-segment` and `end-segment` that define the representation of segments in

terms of points. Furthermore, a point can be represented as a pair of numbers: the x coordinate and the y coordinate. Accordingly, specify a constructor `make-point` and selectors `x-point` and `y-point` that define this representation. Finally, using your selectors and constructors, define a procedure `midpoint-segment` that takes a line segment as argument and returns its midpoint (the point whose coordinates are the average of the coordinates of the endpoints). To try your procedures, you'll need a way to print points:

Exercise 2.2: 考慮表示平面頂 ê 線段 ê 問題。逐段由一對點所表示：開始點 kap 中止點。定義一个建構器 `make-segment` kap 揀選器 `start-segment` 以及 `end-segment`，in 用點定義線段 ê 表示。進一步，點 ē 當用一對數來表示：x 座標 kap y 座標。因此，koh 指定建構器 `make-point` kap 揀選器 `x-point` 以及 `y-point` 來定義 chit 款表示。落尾，用汝 ê 揀選器 kap 建構器，定義程序 `midpoint-segment`，伊 thèh 一个線段當做引數，傳轉伊 ê 中點（就是座標是端點座標平均 ê 點）。Beh 試汝 ê 程序，汝需要印出點 ê 方法：

```
(define (print-point p)
  (newline)
  (display "(")
  (display (x-point p))
  (display ",")
  (display (y-point p))
  (display ")"))
```

Exercise 2.3: Implement a representation for rectangles in a plane. (Hint: You may want to make use of Exercise 2.2.) In terms of your constructors and selectors, create procedures that compute

the perimeter and the area of a given rectangle. Now implement a different representation for rectangles. Can you design your system with suitable abstraction barriers, so that the same perimeter and area procedures will work using either representation?

Exercise 2.3: 實做平面頂表示四角形 ê 方法（提示：汝可能想欲用 Exercise 2.2。）用 lí ê 建構器 kap 揀選器，來建立算四角形 ê 周長 kap 面積 ê 程序。Chit-má 實做無 kâng ê 四角形表示。汝敢 ē 當用適當 ê 抽象化障礙設計汝 ê 系統，致使仝款 ê 周長 kap 面積 ê 程序就算用別款表示，猶原 ē 當運作？

2.1.3 What Is Meant by Data? 資料 ê 意思是 siáⁿ 物？

We began the rational-number implementation in Section 2.1.1 by implementing the rational-number operations `add-rat`, `sub-rat`, and so on in terms of three unspecified procedures: `make-rat`, `numer`, and `denom`. At that point, we could think of the operations as being defined in terms of data objects—numerators, denominators, and rational numbers—whose behavior was specified by the latter three procedures.
Lán 佇 Section 2.1.1 使用三个無指明 ê 程序（`make-rat`、`numer` kap `denom`），實做有理數操作比如 `add-rat`、`sub-rat` 等等，來開始有理數實做。佇 hit 點，lán 通想著 chiah ê 操作是用資料物件（分子、分母 kap 有理數）所定義，in ê 行為是由 tú 開始 hit 三个程序所特定。

But exactly what is meant by *data*? It is not enough to say "whatever is implemented by the given selectors and constructors." Clearly, not every arbitrary set of three procedures can serve as an appropriate basis for the rational-number implementation. We need to guarantee that, if we construct a rational number `x` from a pair of integers `n` and `d`, then extracting the `numer` and the `denom` of `x` and dividing them should yield the same result

as dividing n by d. In other words, make-rat, numer, and denom must satisfy the condition that, for any integer n and any non-zero integer d, if x is (make-rat n d), then

毋 koh 資料 (data) 正港 ê 意思是 siáⁿ 物？講「揀選器 kap 建構器所實做 ê」mā 無夠。講予清，毋是任何三个程式 ē 當當做有理數適當 ê 實做基礎。Lán 著愛保證，若是 lán 對整數 n kap d ê 對，建構有理數 x，抽出 x ê number kap denom，koh kā in 相除 ê 結果，應該 hām n 予 d 除 ê 結果 kâng 款。別句話講，make-rat、numer kap denom 著滿足 chit ê 條件，就是對任何整數 n kap 毋是 0 ê 整數 d，若 x 是 (make-rat n d)，就會有

$$\frac{\texttt{(numer x)}}{\texttt{(denom x)}} = \frac{\texttt{n}}{\texttt{d}}.$$

In fact, this is the only condition make-rat, numer, and denom must fulfill in order to form a suitable basis for a rational-number representation. In general, we can think of data as defined by some collection of selectors and constructors, together with specified conditions that these procedures must fulfill in order to be a valid representation.[9]

實際上，che 是為著 beh 形成有理數表示 ê 適當 ê 基礎，make-rat、numer kap denom 著符合 ê 唯一 ê 條件。一般來講，lán 通 kā 資料掠做由

[9]Surprisingly, this idea is very difficult to formulate rigorously. There are two approaches to giving such a formulation. One, pioneered by C. A. R. Hoare (1972), is known as the method of *abstract models*. It formalizes the "procedures plus conditions" specification as outlined in the rational-number example above. Note that the condition on the rational-number representation was stated in terms of facts about integers (equality and division). In general, abstract models define new kinds of data objects in terms of previously defined types of data objects. Assertions about data objects can therefore be checked by reducing them to assertions about previously defined data objects. Another approach, introduced by Zilles at MIT, by Goguen, Thatcher, Wagner, and Wright at IBM (see Thatcher et al. 1978), and by Guttag at Toronto (see Guttag 1977), is called *algebraic specification*. It regards the "procedures" as elements of an abstract algebraic system whose behavior is specified by axioms that correspond to our "conditions," and uses the techniques of abstract algebra to check assertions about data objects. Both methods are surveyed in the paper by Liskov and Zilles (1975).

揀選器 kap 建構器 ê 集合，以及 chiah ê 程序定著滿足，予表示合規定 ê 指定 ê 條件。[10]

This point of view can serve to define not only “high-level” data objects, such as rational numbers, but lower-level objects as well. Consider the notion of a pair, which we used in order to define our rational numbers. We never actually said what a pair was, only that the language supplied procedures `cons`, `car`, and `cdr` for operating on pairs. But the only thing we need to know about these three operations is that if we glue two objects together using `cons` we can retrieve the objects using `car` and `cdr`. That is, the operations satisfy the condition that, for any objects `x` and `y`, if `z` is `(cons x y)` then `(car z)` is `x` and `(cdr z)` is `y`. Indeed, we mentioned that these three procedures are included as primitives in our language. However, any triple of procedures that satisfies the above condition can be used as the basis for implementing pairs. This point is illustrated strikingly by the fact that we could implement `cons`, `car`, and `cdr` without using any data structures at all but only using procedures. Here are the definitions:

Chit ê 觀點毋但 ē 當 thèh 來定義「koân 階」ê 資料物件，比如有理數，mā ē 使定義 kē 階 ê 物件。考慮對 ê 概念，lán thèh che 來定義有理數。Lán 實際毋捌講對是 siáⁿ 物，kan-ta 講語言提供程序 `cons`、`car` kap `cdr` 來操作對。毋過關係 chit 三个操作 lán 獨獨需要知影 ê 是，若是 lán kā 兩个物件用 `cons` 黏做伙，lán 通用 `car` kap `cdr` kā 物件 thèh 轉去。就是操作滿

[10] 預料外 ê 是，chit ê 想法真 oh 嚴格形式化。有兩个方法來 kā 形式化。一个是號做抽象模型 (abstract models) ê 方法，由 C. A. R. Hoare (1972)代先提出。伊形式化「程序 + 條件」ê 規範，像頂 koân 有理數 ê 例所大概講 ê。注意有理數表示 ê chit ê 條件是用關係整數 ê 事實（相等性 kap 除法）所表示 ê。一般來講，抽象模型用進前定義 ê 資料物件 ê 類型，來定義資料物件 ê 新 ê 款。關係資料物件 ê 表明 (assertions) 因此 ē 當用縮小 in kàu 關係進前定義 ê 資料物件 ê 表明來檢查。另外一个方法，由 MIT ê Zilles 紹介，由 IBM ê Goguen、Thatcher、Wagner kap Wright（看Thatcher et al. 1978），以及 Toronto ê Guttag（看 Guttag 1977）所提出，號做代數規範 (algebraic specification)。伊 kā「程序」當做抽象代數系統 ê 要素，系統 ê 行為由對應 kàu lán ê「條件」ê 公理來規範，用抽象代數 ê 技術來檢查資料物件 ê 表明。兩个方法 lóng 佇 Liskov and Zilles (1975) ê 論文受審視。

足 chit ê 條件，就是對任何物件 `x` kap `y`，`z` 若是 `(cons x y)`，`(car z)` 就是 `x`，`(cdr z)` 就是 `y`。Lán 的確捌提起 chit 三个程序 lóng 當做基礎函數包佇 lán ê 語言。是講，任何三个一組 ê 程序，若是滿足頂懸 ê 條件，lóng ē 當用做實做對 ê 基礎。Chit 點 ē 當用 chit ê 事實大大說明，就是 lán ē 當毋免用任何資料結構，反轉 kan-ta 用程序實做 `cons`、`car`、and `cdr`。定義佇下 kha：

```
(define (cons x y)
  (define (dispatch m)
    (cond ((= m 0) x)
          ((= m 1) y)
          (else (error "Argument not 0 or 1: CONS" m))))
  dispatch)
(define (car z) (z 0))
(define (cdr z) (z 1))
```

This use of procedures corresponds to nothing like our intuitive notion of what data should be. Nevertheless, all we need to do to show that this is a valid way to represent pairs is to verify that these procedures satisfy the condition given above.

Chit ê 程序 ê 使用無對應 kàu 任何相 siâng lán 對資料應該是 siáⁿ 物 ê 直覺概念 ê。毋 koh，所有 lán 所需要來展示 che 是合規定 ê，表示對 ê 方法 ê，是驗證 chiah ê 程序滿足頂懸 ê 條件。

The subtle point to notice is that the value returned by `(cons x y)` is a procedure—namely the internally defined procedure `dispatch`, which takes one argument and returns either `x` or `y` depending on whether the argument is 0 or 1. Correspondingly, `(car z)` is defined to apply `z` to 0. Hence, if `z` is the procedure formed by `(cons x y)`, then `z` applied to 0 will yield `x`. Thus, we have shown that `(car (cons x y))` yields `x`, as desired. Similarly, `(cdr (cons x y))` applies the procedure returned by `(cons x y)` to 1, which returns `y`. Therefore, this procedural implementation of pairs is a valid implementation, and if we access pairs using only

`cons`, `car`, and `cdr` we cannot distinguish this implementation from one that uses "real" data structures.

著注意 ê 微妙 ê 點是，`(cons x y)` 傳轉 ê 值是程序——就是內部定義 ê 程序 `dispatch`，伊 thèh 一个引數，照引數 ê 值是 0 iah 是 1，來傳轉 `x` iah 是 `y` ê 值。對應 ê 是，`(car z)` 定義做 kā 0 應用 kàu `z`。因此，若是 `z` 是由 `(cons x y)` 所建構 ê 程式，kā 0 應用 kàu `z` ē thèh 著 `x`。就 án-ne，lán 已經展示 `(car (cons x y))` 得著 `x`，照 lán 所意愛 ê。`(cdr (cons x y))` siâng 款 ē kā 1 應用 kàu `(cons x y)` 所傳轉 ê 程序，伊 ê kā `y` 傳轉去。就 án-ne，chit ê 對 ê 程序實做是合法 ê 實做，若是 lán kan-ta 用 `cons`、`car` kap `cdr` 接近使用對，lán bōe 當 kā chit ê 實做 hām 用真 ê 資料結構 ê 區別。

The point of exhibiting the procedural representation of pairs is not that our language works this way (Scheme, and Lisp systems in general, implement pairs directly, for efficiency reasons) but that it could work this way. The procedural representation, although obscure, is a perfectly adequate way to represent pairs, since it fulfills the only conditions that pairs need to fulfill. This example also demonstrates that the ability to manipulate procedures as objects automatically provides the ability to represent compound data. This may seem a curiosity now, but procedural representations of data will play a central role in our programming repertoire. This style of programming is often called *message passing*, and we will be using it as a basic tool in Chapter 3 when we address the issues of modeling and simulation.

展示對 ê 程序表示 ê 重點，毋是 lán ê 語言 án-ne 運作（Scheme kap 一般 ê Lisp 系統，因為效率 ê 緣故，就直接實做對），卻是伊 ē 當 án-ne 做。雖bóng 程序表示 oh 理解，毋 koh 是完美 koh 夠額 ê 方法來表示對，因為伊滿足對需要滿足 ê 必要條件。Chit ê 例 mā 展示 kā 程序當做物件操作 ê 能力，ē 自動提供表示複合資料 ê 能力。Che 假若看起來真稀奇，毋 koh 資料 ê 程序表示，ē 佇 lán ê 程式設計 ê 戲文中扮中心 ê 角色。Chit ê 程式設計 ê 風格定定號做 *message passing*，lán ē 佇Chapter 3，當 lán 處理起造模型 (modeling)

kap 模擬 ê 問題 ê 時，kā 當做是基礎 ê 家私來使用。

Exercise 2.4: Here is an alternative procedural representation of pairs. For this representation, verify that `(car (cons x y))` yields `x` for any objects `x` and `y`.

Exercise 2.4: Che 是別 ê 對 ê 程序表示。對 chit ê 表示，請驗證對任何物件 `x` kap `y`，`(car (cons x y))` 得著 `x`。

```
(define (cons x y)
  (lambda (m) (m x y)))
(define (car z)
  (z (lambda (p q) p)))
```

What is the corresponding definition of `cdr`? (Hint: To verify that this works, make use of the substitution model of Section 1.1.5.)

`cdr` 對應 ê 定義是 siáⁿ 物？(提示：若 beh 驗證 che 有效，用 Section 1.1.5 ê 取代模型)

Exercise 2.5: Show that we can represent pairs of nonnegative integers using only numbers and arithmetic operations if we represent the pair a and b as the integer that is the product $2^a 3^b$. Give the corresponding definitions of the procedures `cons`, `car`, and `cdr`.

Exercise 2.5: 展示 lán ē 當 kan-ta 用數字 kap 運算操作，來表示毋是負 ê 整數 ê 對，若是 lán kā 非負整數 a kap b ê 對表示做整數 $2^a 3^b$ ê 積。請提供程序 `cons`、`car` kap `cdr` ê 對應 ê 定義。

Exercise 2.6: In case representing pairs as procedures wasn't mind-boggling enough, consider that, in a language that can ma-

nipulate procedures, we can get by without numbers (at least insofar as nonnegative integers are concerned) by implementing 0 and the operation of adding 1 as

Exercise 2.6: 若準講用程序表達對無夠驚--lâng，考慮下 kha ê，佇 ē 當操作程序 ê 語言，lán 毋免數（上無毋是負 ê 整數），mā ē 當勉強運作，只要實做 0 kap 加 1 ê 操作，若下 kha：

```
(define zero (lambda (f) (lambda (x) x)))
(define (add-1 n)
  (lambda (f) (lambda (x) (f ((n f) x)))))
```

This representation is known as *Church numerals*, after its inventor, Alonzo Church, the logician who invented the λ-calculus.

Chit ê 表示方法號做*Church* 數 (Church numerals)，照發明伊 ê Alonzo Church，就是發明 λ 運算 ê 邏輯學家號 ê 名。

Define `one` and `two` directly (not in terms of `zero` and `add-1`). (Hint: Use substitution to evaluate `(add-1 zero)`). Give a direct definition of the addition procedure + (not in terms of repeated application of `add-1`).

請直接定義 `one` kap `two`（毋是用 `zero` kap `add-1`）。(提示：用取代來擴展 `(add-1 zero)`)。請提供加法程序 + ê 直接 ê 定義（毋是重覆應用 `add-1`）。

2.1.4 Extended Exercise: Interval Arithmetic 擴展 ê 練習：區間運算

Alyssa P. Hacker is designing a system to help people solve engineering problems. One feature she wants to provide in her system is the ability to manipulate inexact quantities (such as measured parameters of physical devices) with known precision, so that when computations are done with such approximate quantities the results will be numbers of known precision.

Alyssa P. Hacker leh 設計系統來幫 tsān lâng 解決工程問題。一个伊想欲佇 in 系統提供 ê 特點是，操作知影 ê 精確度 ê 無精確 ê 數量（比論實體設備所量 ê 參數），致使使用 án-ne ê 近似量計算了後，伊 ê 結果是所知 ê 精確度 ê 數。

Electrical engineers will be using Alyssa's system to compute electrical quantities. It is sometimes necessary for them to compute the value of a parallel equivalent resistance R_p of two resistors R_1, R_2 using the formula

電子工程師 ē 用 Alyssa ê 系統來計算電學 ê 量。In 有時仔需要用 chit ê 公式計算電阻器 (resistor) R_1 kap R_2 並列 (parallel) ê 電阻值

$$R_p = \frac{1}{1/R_1 + 1/R_2}.$$

Resistance values are usually known only up to some tolerance guaranteed by the manufacturer of the resistor. For example, if you buy a resistor labeled "6.8 ohms with 10% tolerance" you can only be sure that the resistor has a resistance between $6.8 - 0.68 = 6.12$ and $6.8 + 0.68 = 7.48$ ohms. Thus, if you have a 6.8-ohm 10% resistor in parallel with a 4.7-ohm 5% resistor, the resistance of the combination can range from about 2.58 ohms (if the two resistors are at the lower bounds) to about 2.97 ohms (if the two resistors are at the upper bounds).

電阻值常常受知影佇電阻器 ê 生產廠商標示 ê 誤差內底。比如講，若是汝買標「6.8 ohm，誤差 10%」ê 電阻，lí kan-ta ē 當確定電阻器 ê 電阻值佇 $6.8-0.68 = 6.12$ kap $6.8+0.68 = 7.48$ ohm 之間。就 án-ne，若汝有 6.8 ohm，誤差 10% ê 電阻器，kap 4.7 ohm，誤差 5% ê 電阻器並列，組合 ê 電阻值 ê 範圍是 2.58 ohm（若 2 粒 lóng 佇底限）kap 2.97 ohm（若 2 粒 lóng 佇上限）。

Alyssa's idea is to implement "interval arithmetic" as a set of arithmetic operations for combining "intervals" (objects that represent the range of possible values of an inexact quantity). The result of adding, subtracting, multiplying, or dividing two intervals is itself an interval, representing the range of the result.

Alyssa ê 想法是實做「區間運算」(interval arithmetic)，當做運算組合「區間」ê 操作 ê 集合，其中區間是表示無精確 ê 量 ê 可能值 ê 範圍 ê 物件。加、減、乘、除兩个區間結果家 kī mā 是區間，代表結果 ê 範圍。

Alyssa postulates the existence of an abstract object called an "interval" that has two endpoints: a lower bound and an upper bound. She also presumes that, given the endpoints of an interval, she can construct the interval using the data constructor `make-interval`. Alyssa first writes a procedure for adding two intervals. She reasons that the minimum value the sum could be is the sum of the two lower bounds and the maximum value it could be is the sum of the two upper bounds:

Alyssa 設使有號做「區間」ê 抽象物件佇 leh，伊有兩个端點：底限 kap 上限。伊 koh 假使，若是有區間 ê 端點，伊就 ē 當用資料建構器 `make-interval` 建構區間。Alyssa 代先寫程序來加兩个區間。伊推論和 ê 可能 ê 上細 ê 值，是兩个底限 ê 和；可能 ê 上大 ê 值，是兩个上限 ê 和：

```
(define (add-interval x y)
  (make-interval (+ (lower-bound x) (lower-bound y))
                 (+ (upper-bound x) (upper-bound y))))
```

Alyssa also works out the product of two intervals by finding the minimum and the maximum of the products of the bounds and using them as the bounds of the resulting interval. (`min` and `max` are primitives that find the minimum or maximum of any number of arguments.)
Alyssa mā 用 chhōe 底（上）限相乘 ê 所有結果 ê 上細值 kap 上大值，來算出兩个區間 ê 積。(`min` kap `max` 是 chhōe 任何數 ê 引數 ê 上細 iah 是上大 ê 值 ê 基礎函數)

```
(define (mul-interval x y)
  (let ((p1 (* (lower-bound x) (lower-bound y)))
        (p2 (* (lower-bound x) (upper-bound y)))
        (p3 (* (upper-bound x) (lower-bound y)))
        (p4 (* (upper-bound x) (upper-bound y))))
```

```
    (make-interval (min p1 p2 p3 p4)
                   (max p1 p2 p3 p4))))
```

To divide two intervals, Alyssa multiplies the first by the reciprocal of the second. Note that the bounds of the reciprocal interval are the reciprocal of the upper bound and the reciprocal of the lower bound, in that order.
Alyssa 用第二个區間 ê 倒數乘頭一个，來除兩个區間。注意區間 ê 倒數 ê 底（上）限是上限 ê 倒數 kap 底限 ê 倒數，照 chit 順序。

```
(define (div-interval x y)
  (mul-interval
   x
   (make-interval (/ 1.0 (upper-bound y))
                  (/ 1.0 (lower-bound y)))))
```

Exercise 2.7: Alyssa's program is incomplete because she has not specified the implementation of the interval abstraction. Here is a definition of the interval constructor:

Exercise 2.7: Alyssa ê 程式無完成，因為伊無指定區間抽象化 ê 實做。下 kha 是區間建構器 ê 一个定義：

```
(define (make-interval a b) (cons a b))
```

Define selectors `upper-bound` and `lower-bound` to complete the implementation.

定義揀選器 `upper-bound` kap `lower-bound` 來完成 chit ê 實做。

Exercise 2.8: Using reasoning analogous to Alyssa's, describe how the difference of two intervals may be computed. Define a corresponding subtraction procedure, called `sub-interval`.

Exercise 2.8: 使用 kap Alyssa ê 思考 kâng 款 ê 推論，描述兩个區間 ê 差 ē 當 án-nuá 計算。定義對應 ê 減法程序，伊號做 `sub-interval`。

Exercise 2.9: The *width* of an interval is half of the difference between its upper and lower bounds. The width is a measure of the uncertainty of the number specified by the interval. For some arithmetic operations the width of the result of combining two intervals is a function only of the widths of the argument intervals, whereas for others the width of the combination is not a function of the widths of the argument intervals. Show that the width of the sum (or difference) of two intervals is a function only of the widths of the intervals being added (or subtracted). Give examples to show that this is not true for multiplication or division.

Exercise 2.9: 區間 ê 幅度 (width) 是上限 kap 底限 ê 差 ê 一半。幅度是區間所指定 ê 數 ê 無確定程度 ê 判斷值。對一寡運算操作，組合兩个區間 ê 結果 ê 幅度是，kan-ta 是引數區間 ê 幅度 ê 函數；對其他 ê 操作，組合 ê 幅度毋是引數區間 ê 幅度 ê 函數。展示兩个區間 ê 和（iah 是差）ê 幅度，是一个 kan-ta 是 beh 加（iah 是減）ê 區間 ê 幅度 ê 函數。Koh 舉例來展示對乘法 iah 是除法，che 毋是真 ê。

Exercise 2.10: Ben Bitdiddle, an expert systems programmer, looks over Alyssa's shoulder and comments that it is not clear what it means to divide by an interval that spans zero. Modify Alyssa's code to check for this condition and to signal an error if it occurs.

Exercise 2.10: Ben Bitdiddle，伊是系統程式設計 ê 專家，對 Alyssa 後壁看程式碼，建議講，用幅度是 0 ê 區間除 ê 意思無清

楚。請修改 Alyssa ê 程式碼來檢查這狀況，若是出現，請送出錯誤。

Exercise 2.11: In passing, Ben also cryptically comments: "By testing the signs of the endpoints of the intervals, it is possible to break `mul-interval` into nine cases, only one of which requires more than two multiplications." Rewrite this procedure using Ben's suggestion.

Exercise 2.11 Ben 順 sòa 秘密提出建議：「用試區間 ê 端點 ê 正負號，有可能 kā `mul-interval` 拆做九个例，kan-ta 其中一个需要兩改以上 ê 乘法。」用 Ben ê 建議來改 chit ê 程序。

After debugging her program, Alyssa shows it to a potential user, who complains that her program solves the wrong problem. He wants a program that can deal with numbers represented as a center value and an additive tolerance; for example, he wants to work with intervals such as 3.5 ± 0.15 rather than [3.35, 3.65]. Alyssa returns to her desk and fixes this problem by supplying an alternate constructor and alternate selectors:

Kā Alyssa ê 程序除去錯誤了後，Alyssa kā 展示予可能 ê 用者看，毋過伊怨講伊 ê 程式解決無正確 ê 問題。伊 beh 愛一个程序，ē 當處理用中值 kap 誤差表示 ê 數；舉例，伊想 beh 處理寫做若 3.5 ± 0.15 ê 區間，毋是 [3.35, 3.65]。Alyssa 轉去伊 ê 桌仔頭前，用提供別 ê 建構器 kap 揀選器，來解決 chit ê 問題：

```
(define (make-center-width c w)
  (make-interval (- c w) (+ c w)))
(define (center i)
  (/ (+ (lower-bound i) (upper-bound i)) 2))
(define (width i)
  (/ (- (upper-bound i) (lower-bound i)) 2))
```

Unfortunately, most of Alyssa's users are engineers. Real engineering situations usually involve measurements with only a small uncertainty, measured as the ratio of the width of the interval to the midpoint of the interval. Engineers usually specify percentage tolerances on the parameters of devices, as in the resistor specifications given earlier.

Alyssa ê 程式 ê 大部份用者，不幸 lóng 是工程師。真正 ê 工程狀況定定干涉有 kan-ta 一屑仔無確定 ê 測量值，伊用區間 ê 幅度 kap 區間 ê 中點 ê 比例來量。工程師定定 kā 設備 ê 參數指定誤差百分比例，親像頂懸所列 ê 電阻規格。

Exercise 2.12: Define a constructor `make-center-percent` that takes a center and a percentage tolerance and produces the desired interval. You must also define a selector `percent` that produces the percentage tolerance for a given interval. The `center` selector is the same as the one shown above.

Exercise 2.12: 定義建構器 `make-center-percent`，伊 thèh 中值 kap 誤差百分比例，產出 beh 愛 ê 區間。汝 mā 定著愛定義揀選器 `percent`，產出區間 ê 誤差百分比例。`center` 揀選器 kap 頂懸 ê kâng 款。

Exercise 2.13: Show that under the assumption of small percentage tolerances there is a simple formula for the approximate percentage tolerance of the product of two intervals in terms of the tolerances of the factors. You may simplify the problem by assuming that all numbers are positive.

Exercise 2.13: 展示佇細細 ê 誤差百分比例 ê 假設，有一个簡單 ê 公式，用誤差係數，來近似兩个區間 ê 乘積 ê 誤差百分比例。汝通假設逐 ê 數 lóng 是正數，來簡化問題。

After considerable work, Alyssa P. Hacker delivers her finished system. Several years later, after she has forgotten all about it, she gets a frenzied call from an irate user, Lem E. Tweakit. It seems that Lem has noticed that the formula for parallel resistors can be written in two algebraically equivalent ways:

佇大工程以後，Alyssa P. Hacker 交出所完成 ê 系統。幾若冬以後，伊 bōe 記得任何關係 che ê 代誌 ê 時陣，伊接著一通氣 phuh-phuh ê 電話，對心狂火著 ê 用者 Lem E. Tweakit khà 來。Lem 假若注意著並列 ê 電阻 ê 公式通寫做兩个代數上 kâng 款 ê 方式：

$$\frac{R_1 R_2}{R_1 + R_2}$$

and

$$\frac{1}{1/R_1 + 1/R_2}.$$

He has written the following two programs, each of which computes the parallel-resistors formula differently:

伊有寫下 kha 兩 ê 程式，任何一个算並列電阻 ê 公式 lóng 無 kâng：

```
(define (par1 r1 r2)
  (div-interval (mul-interval r1 r2)
                (add-interval r1 r2)))

(define (par2 r1 r2)
  (let ((one (make-interval 1 1)))
    (div-interval
     one (add-interval (div-interval one r1)
```

```
                                        (div-interval one r2)))))
```

Lem complains that Alyssa's program gives different answers for the two ways of computing. This is a serious complaint.

Lem 怨講 Alyssa ê 程式用兩 ê 算法，ē 得著無 kâng ê 答案。Che 是嚴重 ê 投訴。

Exercise 2.14: Demonstrate that Lem is right. Investigate the behavior of the system on a variety of arithmetic expressions. Make some intervals A and B, and use them in computing the expressions A/A and A/B. You will get the most insight by using intervals whose width is a small percentage of the center value. Examine the results of the computation in center-percent form (see Exercise 2.12).

Exercise 2.14: 展示 Lem 講著。用多樣 ê 運算表達式調查系統 ê 行為。創造一寡區間 A kap B，用 in 運算表達式 A/A kap A/B。汝用幅度是中值 ê 細細比例 ê 區間，就 ē 當深深了解。用中值—比例 ê 形式測試計算 ê 結果（看 Exercise 2.12）。

Exercise 2.15: Eva Lu Ator, another user, has also noticed the different intervals computed by different but algebraically equivalent expressions. She says that a formula to compute with intervals using Alyssa's system will produce tighter error bounds if it can be written in such a form that no variable that represents an uncertain number is repeated. Thus, she says, `par2` is a "better" program for parallel resistances than `par1`. Is she right? Why?

Exercise 2.15: Eva Lu Ator，另外一个用者，mā 有注意無 kâng soah 代數上等價 (equivalent) ê 表達式，ē 算出無 kâng ê 結果。

伊講，方程式若 ē 當寫做，所有表達無確定 ê 數 ê 變數 lóng 無重覆出現 ê 形式，án-ne 用 Alyssa ê 系統計算有區間 ê 方程式，ē 產生 koh 較細 ê 誤差界。因此，伊講，對算並列電阻，`par2` 是比 `par1`「較好」ê 程式。伊敢講有著？是 án-nóa？

Exercise 2.16: Explain, in general, why equivalent algebraic expressions may lead to different answers. Can you devise an interval-arithmetic package that does not have this shortcoming, or is this task impossible? (Warning: This problem is very difficult.)

Exercise 2.16: 解說一般來講，等價 ê 代數表達式是 án-nóa 算出無 kâng ê 答案。汝敢 ē 當設計一个區間運算 ê 包裹，無 chit ê 瑕疵？抑是 chit ê 任務敢無可能？（警告：Chit ê 問題足困難）

2.2 Hierarchical Data and the Closure Property 階層資料 kap 閉包性質

As we have seen, pairs provide a primitive "glue" that we can use to construct compound data objects. Figure 2.2 shows a standard way to visualize a pair—in this case, the pair formed by `(cons 1 2)`. In this representation, which is called *box-and-pointer notation*, each object is shown as a *pointer* to a box. The box for a primitive object contains a representation of the object. For example, the box for a number contains a numeral. The box for a pair is actually a double box, the left part containing (a pointer to) the `car` of the pair and the right part containing the `cdr`.

親像 lán 所看著 ê，對提供基礎 ê「膠」，Lán ē 當 thèh 來建構複合 ê 資料物件。Figure 2.2 展示標準 ê 方法來圖示對——佇 chit ê 例，對由 `(cons 1 2)` 建立。佇 chit ê 表達式，號做盒仔—指標表示法 (box-and-pointer notation)，逐 ê 物件展示做指盒仔 ê 指標 (pointer)。Té 基礎物件盒仔包含物件 ê 表示。




Figure 2.2: Box-and-pointer representation of `(cons 1 2)`.
`(cons 1 2)` ê 盒仔—指標表示法。

比如講，Té 數字 ê 盒仔包數值。包對箱仔是雙層 ê 箱仔，倒 pêng ê 部份包（指標指 kàu）數對 ê `car`，正 pêng ê 包 `cdr`。

We have already seen that `cons` can be used to combine not only numbers but pairs as well. (You made use of this fact, or should have, in doing Exercise 2.2 and Exercise 2.3.) As a consequence, pairs provide a universal building block from which we can construct all sorts of data structures. Figure 2.3 shows two ways to use pairs to combine the numbers 1, 2, 3, and 4.

The ability to create pairs whose elements are pairs is the essence of list structure's importance as a representational tool. We refer to this ability as the *closure property* of `cons`. In general, an operation for combining data objects satisfies the closure property if the results of combining things with that operation can themselves be combined using the same operation.[11] Closure is the key to power in any means of combination because it permits us to create *hierarchical* structures—structures made up of parts, which themselves are made up of parts, and so on.

[11]The use of the word "closure" here comes from abstract algebra, where a set of elements is said to be closed under an operation if applying the operation to elements in the set produces an element that is again an element of the set. The Lisp community also (unfortunately) uses the word "closure" to describe a totally unrelated concept: A closure is an implementation technique for representing procedures with free variables. We do not use the word "closure" in this second sense in this book.




Figure 2.3: Two ways to combine 1, 2, 3, and 4 using pairs. 兩款用對組合 1、2、3 kap 4 ê 方法。

建立「要素是對 ê 對」ê 能力，是列單結構 ē 當做代表性家私 ê 重要 ê 精華。Lán 指 chit ê 能力做 `cons` ê 閉包性 (closure property)。一般來講，若是用一个操作組合物件 ê 結果 ē 當用 kâng 款 ê 操作來組合，chit ê 組合資料物件 ê 操作滿足閉包性。[12]閉包是 kā 任何組合方法提供能力 ê 關鍵，因為伊容允 lán 建立階層 (hierarchical) 結構——用部份組立 ê 結構，其中部份是由部份所組立，照 án-ne 推論。

From the outset of Chapter 1, we've made essential use of closure in dealing with procedures, because all but the very simplest programs rely on the fact that the elements of a combination can themselves be combinations. In this section, we take up the consequences of closure for compound data. We describe some conventional techniques for using pairs to represent sequences and trees, and we exhibit a graphics language that illustrates closure in a vivid

[12]佇 chia，「閉包」chit ê 詞 ê 使用是對抽象代數來 ê，其中元素 ê 集合若是應用一个操作 kàu chit ê 集合 ê 元素，ē 產出一个 mā 是 chit ê 集合 ê 元素，chit ê 集合 ê 元素就通講是對 chit ê 操作是封閉 *ê*(closed)。Lisp 社里（不幸）mā 使用「閉包」chit 字來描述全然無 tī-tāi ê 概念：一个閉包是實做表示有自由變數 ê 程序 ê 科技。佇本冊 ê「閉包」lán bōe 指第二 ê 用法。

way.[13]

Ùi Chapter 1 tú 開始，lán 佇處理程序 ê 時陣有必要使用閉包性，因為除了上簡單 ê，程式 lóng 倚靠 chit ê 事實，就是組合 ê 要素家 kī mā ē 當是要素。佇 chit 節，lán 使用複合資料 ê 閉包性 ê 結果。Lán 描述一寡使用對來代表列 kap 樹 ê 傳統 ê 技術，koh 展示一个鮮明說明閉包性 ê 圖形語言。[14]

2.2.1 Representing Sequences

One of the useful structures we can build with pairs is a *sequence*—an ordered collection of data objects. There are, of course, many ways to represent sequences in terms of pairs. One particularly straightforward representation is

[13]The notion that a means of combination should satisfy closure is a straightforward idea. Unfortunately, the data combiners provided in many popular programming languages do not satisfy closure, or make closure cumbersome to exploit. In Fortran or Basic, one typically combines data elements by assembling them into arrays—but one cannot form arrays whose elements are themselves arrays. Pascal and C admit structures whose elements are structures. However, this requires that the programmer manipulate pointers explicitly, and adhere to the restriction that each field of a structure can contain only elements of a prespecified form. Unlike Lisp with its pairs, these languages have no built-in general-purpose glue that makes it easy to manipulate compound data in a uniform way. This limitation lies behind Alan Perlis's comment in his foreword to this book: "In Pascal the plethora of declarable data structures induces a specialization within functions that inhibits and penalizes casual cooperation. It is better to have 100 functions operate on one data structure than to have 10 functions operate on 10 data structures."

[14]組合 ê 方法應該滿足閉包性 ê 概念是直接 ê 想法。佇 chē-chē 流行 ê 程式語言提供 ê 資料組合器無滿足閉包性，iáu 是予閉包性傷過 pūn-tshiâng 無好用。佇 Fortran iah 是 Basic，lâng 一般 kā 資料元素 tàu 入去陣列 (array)，來組合 in——毋 koh bōe 當組元素是陣列 ê 陣列。Pascal kap C 接納元素是結構 ê 結構。但是，che 著愛程式設計師明顯操作指標，而且束縛佇結構 ê 逐 ê 欄位 kan-ta 通包含代先指定 ê 形式 ê 元素 ê 限制。無像 Lisp kap 伊 ê 對，chiah ê 語言無內底就有 ê 通用用途 ê 膠，予用統一 ê 方式操作資料較容易。Chit ê 限制是 Alan Perlis 佇本冊 ê 序內底 ê 建議 ê 背景：「佇 Pascal，傷 chē 通宣告 ê 資料結構致使佇函數內底 ê 專門化，伊壓制，koh 不利無正式 ê 合作。有 100 ê 函數操作佇一个資料結構，較贏有 10 ê 函數操作佇 10 ê 資料結構。」




Figure 2.4: The sequence 1, 2, 3, 4 represented as a chain of pairs. 列 1、2、3、4 表達做對 ê 鏈。

illustrated in Figure 2.4, where the sequence 1, 2, 3, 4 is represented as a chain of pairs. The `car` of each pair is the corresponding item in the chain, and the `cdr` of the pair is the next pair in the chain. The `cdr` of the final pair signals the end of the sequence by pointing to a distinguished value that is not a pair, represented in box-and-pointer diagrams as a diagonal line and in programs as the value of the variable `nil`. The entire sequence is constructed by nested `cons` operations:
一个 lán ē 當用對起造 ê 有路用 ê 結構是列 (sequence)——一个有排順序 ê 資料物件 ê 集合。當然有真 chē 方法用對來表示列。一个特別直接 ê 表示，由 Figure 2.4 說明，其中列 1、2、3、4 是表示做對 ê 鏈。逐 ê 對 ê `car` 是鏈內底對應 ê 項目，對 ê `cdr` 是鏈內底 ê 後一个對。上尾 ê 對 ê `cdr` 用指 kàu 一个毋是對 ê 區別 ê 值，來代表列 ê 尾溜，佇盒仔—指標表示法 ê 圖，表示做對角線，佇程式表達做變數 `nil` ê 值。規个列是由岫 á 形 ê `cons` 操作組成：

```
(cons 1
      (cons 2
            (cons 3
                  (cons 4 nil))))
```

Such a sequence of pairs, formed by nested `cons`es, is called a *list*, and Scheme provides a primitive called `list` to help in constructing lists.[15] The

[15] In this book, we use *list* to mean a chain of pairs terminated by the end-of-list marker. In

above sequence could be produced by `(list 1 2 3 4)`. In general,

Chit 款用岫 á 形 ê `cons` 組成 ê 對 ê 列，號做列單 (list)，Scheme 提供基礎函數 `list` 來幫 chān 建立 in。[16]頂懸 ê 列 ē 當用 `(list 1 2 3 4)` 產出。一般來講，

```
(list ⟨a1⟩ ⟨a2⟩ ... ⟨an⟩)
```

is equivalent to
kap 下 kha ê 等價

```
(cons ⟨a1⟩
      (cons ⟨a2⟩
            (cons ...
                  (cons ⟨an⟩
                        nil)...)))
```

Lisp systems conventionally print lists by printing the sequence of elements, enclosed in parentheses. Thus, the data object in Figure 2.4 is printed as `(1 2 3 4)`:
Lisp 系統傳統上用印出元素 ê 列，閣用括弧 kā in 包起來，來印出列單。就 án-ne，佇 Figure 2.4 ê 資料物件，hǒng 印做 `(1 2 3 4)`：

```
(define one-through-four (list 1 2 3 4))
one-through-four
(1 2 3 4)
```

Be careful not to confuse the expression `(list 1 2 3 4)` with the list `(1 2 3 4)`, which is the result obtained when the expression is evaluated. Attempting to evaluate the expression `(1 2 3 4)` will signal an error when the interpreter tries to apply the procedure `1` to arguments `2`, `3`, and `4`.

---

contrast, the term *list structure* refers to any data structure made out of pairs, not just to lists.

[16]佇 chit 本冊，lán 用列單來指由 end-of-list 標記收 soah ê 對 ê 列。Kah 伊比較，術語「列單結構」(list structure) 指用對做 ê 任何資料結構，毋但列單。

著注意毋通 kā 表達式 `(list 1 2 3 4)` kap 列單 `(1 2 3 4)` 舞花去，後壁 ê 是 chit ê 表達式 ê 值算出來得著 ê 結果。試算表達式 `(1 2 3 4)` ê 值 ē 得著錯誤，因為直譯器試 kā 引數 2、3 kap 4，應用 kàu 程序 1。

We can think of `car` as selecting the first item in the list, and of `cdr` as selecting the sublist consisting of all but the first item. Nested applications of `car` and `cdr` can be used to extract the second, third, and subsequent items in the list.[17] The constructor `cons` makes a list like the original one, but with an additional item at the beginning.

Lán ē 當 kā `car` 掠做揀列單 ê 頭一个項目，kā `cdr` 掠做是揀 kiáⁿ 列單，包含除了頭一个 ê 所有 ê 項目。`car` kap `cdr` ê 岫 á 形 ê 應用 ē 當用來抽出列單 ê 第二 ê、第三 ê，kah 落尾 ê 項目。[18]建構器 `cons` 建構一个列單，像原本 ê，毋過佇起頭加添項目。

```
(car one-through-four)
1
(cdr one-through-four)
(2 3 4)
(car (cdr one-through-four))
2
```

[17] Since nested applications of `car` and `cdr` are cumbersome to write, Lisp dialects provide abbreviations for them—for instance,

`(cadr ⟨arg⟩) = (car (cdr ⟨arg⟩))`

The names of all such procedures start with `c` and end with `r`. Each `a` between them stands for a `car` operation and each `d` for a `cdr` operation, to be applied in the same order in which they appear in the name. The names `car` and `cdr` persist because simple combinations like `cadr` are pronounceable.

[18] 因為岫 á 形 ê `car` kap `cdr` ê 應用真 oh 寫，Lisp 方言提供 in ê 簡略——舉例，

`(cadr ⟨arg⟩) = (car (cdr ⟨arg⟩))`

所有 chit 款程序 ê 名 lóng 是 `c` 起頭 `r` 收 soah。中間 ê 逐 ê `a` 指 `car` ê 操作，`d` 指 `cdr` ê 操作，應用 ê 順序 kap in 佇名內底 ê 順序仝款。`car` kap `cdr` ê 名保持，因為像 `cadr` ê 簡單 ê 組合 ē 當發音。

```
(cons 10 one-through-four)
(10 1 2 3 4)
(cons 5 one-through-four)
(5 1 2 3 4)
```

The value of `nil`, used to terminate the chain of pairs, can be thought of as a sequence of no elements, the *empty list*. The word *nil* is a contraction of the Latin word *nihil*, which means "nothing."[19]
用來收 soah 對 ê 鏈 ê `nil` ê 值，ē 當掠做無元素 ê 列，空 *ê* 列單 (empty list)。*nil* chit ê 詞是拉丁語指「無物件」ê 詞 *nihil* ê 簡稱。[20]

List operations 列單操作

The use of pairs to represent sequences of elements as lists is accompanied by conventional programming techniques for manipulating lists by successively "`cdr`ing down" the lists. For example, the procedure `list-ref` takes as arguments a list and a number n and returns the nth item of the list. It is customary to number the elements of the list beginning with 0. The method

[19] It's remarkable how much energy in the standardization of Lisp dialects has been dissipated in arguments that are literally over nothing: Should `nil` be an ordinary name? Should the value of `nil` be a symbol? Should it be a list? Should it be a pair? In Scheme, `nil` is an ordinary name, which we use in this section as a variable whose value is the end-of-list marker (just as `true` is an ordinary variable that has a true value). Other dialects of Lisp, including Common Lisp, treat `nil` as a special symbol. The authors of this book, who have endured too many language standardization brawls, would like to avoid the entire issue. Once we have introduced quotation in Section 2.3, we will denote the empty list as `'()` and dispense with the variable `nil` entirely.

[20] 佇 Lisp 方言 ê 標準化中，對字面上「無物件」ê 爭論所開 ê 氣力不止仔大：`nil` kám 應該是一般 ê 名？`nil` ê 值 kám 應該是符號？Kám 應該是列單？Kám 應該是對？佇 Scheme，`nil` 是一般 ê 名，lán 佇本節 ē 當用來做變數，伊 ê 值是 end-of-list 標記（就親像 `true` 是一般 ê 變數，伊有真 ê 值）。其他 ê Lisp 方言，包含 Common Lisp，kā `nil` 當做特殊 ê 符號。Chit 本冊 ê 作者，已經吞忍傷 chē 語言標準化 ê 冤家，想 beh 走閃 kui 个議題。Lán 一下佇 Section 2.3 紹介 quotation，ē kā 空列單用 `'()` 表示，全部提供予變數 `nil`。

for computing `list-ref` is the following:
使用對來 kā 元素 ê 列表示做列單，是 kap 傳統 ê，用 kā 列單連 sòa「`cdr` 落去」ê 操作列單 ê 程式設計技術做伙。比論講，程序 `list-ref` ê 引數是列單 kap 數字 n，伊傳倒轉列單 ê 第 n ê 元素。Lán-lâng 慣勢 kā 列單 ê 元素對 0 開始算。算 `list-ref` ê 方法佇下 kha：

- For $n = 0$, `list-ref` should return the `car` of the list.

  若是 $n = 0$，`list-ref` 應該傳轉列單 ê `car`。

- Otherwise, `list-ref` should return the $(n-1)$-st item of the `cdr` of the list.

  Ah 無，`list-ref` 應該傳轉列單 ê `cdr` ê 第 $(n-1)$ ê 元素。

```
(define (list-ref items n)
  (if (= n 0)
      (car items)
      (list-ref (cdr items) (- n 1))))
(define squares (list 1 4 9 16 25))
(list-ref squares 3)
16
```

Often we `cdr` down the whole list. To aid in this, Scheme includes a primitive predicate `null?`, which tests whether its argument is the empty list. The procedure `length`, which returns the number of items in a list, illustrates this typical pattern of use:
Lán 通常 ē kā kui 條列單 `cdr` 落去。為著幫 chān che，Scheme 包基礎調詞函數 `null?` ，測試伊 ê 引數敢是空 ê 列單。程序 `length`，伊傳轉列單 ê 項目數，說明使用 ê 一般模式：

```
(define (length items)
  (if (null? items)
      0
```

```
      (+ 1 (length (cdr items)))))
(define odds (list 1 3 5 7))
(length odds)
4
```

The `length` procedure implements a simple recursive plan. The reduction step is:
`length` 程序實做簡單 ê 遞迴計畫，縮小 ê 手續是：

- The `length` of any list is 1 plus the `length` of the `cdr` of the list.
  任何列單 ê `length` 是 1+chit ê 列單 ê `cdr` ê `length`。

This is applied successively until we reach the base case:
Che ē 連 sòa 應用，直 kàu lán kàu 基本 ê 案例：

- The `length` of the empty list is 0.
  空 ê 列單 ê `length` 是 0。

We could also compute `length` in an iterative style:
Lán mā ē 當用反覆 ê 風格算 `length`：

```
(define (length items)
  (define (length-iter a count)
    (if (null? a)
        count
        (length-iter (cdr a) (+ 1 count))))
  (length-iter items 0))
```

Another conventional programming technique is to "`cons` up" an answer list while `cdr`ing down a list, as in the procedure `append`, which takes two lists as arguments and combines their elements to make a new list:
另外一个傳統 ê 程式設計技術是佇 kā 列單「`cdr` 落去」ê 時陣，kā 答案列單「`cons` 起去」，像程序 `append`，伊 thèh 兩 ê 列單當做引數，組合 in ê 元素，成做新 ê 列單：

```
(append squares odds)
(1 4 9 16 25 1 3 5 7)
(append odds squares)
(1 3 5 7 1 4 9 16 25)
```

`append` is also implemented using a recursive plan. To `append` lists `list1` and `list2`, do the following:
`append` mā 用遞迴 ê 計畫實做。Beh `append` 列單 `list1` kap `list2`，就照下 kha 行：

- If `list1` is the empty list, then the result is just `list2`.

  `list1` 若是空 ê 列單，結果就是 `list2`。

- Otherwise, `append` the `cdr` of `list1` and `list2`, and `cons` the `car` of `list1` onto the result:

  Ah̀ 無，`append` `list1` ê `cdr` kap `list2`，koh kā 伊 ê 結果 kap `list1` ê `car` `cons` 做伙：

```
(define (append list1 list2)
  (if (null? list1)
      list2
      (cons (car list1) (append (cdr list1) list2))))
```

Exercise 2.17: Define a procedure `last-pair` that returns the list that contains only the last element of a given (nonempty) list:

Exercise 2.17: 定義程序 `last-pair`，伊傳轉 kan-ta 包含傳入去（koh 毋是空）ê 列單 ê，上尾 ê 元素 ê 列單：

```
(last-pair (list 23 72 149 34))
(34)
```

Exercise 2.18: Define a procedure `reverse` that takes a list as argument and returns a list of the same elements in reverse order:

Exercise 2.18: 定義程序 `reverse`，伊 thèh 列單當做引數，傳轉一个列單，內容是原列單所有元素顛倒排：

```
(reverse (list 1 4 9 16 25))
(25 16 9 4 1)
```

Exercise 2.19: Consider the change-counting program of Section 1.2.2. It would be nice to be able to easily change the currency used by the program, so that we could compute the number of ways to change a British pound, for example. As the program is written, the knowledge of the currency is distributed partly into the procedure `first-denomination` and partly into the procedure `count-change` (which knows that there are five kinds of U.S. coins). It would be nicer to be able to supply a list of coins to be used for making change.

Exercise 2.19: 考慮 Section 1.2.2 ê 找錢 ê 程式。若是 ē 當較快換程式所用貨幣 ē 較好，致使 lán ē 當算不列顛 pound ê 找錢方法數（譬論講）。當程式寫出來 ê 時，貨幣 sài-suh ê 智識分散佇程序 `first-denomination` kap 程序 `count-change`（伊知影美國 ê 銀角仔有五款）。若是 ē 當提供 ē 當換錢 ê 銀角仔 ê 面額 ê 列單 ē koh 較好。

We want to rewrite the procedure `cc` so that its second argument is a list of the values of the coins to use rather than an integer specifying which coins to use. We could then have lists that defined each kind of currency:

Lán beh 重寫程序 `cc`，予伊 ê 第二 ê 引數是銀角仔 ê 面額 ê 列

單，毋是指示用 tó 一个銀角 ê 整數。Lán ē 當有定義逐款貨幣面額 ê 列單：

```
(define us-coins (list 50 25 10 5 1))
(define uk-coins (list 100 50 20 10 5 2 1 0.5))
```

We could then call `cc` as follows:

了後 lán ē 當呼叫 `cc`，像下 kha：

```
(cc 100 us-coins)
292
```

To do this will require changing the program `cc` somewhat. It will still have the same form, but it will access its second argument differently, as follows:

Beh 做 che，著愛改變程序 `cc`。伊 iáu 是 ē 有 siâng 款 ê 形，但是伊接近使用第二 ê 引數 ê 方式 ē 無仝，像下 kha：

```
(define (cc amount coin-values)
  (cond ((= amount 0) 1)
        ((or (< amount 0) (no-more? coin-values)) 0)
        (else
         (+ (cc amount
                (except-first-denomination
                 coin-values))
            (cc (- amount
                   (first-denomination
                    coin-values))
                coin-values)))))
```

Define the procedures `first-denomination`, `except-first-denomination`, and `no-more?` in terms of primitive operations on list structures. Does the order of the

list `coin-values` affect the answer produced by `cc`? Why or why not?

請用列單結構 ê 基礎操作，來定義程序 `first-denomination`、`except-first-denomination` kap `no-more?`。列單 `coin-values` ê 順序敢會影響 `cc` 所產出 ê 答案？是按怎（bōe）？

Exercise 2.20: The procedures `+`, `*`, and `list` take arbitrary numbers of arguments. One way to define such procedures is to use `define` with *dotted-tail notation*. In a procedure definition, a parameter list that has a dot before the last parameter name indicates that, when the procedure is called, the initial parameters (if any) will have as values the initial arguments, as usual, but the final parameter's value will be a *list* of any remaining arguments. For instance, given the definition

Exercise 2.20: 程序 `+`、`*` kap `list` thèh 任何數量 ê 引數。一款定義 án-ne ê 程序 ê 方法是用 `define` kap 尾 *liu* 有點 *ê* 表示法 (dotted-tail notation)。佇程序 ê 定義內底，上尾 ê 參數進前有點 ê 參數列單表示，當程序呼叫 ê 時，點進前 ê 參數（若是有），ē 當做起初 ê 引數 ê 值，kap 以早 kâng 款，毋 koh 上尾 ê 參數值 ē 是 chhun ê 引數 ê列單。譬論講，有定義

```
(define (f x y . z) ⟨body⟩)
```

the procedure `f` can be called with two or more arguments. If we evaluate

程序 `f` ē 當用兩个以上 ê 引數呼叫。Lán 若是計算

```
(f 1 2 3 4 5 6)
```

then in the body of `f`, `x` will be 1, `y` will be 2, and `z` will be the list `(3 4 5 6)`. Given the definition

佇 `f` ê 本體，`x` 就 ē 是 1，`y` 是 2，`z`ē 是列單 `(3 4 5 6)`。有定義

```
(define (g . w) ⟨body⟩)
```

the procedure `g` can be called with zero or more arguments. If we evaluate

程序 `g` ē 當用零个以上 ê 引數呼叫。Lán 若是計算

```
(g 1 2 3 4 5 6)
```

then in the body of `g`, `w` will be the list `(1 2 3 4 5 6)`.

佇 `g` ê 本體，`w` ē 是列單 `(1 2 3 4 5 6)`。

21

Use this notation to write a procedure `same-parity` that takes one or more integers and returns a list of all the arguments that have the same even-odd parity as the first argument. For example,

用 chit ê 表示法寫程序 `same-parity`，伊 thèh 一个以上 ê 整數，傳轉一个列單，若是頭一个引數是奇數，伊 ê 元素是所有奇數 ê 引數；若頭一个引數是雙數，伊 ê 元素是所有雙數 ê 引數。

[21] To define `f` and `g` using `lambda` we would write
Beh 用 `lambda` 定義 `f` kap `g`，lán ē 寫做

```
(define f (lambda (x y . z) ⟨body⟩))
(define g (lambda w ⟨body⟩))
```

```
(same-parity 1 2 3 4 5 6 7)
(1 3 5 7)
(same-parity 2 3 4 5 6 7)
(2 4 6)
```

Mapping over lists Map 過列單

One extremely useful operation is to apply some transformation to each element in a list and generate the list of results. For instance, the following procedure scales each number in a list by a given factor:

一个極其有路用 ê 操作是應用轉換 kàu 列單 ê 逐 ê 元素，了後生成結果 ê 列單。舉例，下 kha ê 程序用一个係數來 chhun-kiu 列單 ê 逐 ê 數字：

```
(define (scale-list items factor)
  (if (null? items)
      nil
      (cons (* (car items) factor)
            (scale-list (cdr items)
                        factor))))
(scale-list (list 1 2 3 4 5) 10)
(10 20 30 40 50)
```

We can abstract this general idea and capture it as a common pattern expressed as a higher-order procedure, just as in Section 1.3. The higher-order procedure here is called `map`. `map` takes as arguments a procedure of one argument and a list, and returns a list of the results produced by applying the procedure to each element in the list:[22]

[22] Scheme standardly provides a `map` procedure that is more general than the one described here. This more general `map` takes a procedure of n arguments, together with n lists, and applies the procedure to all the first elements of the lists, all the second elements of the lists, and so on, returning a list of the results. For example:

```
(map + (list 1 2 3) (list 40 50 60) (list 700 800 900))
```

Lán ē 當抽象 chit ê 一般 ê 想法，kā 掠做通常 ê 模式，伊表示做 koân 階程序，像佇 Section 1.3。佇 chia，chit ê koân 階程序號做 `map`。`map` thèh 單引數函數 kap 列單做引數，傳轉應用程序 kàu 列單 ê 逐 ê 元素，所得著 ê 結果 ê 列單：

[23]

```
(define (map proc items)
  (if (null? items)
      nil
      (cons (proc (car items))
            (map proc (cdr items)))))
(map abs (list -10 2.5 -11.6 17))
(10 2.5 11.6 17)
(map (lambda (x) (* x x)) (list 1 2 3 4))
(1 4 9 16)
```

Now we can give a new definition of `scale-list` in terms of `map`:

```
(741 852 963)
(map (lambda (x y) (+ x (* 2 y)))
     (list 1 2 3)
     (list 4 5 6))
(9 12 15)
```

[23]Scheme 標準提供 ê `map` 程序，伊比佇 chia 描述 ê koh 較一般化。Chit ê koh 較一般 ê `map` thèh n ê 引數 ê 程序 kap n ê 列單做伙成做引數，應用程序 kàu 逐 ê 列單 ê 頭一个元素、逐 ê ê 第二 ê 元素，等等，落尾傳轉結果 ê 列單。譬論講：

```
(map + (list 1 2 3) (list 40 50 60) (list 700 800 900))
(741 852 963)
(map (lambda (x y) (+ x (* 2 y)))
     (list 1 2 3)
     (list 4 5 6))
(9 12 15)
```

Chit-má lán 通用 `map` kā `scale-list` koh 再定義：

```
(define (scale-list items factor)
  (map (lambda (x) (* x factor))
       items))
```

`map` is an important construct, not only because it captures a common pattern, but because it establishes a higher level of abstraction in dealing with lists. In the original definition of `scale-list`, the recursive structure of the program draws attention to the element-by-element processing of the list. Defining `scale-list` in terms of `map` suppresses that level of detail and emphasizes that scaling transforms a list of elements to a list of results. The difference between the two definitions is not that the computer is performing a different process (it isn't) but that we think about the process differently. In effect, `map` helps establish an abstraction barrier that isolates the implementation of procedures that transform lists from the details of how the elements of the list are extracted and combined. Like the barriers shown in Figure 2.1, this abstraction gives us the flexibility to change the low-level details of how sequences are implemented, while preserving the conceptual framework of operations that transform sequences to sequences. Section 2.2.3 expands on this use of sequences as a framework for organizing programs.
`map` 是重要 ê 建構，毋但因為伊掠通常 ê 模式，koh 因為伊佇處理列單 ê 範圍，設立 koh 較 koân ê 抽象。佇起頭 ê `scale-list` ê 定義，程式 ê 遞迴結構 ē 吸收 lâng 注意 kàu 列單一个一个元素 ê 操作。用 `map` 定義 `scale-list` teh 掉 hit 層 ê 詳細，強調 chhun-kiu 改變元素 ê 列單 kàu 結果 ê 列單。Chit 兩 ê 定義 ê 無 kâng，毋是電腦行無 kâng ê 過程（其實是 kâng ê），反轉是 lán 對程序 ê 思考無 kâng。照結果來講，`map` 幫 chān lán 成立抽象化障礙，自列單 ê 元素 án-nóa 抽出 kap 組合 ê 詳細，孤立出轉換列單 ê 程序 ê 實做。像 Figure 2.1 展示 ê 障礙，chit ê 抽象佇保存轉換列 kàu 列 ê 操作 ê 概念框殼 ê 時陣，mā 予 lán 靈活性來改變列 án-nóa 實做 ê 底層詳細。Section 2.2.3 擴展 chit 款列 ê 使用，當做組織程式 ê 框殼。

Exercise 2.21: The procedure `square-list` takes a list of numbers as argument and returns a list of the squares of those numbers.

Exercise 2.21: 程序 `square-list` thèh 數字 ê 列單當做引數，傳轉 chiah ê 列單 ê 平方。

```
(square-list (list 1 2 3 4))
(1 4 9 16)
```

Here are two different definitions of `square-list`. Complete both of them by filling in the missing expressions:

Chia 是 `square-list` ê 兩个無仝款 ê 定義。用添欠缺 ê 表達式，來完成 in 兩个。

```
(define (square-list items)
  (if (null? items)
      nil
      (cons ⟨??⟩ ⟨??⟩)))
(define (square-list items)
  (map ⟨??⟩ ⟨??⟩))
```

Exercise 2.22: Louis Reasoner tries to rewrite the first `square-list` procedure of Exercise 2.21 so that it evolves an iterative process:

Exercise 2.22: Louis Reasoner 試重頭寫 Exercise 2.21 ê 頭一个 `square-list` 程序，致使伊展開做反覆 ê 過程：

```
(define (square-list items)
  (define (iter things answer)
    (if (null? things)
        answer
        (iter (cdr things)
```

```
                (cons (square (car things))
                      answer))))
  (iter items nil))
```

Unfortunately, defining `square-list` this way produces the answer list in the reverse order of the one desired. Why?

Án-ne 定義 `square-list`，不幸 ē kā 結果列單內底 ê 內容顛倒排。是 án-nóa？

Louis then tries to fix his bug by interchanging the arguments to `cons`:

Louis koh 用交換 `cons` ê 引數來試修正 chit ê bug：

```
(define (square-list items)
  (define (iter things answer)
    (if (null? things)
        answer
        (iter (cdr things)
              (cons answer
                    (square (car things))))))
  (iter items nil))
```

This doesn't work either. Explain.

Che mā 無效。請解說。

Exercise 2.23: The procedure `for-each` is similar to `map`. It takes as arguments a procedure and a list of elements. However, rather than forming a list of the results, `for-each` just applies the procedure to each of the elements in turn, from left to right. The values returned by applying the procedure to the elements are not used at all—`for-each` is used with procedures that perform an action, such as printing. For example,

Exercise 2.23: 程序 `for-each` kap `map` 相 siâng。伊 thèh 程序 kap 元素 ê 列單當做引數。毋 koh，毋是組成結果 ê 列單，`for-each` 顛倒是 kan-ta kā 程序對倒 pêng kàu 正 pêng，一个一个應用 kàu 逐 ê 元素。應用程序 kàu 所有 ê 元素了後傳轉 ê 值 lóng 無使用——`for-each` 是 thèh 來 kap 行動作 ê 程序（親像印出）做伙用。比論講：

```
(for-each (lambda (x)
            (newline)
            (display x))
          (list 57 321 88))
57
321
88
```

The value returned by the call to `for-each` (not illustrated above) can be something arbitrary, such as true. Give an implementation of `for-each`.

呼叫 `for-each`（頂 koân 無說明）所傳轉 ê 值 ē 當是隨意 ê，親像 true（真）。請寫出 `for-each` ê 實做。

2.2.2 Hierarchical Structures 階層結構

The representation of sequences in terms of lists generalizes naturally to represent sequences whose elements may themselves be sequences. For example, we can regard the object `((1 2) 3 4)` constructed by
用列單來表示列，自然 ē 當推廣 kàu 表示元素本身 ē 當是列 ê 列。舉例，lán ē 當 kā 物件 `((1 2) 3 4)` 掠做由下 kha ê 表達式組成：

```
(cons (list 1 2) (list 3 4))
```




Figure 2.5: Structure formed by `(cons (list 1 2) (list 3 4))`. 由 `(cons (list 1 2) (list 3 4))` 組成 ê 結構。

as a list of three items, the first of which is itself a list, `(1 2)`. Indeed, this is suggested by the form in which the result is printed by the interpreter. Figure 2.5 shows the representation of this structure in terms of pairs.
做著一个有三 ê 元素 ê 列單，伊 ê 頭一个元素是列單 `(1 2)`。實際上，直譯器印出結果所用 ê 格式推薦 che。Figure 2.5 展示 án-nóa 用對表示 chit ê 結構。

Another way to think of sequences whose elements are sequences is as *trees*. The elements of the sequence are the branches of the tree, and elements that are themselves sequences are subtrees. Figure 2.6 shows the structure in Figure 2.5 viewed as a tree.

別 ê 思考元素是列 ê 列方法是親像樹 *á* (trees)。列 ê 元素是樹 á ê 樹椏，koh 家己是列 ê 元素是 kiáⁿ 樹。Figure 2.6 kā Figure 2.5 ê 結構展示做樹 á。

Recursion is a natural tool for dealing with tree structures, since we can often reduce operations on trees to operations on their branches, which reduce in turn to operations on the branches of the branches, and so on, until we reach the leaves of the tree. As an example, compare the `length` procedure of




Figure 2.6: The list structure in Figure 2.5 viewed as a tree. Figure 2.5 ê 列單結構用樹 á 形展示。

Section 2.2.1 with the `count-leaves` procedure, which returns the total number of leaves of a tree:

遞迴是處理樹結構 ê 自然 ê 家私，因為 lán 定定 ē 當 kā 操作樹 á 縮小 kàu 操作 in ê 樹椏，操作 in ê 分支 ē 一个一个縮小 kàu 操作樹椏 ê 樹椏，等等，直到 lán kàu 樹 á ê 葉。Thèh 一个例，比較 Section 2.2.1 ê `length` 程序 kap `count-leaves` 程序，伊傳轉樹 ê 葉 á ê 總數：

```
(define x (cons (list 1 2) (list 3 4)))
(length x)
3
(count-leaves x)
4
(list x x)
(((1 2) 3 4) ((1 2) 3 4))
(length (list x x))
2
(count-leaves (list x x))
8
```

To implement `count-leaves`, recall the recursive plan for computing `length`:
若 beh 實做 `count-leaves`，請想起算 `length` ê 遞迴計畫：

- `length` of a list `x` is 1 plus `length` of the `cdr` of `x`.

  列單 `x` ê `length` 是 1+ `x` ê `cdr` ê `length`。

- `length` of the empty list is 0.

  空列單 ê `length` 是 0。

`count-leaves` is similar. The value for the empty list is the same:
`count-leaves` mā 相 siâng。空列單 ê 值 mā kâng 款：

- `count-leaves` of the empty list is 0.

  空列單 ê `count-leaves` 是 0。

But in the reduction step, where we strip off the `car` of the list, we must take into account that the `car` may itself be a tree whose leaves we need to count. Thus, the appropriate reduction step is
毋 koh 佇縮小 ê 手續，其中 lán 剝掉列單 ê `car`，lán 愛考慮著 `car` 家己可能是樹 á，伊 ê 葉 á lán 著愛算。就 án-ne，適當 ê 縮小手續是：

- `count-leaves` of a tree `x` is `count-leaves` of the `car` of `x` plus `count-leaves` of the `cdr` of `x`.

  樹 á `x` ê `count-leaves` 是 `x` ê `car` ê `count-leaves` + `x` ê `cdr` ê `count-leaves`。

Finally, by taking `cars` we reach actual leaves, so we need another base case:
落尾，倚靠 thèh 逐 ê `car`，lán 及至實際 ê 葉 á，所以 lán 著愛另外一个基本情況：

- `count-leaves` of a leaf is 1.

  葉 á ê `count-leaves` 是 1。

To aid in writing recursive procedures on trees, Scheme provides the primitive predicate `pair?`, which tests whether its argument is a pair. Here is the complete procedure:[24]

為著幫 chān 寫操作樹 á ê 遞迴程序，Scheme 提供基礎謂詞 `pair?`，伊試伊 ê 引數敢是對。全部 ê 程序佇 chia：[25]

```
(define (count-leaves x)
  (cond ((null? x) 0)
        ((not (pair? x)) 1)
        (else (+ (count-leaves (car x))
                 (count-leaves (cdr x))))))
```

Exercise 2.24: Suppose we evaluate the expression `(list 1 (list 2 (list 3 4)))`. Give the result printed by the interpreter, the corresponding box-and-pointer structure, and the interpretation of this as a tree (as in Figure 2.6).

Exercise 2.24: 假使 lán 算表達式 `(list 1 (list 2 (list 3 4)))`，請提供直譯器所印 ê 結構，對應 ê 盒仔—指標結構，kap 當做樹 á ê 解說（像 Figure 2.6）。

Exercise 2.25: Give combinations of `cars` and `cdrs` that will pick 7 from each of the following lists:

Exercise 2.25: 提供 ē 當 kā 7 對下 kha ê 列單 thèh 出來 ê，`car` kap `cdr` ê 組合：

```
(1 3 (5 7) 9)
((7))
(1 (2 (3 (4 (5 (6 7))))))
```

[24]The order of the first two clauses in the `cond` matters, since the empty list satisfies `null?` and also is not a pair.

[25]佇 `cond` 內底頭兩个 kiáⁿ 句 ê 順序有要緊，因為空 ê 列單滿足 `null?`，mā 毋是對。

Exercise 2.26: Suppose we define `x` and `y` to be two lists:

Exercise 2.26: 假使 lán kā `x` kap `y` 定義做下 kha ê 列單：

```
(define x (list 1 2 3))
(define y (list 4 5 6))
```

What result is printed by the interpreter in response to evaluating each of the following expressions:

直譯器算下 kha 逐 ê 表達式了後印出來 ê 結果是 siáⁿ 物：

```
(append x y)
(cons x y)
(list x y)
```

Exercise 2.27: Modify your `reverse` procedure of Exercise 2.18 to produce a `deep-reverse` procedure that takes a list as argument and returns as its value the list with its elements reversed and with all sublists deep-reversed as well. For example,

Exercise 2.27: 改汝佇 Exercise 2.18 ê `reverse` 程序，來產出 `deep-reverse` 程序，伊 thèh 列單當做引數，傳轉 ê 值是列單，伊 ê 元素 kap 所有 ê kiáⁿ 列單內底 ê 元素 lóng 顛倒排。比論講：

```
(define x (list (list 1 2) (list 3 4)))
x
((1 2) (3 4))
(reverse x)
((3 4) (1 2))
(deep-reverse x)
((4 3) (2 1))
```

Exercise 2.28: Write a procedure `fringe` that takes as argument a tree (represented as a list) and returns a list whose elements are all the leaves of the tree arranged in left-to-right order. For example,

Exercise 2.28: 寫程序 `fringe`，伊 thèh 樹 á 當做引數（用列單表示），傳轉列單，伊 ê 元素是所有樹 á ê 葉 á，對倒 pêng kàu 正 pêng 排。譬論講：

```
(define x (list (list 1 2) (list 3 4)))
(fringe x)
(1 2 3 4)
(fringe (list x x))
(1 2 3 4 1 2 3 4)
```

Exercise 2.29: A binary mobile consists of two branches, a left branch and a right branch. Each branch is a rod of a certain length, from which hangs either a weight or another binary mobile. We can represent a binary mobile using compound data by constructing it from two branches (for example, using `list`):

Exercise 2.29: 二元平衡裝飾 (binary mobile) 包含兩个分支，倒 pêng ê kap 正 pêng ê。逐 ê 分支是一定長度 ê 棍 á，吊一个磅子 iah 是另外 ê 二元平行裝飾。Lán 通 thèh 複合資料，用對兩个分支建構伊 ê 方法，kā 二元平衡裝飾表示（舉例，用 `list`）：

```
(define (make-mobile left right)
  (list left right))
```

A branch is constructed from a `length` (which must be a number) together with a `structure`, which may be either a number (representing a simple weight) or another mobile:

分支是用 `length`（伊定著是數）kap ē 當是數（表示簡單 ê 磅子重量）iah 是別 ê 裝飾 ê `structure`，做伙建構 ê：

```
(define (make-branch length structure)
  (list length structure))
```

a. Write the corresponding selectors `left-branch` and `right-branch`, which return the branches of a mobile, and `branch-length` and `branch-structure`, which return the components of a branch.
寫對應 ê 揀選器 `left-branch` 以及 `right-branch`，in 傳轉裝飾 ê 分支，kap `branch-length` 以及 `branch-structure`，in 傳轉分支 ê 組件。

b. Using your selectors, define a procedure `total-weight` that returns the total weight of a mobile.
用汝 ê 揀選器，定義程序 `total-weight` ，伊傳轉裝飾 ê 總重量。

c. A mobile is said to be *balanced* if the torque applied by its top-left branch is equal to that applied by its top-right branch (that is, if the length of the left rod multiplied by the weight hanging from that rod is equal to the corresponding product for the right side) and if each of the submobiles hanging off its branches is balanced. Design a predicate that tests whether a binary mobile is balanced.
上頂懸 ê 倒 pêng 分支 ê 力矩 kap 上頂懸 ê 正 pêng ê 若相 kâng（就是講，若是倒 pêng 棍仔 ê 長度乘以所吊 ê ê 重量 kap 正 pêng ê 相乘結果相 kâng），而且所有分支所吊 ê kiáⁿ 裝飾 lóng 平衡，就通講裝飾是平衡 ê。設計一个謂詞，伊試二元平衡裝飾敢有平衡。

d. Suppose we change the representation of mobiles so that the constructors are
設使 lán 改變裝飾 ê 表示，致 kàu 建構器變做

```
(define (make-mobile left right) (cons left right))
(define (make-branch length structure)
  (cons length structure))
```

How much do you need to change your programs to convert to the new representation?
汝著 kā 汝 ê 程式改 gōa chē 來轉換 kàu 新 ê 表示？

Mapping over trees Map 過樹 á

Just as `map` is a powerful abstraction for dealing with sequences, `map` together with recursion is a powerful abstraction for dealing with trees. For instance, the `scale-tree` procedure, analogous to `scale-list` of Section 2.2.1, takes as arguments a numeric factor and a tree whose leaves are numbers. It returns a tree of the same shape, where each number is multiplied by the factor. The recursive plan for `scale-tree` is similar to the one for `count-leaves`:
就因為 `map` 是有能力處理列 ê 抽象，`map` kap 遞迴做伙是有能力處理樹 á ê 抽象。舉例，`scale-tree` 程序，kap Section 2.2.1 ê `scale-list` 相 siâng，thèh 係數 kap 葉 á 是數 ê 樹 á 當做引數。伊傳轉 kâng 款形 ê 樹 á，其中逐 ê 數 lóng 予係數乘。`scale-tree` ê 遞迴計畫 kap `count-leaves` ê 相 siâng：

```
(define (scale-tree tree factor)
  (cond ((null? tree) nil)
        ((not (pair? tree)) (* tree factor))
        (else (cons (scale-tree (car tree) factor)
                    (scale-tree (cdr tree) factor)))))
(scale-tree (list 1 (list 2 (list 3 4) 5) (list 6 7)) 10)
(10 (20 (30 40) 50) (60 70))
```

Another way to implement `scale-tree` is to regard the tree as a sequence of sub-trees and use `map`. We map over the sequence, scaling each sub-tree

in turn, and return the list of results. In the base case, where the tree is a leaf, we simply multiply by the factor:
別款實做 `scale-tree` ê 方法是，kā 樹 á 準做 kiáⁿ 樹 ê 列，koh 用 `map`。Lán map 過列，一欉一欉 kiáⁿ 樹 lóng chhun-kiu，傳轉結果 ê 列單。佇基礎 ê 情況，其中樹 á 是葉，lán 就簡單用係數乘：

```
(define (scale-tree tree factor)
  (map (lambda (sub-tree)
         (if (pair? sub-tree)
             (scale-tree sub-tree factor)
             (* sub-tree factor)))
       tree))
```

Many tree operations can be implemented by similar combinations of sequence operations and recursion.
Chē-chē 操作 ē 當用相 siâng ê 列操作 kap 遞迴 ê 組合來實做。

> **Exercise 2.30:** Define a procedure `square-tree` analogous to the `square-list` procedure of Exercise 2.21. That is, `square-tree` should behave as follows:
>
> **Exercise 2.30:** 定義程序 `square-tree`，伊 kap Exercise 2.21 ê `square-list` 程序相 siâng。Che 就是，`square-tree` 著有下 kha ê 行為：
>
> ```
> (square-tree
>  (list 1
>        (list 2 (list 3 4) 5)
>        (list 6 7)))
> (1 (4 (9 16) 25) (36 49))
> ```
>
> Define `square-tree` both directly (i.e., without using any higher-order procedures) and also by using `map` and recursion.

請直接（無用任何 koân 階程序）定義，koh 用 `map` kap 遞迴定義 `square-tree`。

Exercise 2.31: Abstract your answer to Exercise 2.30 to produce a procedure `tree-map` with the property that `square-tree` could be defined as

Exercise 2.31: 抽象化汝 ê 答案 kàu Exercise 2.30，來產出程序 `tree-map`，伊有性質是，`square-tree` 通定義做

```
(define (square-tree tree) (tree-map square tree))
```

Exercise 2.32: We can represent a set as a list of distinct elements, and we can represent the set of all subsets of the set as a list of lists. For example, if the set is `(1 2 3)`, then the set of all subsets is `(() (3) (2) (2 3) (1) (1 3) (1 2) (1 2 3))`. Complete the following definition of a procedure that generates the set of subsets of a set and give a clear explanation of why it works:

Exercise 2.32: Lán ē 當表示集合做有無 kâng 元素 ê 列單，mā ē 當表示 chit ê 集合 ê kiáⁿ 集合 ê 集合，做列單 ê 列單。譬論講，若是集合是 `(1 2 3)`，kiáⁿ 集合 ê 集合是 `(() (3) (2) (2 3) (1) (1 3) (1 2) (1 2 3))`。請完成下 kha ê 程序 ê 定義，伊產出一个集合 ê kiáⁿ 集合 ê 集合，koh 請清楚解說伊是 án-nóa 運作：

```
(define (subsets s)
  (if (null? s)
      (list nil)
      (let ((rest (subsets (cdr s))))
        (append rest (map ⟨??⟩ rest)))))
```

2.2.3 Sequences as Conventional Interfaces 列當做慣例介面

In working with compound data, we've stressed how data abstraction permits us to design programs without becoming enmeshed in the details of data representations, and how abstraction preserves for us the flexibility to experiment with alternative representations. In this section, we introduce another powerful design principle for working with data structures—the use of *conventional interfaces*.
佇處理複合資料 ê 時陣，lán 有強調資料抽象化允准 lán 設計程式，soah 毋免 tiâu 佇資料表達方式 ê 詳細。佇本節，lán 介紹另外一个有能力 ê，處理資料結構 ê 設計原則——使用慣例介面 (conventional interfaces)。

In Section 1.3 we saw how program abstractions, implemented as higher-order procedures, can capture common patterns in programs that deal with numerical data. Our ability to formulate analogous operations for working with compound data depends crucially on the style in which we manipulate our data structures. Consider, for example, the following procedure, analogous to the `count-leaves` procedure of Section 2.2.2, which takes a tree as argument and computes the sum of the squares of the leaves that are odd:

Lán 佇 Section 1.3 看見是 án-nóa 實做做 koân 階程序 ê 程式抽象化，ē 當掠佇處理數值資料 ê 程式內底 ê 通常 ê 模式。Lán 形式化處理複合資料 ê，相 siâng ê 操作 ê 能力，上主要倚靠 lán thèh 來操作 lán ê 資料結構 ê 風格。比論講，考慮下 kha ê 程序，伊 kap Section 2.2.2 ê `count-leaves` 程序相 siâng，thèh 樹 á 當做引數，算出是奇數 ê 葉 á ê 平方和：

```
(define (sum-odd-squares tree)
  (cond ((null? tree) 0)
        ((not (pair? tree))
         (if (odd? tree) (square tree) 0))
        (else (+ (sum-odd-squares (car tree))
                 (sum-odd-squares (cdr tree))))))
```

On the surface, this procedure is very different from the following one, which

constructs a list of all the even Fibonacci numbers $\mathrm{Fib}(k)$, where k is less than or equal to a given integer n:
表面上，chit ê 程式 kap 下 kha ê 程序無 kâng，下 kha ê 程序建構列出雙數 ê Fibonacci 數 $\mathrm{Fib}(k)$ ê 列單，其中 k 無比整數 n 較大：

```
(define (even-fibs n)
  (define (next k)
    (if (> k n)
        nil
        (let ((f (fib k)))
          (if (even? f)
              (cons f (next (+ k 1)))
              (next (+ k 1))))))
  (next 0))
```

Despite the fact that these two procedures are structurally very different, a more abstract description of the two computations reveals a great deal of similarity. The first program
雖然 chit 兩个程序結構上非常無 kâng，毋 koh 對 chit 兩个計算 ê koh 較抽象 ê 敘述，顯明蓋 chē 相 siâng ê 所在。頭一个程式

- enumerates the leaves of a tree;

  列舉樹 á ê 葉；

- filters them, selecting the odd ones;

  過濾 in，揀奇數 ê；

- squares each of the selected ones; and

  kā 所揀 ê 平方；koh

- accumulates the results using +, starting with 0.

  ùi 0 起，用 + 累積結果。




Figure 2.7: The signal-flow plans for the procedures `sum-odd-squares` (top) and `even-fibs` (bottom) reveal the commonality between the two programs. 程序 `sum-odd-squares`（頂 koân）kap `even-fibs`（下底）ê 訊號流圖 (signal-flow plans) 顯明兩个程式 ê 共通點。

The second program
第二 ê 程式

- enumerates the integers from 0 to n;

  ùi 0 kàu n 列舉整數；

- computes the Fibonacci number for each integer;

  算逐 ê 整數 ê Fibonacci 數；

- filters them, selecting the even ones; and

  過濾 in，揀雙數 ê；koh

- accumulates the results using `cons`, starting with the empty list.

  ùi 空 ê 列單開始，用 `cons` khioh 結果。

A signal-processing engineer would find it natural to conceptualize these processes in terms of signals flowing through a cascade of stages, each of which

implements part of the program plan, as shown in Figure 2.7. In `sum-odd-squares`, we begin with an *enumerator*, which generates a "signal" consisting of the leaves of a given tree. This signal is passed through a *filter*, which eliminates all but the odd elements. The resulting signal is in turn passed through a *map*, which is a "transducer" that applies the `square` procedure to each element. The output of the map is then fed to an *accumulator*, which combines the elements using +, starting from an initial 0. The plan for `even-fibs` is analogous.

訊號處理 ê 工程師會發現用通過一 koāⁿ 階段 ê 訊號流動，來概念化 chiah ê 程序真自然，其中逐 ê 階段實做程式計畫 ê 一部份，展示佇 Figure 2.7。佇 `sum-odd-squares` ，lán ùi 列舉器 (enumerator) 開始，伊產生包含樹 á ê 所有葉 á ê「訊號」。Chit ê 訊號 soà kàu 過濾器 (filter)，伊 kā 除了奇數 ê 要素 lóng 排除。結果 ê 訊號一个一个送過 *map*，伊是 kā `square` 程序應用 kàu 逐 ê 要素 ê 變換器。Map ê 輸出了後送 kah 累積器 (accumulator)，伊用 + 組合要素，起初 ê 值是 0。`even-fibs` ê 計畫 mā 相 siâng。

Unfortunately, the two procedure definitions above fail to exhibit this signal-flow structure. For instance, if we examine the `sum-odd-squares` procedure, we find that the enumeration is implemented partly by the `null?` and `pair?` tests and partly by the tree-recursive structure of the procedure. Similarly, the accumulation is found partly in the tests and partly in the addition used in the recursion. In general, there are no distinct parts of either procedure that correspond to the elements in the signal-flow description. Our two procedures decompose the computations in a different way, spreading the enumeration over the program and mingling it with the map, the filter, and the accumulation. If we could organize our programs to make the signal-flow structure manifest in the procedures we write, this would increase the conceptual clarity of the resulting code.

頂懸 chit 兩个程序 ê 定義不幸 lóng bōe 當展現 chit ê 訊號流結構。舉例，若是 lán 檢查 `sum-odd-squares` 程序，lán ē 發現列舉部份是由

`null?` kap `pair?` 測試實做，部份是由程序 ê 樹遞迴結構實做。Kâng 款，累積功能部份佇測試，部份是佇遞迴內底 ê 加法。一般來講，兩个程序 lóng 無明確部份，通對應 kàu 資訊流 ê 敘述要素。Lán ê 兩个程序用無 kâng 方法分解計算，擴展列舉遍佈規个程式，mā kap map、過濾器、累積器 lām 做伙。若準講 lán 通組織 lán ê 程式，予訊號流結構表明佇 lán 寫 ê 程序，che ē 予結果 ê 原始碼 ê 概念 koh 較清楚。

Sequence Operations 列操作

The key to organizing programs so as to more clearly reflect the signal-flow structure is to concentrate on the "signals" that flow from one stage in the process to the next. If we represent these signals as lists, then we can use list operations to implement the processing at each of the stages. For instance, we can implement the mapping stages of the signal-flow diagrams using the `map` procedure from Section 2.2.1:
組織程序來 koh 較清楚反映訊號流結果 ê 關鍵，是專注佇過程內底 ùi 一个階段流 kah 後一个 ê「訊號」。若準講 lán 用列單表示 chiah ê 訊號，lán 就通用列表操作來實做處理逐个階段。比論講，lán ē 當用 Section 2.2.1 ê `map`，來實做訊號流圖 ê map 階段：

```
(map square (list 1 2 3 4 5))
(1 4 9 16 25)
```

Filtering a sequence to select only those elements that satisfy a given predicate is accomplished by
過濾一个列來 kan-ta 揀滿足指定 ê 謂詞 ê 要素，ē 當用下 kha ê 程式碼來完成：

```
(define (filter predicate sequence)
  (cond ((null? sequence) nil)
        ((predicate (car sequence))
         (cons (car sequence)
```

```
                (filter predicate (cdr sequence))))
        (else (filter predicate (cdr sequence)))))
```

For example,
譬論講：

```
(filter odd? (list 1 2 3 4 5))
(1 3 5)
```

Accumulations can be implemented by
累積器 ē 當用下 kha ê 程式碼實做：

```
(define (accumulate op initial sequence)
  (if (null? sequence)
      initial
      (op (car sequence)
          (accumulate op initial (cdr sequence)))))
(accumulate + 0 (list 1 2 3 4 5))
15
(accumulate * 1 (list 1 2 3 4 5))
120
(accumulate cons nil (list 1 2 3 4 5))
(1 2 3 4 5)
```

All that remains to implement signal-flow diagrams is to enumerate the sequence of elements to be processed. For `even-fibs`, we need to generate the sequence of integers in a given range, which we can do as follows:
實做訊號流圖 ê 手續，干焦 chhun 列舉 beh 處理 ê 要素 ê 列。對 `even-fibs`，lán 著產生指定範圍 ê 整數 ê 列，ē 當用下 kha ê 來實現：

```
(define (enumerate-interval low high)
  (if (> low high)
      nil
      (cons low (enumerate-interval (+ low 1) high))))
(enumerate-interval 2 7)
(2 3 4 5 6 7)
```

To enumerate the leaves of a tree, we can use[26]
Beh 列舉樹 á ê 葉，lán 通用[27]

```
(define (enumerate-tree tree)
  (cond ((null? tree) nil)
        ((not (pair? tree)) (list tree))
        (else (append (enumerate-tree (car tree))
                      (enumerate-tree (cdr tree))))))
(enumerate-tree (list 1 (list 2 (list 3 4)) 5))
(1 2 3 4 5)
```

Now we can reformulate `sum-odd-squares` and `even-fibs` as in the signal-flow diagrams. For `sum-odd-squares`, we enumerate the sequence of leaves of the tree, filter this to keep only the odd numbers in the sequence, square each element, and sum the results:
Ta^{n} lán 通用像訊號流圖 ê 方式來重頭起造 `sum-odd-squares` kap `even-fibs`。針對 `sum-odd-squares`，lán 列舉樹 á ê 葉 ê 列，過濾 che，來予列 kan-ta chhun 奇數，koh kā 平方，落尾合計結果：

```
(define (sum-odd-squares tree)
  (accumulate
   + 0 (map square (filter odd? (enumerate-tree tree)))))
```

For `even-fibs`, we enumerate the integers from 0 to n, generate the Fibonacci number for each of these integers, filter the resulting sequence to keep only the even elements, and accumulate the results into a list:
對 `even-fibs`，lán 列舉對 0 kàu n ê 整數，生成逐 ê 整數 ê Fibonacci 數，過濾結果 ê 列，予 kan-ta chhun 雙數 ê 要素，落尾 kā 結果累積 kàu 列單內底：

[26]This is, in fact, precisely the `fringe` procedure from Exercise 2.28. Here we've renamed it to emphasize that it is part of a family of general sequence-manipulation procedures.

[27]Che 實際上的確是 Exercise 2.28 ê `fringe` 。佇 chia lán 有 kā 重號名，來強調 che 是一般 ê 列操作程序家族 ê 一部份。

```
(define (even-fibs n)
  (accumulate
   cons
   nil
   (filter even? (map fib (enumerate-interval 0 n)))))
```

The value of expressing programs as sequence operations is that this helps us make program designs that are modular, that is, designs that are constructed by combining relatively independent pieces. We can encourage modular design by providing a library of standard components together with a conventional interface for connecting the components in flexible ways.
Kā 程式表達做列操作 ê 價值是，伊幫 chān 行 module 化 ê 程式設計，就是由組合相對獨立 ê 部份來建構 ê 設計。Lán 通用提供標準部件 ê 函式庫，以及用靈活方式 thèh 來相接部件 ê 慣例介面，來鼓勵 module 化設計。

Modular construction is a powerful strategy for controlling complexity in engineering design. In real signal-processing applications, for example, designers regularly build systems by cascading elements selected from standardized families of filters and transducers. Similarly, sequence operations provide a library of standard program elements that we can mix and match. For instance, we can reuse pieces from the `sum-odd-squares` and `even-fibs` procedures in a program that constructs a list of the squares of the first $n + 1$ Fibonacci numbers:

Module 化建構是對佇工程設計內底控制複雜性，有能力 ê 策略。譬論講，佇現實 ê 訊號處理 ê 應用程式，設計者定定用對標準化 ê 過濾器 kap 變換器家族所揀 ê相連 *sòa ê* (cascading) 要素，來起造系統。Siâng 款，列操作提供 lán ē 當相 lām kap 配對 ê 標準程式要素 ê 函式庫。舉例，lán ē 當佇建構頭 $n + 1$ ê Fibonacci 數 ê 平方 ê 列單 ê 程式，重用 `sum-odd-squares` kap `even-fibs` 程序內底 ê 程式碼節 á：

```
(define (list-fib-squares n)
  (accumulate
```

```
   cons
   nil
   (map square (map fib (enumerate-interval 0 n)))))
(list-fib-squares 10)
(0 1 1 4 9 25 64 169 441 1156 3025)
```

We can rearrange the pieces and use them in computing the product of the squares of the odd integers in a sequence:
Lán 通重排列程式節 á，佇算列內底 ê 奇數 ê 平方 ê 乘積用 in：

```
(define (product-of-squares-of-odd-elements sequence)
  (accumulate * 1 (map square (filter odd? sequence))))
(product-of-squares-of-odd-elements (list 1 2 3 4 5))
225
```

We can also formulate conventional data-processing applications in terms of sequence operations. Suppose we have a sequence of personnel records and we want to find the salary of the highest-paid programmer. Assume that we have a selector `salary` that returns the salary of a record, and a predicate `programmer?` that tests if a record is for a programmer. Then we can write
Lán mā ē 當用列操作形式化傳統 ê 資料處理應用。假使 lán 有員工記錄 ê 列，koh 想 beh chhōe 著薪水上 koân ê 程式設計師 ê 薪水。設使 lán 有揀選器 `salary`，伊傳轉記錄 ê 薪水部份，koh 有謂詞 `programmer?`，測試記錄敢是程式設計師 ê。Lán 就 ē 使寫

```
(define (salary-of-highest-paid-programmer records)
  (accumulate max 0 (map salary (filter programmer? records)
```

These examples give just a hint of the vast range of operations that can be expressed as sequence operations.[28]

[28] Richard Waters (1979) developed a program that automatically analyzes traditional Fortran programs, viewing them in terms of maps, filters, and accumulations. He found that

Chiah ê 例不過是大量 ê，ē 當表達做列操作 ê 處理 ê 一部份。[29]

Sequences, implemented here as lists, serve as a conventional interface that permits us to combine processing modules. Additionally, when we uniformly represent structures as sequences, we have localized the data-structure dependencies in our programs to a small number of sequence operations. By changing these, we can experiment with alternative representations of sequences, while leaving the overall design of our programs intact. We will exploit this capability in Section 3.5, when we generalize the sequence-processing paradigm to admit infinite sequences.

佇 chia 實做做列單 ê 列，當做慣例介面，允准 lán 組合逐 ê 處理 ê module。此外，當 lán kā 結構統一表示做列 ê 時，lán 就佇 lán ê 程式，kā 資料結構所倚靠 *ê* (dependencies)，限制 kàu 幾个列操作。用改變 chiah ê，lán ē 當用列 ê 別 ê 表達式實驗，同時予 lán ê 程式 ê 整個毋免改變。Lán ē 佇Section 3.5，當 lán kā 列操作 ê 模範普及 kàu 允准無限 ê 列 ê 時陣，充分利用 chit ê 能力。

> **Exercise 2.33:** Fill in the missing expressions to complete the following definitions of some basic list-manipulation operations as accumulations:

---

fully 90 percent of the code in the Fortran Scientific Subroutine Package fits neatly into this paradigm. One of the reasons for the success of Lisp as a programming language is that lists provide a standard medium for expressing ordered collections so that they can be manipulated using higher-order operations. The programming language APL owes much of its power and appeal to a similar choice. In APL all data are represented as arrays, and there is a universal and convenient set of generic operators for all sorts of array operations.

[29] Richard Waters (1979)開發一个程式，自動分析傳統 ê Fortran 程式，用 map、過濾器 kap 累積器 ê 方式來 kā in 看。伊發現佇 Fortran Scientific Subroutine Package ê 程式碼，90% 貼貼完全符合 chit ê 模範 (paradigm)。做著一个程式語言，Lisp 成功 ê 原因之一是，列單提供標準 ê 媒介，來表達有序 ê 集合，致使 in ē 當用 koân 階函數操作。程式語言 APL ê 能力 kap 魅力 ê 大部份，mā 因為相 siâng ê 選擇。佇 APL，逐筆資料，lóng 用陣列表示，mā 有通用 koh 方便 ê，一般 ê 運算子 ê 集合，來操作逐款 ê 陣列操作。

Exercise 2.33: 添 ka-lâuh ê 表達式，來完成下 kha 一寡基礎 ê，當做是累積器 ê 列單操作 ê 定義：

```
(define (map p sequence)
  (accumulate (lambda (x y) ⟨??⟩) nil sequence))
(define (append seq1 seq2)
  (accumulate cons ⟨??⟩ ⟨??⟩))
(define (length sequence)
  (accumulate ⟨??⟩ 0 sequence))
```

Exercise 2.34: Evaluating a polynomial in x at a given value of x can be formulated as an accumulation. We evaluate the polynomial

Exercise 2.34: 算 x ê 多項式佇 x 是某物值 ê 值，ē 當用累積器來形式化。Lán 用出名 ê 演算法，號做 *Horner* 法則 (Horner's rule)，算下 kha ê 多項式 ê 值

$$a_n x^n + a_{n-1} x^{n-1} + \cdots + a_1 x + a_0$$

using a well-known algorithm called *Horner's rule*, which structures the computation as

chit ê 演算法 kā 計算式排做

$$(\ldots (a_n x + a_{n-1}) x + \cdots + a_1) x + a_0.$$

In other words, we start with a_n, multiply by x, add a_{n-1}, multiply by x, and so on, until we reach a_0.[30]

[30] According to Knuth 1981, this rule was formulated by W. G. Horner early in the nineteenth century, but the method was actually used by Newton over a hundred years earlier.

換一款講法，lán 對 a_n 開始，予 x 乘，koh 加 a_{n-1}，予 x 乘，直到 a_0。[31]

Fill in the following template to produce a procedure that evaluates a polynomial using Horner's rule. Assume that the coefficients of the polynomial are arranged in a sequence, from a_0 through a_n.

添下 kha ê 枋模，來產出用 Horner 法則算多項式 ê 程序。假設多項式 ê 係數排做列，ùi a_0 kàu a_n。

```
(define (horner-eval x coefficient-sequence)
  (accumulate (lambda (this-coeff higher-terms) ⟨??⟩)
              0
              coefficient-sequence))
```

For example, to compute $1 + 3x + 5x^3 + x^5$ at $x = 2$ you would evaluate

---

Horner's rule evaluates the polynomial using fewer additions and multiplications than does the straightforward method of first computing $a_n x^n$, then adding $a_{n-1}x^{n-1}$, and so on. In fact, it is possible to prove that any algorithm for evaluating arbitrary polynomials must use at least as many additions and multiplications as does Horner's rule, and thus Horner's rule is an optimal algorithm for polynomial evaluation. This was proved (for the number of additions) by A. M. Ostrowski in a 1954 paper that essentially founded the modern study of optimal algorithms. The analogous statement for multiplications was proved by V. Y. Pan in 1966. The book by Borodin and Munro (1975) provides an overview of these and other results about optimal algorithms.

[31] 根據 Knuth 1981，chit ê 法則是由 W. G. Horner 佇十九世紀早期形式化，毋 kú chit ê 方法實際上佇超過 100 年進前 Newton 就使用 ah。Horner 法則算多項式 ê 值，比直接先算 $a_n x^n$，koh 算 $a_{n-1}x^{n-1}$ 等等 ê 方法，需要 koh 較少 ê 加法 kap 乘法。實際上，ē 當證明所有算任何演算法 ê 值，定著用上少 kap Horner 法則平 chē ê 加法 kap 乘法。因此 Horner 法則是算多項式 ê 值 ê 最佳演算法。Che 由 A. M. Ostrowski 證明（加法數 ê 部份），刊佇 1954 年 ê 論文，伊起造現代研究最佳化演算法 ê 基礎。乘法數 ê 相 siâng ê 表示是由 V. Y. Pan 佇 1966 年所證明。Borodin and Munro (1975) ê 冊提供 chiah ê kap 其他關係最佳化演算法 ê 結果 ê 概觀。

譬論講，beh 算 $1 + 3x + 5x^3 + x^5$ 佇 $x = 2$ ê 值，lí ē 算下 kha ê：

```
(horner-eval 2 (list 1 3 0 5 0 1))
```

Exercise 2.35: Redefine `count-leaves` from Section 2.2.2 as an accumulation:

Exercise 2.35: Kā Section 2.2.2 ê `count-leaves` 用累積器 ê 方式重頭定義。

```
(define (count-leaves t)
  (accumulate ⟨??⟩ ⟨??⟩ (map ⟨??⟩ ⟨??⟩)))
```

Exercise 2.36: The procedure `accumulate-n` is similar to `accumulate` except that it takes as its third argument a sequence of sequences, which are all assumed to have the same number of elements. It applies the designated accumulation procedure to combine all the first elements of the sequences, all the second elements of the sequences, and so on, and returns a sequence of the results. For instance, if `s` is a sequence containing four sequences, `((1 2 3) (4 5 6) (7 8 9) (10 11 12))`, then the value of `(accumulate-n + 0 s)` should be the sequence `(22 26 30)`. Fill in the missing expressions in the following definition of `accumulate-n`:

Exercise 2.36: 程序 `accumulate-n` kap `accumulate` 相 siâng，除了伊 thèh 列 ê 列當做第三个引數。Chit ê 引數內底，逐列 ê 元素額 lóng 平 chē。伊應用指定 ê 累積器程序來組合逐列 ê 頭一个元素、逐列 ê 第二个引數，等等，傳轉列 ê 所有結果。譬論講，`s` 若是包含四个列 ê 列 `((1 2 3) (4 5 6) (7`

`8 9) (10 11 12))`，`(accumulate-n + 0 s)` ê 值就應該是列 `(22 26 30)`。添下 kha `accumulate-n` ê 定義內底 ka-lâuh ê 表達式：

```
(define (accumulate-n op init seqs)
  (if (null? (car seqs))
      nil
      (cons (accumulate op init ⟨??⟩)
            (accumulate-n op init ⟨??⟩))))
```

Exercise 2.37: Suppose we represent vectors $\mathbf{v} = (v_i)$ as sequences of numbers, and matrices $\mathbf{m} = (m_{ij})$ as sequences of vectors (the rows of the matrix). For example, the matrix

假使 lán kā 向量 (vector) $\mathbf{v} = (v_i)$ 表示做數 ê 列，kā 矩陣 $\mathbf{m} = (m_{ij})$ 表示做向量（矩陣 ê 列）ê 列。比論講，矩陣

$$\begin{pmatrix} 1 & 2 & 3 & 4 \\ 4 & 5 & 6 & 6 \\ 6 & 7 & 8 & 9 \end{pmatrix}$$

is represented as the sequence `((1 2 3 4) (4 5 6 6) (6 7 8 9))`. With this representation, we can use sequence operations to concisely express the basic matrix and vector operations. These operations (which are described in any book on matrix algebra) are the following:

表示做列 `((1 2 3 4) (4 5 6 6) (6 7 8 9))`。用 chit 款表示法，lán 通用列操作來簡單表示基本 ê 矩陣 kap 向量操作。Chiah ê 操作（佇任何矩陣代數 ê 冊有描述）佇下 kha：

`(dot-product v w)`	returns the sum (傳轉和)$\Sigma_i v_i w_i$;
`(matrix-*-vector m v)`	returns the vector (傳轉向量)**t**, where $t_i = \Sigma_j m_{ij} v_j$;
`(matrix-*-matrix m n)`	returns the matrix (傳轉矩陣)**p**, where (其中)$p_{ij} = \Sigma_k m_{ik} n_{kj}$;
`(transpose m)`	returns the matrix (傳轉矩陣)**n**, where (其中)$n_{ij} = m_{ji}$.

We can define the dot product as[32]

Lán ē 當定義內積做[33]

```
(define (dot-product v w)
  (accumulate + 0 (map * v w)))
```

Fill in the missing expressions in the following procedures for computing the other matrix operations. (The procedure `accumulate-n` is defined in Exercise 2.36.)

添下 kha ê 程序內底 ê ka-lâuh ê 表達式，來計算其他 ê 矩陣操作（程序 `accumulate-n` 定義佇 Exercise 2.36）。

```
(define (matrix-*-vector m v)
  (map ⟨??⟩ m))
(define (transpose mat)
  (accumulate-n ⟨??⟩ ⟨??⟩ mat))
(define (matrix-*-matrix m n)
  (let ((cols (transpose n)))
    (map ⟨??⟩ m)))
```

[32] This definition uses the extended version of `map` described in Footnote 12.

[33] Chit ê 定義用佇 Footnote 12 描述 ê `map` ê 擴展版本。

Exercise 2.38: The `accumulate` procedure is also known as `fold-right`, because it combines the first element of the sequence with the result of combining all the elements to the right. There is also a `fold-left`, which is similar to `fold-right`, except that it combines elements working in the opposite direction:

Exercise 2.38: `accumulate` 程序 mā 號做 `fold-right`，因為伊組合列 ê 頭一个元素 kap kā 伊正 pêng 逐 ê 元素組合 ê 結果。Mā 有 `fold-left`，kap `fold-right` 相 siâng，除了伊組合元素 ê 方向對反：

```
(define (fold-left op initial sequence)
  (define (iter result rest)
    (if (null? rest)
        result
        (iter (op result (car rest))
              (cdr rest))))
  (iter initial sequence))
```

What are the values of

下 kha ê 表達式 ê 值是 siáⁿ？

```
(fold-right / 1 (list 1 2 3))
(fold-left / 1 (list 1 2 3))
(fold-right list nil (list 1 2 3))
(fold-left list nil (list 1 2 3))
```

Give a property that `op` should satisfy to guarantee that `fold-right` and `fold-left` will produce the same values for any sequence.

寫出一个 `op` 著滿足 ê 特性，來保證對所有 ê 列，`fold-right` kap `fold-left` ē 產出 kâng 款 ê 值。

Exercise 2.39: Complete the following definitions of `reverse` (Exercise 2.18) in terms of `fold-right` and `fold-left` from Exercise 2.38:

Exercise 2.39: 用 Exercise 2.38 ê `fold-right` kap `fold-left`，來完成下 kha ê `reverse` (Exercise 2.18) ê 定義：

```
(define (reverse sequence)
  (fold-right (lambda (x y) ⟨??⟩) nil sequence))
(define (reverse sequence)
  (fold-left (lambda (x y) ⟨??⟩) nil sequence))
```

Nested Mappings 岫 á 形 ê Map

We can extend the sequence paradigm to include many computations that are commonly expressed using nested loops.[34] Consider this problem: Given a positive integer n, find all ordered pairs of distinct positive integers i and j, where $1 \leq j < i \leq n$, such that $i + j$ is prime. For example, if n is 6, then the pairs are the following:

Lán 通擴展列 ê 模範，來包含 chē-chē 通常用岫 á 形 ê loop 表達 ê 計算。[35]考慮 chit ê 問題：有正整數 n，chhōe 逐 ê 無 kâng ê 正整數 i kap j ê 順序對 (ordered pair)，其中 $1 \leq j < i \leq n$，koh 滿足 $i + j$ 是質數。比論講，n 若是 6，下 kha 是所有 ê 對：

[34]This approach to nested mappings was shown to us by David Turner, whose languages KRC and Miranda provide elegant formalisms for dealing with these constructs. The examples in this section (see also Exercise 2.42) are adapted from Turner 1981. In Section 3.5.3, we'll see how this approach generalizes to infinite sequences.

[35]Chit ê 對岫 á 形 ê map ê 方法是由 David Turner 展示予 goán，伊使用 ê KRC kap Miranda 語言提供優雅 ê 形式，來處理 chit 款概念。佇 chit 節 ê 例（請看 Exercise 2.42）是 ùi Turner 1981 摘 ê。佇 Section 3.5.3，lán ē 看見 chit ê 方法 án-nóa 擴展 kàu 無限 ê 列。

i	2	3	4	4	5	6	6
j	1	2	1	3	2	1	5
$i+j$	3	5	5	7	7	7	11

A natural way to organize this computation is to generate the sequence of all ordered pairs of positive integers less than or equal to n, filter to select those pairs whose sum is prime, and then, for each pair (i, j) that passes through the filter, produce the triple $(i, j, i + j)$.

一个自然組織 chit ê 計算 ê 方法，是生成所有無超過 n ê 正整數 ê 順序對 ê 列，用過濾器揀出和是質數 ê 對了後，對所有通過過濾器 ê 對 (i, j)，產出三元組 (triple) $(i, j, i + j)$。

Here is a way to generate the sequence of pairs: For each integer $i \leq n$, enumerate the integers $j < i$, and for each such i and j generate the pair (i, j). In terms of sequence operations, we map along the sequence `(enumerate-interval 1 n)`. For each i in this sequence, we map along the sequence `(enumerate-interval 1 (- i 1))`. For each j in this latter sequence, we generate the pair `(list i j)`. This gives us a sequence of pairs for each i. Combining all the sequences for all the i (by accumulating with `append`) produces the required sequence of pairs:[36]

Chia 是一款生成對 ê 列 ê 方法：對所有 ê 正整數 $i \leq n$，列舉整數 $j < i$，而且對所有 ê i kap j，生成對 (i, j)。用列操作 ê 方式，lán 順著列 `(enumerate-interval 1 n)` 來 map。對 chit ê 列內底 ê 逐 ê i，lán 順著列 `(enumerate-interval 1 (- i 1))` 來 map。對所有 i，組合逐 ê 列（藉 `append` 來累積），產出所需要 ê 列 ê 對：[37]

[36] We're representing a pair here as a list of two elements rather than as a Lisp pair. Thus, the "pair" (i, j) is represented as `(list i j)`, not `(cons i j)`.

[37] Lán leh 用兩个元素 ê 列單，soah 毋是用 Lisp ê 對，佇 chia 來表示對。就 án-ne，「對」(i, j) 表示做 `(list i j)`，毋是 `(cons i j)`。

```
(accumulate
 append nil (map (lambda (i)
                   (map (lambda (j) (list i j))
                        (enumerate-interval 1 (- i 1))))
                 (enumerate-interval 1 n)))
```

The combination of mapping and accumulating with `append` is so common in this sort of program that we will isolate it as a separate procedure:
Map kap 用 `append` 累積 ê 組合，佇 chit 款程式 chiâⁿ chiảp 用，致使 lán kā 孤立做分開 ê 程序：

```
(define (flatmap proc seq)
  (accumulate append nil (map proc seq)))
```

Now filter this sequence of pairs to find those whose sum is prime. The filter predicate is called for each element of the sequence; its argument is a pair and it must extract the integers from the pair. Thus, the predicate to apply to each element in the sequence is
Taⁿ 過濾 chit ê 對 ê 列來 chhōe 和是質數 ê。對列 ê 逐个元素，過濾 ê 謂詞 lóng ē 呼叫；伊 ê 引數是對，mā 定著對對來抽出整數。就 án-ne，應用 kàu 列 ê 逐 ê 元素 ê 謂詞是

```
(define (prime-sum? pair)
  (prime? (+ (car pair) (cadr pair))))
```

Finally, generate the sequence of results by mapping over the filtered pairs using the following procedure, which constructs a triple consisting of the two elements of the pair along with their sum:
落尾，倚靠 kā 過濾好 ê 對，用下 kha ê 程序 map，來生成結果 ê 列。下 kha ê 程序建構包含對 ê 兩个元素，kap in ê 和 ê 三元組：

```
(define (make-pair-sum pair)
  (list (car pair) (cadr pair) (+ (car pair) (cadr pair))))
```

Combining all these steps yields the complete procedure:

```
(define (prime-sum-pairs n)
  (map make-pair-sum
       (filter prime-sum? (flatmap
                           (lambda (i)
                             (map (lambda (j) (list i j))
                                  (enumerate-interval 1 (- i 1))))
                           (enumerate-interval 1 n)))))
```

Nested mappings are also useful for sequences other than those that enumerate intervals. Suppose we wish to generate all the permutations of a set S; that is, all the ways of ordering the items in the set. For instance, the permutations of $\{1, 2, 3\}$ are $\{1, 2, 3\}$, $\{1, 3, 2\}$, $\{2, 1, 3\}$, $\{2, 3, 1\}$, $\{3, 1, 2\}$, and $\{3, 2, 1\}$. Here is a plan for generating the permutations of S: For each item x in S, recursively generate the sequence of permutations of $S - x$,[38] and adjoin x to the front of each one. This yields, for each x in S, the sequence of permutations of S that begin with x. Combining these sequences for all x gives all the permutations of S:[39]

除了列舉區間 ê 以外，岫 á 形 ê map mā 對列來講誠有路用。設使 lán 向望生成集合 S ê 所有排列形式，就是集合內底 ê 項目所有 ê 排順序 ê 方法。舉例，$\{1, 2, 3\}$ 所有 ê 排列形式是 $\{1, 2, 3\}$, $\{1, 3, 2\}$, $\{2, 1, 3\}$, $\{2, 3, 1\}$, $\{3, 1, 2\}$, and $\{3, 2, 1\}$。生成 S ê 排列形式 ê 計畫佇 chia：對逐 ê 佇 S ê 項目 x，遮迴生成 $S - x$ ê 排列 ê 列，[40]koh kā x 接 kàu 逐 ê 排列 ê 頭前。對所有佇 S ê x，che ê thèh 著 S ê，起頭是 x ê 排列形式。組合 chia 所有無 kâng x 起頭 ê 列，ē 得著所有 S ê 排列方式：[41]

[38] The set $S - x$ is the set of all elements of S, excluding x.

[39] Semicolons in Scheme code are used to introduce *comments*. Everything from the semicolon to the end of the line is ignored by the interpreter. In this book we don't use many comments; we try to make our programs self-documenting by using descriptive names.

[40] 集合 $S - x$ 是所有 S ê 元素，扣掉 x ê 集合。

[41] 佇 Scheme ê 程式碼，分號用來表示註 *kha*(comments)。Ùi 分號 kàu chōa 尾 ê 所有文字，編譯器 lóng ē 忽略。佇本冊 lán bōe 用足 chē 註 kha。Lán 用描述性 ê 名來予 lán ê 程式碼 ē 當說明家 kī。

```
(define (permutations s)
  (if (null? s)                    ; empty set?
      (list nil)                   ; sequence containing empty set
      (flatmap (lambda (x)
                 (map (lambda (p) (cons x p))
                      (permutations (remove x s))))
               s)))
```

Notice how this strategy reduces the problem of generating permutations of S to the problem of generating the permutations of sets with fewer elements than S. In the terminal case, we work our way down to the empty list, which represents a set of no elements. For this, we generate `(list nil)`, which is a sequence with one item, namely the set with no elements. The `remove` procedure used in `permutations` returns all the items in a given sequence except for a given item. This can be expressed as a simple filter:
請注意 chit ê 策略 án-nóa 縮小生成 S ê 排列問題，kàu 生成有比 S 較少要素集合 ê 排列 ê 問題。佇上尾 ê 情形，lán 一步一步處理 kàu 空列單，伊代表無元素 ê 集合。對 che，lán 生成 `(list nil)`，he 是有一个項目 ê 列，就是無元素 ê 集合。佇 `permutations` 所用 ê`remove` 程序，傳轉列內底 ê 逐 ê 項目，毋 koh 扣掉指定 ê 元素。Che ē 當用一个過濾器表達：

```
(define (remove item sequence)
  (filter (lambda (x) (not (= x item)))
          sequence))
```

Exercise 2.40: Define a procedure `unique-pairs` that, given an integer n, generates the sequence of pairs (i, j) with $1 \leq j < i \leq n$. Use `unique-pairs` to simplify the definition of `prime-sum-pairs` given above.

Exercise 2.40: 定義程序 `unique-pairs`，伊 thèh 整數 n，生成對 (i, j) ê 列，其中 $1 \leq j < i \leq n$。用 `unique-pairs` 來 kā 頂懸 `prime-sum-pairs` ê 定義變簡單。

Exercise 2.41: Write a procedure to find all ordered triples of distinct positive integers i, j, and k less than or equal to a given integer n that sum to a given integer s.

Exercise 2.41: 寫程序 chhōe 逐 ê 無 kâng 正整數 i、j kap k ê，照順序排 ê 三元組。其中 i、j kap k 無超過指定 ê 整數 n，in 三个 ê 和是指定 ê 整數 s。

Exercise 2.42: The "eight-queens puzzle" asks how to place eight queens on a chessboard so that no queen is in check from any other (i.e., no two queens are in the same row, column, or diagonal). One possible solution is shown in Figure 2.8. One way to solve the puzzle is to work across the board, placing a queen in each column. Once we have placed $k - 1$ queens, we must place the kth queen in a position where it does not check any of the queens already on the board. We can formulate this approach recursively: Assume that we have already generated the sequence of all possible ways to place $k - 1$ queens in the first $k - 1$ columns of the board. For each of these ways, generate an extended set of positions by placing a queen in each row of the kth column. Now filter these, keeping only the positions for which the queen in the kth column is safe with respect to the other queens. This produces the sequence of all ways to place k queens in the first k columns. By continuing this process, we will produce not only one solution, but all solutions to the puzzle.

Exercise 2.42: 「八王后問題」是問 án-nóa khǹg 西洋棋王后 ê 棋仔佇棋盤頂，予所有王后 lóng bōe hǒng 將軍（就是無兩个王后佇 kâng 一个行、列，或者是對角線）。一个可能 ê 改展示佇 Figure 2.8。一个解 chit ê 問題 ê 方法是佇 kui 个棋盤 ê 逐行 khǹg lóng 一粒皇后。Lán 一下 khǹg 好 $k - 1$ ê 王后，就定著




Figure 2.8: A solution to the eight-queens puzzle. 八王后問題 ê 一个解。

khǹg 第 k 粒皇后佇伊 bē 予其他 ê 皇后將軍。Lán 通用遞迴形式化 chit ê 方法：假使 lán 有生成所有可能 ê 方法，來 kā $k-1$ 粒皇后 khǹg 佇棋盤 ê 頭 $k-1$ 行。對逐 ê 方法，用 khǹg 一粒皇后佇第 k 行 ê 逐列，來生成擴充 ê 位置 ê 集合。Chit-má 過濾 chiah ê，保留予佇第 k 行 ê 皇后 bōe hǒng 將軍 ê 位置。Che 產出逐款 kā k 粒皇后 khǹg 佇頭 k 行 ê 方法 ê 列。繼續 chit ê 過程，lán 通產出毋但一个解，koh 有 chit ê 問題 ê 逐个解。

We implement this solution as a procedure `queens`, which returns a sequence of all solutions to the problem of placing n queens on an $n \times n$ chessboard. `queens` has an internal procedure `queen-cols` that returns the sequence of all ways to place queens in the first k columns of the board.

Lán kā chit ê 改法實做做程序 `queens`，伊傳轉一个列，包含 kā n 粒皇后 khǹg 佇 $n \times n$ ê 棋盤 ê 所有解。`queens` 有內部程序 `queen-cols`，伊傳轉一个列，包含 kā 皇后 khǹg 佇棋

盤頭 k 行 ê 所有方法。

```
(define (queens board-size)
  (define (queen-cols k)
    (if (= k 0)
        (list empty-board)
        (filter
         (lambda (positions) (safe? k positions))
         (flatmap
          (lambda (rest-of-queens)
            (map (lambda (new-row)
                   (adjoin-position
                    new-row k rest-of-queens))
                 (enumerate-interval 1 board-size)))
          (queen-cols (- k 1))))))
  (queen-cols board-size))
```

In this procedure `rest-of-queens` is a way to place $k-1$ queens in the first $k-1$ columns, and `new-row` is a proposed row in which to place the queen for the kth column. Complete the program by implementing the representation for sets of board positions, including the procedure `adjoin-position`, which adjoins a new row-column position to a set of positions, and `empty-board`, which represents an empty set of positions. You must also write the procedure `safe?`, which determines for a set of positions, whether the queen in the kth column is safe with respect to the others. (Note that we need only check whether the new queen is safe—the other queens are already guaranteed safe with respect to each other.)

佇 chit ê 程序內底，`rest-of-queens`，是 khǹg $k-1$ 粒皇后佇頭 $k-1$ 行 ê 一个方法，`new-row` 是提案來 khǹg 第

k 行 ê 皇后 ê 列。用實做棋盤位置 ê 集合 ê 表達方法，包含程序 `adjoin-position` ，伊相接新 ê 列—行位置 (row-column position) kàu 位置 ê 集合，kap `empty-board`，伊表示位置 ê 空集合。來完成 chit ê 程序。汝 mā 著寫程序 `safe?`，伊對位置 ê 集合，決定佇 k 行 ê 皇后 kám 安全。（注意 lán kan-ta 需要檢查新 ê 皇后 kám 安全——其他皇后代先 lóng 有保證安全 ah。）

Exercise 2.43: Louis Reasoner is having a terrible time doing Exercise 2.42. His `queens` procedure seems to work, but it runs extremely slowly. (Louis never does manage to wait long enough for it to solve even the 6×6 case.) When Louis asks Eva Lu Ator for help, she points out that he has interchanged the order of the nested mappings in the `flatmap`, writing it as

Exercise 2.43: Louis Reasoner 佇寫 Exercise 2.42 ê 時無歡喜。伊 ê `queens` 程序假若 ē 當走，毋過極其慢。（連解 6×6 ê 案例，Louis 都忍 bōe 牢。）當 Louis 問 Eva Lu Ator kám 通幫 chān，伊指明 Louis 有佇 `flatmap` 內，交換岫 á 形 ê map ê 順序，kā 寫做

```
(flatmap
 (lambda (new-row)
   (map (lambda (rest-of-queens)
          (adjoin-position new-row k rest-of-queens))
        (queen-cols (- k 1))))
 (enumerate-interval 1 board-size))
```

Explain why this interchange makes the program run slowly. Estimate how long it will take Louis's program to solve the eight-queens puzzle, assuming that the program in Exercise 2.42 solves the puzzle in time T.

請解說是 án-nóa án-ne 交換予程序 pháng kah 足慢。估計 Louis ê 程式解八王后 ê 問題著開 gōa chē 時間，設使佇 Exercise 2.42 ê 程序解 chit ê 問題需要時間 T。

2.2.4 Example: A Picture Language 例：圖片語言

This section presents a simple language for drawing pictures that illustrates the power of data abstraction and closure, and also exploits higher-order procedures in an essential way. The language is designed to make it easy to experiment with patterns such as the ones in Figure 2.9, which are composed of repeated elements that are shifted and scaled.[42] In this language, the data objects being combined are represented as procedures rather than as list structure. Just as `cons`, which satisfies the closure property, allowed us to easily build arbitrarily complicated list structure, the operations in this language, which also satisfy the closure property, allow us to easily build arbitrarily complicated patterns.

Chit 節展示簡單 ê 畫圖片 ê 語言，伊說明資料抽象 kap 閉包 ê 能力，koh 照必要 ê 方式用 koân 階程序。Chit ê 語言 hŏng 設計來予實驗像佇 Figure 2.9 ê 模式較快，hiah ê 模式是由重覆 ê，sóa 動 kap chhun-kiu 元素所組成。[43]佇 Chit ê 語言，beh 組合 ê 資料物件是用程序表示，毋是列單結構。就親像 `cons`，伊滿足閉包 ê 特性，予 lán 較快起造任意 ê 複雜列單結構，佇 chit ê 語言 ê 操作，伊 mā 滿足閉包特性，允准 lán 較快起造任意 ê 複雜模式。

[42] The picture language is based on the language Peter Henderson created to construct images like M.C. Escher's "Square Limit" woodcut (see Henderson 1982). The woodcut incorporates a repeated scaled pattern, similar to the arrangements drawn using the `square-limit` procedure in this section.

[43] Chit ê 圖片語言是 chhāi 佇 Peter Henderson 創造 ê 語言，來建構像 M.C. Escher ê「Square Limit」柴版畫 ê 圖（看 Henderson 1982）。Chit 幅柴版畫包含重覆 koh chhun-kiu ê 模式，kap 佇本節用 `square-limit` 所畫 ê 排列相 siâng。




Figure 2.9: Designs generated with the picture language. 用圖片語言生成 ê 設計

The picture language 圖片語言

When we began our study of programming in Section 1.1, we emphasized the importance of describing a language by focusing on the language's primitives, its means of combination, and its means of abstraction. We'll follow that framework here.

當 lán 佇 Section 1.1 開始研究程式 ê 時陣，lán 強調用注神佇語言 ê 基礎函數、組合 ê 方法 kap 抽象 ê 方法，來描述語言 ê 重要。Lán 佇 chia ē 跟 tòe chit ê 框殼。

Part of the elegance of this picture language is that there is only one kind of element, called a *painter*. A painter draws an image that is shifted and scaled to fit within a designated parallelogram-shaped frame. For example, there's a primitive painter we'll call `wave` that makes a crude line drawing, as shown in Figure 2.10. The actual shape of the drawing depends on the frame




Figure 2.10: Images produced by the `wave` painter, with respect to four different frames. The frames, shown with dotted lines, are not part of the images. 畫圖器 `wave` 產出 ê 圖片，關係四个無 kâng ê 框殼。框殼，用點線表示，毋是圖片 ê 一部份。

—all four images in figure 2.10 are produced by the same `wave` painter, but with respect to four different frames. Painters can be more elaborate than this: The primitive painter called `rogers` paints a picture of MIT's founder, William Barton Rogers, as shown in Figure 2.11.[44] The four images in figure

[44] William Barton Rogers (1804-1882) was the founder and first president of MIT. A geologist and talented teacher, he taught at William and Mary College and at the University of Virginia. In 1859 he moved to Boston, where he had more time for research, worked on a plan for establishing a "polytechnic institute," and served as Massachusetts's first State Inspector of Gas Meters.

When MIT was established in 1861, Rogers was elected its first president. Rogers espoused an ideal of "useful learning" that was different from the university education of the time, with its overemphasis on the classics, which, as he wrote, "stand in the way of the broader, higher and more practical instruction and discipline of the natural and social sciences." This education

2.11 are drawn with respect to the same four frames as the `wave` images in figure 2.10.

Chit ê 圖片語言 ê 優雅，一部份是，kan-ta 有 chit 款要素，號做畫圖器 (painter)。畫圖器畫 chit 幅圖，伊受 sóa 振動 kap chhun-kiu，來 tàu 入去設計好 ê 平行四角形框殼。比如講，有基礎 ê 畫圖器，lán ē kā 號做 `wave`，伊

---

was likewise to be different from narrow trade-school education. In Rogers's words:

> The world-enforced distinction between the practical and the scientific worker is utterly futile, and the whole experience of modern times has demonstrated its utter worthlessness.

Rogers served as president of MIT until 1870, when he resigned due to ill health. In 1878 the second president of MIT, John Runkle, resigned under the pressure of a financial crisis brought on by the Panic of 1873 and strain of fighting off attempts by Harvard to take over MIT. Rogers returned to hold the office of president until 1881.

Rogers collapsed and died while addressing MIT's graduating class at the commencement exercises of 1882. Runkle quoted Rogers's last words in a memorial address delivered that same year:

> "As I stand here today and see what the Institute is, . . . I call to mind the beginnings of science. I remember one hundred and fifty years ago Stephen Hales published a pamphlet on the subject of illuminating gas, in which he stated that his researches had demonstrated that 128 grains of bituminous coal – " "Bituminous coal," these were his last words on earth. Here he bent forward, as if consulting some notes on the table before him, then slowly regaining an erect position, threw up his hands, and was translated from the scene of his earthly labors and triumphs to "the tomorrow of death," where the mysteries of life are solved, and the disembodied spirit finds unending satisfaction in contemplating the new and still unfathomable mysteries of the infinite future.

In the words of Francis A. Walker (MIT's third president):

> All his life he had borne himself most faithfully and heroically, and he died as so good a knight would surely have wished, in harness, at his post, and in the very part and act of public duty.

畫原油線 (crude line)，像佇 Figure 2.10 所展示 ê。畫圖 ê 實際 ê 形由框殼決定——所有佇 Figure 2.10 ê 四幅圖，是由 kâng 款 ê `wave` 畫圖器產出，毋 kú 限制佇四个無 kâng ê 框殼。畫圖器 ē 當比 che koh 較幼路：號做 `rogers` 基礎 ê 畫圖器畫 MIT ê 創辦人 ê 像，展示佇 Figure 2.11。[45]佇 Figure 2.11 ê 四幅圖，mā 照 Figure 2.10 內底 `wave` ê 圖所用 ê 框殼來畫。

[45]William Barton Rogers (1804-1882) 是 MIT ê 創辦人 kap 頭任校長。做著一位地質學家 kap 有才情 ê 老師，伊佇 William and Mary 學院 kap Virginia 大學教冊。1859 年伊搬 kàu Boston，佇 hia 有較 chē 時間通好研究，骨力佇成立「理工學院」ê 計畫，koh 擔任 Massachusetts ê 頭一个 gà-suh 表州檢察官。

當 MIT 佇 1861 年成立 ê 時，Rogers 受選做頭一任校長。Rogers thīn「實用 ê 學習」ê 理想，hām hit 時 ê 傷強調古典 ê 大學教育無 kâng，像伊所寫：「擋牢較闊、較 koân kap 較應用性 ê 自然 kap 社會科學 ê 教學 kap 學問。」Chit ê 教育 mā kâng 款 hām ėh ê 貿易學校教育無 kâng。若 Roger 所講：

> 世界硬加 ê，佇應用 ê 工 lâng kap 科學 ê ê 區別是全然無彩工，現代 ê kui 个經驗證明伊 lóng 總無價值 ah。

Rogers 擔任 MIT ê 校長直到 1870 年，hit 時因為健康無好 chiah 辭職。1878 年，MIT ê 第二任校長 John Runkle 因為*1873* 年 *ê* 經濟懍 *neh* (Panic of 1873) 引起 ê 財務危機 kap 對抗 Harvard 大學併掉 MIT ê 壓力辭職。Rogers 轉去 hoān 校長室直 kàu 1881 年。

Rogers 佇 1882 年 MIT 大學部畢業典禮致詞 ê 時倒去 soah 過身。Runkle 佇 kâng 年 ê 追思會致詞，引用 Rogers ê 遺言：

> 「當我 khiā 佇 chia，看見學院是怎樣，……我想起科學 ê 起頭。我記得一百五十年前，Stephen Hales 出版關係照明氣體 ê 冊仔，其中伊表示伊 ê 研究展示 128 grain ê 瀝青塗炭——」「瀝青塗炭」是伊佇世上上尾所講 ê。佇 chia 伊 àn 落，假若 beh 確認伊頭前 ê 筆記，了後 tàuh-tàuh-á 恢復 khiā leh，giâ 起雙手，對伊 ê 地上勞動 kap 勝利 ê 場面，受 chhōa kàu「死亡 ê 明 á-chài」，其中性命 ê 奧秘受解破，對肉體解放 ê 靈魂，佇深思無限未來 ê，新 koh 猶原不可測 ê 奧秘內底，chhōe 著 bōe soah ê 滿足。

Francis A. Walker（MIT ê 第三任校長）講：

> 伊家己擔 ê 人生，lóng 是上忠實，mā 若英雄。伊像騎士誠實向望 ê，佇工課中，佇伊 ê 職位，koh 佇公務職責 ê 當中過身。




Figure 2.11: Images of William Barton Rogers, founder and first president of MIT, painted with respect to the same four frames as in Figure 2.10 (original image from Wikimedia Commons). MIT ê 創辦人 kap 頭任校長 William Barton Rogers ê 像，用佇 Figure 2.10 siâng 款 ê 四个框殼來畫（原圖對 Wikimedia Commons 來）。

To combine images, we use various operations that construct new painters from given painters. For example, the `beside` operation takes two painters and produces a new, compound painter that draws the first painter's image in the left half of the frame and the second painter's image in the right half of the frame. Similarly, `below` takes two painters and produces a compound painter that draws the first painter's image below the second painter's image. Some operations transform a single painter to produce a new painter. For example, `flip-vert` takes a painter and produces a painter that draws its image upside-down, and `flip-horiz` produces a painter that draws the original painter's image left-to-right reversed.




Figure 2.12: Creating a complex figure, starting from the `wave` painter of Figure 2.10. 建立複雜 ê ang 仔，伊 ê 基礎是 Figure 2.10 ê `wave` 畫圖器。

Beh 組合圖片，lán 使用對有 ê 畫圖器起造新 ê 畫圖器 ê chē-chē 操作。比論講，`beside` 操作 thèh 兩个畫圖器，產出新 ê 複合畫圖器，伊畫頭一个畫圖器 ê 圖 ê 圖佇框殼 ê 倒半 pêng，koh 畫第二个畫圖器 ê 圖佇框殼 ê 正半 pêng。Siâng 款，`below` thèh 兩个畫圖器，產出新 ê 複合畫圖器，伊畫頭一个畫圖器 ê 圖佇第二个 ê 圖下底。一寡操作轉換孤个畫圖器，來生成新 ê 畫圖器。舉例，`flip-vert` thèh 一个畫圖器，產出 kā 伊 ê 圖頂下倒反來畫 ê 畫圖器，`flip-horiz` 產出 kā 原來 ê 畫圖器 ê 圖左右倒反來畫 ê 畫圖器。

Figure 2.12 shows the drawing of a painter called `wave4` that is built up in two stages starting from `wave`:

Figure 2.12展示號做 `wave4` ê 畫圖器所畫 ê，伊起造佇對 `wave` 開始 ê 兩个階段：

```
(define wave2 (beside wave (flip-vert wave)))
(define wave4 (below wave2 wave2))
```

In building up a complex image in this manner we are exploiting the fact that painters are closed under the language's means of combination. The `beside` or `below` of two painters is itself a painter; therefore, we can use it as an element in making more complex painters. As with building up list structure using `cons`, the closure of our data under the means of combina-

tion is crucial to the ability to create complex structures while using only a few operations.

用 chit 款手路起造複雜 ê 圖 ê 時陣，lán leh 利用畫圖器佇語言 ê 組合手段下底包起來 ê 事實。兩个畫圖器 ê `beside` iah 是 `below` 家 kī 嘛是畫圖器；因此，lán ē 當 kā 伊用做製造較複雜 ê 畫圖器 ê 元素。像用 `cons` 起造列單結構 kâng 款，lán 佇組合手段下底 ê 資料閉包，對佇用少少操作 ê 時，建立複雜結構 ê 能力蓋重要。

Once we can combine painters, we would like to be able to abstract typical patterns of combining painters. We will implement the painter operations as Scheme procedures. This means that we don't need a special abstraction mechanism in the picture language: Since the means of combination are ordinary Scheme procedures, we automatically have the capability to do anything with painter operations that we can do with procedures. For example, we can abstract the pattern in `wave4` as

Lán 若 ē 當建立閉包，lán 就想 beh ē 當抽象化典型 ê 組合畫圖器 ê 模式。Lán ē kā 畫圖器操作實做做 Scheme 程序。Che 意思是 lán 佇圖片語言，無需要特殊 ê 抽象機制：因為組合手段是一般 ê Scheme 程序，lán 就自動有能力用畫圖器，行任何 lán ē 當用程序做 ê。舉例，lán ē 當 kā `wave4` ê 模式抽象做

```
(define (flipped-pairs painter)
  (let ((painter2 (beside painter (flip-vert painter))))
    (below painter2 painter2)))
```

and define `wave4` as an instance of this pattern:
koh kā `wave4` 定義做下 kha ê 模式 ê 實例：

```
(define wave4 (flipped-pairs wave))
```

We can also define recursive operations. Here's one that makes painters split and branch towards the right as shown in Figure 2.13 and Figure 2.14:
Lán mā ē 當定義遞迴操作。予畫圖器向正 pêng 分開 koh 分 oe ê 佇 chia，顯示佇 Figure 2.13：




Figure 2.13: Recursive plans for `right-split` and `corner-split`.
`right-split` kap `corner-split` ê 遞迴計畫。

```
(define (right-split painter n)
  (if (= n 0)
      painter
      (let ((smaller (right-split painter (- n 1))))
        (beside painter (below smaller smaller)))))
```

We can produce balanced patterns by branching upwards as well as towards the right (see exercise Exercise 2.44 and figures Figure 2.13 and Figure 2.14): Lán 通用向面頂 kap 向正 pêng 分 oe，來產出平衡 ê 模式（看練習 Exercise 2.44 kap 圖片 Figure 2.13 kap Figure 2.14）：

```
(define (corner-split painter n)
  (if (= n 0)
      painter
      (let ((up (up-split painter (- n 1))))
```

```
            (right (right-split painter (- n 1))))
          (let ((top-left (beside up up))
                (bottom-right (below right right))
                (corner (corner-split painter (- n 1))))
            (beside (below painter top-left)
                    (below bottom-right corner))))))
```

By placing four copies of a `corner-split` appropriately, we obtain a pattern called `square-limit`, whose application to `wave` and `rogers` is shown in Figure 2.9:
倚靠適當 khn̄g `corner-split` ê 四份 khóo-pih，lán thèh 著號做 `square-limit` ê 模式，伊應用 kàu `wave` kap `rogers` ê 結果顯示佇 Figure 2.9：


```
(define (square-limit painter n)
  (let ((quarter (corner-split painter n)))
    (let ((half (beside (flip-horiz quarter) quarter)))
      (below (flip-vert half) half))))
```

Exercise 2.44: Define the procedure `up-split` used by `corner-split`. It is similar to `right-split`, except that it switches the roles of `below` and `beside`.

Exercise 2.44: 定義予 `corner-split` 用 ê 程序 `up-split`。伊 kap `right-split` 相 siâng，除了伊 kā `below` kap `beside` ê 角色相換。

Higher-order operations koân 階操作


In addition to abstracting patterns of combining painters, we can work at a higher level, abstracting patterns of combining painter operations. That is, we can view the painter operations as elements to manipulate and can write means




(right-split wave 4)



(right-split rogers 4)



(corner-split wave 4)



(corner-split rogers 4)

Figure 2.14: The recursive operations `right-split` and `corner-split` applied to the painters `wave` and `rogers`. Combining four `corner-split` figures produces symmetric `square-limit` designs as shown in Figure 2.9. 遞迴操作 `right-split` kap `corner-split` 應用 kàu 畫圖器 `wave` kap `rogers` ê 結果。組合四幅 `corner-split` ê 圖片，ē 產出對 thīn ê `square-limit` 設計，像佇 Figure 2.9 所展示 ê。

of combination for these elements—procedures that take painter operations as arguments and create new painter operations.
除了抽象化組合畫圖器 ê 模式，lán 通佇較 koân ê 水準，行抽象化組合畫圖器 ê 模式 ê 操作。就是，lán 通 kā 畫圖器操作看做元素來操作，而且 ē 當寫組合 chiah ê 元素 ê 手段——thèh 畫圖器操作做引數，koh 建立新 ê 畫圖器操作 ê 程序。

For example, `flipped-pairs` and `square-limit` each arrange four copies of a painter's image in a square pattern; they differ only in how they orient the copies. One way to abstract this pattern of painter combination is with the following procedure, which takes four one-argument painter operations and produces a painter operation that transforms a given painter with those four operations and arranges the results in a square. `tl`, `tr`, `bl`, and `br` are the transformations to apply to the top left copy, the top right copy, the bottom left copy, and the bottom right copy, respectively.

比論講，`flipped-pairs` kap `square-limit` 逐 ê 排列畫圖器 ê 圖 ê 四份 khóo-pih ，做一个正四角形 ê 模式；in kan-ta 佇確定 khóo-pih ê 方向無 kâng。一个抽象 chit ê 畫圖器組合 ê 模式 ê 方法就是用下 kha ê 程序，伊 thèh 四个單引數畫圖器 ê 操作，產出一个畫圖器 ê 操作，chit ê 畫圖器 ê 操作用 chit 四个操作轉換輸入 ê 畫圖器，排列結果做正四角形。`tl`、`tr`、`bl` kap`br` 分別是應用 kàu 倒 pêng 頂 koân、正 pêng 頂 koân、倒 pêng 下底 kap 正 pêng 下底 ê khóo-pih ê 轉換。

```
(define (square-of-four tl tr bl br)
  (lambda (painter)
    (let ((top (beside (tl painter) (tr painter)))
          (bottom (beside (bl painter) (br painter))))
      (below bottom top))))
```

Then `flipped-pairs` can be defined in terms of `square-of-four` as follows:[46]

[46] Equivalently, we could write

了後 `flipped-pairs` ē 當用 `square-of-four` 定義若下 kha：[47]

```
(define (flipped-pairs painter)
  (let ((combine4 (square-of-four identity flip-vert
                                  identity flip-vert)))
    (combine4 painter)))
```

and `square-limit` can be expressed as[48]
而且 `square-limit` ē 當表示做下 kha ê[49]

```
(define (square-limit painter n)
  (let ((combine4 (square-of-four flip-horiz identity
                                  rotate180 flip-vert)))
    (combine4 (corner-split painter n))))
```

Exercise 2.45: `right-split` and `up-split` can be expressed as instances of a general splitting operation. Define a procedure `split` with the property that evaluating

Exercise 2.45: `right-split` kap `up-split` ē 當用一般

```
(define flipped-pairs
  (square-of-four identity flip-vert identity flip-vert))
```

[47] Kâng 款，lán 通寫

```
(define flipped-pairs
  (square-of-four identity flip-vert identity flip-vert))
```

[48] `rotate180` rotates a painter by 180 degrees (see Exercise 2.50). Instead of `rotate180` we could say `(compose flip-vert flip-horiz)`, using the `compose` procedure from Exercise 1.42.

[49] `rotate180` 轉 sèh 畫圖器 180 度(看 Exercise 2.50)。除了 `rotate180`，lán mā ē 當 thèh ùi Exercise 1.42 來 ê `compose` 程序，kā 講做 `(compose flip-vert flip-horiz)`。

ê 分割操作 ê 實例來表示。定義程序 `split`，伊有算下 kha ê 程式碼 ê 性質：

```
(define right-split (split beside below))
(define up-split (split below beside))
```

produces procedures `right-split` and `up-split` with the same behaviors as the ones already defined.

Frames 框殼

Before we can show how to implement painters and their means of combination, we must first consider frames. A frame can be described by three vectors—an origin vector and two edge vectors. The origin vector specifies the offset of the frame's origin from some absolute origin in the plane, and the edge vectors specify the offsets of the frame's corners from its origin. If the edges are perpendicular, the frame will be rectangular. Otherwise the frame will be a more general parallelogram.

佇 lán ē 當展示 án-nóa 實做畫圖器，kap in ê 組合手段進前，lán 著先考慮框殼。框殼 ē 當用三个向量表示——一个原點向量 (origin vector) kap 兩个邊向量 (edge vector)。原點向量指定對平面 ê 絕對原點 kàu 框殼 ê 偏差量，邊向量指定原點 kàu 框 á 角 ê 偏差量。若是邊是垂直 ê，框殼 ē 是長方形。Ah̍ 無框殼 ē 是 koh 較一般 ê 平行四角形。

Figure 2.15 shows a frame and its associated vectors. In accordance with data abstraction, we need not be specific yet about how frames are represented, other than to say that there is a constructor `make-frame`, which takes three vectors and produces a frame, and three corresponding selectors `origin-frame`, `edge1-frame`, and `edge2-frame` (see Exercise 2.47).

Figure 2.15 展示一个框殼 kap 相關 ê 向量。照資料抽象化，lán 猶原無需要指定框殼 án-nóa 抽象化，kan-ta 講有建構器 `make-frame`，伊




Figure 2.15: A frame is described by three vectors — an origin and two edges. 框殼由三个向量描述——一个原點 ê kap 兩个邊 ê。

thèh 三个向量，產出一个框殼，kap 三个對應 ê 選擇器 `origin-frame`、`edge1-frame` kap `edge2-frame`（看 Exercise 2.47）。

We will use coordinates in the unit square $(0 \leq x, y \leq 1)$ to specify images. With each frame, we associate a *frame coordinate map*, which will be used to shift and scale images to fit the frame. The map transforms the unit square into the frame by mapping the vector $\mathbf{v} = (x, y)$ to the vector sum

Lán ē 用單位正四角形 $(0 \leq x, y \leq 1)$ ê 座標來指定圖片。Lán kā 逐 ê 框殼 kap 框殼座標地圖 (frame coordinate map) 相關聯，框殼座標地圖 ē thèh 來 kā 圖片 sóa 位 kap chhun-kiu 圖片，來符合框殼 ê 款。Map 用 kā $\mathbf{v} = (x, y)$

map kàu 下 kha ê 向量和，來 kā 單位正四角形轉換做框殼：

$$\mathrm{Origin}(\mathrm{Frame}) + x \cdot \mathrm{Edge}_1(\mathrm{Frame}) + y \cdot \mathrm{Edge}_2(\mathrm{Frame}).$$

For example, (0, 0) is mapped to the origin of the frame, (1, 1) to the vertex diagonally opposite the origin, and (0.5, 0.5) to the center of the frame. We can create a frame's coordinate map with the following procedure:[50]
比論講，(0, 0) 受 map kàu 框殼 ê 原點，(1, 1) 受 map kàu 原點 ê chhoah 對角 ê 點，(0.5, 0.5) 受 map kàu 框殼 ê 中心。Lán 通用下 kha ê 程序，建立框殼 ê 座標 map：[51]

```
(define (frame-coord-map frame)
  (lambda (v)
    (add-vect
     (origin-frame frame)
     (add-vect (scale-vect (xcor-vect v) (edge1-frame frame))
               (scale-vect (ycor-vect v) (edge2-frame frame))
```

Observe that applying `frame-coord-map` to a frame returns a procedure that, given a vector, returns a vector. If the argument vector is in the unit square, the result vector will be in the frame. For example,
觀察 kā `frame-coord-map` 應用 kàu 框殼，就 ē 傳轉一个程序，伊輸入一个向量，傳轉一个向量。若是引數向量佇單位正四角形內底，輸出 ê 向量 ē 佇框殼內底。舉例，

```
((frame-coord-map a-frame) (make-vect 0 0))
```

[50] `frame-coord-map` uses the vector operations described in Exercise 2.46 below, which we assume have been implemented using some representation for vectors. Because of data abstraction, it doesn't matter what this vector representation is, so long as the vector operations behave correctly.

[51] `frame-coord-map` 用下 kha Exercise 2.46 ê 描述 ê 向量操作，lán 設使伊有予 lâng 用一款向量 ê 表示法來實做。因為資料抽象化，只要向量操作 ê 行為正確，向量表示法 choáⁿ 樣 lóng 無要緊。

returns the same vector as
傳轉 kap 下 kha ê kâng 款 ê 向量

```
(origin-frame a-frame)
```

Exercise 2.46: A two-dimensional vector **v** running from the origin to a point can be represented as a pair consisting of an x-coordinate and a y-coordinate. Implement a data abstraction for vectors by giving a constructor `make-vect` and corresponding selectors `xcor-vect` and `ycor-vect`. In terms of your selectors and constructor, implement procedures `add-vect`, `sub-vect`, and `scale-vect` that perform the operations vector addition, vector subtraction, and multiplying a vector by a scalar:

Exercise 2.46: 對原點 kàu 某物點 ê 二度向量 **v**，通表示做包含 x 座標 kap y 座標 ê 對。請用提供建構器 `make-vect` kap 對應 ê 揀選器 `xcor-vect` kap `ycor-vect`，來實做向量 ê 資料抽象化。Koh 用汝 ê 揀選器 kap 建構器，實做程序 `add-vect`、`sub-vect` kap `scale-vect`，in 個別行向量加法、減法，以及 kā 向量用純量 (scalar) 乘 ê 操作：

$$\begin{aligned}(x_1, y_1) + (x_2, y_2) &= (x_1 + x_2, y_1 + y_2),\\ (x_1, y_1) - (x_2, y_2) &= (x_1 - x_2, y_1 - y_2),\\ s \cdot (x, y) &= (sx, sy).\end{aligned}$$

Exercise 2.47: Here are two possible constructors for frames:

Exercise 2.47: Chia 有兩个可能 ê 框殼建構器：

```
(define (make-frame origin edge1 edge2)
  (list origin edge1 edge2))
(define (make-frame origin edge1 edge2)
```

```
(cons origin (cons edge1 edge2)))
```

For each constructor supply the appropriate selectors to produce an implementation for frames.

請 kā 逐 ê 建構器，提供適當 ê 揀選器來產出框殼 ê 實做。

Painters 畫圖器

A painter is represented as a procedure that, given a frame as argument, draws a particular image shifted and scaled to fit the frame. That is to say, if `p` is a painter and `f` is a frame, then we produce `p`'s image in `f` by calling `p` with `f` as argument.
畫圖器是由程序表示，chit ê 程序掠框殼做引數，畫特定 ê 圖，koh 用 sóa 位 kap chhun-kiu ê 方式，予伊符合框殼。Mā 就是講，若 `p` 是畫圖器，`f` 是框殼，lán 用呼叫 `p` kap 引數 `f`，就產出 tàu 入去 `f` ê，`p` ê 圖片。

The details of how primitive painters are implemented depend on the particular characteristics of the graphics system and the type of image to be drawn. For instance, suppose we have a procedure `draw-line` that draws a line on the screen between two specified points. Then we can create painters for line drawings, such as the `wave` painter in Figure 2.10, from lists of line segments as follows:[52]

基礎 ê 畫圖器實做方法 ê 詳細，倚靠佇圖形系統 ê 特定特徵 kap beh 畫 ê 圖 ê 款。舉例，假使 lán 有程序 `draw-line`，伊佇螢幕頂畫一條連接特定兩點 ê 線。了後 lán 就通對線段 ê 列單來建立畫線 ê 畫圖器，比如佇 Figure 2.10 ê `wave` 畫圖器，若下 kha：[53]

```
(define (segments->painter segment-list)
```

[52] `segments->painter` uses the representation for line segments described in Exercise 2.48 below. It also uses the `for-each` procedure described in Exercise 2.23.

[53] `segments->painter` 用佇下 kha Exercise 2.48 描述 ê 線段 ê 表示法。伊 mā 用佇 Exercise 2.23 描述 ê `for-each` 程序。

```
(lambda (frame)
  (for-each
   (lambda (segment)
     (draw-line
      ((frame-coord-map frame)
       (start-segment segment))
      ((frame-coord-map frame)
       (end-segment segment))))
   segment-list)))
```

The segments are given using coordinates with respect to the unit square. For each segment in the list, the painter transforms the segment endpoints with the frame coordinate map and draws a line between the transformed points.
線段由用單位正四角形做基準 ê 座標提供。對列單內 ê 逐線段，畫圖器用框殼 ê 座標 map，來轉換線段 ê 端點，而且佇轉換過 ê 點之間 ê 畫連線。

Representing painters as procedures erects a powerful abstraction barrier in the picture language. We can create and intermix all sorts of primitive painters, based on a variety of graphics capabilities. The details of their implementation do not matter. Any procedure can serve as a painter, provided that it takes a frame as argument and draws something scaled to fit the frame.[54]

Kā 畫圖器表達做程序，ē 佇圖片語言 chhāi 起有能力 ê 抽象化障礙。Lán ē 當佇 khiā 起佇 chē 樣 ê 圖形能力，來建立 kap 相濫逐種 ê 基礎畫圖器。In

[54]For example, the `rogers` painter of Figure 2.11 was constructed from a gray-level image. For each point in a given frame, the `rogers` painter determines the point in the image that is mapped to it under the frame coordinate map, and shades it accordingly. By allowing different types of painters, we are capitalizing on the abstract data idea discussed in Section 2.1.3, where we argued that a rational-number representation could be anything at all that satisfies an appropriate condition. Here we're using the fact that a painter can be implemented in any way at all, so long as it draws something in the designated frame. Section 2.1.3 also showed how pairs could be implemented as procedures. Painters are our second example of a procedural representation for data.

ê 實做詳細無要緊。佇「程序通 thèh 框殼做引數，畫一寡 chhun-kiu 出來 ê 影像，來符合框殼」ê 條件之下，逐 ê 程序通當做畫圖器。[55]

Exercise 2.48: A directed line segment in the plane can be represented as a pair of vectors—the vector running from the origin to the start-point of the segment, and the vector running from the origin to the end-point of the segment. Use your vector representation from Exercise 2.46 to define a representation for segments with a constructor `make-segment` and selectors `start-segment` and `end-segment`.

Exercise 2.48: 平面頂 ê 有向線段 ē 當用向量 ê 對表示——對原點 kàu 線段 ê 起點 ê 向量，以及對線段 ê 起點 kàu 線段 ê 終點 ê。用汝佇 Exercise 2.46 ê 向量表示法來定義線段表示法，以及建構器 `make-segment` kap 揀選器 `start-segment` hām `end-segment`。

Exercise 2.49: Use `segments->painter` to define the following primitive painters:

Exercise 2.49: 用 `segments->painter` 來定義下 kha ê 基礎畫圖器：

a. The painter that draws the outline of the designated frame.
畫指定框殼 ê 框仔 ê 畫圖器。

[55] 比論講，Figure 2.11 ê `rogers` 畫圖器是對 *phú* 色層 (grey-level) ê 影像建立 ê。對框殼內底 ê 逐點，`rogers` 畫圖器決定佇框殼座標 map 之下，受 map kàu 伊 ê，影像內底 ê 點，然後適當 kā 影畫起去。用允准無 kâng 款畫圖器，lán leh 利用佇 Section 2.1.3 討論 ê 抽象化資料 ê 想法，其中 lán 論證有理數 ē 當是符合適當條件 ê 所有物件。佇 chia lán teh 用 chit ê 事實，就是畫圖器 ē 當用逐款手段實做，只要伊佇指定 ê 框殼畫物件。Section 2.1.3 mā 展示對 án-nóa 實做做程序。畫圖器是 lán 第二个用程序表示資料 ê 例。

b. The painter that draws an “X” by connecting opposite corners of the frame.
用 kā 框殼 ê 一雙 chhoảh 對角連線，來畫「X」形 ê 畫圖器。

c. The painter that draws a diamond shape by connecting the midpoints of the sides of the frame.
用相接框殼四邊 ê 中點，來畫出麻芳 *chhoảh* (diamond shape) ê 畫圖器。

d. The `wave` painter.
`wave` 畫圖器。

Transforming and combining painters 變換 kap 組合畫圖器

An operation on painters (such as `flip-vert` or `beside`) works by creating a painter that invokes the original painters with respect to frames derived from the argument frame. Thus, for example, `flip-vert` doesn't have to know how a painter works in order to flip it—it just has to know how to turn a frame upside down: The flipped painter just uses the original painter, but in the inverted frame.
佇畫圖器面頂 ê 操作（比如 `flip-vert` iah 是 `beside`）是用建立一个畫圖器來行，chit ê 畫圖器照派生對引數框殼 ê 框殼，呼叫原本 ê 畫圖器操作。因此，比論講，`flip-vert` beh péng 一个畫圖器，毋免知影伊 án-nóa 運作——伊 kan-ta 著需要知影 án-nóa kā 框殼頂下倒反：péng 過 ê 畫圖器 kan-ta 使用原底 ê 畫圖器，毋 koh 佇倒反 ê 框殼。

Painter operations are based on the procedure `transform-painter`, which takes as arguments a painter and information on how to transform a frame and produces a new painter. The transformed painter, when called on a frame, transforms the frame and calls the original painter on the transformed frame. The arguments to `transform-painter` are points (represented

as vectors) that specify the corners of the new frame: When mapped into the frame, the first point specifies the new frame's origin and the other two specify the ends of its edge vectors. Thus, arguments within the unit square specify a frame contained within the original frame.

印刷器 (printer) 操作是 chhāi 佇程序 `transform-painter` 頂，伊 thèh 印刷器 kap án-nóa 轉換框殼 ê 資訊當做引數，傳轉一个新 ê 印刷器。變換 ê 印刷器，當佇框殼頂呼叫 ê 時，ē 轉換框殼，koh 佇轉換過 ê 框殼呼叫原底 ê 印刷器。傳予 `transform-painter` ê 引數是一寡點（用向量表示），in 指定新 ê 框殼 ê 角：當 map kàu 新 ê 框殼 ê 時，頭一个點指定新 ê 框殼 ê 原點，另外兩个指定伊 ê 邊向量 ê 終點。就 án-ne，佇單位正四角形內底 ê 引數，指定包含佇原底 ê 框殼內底 ê 框殼。

```
(define (transform-painter painter origin corner1 corner2)
  (lambda (frame)
    (let ((m (frame-coord-map frame)))
      (let ((new-origin (m origin)))
        (painter (make-frame
                  new-origin
                  (sub-vect (m corner1) new-origin)
                  (sub-vect (m corner2) new-origin)))))))
```

Here's how to flip painter images vertically:
Kā 印刷機 ê 圖片頂下對反 ê 方法佇 chia：

```
(define (flip-vert painter)
  (transform-painter painter
                     (make-vect 0.0 1.0)    ;new origin
                     (make-vect 1.0 1.0)    ; new end of
edge1
                     (make-vect 0.0 0.0)))  ; new end of
edge2
```

Using `transform-painter`, we can easily define new transformations. For example, we can define a painter that shrinks its image to the upper-right

quarter of the frame it is given:
用 `transform-painter`，lán 通容易定義新 ê 轉換。舉例，lán ē 當定義一个印刷機，伊收縮伊 ê 影像 kàu 指定框殼 ê 正爿頂懸 ê，四分一 ê sài-suh：

```
(define (shrink-to-upper-right painter)
  (transform-painter
   painter (make-vect 0.5 0.5)
   (make-vect 1.0 0.5) (make-vect 0.5 1.0)))
```

Other transformations rotate images counterclockwise by 90 degrees[56]
其他 kā 影像反時針倒 sèh 90 圖 ê 轉換[57]

```
(define (rotate90 painter)
  (transform-painter painter
                     (make-vect 1.0 0.0)
                     (make-vect 1.0 1.0)
                     (make-vect 0.0 0.0)))
```

or squash images towards the center of the frame:[58]
或者是 kā 影像 seh 入去框殼 ê 中央：[59]

```
(define (squash-inwards painter)
  (transform-painter painter
                     (make-vect 0.0 0.0)
                     (make-vect 0.65 0.35)
                     (make-vect 0.35 0.65)))
```

[56] `rotate90` is a pure rotation only for square frames, because it also stretches and shrinks the image to fit into the rotated frame.

[57] `rotate90` 是正四角形 ê 框殼專用 ê 純 ê 轉 sèh，因為伊 iā giú 開 kap 縮小影像來符合轉 sèh 過 ê 框殼。

[58] The diamond-shaped images in Figure 2.10 and Figure 2.11 were created with `squash-inwards` applied to `wave` and `rogers`.

[59] 佇Figure 2.10 kap Figure 2.11 ê 麻芳 chhoáh ê 影像，是由 `squash-inwards` 應用 kàu `wave` kap `rogers` 所建立 ê。

Frame transformation is also the key to defining means of combining two or more painters. The `beside` procedure, for example, takes two painters, transforms them to paint in the left and right halves of an argument frame respectively, and produces a new, compound painter. When the compound painter is given a frame, it calls the first transformed painter to paint in the left half of the frame and calls the second transformed painter to paint in the right half of the frame:
框殼轉換 mā 是定義組合兩个以上 ê 畫圖器 ê 手段 ê 關鍵。比論講，`beside` 程序 thèh 兩个畫圖器，轉換 in 來個別佇引數框殼 ê 倒半 pêng kap 正半 pêng 畫，koh 產出新 ê，複合 ê 畫圖器。當複合畫圖器收著框殼 ê 時，伊呼叫頭一个受轉換 ê 畫圖器，佇框殼 ê 倒半 pêng 畫，koh 呼叫第二个受轉換 ê 畫圖器，佇框殼 ê 正半 pêng 畫：

```
(define (beside painter1 painter2)
  (let ((split-point (make-vect 0.5 0.0)))
    (let ((paint-left
           (transform-painter
            painter1
            (make-vect 0.0 0.0)
            split-point
            (make-vect 0.0 1.0)))
          (paint-right
           (transform-painter
            painter2
            split-point
            (make-vect 1.0 0.0)
            (make-vect 0.5 1.0))))
      (lambda (frame)
        (paint-left frame)
        (paint-right frame)))))
```

Observe how the painter data abstraction, and in particular the representation of painters as procedures, makes `beside` easy to implement. The `beside`

procedure need not know anything about the details of the component painters other than that each painter will draw something in its designated frame.
觀察畫圖器 ê 資料抽象化，特別是 kā 畫圖器當做函數 ê 表示，án-nóa 予 `beside` chiah 快實做。`beside` 程序除了逐 ê 畫圖器 ē 佇伊所指定 ê 框殼畫物件以外，無需要知影一切複合畫圖器 ê 詳細。

> **Exercise 2.50:** Define the transformation `flip-horiz`, which flips painters horizontally, and transformations that rotate painters counterclockwise by 180 degrees and 270 degrees.
>
> **Exercise 2.50:** 定義 kā 畫圖器左右對反 ê 轉換 `flip-horiz`，以及 kā 畫圖器逆向（反時針）轉 sèh 180 度 kap 270 度 ê 轉換。

> **Exercise 2.51:** Define the `below` operation for painters. `below` takes two painters as arguments. The resulting painter, given a frame, draws with the first painter in the bottom of the frame and with the second painter in the top. Define `below` in two different ways—first by writing a procedure that is analogous to the `beside` procedure given above, and again in terms of `beside` and suitable rotation operations (from Exercise 2.50).
>
> **Exercise 2.51:** 定義予畫圖器 ê `below` 操作。`below` thèh 兩个畫圖器當做引數。伊輸出 ê 畫圖器，若指定一个框殼，會佇框殼 ê 底用頭一个畫圖器畫圖，佇框殼頂用第二个畫圖。用兩款無 kâng ê 方法定義 `below`——代先寫 kap 面頂 `beside` 相 siâng ê 程序，然後用 `beside` kap (Exercise 2.50 ê) 適當 ê 轉 sèh 操作來寫。

Levels of language for robust design 勇健設計 ê 語言水準

The picture language exercises some of the critical ideas we've introduced about abstraction with procedures and data. The fundamental data abstrac-

tions, painters, are implemented using procedural representations, which enables the language to handle different basic drawing capabilities in a uniform way. The means of combination satisfy the closure property, which permits us to easily build up complex designs. Finally, all the tools for abstracting procedures are available to us for abstracting means of combination for painters. 圖片語言運用 lán 捌紹介關係用程序 kap 資料來抽象化 ê 關鍵觀念。基本 ê 資料抽象化，畫圖器，是用程序表示實做 ê，伊予 chit 个語言佇統一 ê 方式，處理無 kâng ê 基礎畫圖能力。組合 ê 手段滿足閉包特性，允准 lán 較快起造複雜 ê 設計。落尾，所有 thèh 來抽象化程序 ê 家私 lán lóng ē 當用，做抽象化畫圖器組合 ê 手段。

We have also obtained a glimpse of another crucial idea about languages and program design. This is the approach of *stratified design*, the notion that a complex system should be structured as a sequence of levels that are described using a sequence of languages. Each level is constructed by combining parts that are regarded as primitive at that level, and the parts constructed at each level are used as primitives at the next level. The language used at each level of a stratified design has primitives, means of combination, and means of abstraction appropriate to that level of detail.

Lán mā 有 kā 關係語言 kap 程式設計 ê 另外一个重大 ê 概念影一下。就是分層設計 (stratified design)ê 方法，分層設計就是複雜 ê 系統應該愛結構化做層級 ê 列 ê 觀念，其中層級 ê 列用語言 ê 列描述。逐 ê 層級是由 kā 佇 chit 層掠做是基礎要件 (primitives) ê 部件組合所建構，而且建構佇逐層 ê 部件，佇後一層當做基礎要件來使用。佇分層設計 ê 每一層所用 ê 語言，有基礎要件、組合手段，kap 適合 chit 个層級 ê 詳細 ê 抽象手段。

Stratified design pervades the engineering of complex systems. For example, in computer engineering, resistors and transistors are combined (and described using a language of analog circuits) to produce parts such as and-gates and or-gates, which form the primitives of a language for digital-circuit

design.[60] These parts are combined to build processors, bus structures, and memory systems, which are in turn combined to form computers, using languages appropriate to computer architecture. Computers are combined to form distributed systems, using languages appropriate for describing network interconnections, and so on.

分層設計充滿佇複雜系統 ê 工程。比論講，佇電腦工程，電阻 kap 電晶體受組合（koh 用類比電路 ê 語言）來產出像 *AND* 門 (and-gates) kap *OR* 門 (or-gates) 部件，伊成形數位電路 ê 語言[61] ê 基礎要件。Chiah ê 部件受組合，用適合計算機結構 ê 語言，來起造計算機。電腦受組合，用適合描述網路相連結 ê 語言，來成形分散式系統，等等。

As a tiny example of stratification, our picture language uses primitive elements (primitive painters) that are created using a language that specifies points and lines to provide the lists of line segments for `segments->painter`, or the shading details for a painter like `rogers`. The bulk of our description of the picture language focused on combining these primitives, using geometric combiners such as `beside` and `below`. We also worked at a higher level, regarding `beside` and `below` as primitives to be manipulated in a language whose operations, such as `square-of-four`, capture common patterns of combining geometric combiners.

做著細細 ê 分層 ê 例，lán ê 圖片語言使用基礎要素（基礎畫圖器），in 是用一款語言創造，chit 款語言指定點 kap 線，成做線段 ê 列單，提供予 `segments->painter` ê，iah 是成做陰影 ê 詳細，予像 `rogers` ê 畫圖器。Lán 對圖片語言 ê 大量描述專注佇組合 chiah ê 要素，使用親像 `beside` kap `below` ê 幾何 ê 組合器。Lán mā 佇較 koân ê 層次操作，kā `beside` kap `below` 當做是通佇一種語言操作 ê 基礎要素，chit ê 語言 ê 操作，比如 `square-of-four`，表現 kā 幾何組合器組合 ê 一般模式。

Stratified design helps make programs *robust*, that is, it makes it likely that

[60] Section 3.3.4 describes one such language.

[61] Section 3.3.4 描述一个 chit 款 ê 語言。

small changes in a specification will require correspondingly small changes in the program. For instance, suppose we wanted to change the image based on `wave` shown in Figure 2.9. We could work at the lowest level to change the detailed appearance of the `wave` element; we could work at the middle level to change the way `corner-split` replicates the `wave`; we could work at the highest level to change how `square-limit` arranges the four copies of the corner. In general, each level of a stratified design provides a different vocabulary for expressing the characteristics of the system, and a different kind of ability to change it.

分層設計幫 chān 予程式粗勇 (robust)，就是伊予規格 ê 小寡改變，ē 需要小寡改變對應 ê 程式成做可能。比論講，假使 lán beh 改變起造佇Figure 2.9 ê `wave` 頂 ê 圖。Lán 通佇上底層操作來改 `wave` 要素 ê 詳細 ê 外觀；lán 通佇中層操作來改變 `corner-split` 重覆 `wave` ê 方法；lán 通佇上頂層來改 `square-limit` 安排角 ê 四个 khóo-pih ê 方法。一般來講，分層設計 ê 逐層提供無 kâng ê 詞語來表示系統 ê 特徵，以及無 kâng 款 ê，kā 伊改變 ê 能力。

> **Exercise 2.52:** Make changes to the square limit of `wave` shown in Figure 2.9 by working at each of the levels described above. In particular:
>
> **Exercise 2.52:** 用佇頂懸描述 ê 逐層操作，來改變佇 Figure 2.9 展示 ê `wave` 正四角形限制 (square limit)。特別是：

a. Add some segments to the primitive `wave` painter of Exercise 2.49 (to add a smile, for example).
加添一寡線段 kàu Exercise 2.49 ê 基礎要件 `wave` 畫圖器（舉例：加笑面）

b. Change the pattern constructed by `corner-split` (for example, by using only one copy of the `up-split` and `right-split` images instead of two).

改變 `corner-split` 所建構 ê 模式（舉例，用 kan-ta 改 `up-split` kap `right-split` ê 一个 khóo-pih，毋是改兩个）

c. Modify the version of `square-limit` that uses `square-of-four` so as to assemble the corners in a different pattern. (For example, you might make the big Mr. Rogers look outward from each corner of the square.)

改 `square-limit` ê 版本，伊用 `square-of-four`，來用無 kâng ê 模式 kā 角組立。（舉例，汝可能予 Rogers 大先生，自正四角形 ê 逐个角看出外面。）

2.3 Symbolic Data 符號資料

All the compound data objects we have used so far were constructed ultimately from numbers. In this section we extend the representational capability of our language by introducing the ability to work with arbitrary symbols as data. Lán 目前為止所用 ê 逐个複合資料，最終 lóng 是由數起造 ê。佇本節 lán 用引入 kā 任何符號 (symbol) 當做資料操作 ê 能力，來擴充 lán 語言 ê 表達能力。

2.3.1 Quotation 引用

If we can form compound data using symbols, we can have lists such as
Lán 若會使用符號組合組成複合資料，lán 通有像下底 ê 列單：

```
(a b c d)
(23 45 17)
((Norah 12) (Molly 9) (Anna 7) (Lauren 6) (Charlotte 4))
```

Lists containing symbols can look just like the expressions of our language:
包含符號 ê 列單通看起來像 lán ê 語言 ê 表達式：

```
(* (+ 23 45)
   (+ x 9))
(define (fact n)
  (if (= n 1) 1 (* n (fact (- n 1)))))
```

In order to manipulate symbols we need a new element in our language: the ability to *quote* a data object. Suppose we want to construct the list `(a b)`. We can't accomplish this with `(list a b)`, because this expression constructs a list of the *values* of `a` and `b` rather than the symbols themselves. This issue is well known in the context of natural languages, where words and sentences may be regarded either as semantic entities or as character strings (syntactic entities). The common practice in natural languages is to use quotation marks to indicate that a word or a sentence is to be treated literally as a string of characters. For instance, the first letter of "John" is clearly "J." If we tell somebody "say your name aloud," we expect to hear that person's name. However, if we tell somebody "say 'your name' aloud," we expect to hear the words "your name." Note that we are forced to nest quotation marks to describe what somebody else might say.[62]

為著操作符號，lán 佇 lán ê 語言需要一个新 ê 要素：引用 (quote) 資料物件 ê 能力。假使 lán 想 beh 建構列單 `(a b)`。Lán bōe 當用 `(list a b)` 完成 che，因為 chit ê 表達式建構一个 `a` kap `b` ê 值 (values) ê，反轉毋是符

[62] Allowing quotation in a language wreaks havoc with the ability to reason about the language in simple terms, because it destroys the notion that equals can be substituted for equals. For example, three is one plus two, but the word "three" is not the phrase "one plus two." Quotation is powerful because it gives us a way to build expressions that manipulate other expressions (as we will see when we write an interpreter in Chapter 4). But allowing statements in a language that talk about other statements in that language makes it very difficult to maintain any coherent principle of what "equals can be substituted for equals" should mean. For example, if we know that the evening star is the morning star, then from the statement "the evening star is Venus" we can deduce "the morning star is Venus." However, given that "John knows that the evening star is Venus" we cannot infer that "John knows that the morning star is Venus."

號家己 ê 列單。Chit ê 議題佇自然語言誠出名，其中字 kap 句 ē 當掠做語義實體或者是字元 ê 串 (string) （句法實體）。佇自然語言，通常 ê 作法就是用引號來指示一个詞 iah 是句敢愛直接當做字元 ê 串。譬論講，「John」ê 頭一个字母的確是「J.」。若準 lán kā 某物 lâng「大聲講出 lí ê 名」，lán 向望聽著 hit 个 lâng ê 名。毋過，若準講 lán kā 伊講「大聲講出『lí ê 名』」，lán 向望通聽見「lí ê 名」。注意 lán hǒng 要求愛用屶 á 形 ê 引號，來描述別 lâng 通講 ê。[63]

We can follow this same practice to identify lists and symbols that are to be treated as data objects rather than as expressions to be evaluated. However, our format for quoting differs from that of natural languages in that we place a quotation mark (traditionally, the single quote symbol ') only at the beginning of the object to be quoted. We can get away with this in Scheme syntax because we rely on blanks and parentheses to delimit objects. Thus, the meaning of the single quote character is to quote the next object.[64]

Lán 通跟 tòe kâng 款 ê 做法來辨別 beh 予 lâng 掠做資料物件，毋是 beh 算 ê 表達式 ê 列單 kap 符號。毋 koh，lán 引用 ê 形式 kap 自然語言 ê 無 kâng，lán kan-ta 佇 beh 引用 ê 物件頭前下引號（傳統是單引號 '）。L 因為 lán 倚靠空白 kap 括弧來斷開物件，lán 通佇 Scheme ê 語法 bóng 用 che。就 án-ne，單引號字元 ê 意義是引用後一个物件。[65]

[63]佇語言內底允准引號，ē 予用簡單 ê 項 (term) 來推論語言產生大混亂，因為伊毀壞相等 ê 通用相等 ê 替代 ê 概念。比論講，三是一加二，但是「三」hit 字毋是片語「一加二」。引用有能力，因為伊予 lán 方法來起造操作別个表達式 ê 表達式（lán ē 佇 Chapter 4 寫直譯器 ê 時陣看見）。毋 koh 允准語言 ê 句 (statement) 講起 hit 个語言 ê 別 ê 句，會予維持任何「相等 ê 通用相等 ê 替代」所應該指 ê ê 一貫性 ê 原則蓋困難。比論講，若準 lán 知影長庚是啟明星，了後自 chit 句「長庚是金星」就通演繹出「啟明星是金星」。但是，若是有「約翰知影長庚是金星」，lán 無法度推論出「約翰知影啟明星是金星」。

[64]The single quote is different from the double quote we have been using to enclose character strings to be printed. Whereas the single quote can be used to denote lists or symbols, the double quote is used only with character strings. In this book, the only use for character strings is as items to be printed.

[65]單引號 kap lán thèh 來包 beh 印 ê 字串無相 kâng。其中單引號通 thèh 來表列單 iáu 是符號，雙引號 kan-ta 用佇字串。佇 chit 本冊，字元 ê 串獨獨當做 beh 印出來 ê 項目 niâ。

Now we can distinguish between symbols and their values:
Ta^{n} lán 通辨別符號 kap in ê 值：

```
(define a 1)
(define b 2)
(list a b)
(1 2)
(list 'a 'b)
(a b)
(list 'a b)
(a 2)
```

Quotation also allows us to type in compound objects, using the conventional printed representation for lists:[66]
引用 mā 允准 lán 佇複合物件內底輸入，用列單 ê 傳統印出 ê 表示法：[67]

[66] Strictly, our use of the quotation mark violates the general rule that all compound expressions in our language should be delimited by parentheses and look like lists. We can recover this consistency by introducing a special form `quote`, which serves the same purpose as the quotation mark. Thus, we would type `(quote a)` instead of `'a`, and we would type `(quote (a b c))` instead of `'(a b c)`. This is precisely how the interpreter works. The quotation mark is just a single-character abbreviation for wrapping the next complete expression with `quote` to form `(quote` ⟨*expression*⟩`)`. This is important because it maintains the principle that any expression seen by the interpreter can be manipulated as a data object. For instance, we could construct the expression `(car '(a b c))`, which is the same as `(car (quote (a b c)))`, by evaluating `(list 'car (list 'quote '(a b c)))`.

[67] 嚴嚴來講，lán ê 引號 ê 用法違背逐 ê 複合表達式佇 lán ê 語言內底應該用括弧區分，mā 著看起來像列單 ê 一般規則。Lán ē 當引用特殊形式 `quote`，來恢復 chit ê 一致，`quote` kap 引號 ê 目的 siâng 款。自 án-ne，lán 通拍 `(quote a)` 毋免拍`'a`；koh lán 通拍 `(quote (a b c))`，毋免拍 `'(a b c)`。Che 拄好是編譯器運作 ê 方法，引號 kan-ta 是孤字元 ê 縮略，來建立 `(quote` ⟨**表達式**⟩`)`。Che chiâⁿ 重要，因為伊維持編譯器所看著 ê 逐 ê 表達式，ē 當當做資料物件來操作。比如講，lán ē 當用算 `(list 'car (list 'quote '(a b c)))` ê 值，來起造表達式 `(car '(a b c))`，伊 kap `(car (quote (a b c)))` siâng 款。

```
(car '(a b c))
a
(cdr '(a b c))
(b c)
```

In keeping with this, we can obtain the empty list by evaluating `'()`, and thus dispense with the variable `nil`.

為著照 che，lán 通用算`'()` ê 值來 thèh 著空 ê 列單，因此毋免用變數 `nil`。

One additional primitive used in manipulating symbols is `eq?`, which takes two symbols as arguments and tests whether they are the same.[68] Using `eq?`, we can implement a useful procedure called `memq`. This takes two arguments, a symbol and a list. If the symbol is not contained in the list (i.e., is not `eq?` to any item in the list), then `memq` returns false. Otherwise, it returns the sublist of the list beginning with the first occurrence of the symbol:

一个加添操作符號 ê 基礎函數是 `eq?`，伊 thèh 兩个符號當做引數，試 in 敢 kâng 款。[69]用 `eq?`，lán 通實做一个有路用 ê 程序，號做 `memq`。伊 thèh 兩个引數，一个符號 kap 一个列單。符號若無包佇列單內底（就是對列單 ê 逐項 lóng 無 `eq?`），`memq` 傳轉假。Ah 無，伊傳轉頭一改出現 hit ê 符號開始 ê，輸入列單 ê kiáⁿ 列單：

```
(define (memq item x)
  (cond ((null? x) false)
        ((eq? item (car x)) x)
        (else (memq item (cdr x)))))
```

For example, the value of

[68] We can consider two symbols to be “the same” if they consist of the same characters in the same order. Such a definition skirts a deep issue that we are not yet ready to address: the meaning of “sameness” in a programming language. We will return to this in Chapter 3 (Section 3.1.3).

[69] 若準 in 包含仝款 ê 字元，排列 koh 仝款，lán 就 ē 當 kā 兩个符號掠做「相 kâng」。Án-ne ê 定義 khau 過一个 lán iáu bōe 備辦好勢來解決 ê，深深 ê 議題：佇程式語言內底，「相 kâng 度」ê 意思。Lán 佇 Chapter 3 ē 轉去 hit ê 主題 (Section 3.1.3)。

比論講，

```
(memq 'apple '(pear banana prune))
```

is false, whereas the value of
ê 值是假，同時

```
(memq 'apple '(x (apple sauce) y apple pear))
```

is `(apple pear)`.
ê 值是 `(apple pear)`。

Exercise 2.53: What would the interpreter print in response to evaluating each of the following expressions?

Exercise 2.53: 算下 kha 逐 ê 表達式了後，直譯器 ē 印出啥物？

```
(list 'a 'b 'c)
(list (list 'george))
(cdr '((x1 x2) (y1 y2)))
(cadr '((x1 x2) (y1 y2)))
(pair? (car '(a short list)))
(memq 'red '((red shoes) (blue socks)))
(memq 'red '(red shoes blue socks))
```

Exercise 2.54: Two lists are said to be `equal?` if they contain equal elements arranged in the same order. For example,

Exercise 2.54: 若是兩个列單包含相 kâng ê 要素，koh 照 kâng 款 ê 順序排，in 就 ē 當講是 `equal?`。舉例：

```
(equal? '(this is a list) '(this is a list))
```

is true, but

是真 ê，毋 kú

```
(equal? '(this is a list) '(this (is a) list))
```

is false. To be more precise, we can define `equal?` recursively in terms of the basic `eq?` equality of symbols by saying that `a` and `b` are `equal?` if they are both symbols and the symbols are `eq?`, or if they are both lists such that `(car a)` is `equal?` to `(car b)` and `(cdr a)` is `equal?` to `(cdr b)`. Using this idea, implement `equal?` as a procedure.[70]

是假 ê。Kah 準確講，lán 通 thèh 基礎 ê `eq?` ê 符號相等，怙「若是 `a` kap `b` 兩个是相 `eq?` ê 符號，或者是 in 兩个 lóng 是滿足 `(car a)` kap `(car b)` 是 `equal?`，而且 `(cdr a)` kap `(cdr b)` 是 `equal?`，就 `a` kap `b` 是 `equal?`」ê 原則，來遞迴定義 `equal?`。請 thèh chit 个想法，實做 `equal?` 程序。[71]

Exercise 2.55: Eva Lu Ator types to the interpreter the expression

Exercise 2.55: Eva Lu Ator 拍下 kha ê 表達式，輸入 kàu 直譯器

```
(car ''abracadabra)
```

To her surprise, the interpreter prints back `quote`. Explain.

[70] In practice, programmers use `equal?` to compare lists that contain numbers as well as symbols. Numbers are not considered to be symbols. The question of whether two numerically equal numbers (as tested by =) are also `eq?` is highly implementation-dependent. A better definition of `equal?` (such as the one that comes as a primitive in Scheme) would also stipulate that if `a` and `b` are both numbers, then `a` and `b` are `equal?` if they are numerically equal.

[71] 實際上，程式設計師用 `equal?` 來比較包含數 kap 符號 ê 列單。數無予儂掠做是符號。兩个數值上相 kâng ê 數（用 = 試）敢 mā 是 `eq?`，足倚靠實做內容。`equal?`（像做 Scheme ê 基礎函數 ê）koh 較好 ê 實做，iā 規範若準 `a` kap `b` lóng 是數，koh 數值上相 kâng，in 就 `equal?`。

伊誠好奇，直譯器印出 `quote`。請解說。

2.3.2 Example: Symbolic Differentiation 例：符號微分

As an illustration of symbol manipulation and a further illustration of data abstraction, consider the design of a procedure that performs symbolic differentiation of algebraic expressions. We would like the procedure to take as arguments an algebraic expression and a variable and to return the derivative of the expression with respect to the variable. For example, if the arguments to the procedure are ax^2+bx+c and x, the procedure should return $2ax+b$. Symbolic differentiation is of special historical significance in Lisp. It was one of the motivating examples behind the development of a computer language for symbol manipulation. Furthermore, it marked the beginning of the line of research that led to the development of powerful systems for symbolic mathematical work, which are currently being used by a growing number of applied mathematicians and physicists.

做一个符號操作 kap 進一步 ê 資料抽象化 ê 描述，考慮行代數表達式 ê 符號微分 ê 程序設計。Lán beh 愛程序 thèh 一个代數表達式 kap 一个變數做引數，傳轉 chit ê 表達式 ê 對應 hit ê 變數 ê 導數。比論講，程序 ê 引數若是 $ax^2 + bx + c$ kap x，程序應該就傳轉 $2ax + b$。符號微分佇 Lisp 內底有特別 ê 歷史意義。電腦語言為著符號操作 ê 發展，後壁 ê 動機 ê 例包含伊。Koh 進前，伊表明對符號數學 ê 工作有大路用 ê 系統 ê 開發研究線 ê 起頭，Hia ê 系統 ta^{n} 予 ná 來 ná chē ê 應用數學家 kap 物理學家用。

In developing the symbolic-differentiation program, we will follow the same strategy of data abstraction that we followed in developing the rational-number system of Section 2.1.1. That is, we will first define a differentiation algorithm that operates on abstract objects such as "sums," "products," and "variables" without worrying about how these are to be represented. Only afterward will we address the representation problem.

佇開發 chit ê 符號積分 ê 程式，lán ē 跟 tòe 佇 Section 2.1.1 開發有理數

系統所 tòe ê 資料抽象化 ê 策略。就是，lán ē 先定義操作比論「和」、「積」kap「變數」等抽象物件 ê 微分演算法，毋免煩惱 chia ê beh án-nóa 表示。Kan-ta 佇落尾，lán ē 處理表示 ê 問題。

The differentiation program with abstract data

In order to keep things simple, we will consider a very simple symbolic-differentiation program that handles expressions that are built up using only the operations of addition and multiplication with two arguments. Differentiation of any such expression can be carried out by applying the following reduction rules:

$$\frac{dc}{dx} = 0, \quad \text{for } c \text{ a constant or a variable different from } x,$$

$$\frac{dx}{dx} = 1,$$

$$\frac{d\,(u+v\,)}{dx} = \frac{du}{dx} + \frac{dv}{dx},$$

$$\frac{d\,(uv\,)}{dx} = u\frac{dv}{dx} + v\frac{du}{dx}.$$

Observe that the latter two rules are recursive in nature. That is, to obtain the derivative of a sum we first find the derivatives of the terms and add them. Each of the terms may in turn be an expression that needs to be decomposed. Decomposing into smaller and smaller pieces will eventually produce pieces that are either constants or variables, whose derivatives will be either 0 or 1.

To embody these rules in a procedure we indulge in a little wishful thinking, as we did in designing the rational-number implementation. If we had a

means for representing algebraic expressions, we should be able to tell whether an expression is a sum, a product, a constant, or a variable. We should be able to extract the parts of an expression. For a sum, for example we want to be able to extract the addend (first term) and the augend (second term). We should also be able to construct expressions from parts. Let us assume that we already have procedures to implement the following selectors, constructors, and predicates:

`(variable? e)`	Is `e` a variable?
`(same-variable? v1 v2)`	Are `v1` and `v2` the same variable?
`(sum? e)`	Is `e` a sum?
`(addend e)`	Addend of the sum `e`.
`(augend e)`	Augend of the sum `e`.
`(make-sum a1 a2)`	Construct the sum of `a1` and `a2`.
`(product? e)`	Is `e` a product?
`(multiplier e)`	Multiplier of the product `e`.
`(multiplicand e)`	Multiplicand of the product `e`.
`(make-product m1 m2)`	Construct the product of `m1` and `m2`.

Using these, and the primitive predicate `number?`, which identifies numbers, we can express the differentiation rules as the following procedure:

```
(define (deriv exp var)
  (cond ((number? exp) 0)
        ((variable? exp) (if (same-variable? exp var) 1 0))
        ((sum? exp) (make-sum (deriv (addend exp) var)
                              (deriv (augend exp) var)))
        ((product? exp)
         (make-sum
           (make-product (multiplier exp)
                         (deriv (multiplicand exp) var))
           (make-product (deriv (multiplier exp) var)
                         (multiplicand exp))))
        (else
```

```
        (error "unknown expression type: DERIV" exp))))
```

This `deriv` procedure incorporates the complete differentiation algorithm. Since it is expressed in terms of abstract data, it will work no matter how we choose to represent algebraic expressions, as long as we design a proper set of selectors and constructors. This is the issue we must address next.

Representing algebraic expressions

We can imagine many ways to use list structure to represent algebraic expressions. For example, we could use lists of symbols that mirror the usual algebraic notation, representing $ax + b$ as the list `(a * x + b)`. However, one especially straightforward choice is to use the same parenthesized prefix notation that Lisp uses for combinations; that is, to represent $ax + b$ as `(+ (* a x) b)`. Then our data representation for the differentiation problem is as follows:

- The variables are symbols. They are identified by the primitive predicate `symbol?`:

```
(define (variable? x) (symbol? x))
```

- Two variables are the same if the symbols representing them are `eq?`:

```
(define (same-variable? v1 v2)
  (and (variable? v1) (variable? v2) (eq? v1 v2)))
```

- Sums and products are constructed as lists:

```
(define (make-sum a1 a2) (list '+ a1 a2))
(define (make-product m1 m2) (list '* m1 m2))
```

- A sum is a list whose first element is the symbol +:

```
(define (sum? x) (and (pair? x) (eq? (car x) '+)))
```

- The addend is the second item of the sum list:

```
(define (addend s) (cadr s))
```

- The augend is the third item of the sum list:

```
(define (augend s) (caddr s))
```

- A product is a list whose first element is the symbol `*`:

```
(define (product? x) (and (pair? x) (eq? (car x) '*)))
```

- The multiplier is the second item of the product list:

```
(define (multiplier p) (cadr p))
```

- The multiplicand is the third item of the product list:

```
(define (multiplicand p) (caddr p))
```

Thus, we need only combine these with the algorithm as embodied by `deriv` in order to have a working symbolic-differentiation program. Let us look at some examples of its behavior:

```
(deriv '(+ x 3) 'x)
(+ 1 0)
(deriv '(* x y) 'x)
(+ (* x 0) (* 1 y))
(deriv '(* (* x y) (+ x 3)) 'x)
(+ (* (* x y) (+ 1 0))
   (* (+ (* x 0) (* 1 y))
      (+ x 3)))
```

The program produces answers that are correct; however, they are unsimplified. It is true that

$$\frac{d\,(xy\,)}{dx} = x \cdot 0 + 1 \cdot y,$$

but we would like the program to know that $x \cdot 0 = 0$, $1 \cdot y = y$, and $0 + y = y$. The answer for the second example should have been simply `y`. As the third example shows, this becomes a serious issue when the expressions are complex.

Our difficulty is much like the one we encountered with the rational-number implementation: we haven't reduced answers to simplest form. To accomplish the rational-number reduction, we needed to change only the constructors and the selectors of the implementation. We can adopt a similar strategy here. We won't change `deriv` at all. Instead, we will change `make-sum` so that if both summands are numbers, `make-sum` will add them and return their sum. Also, if one of the summands is 0, then `make-sum` will return the other summand.

```
(define (make-sum a1 a2)
  (cond ((=number? a1 0) a2)
        ((=number? a2 0) a1)
        ((and (number? a1) (number? a2))
         (+ a1 a2))
        (else (list '+ a1 a2))))
```

This uses the procedure `=number?`, which checks whether an expression is equal to a given number:

```
(define (=number? exp num) (and (number? exp) (= exp num)))
```

Similarly, we will change `make-product` to build in the rules that 0 times anything is 0 and 1 times anything is the thing itself:

```
(define (make-product m1 m2)
```

```
(cond ((or (=number? m1 0) (=number? m2 0)) 0)
      ((=number? m1 1) m2)
      ((=number? m2 1) m1)
      ((and (number? m1) (number? m2)) (* m1 m2))
      (else (list '* m1 m2))))
```

Here is how this version works on our three examples:

```
(deriv '(+ x 3) 'x)
1
(deriv '(* x y) 'x)
y
(deriv '(* (* x y) (+ x 3)) 'x)
(+ (* x y) (* y (+ x 3)))
```

Although this is quite an improvement, the third example shows that there is still a long way to go before we get a program that puts expressions into a form that we might agree is "simplest." The problem of algebraic simplification is complex because, among other reasons, a form that may be simplest for one purpose may not be for another.

> **Exercise 2.56:** Show how to extend the basic differentiator to handle more kinds of expressions. For instance, implement the differentiation rule
>
> $$\frac{d\left(u^{n}\right)}{dx} = nu^{n-1}\frac{du}{dx}$$
>
> by adding a new clause to the `deriv` program and defining appropriate procedures `exponentiation?`, `base`, `exponent`, and `make-exponentiation`. (You may use the symbol `**` to denote exponentiation.) Build in the rules that anything raised to the power 0 is 1 and anything raised to the power 1 is the thing itself.

Exercise 2.57: Extend the differentiation program to handle sums and products of arbitrary numbers of (two or more) terms. Then the last example above could be expressed as

```
(deriv '(* x y (+ x 3)) 'x)
```

Try to do this by changing only the representation for sums and products, without changing the `deriv` procedure at all. For example, the `addend` of a sum would be the first term, and the `augend` would be the sum of the rest of the terms.

Exercise 2.58: Suppose we want to modify the differentiation program so that it works with ordinary mathematical notation, in which + and * are infix rather than prefix operators. Since the differentiation program is defined in terms of abstract data, we can modify it to work with different representations of expressions solely by changing the predicates, selectors, and constructors that define the representation of the algebraic expressions on which the differentiator is to operate.

a. Show how to do this in order to differentiate algebraic expressions presented in infix form, such as `(x + (3 * (x + (y + 2))))`. To simplify the task, assume that + and * always take two arguments and that expressions are fully parenthesized.

b. The problem becomes substantially harder if we allow standard algebraic notation, such as `(x + 3 * (x + y + 2))`, which drops unnecessary parentheses and assumes that multiplication is done before addition. Can you design appropriate predicates, selectors, and constructors for this notation such that our derivative program still works?

2.3.3 Example: Representing Sets

In the previous examples we built representations for two kinds of compound data objects: rational numbers and algebraic expressions. In one of these examples we had the choice of simplifying (reducing) the expressions at either construction time or selection time, but other than that the choice of a representation for these structures in terms of lists was straightforward. When we turn to the representation of sets, the choice of a representation is not so obvious. Indeed, there are a number of possible representations, and they differ significantly from one another in several ways.

Informally, a set is simply a collection of distinct objects. To give a more precise definition we can employ the method of data abstraction. That is, we define "set" by specifying the operations that are to be used on sets. These are `union-set`, `intersection-set`, `element-of-set?`, and `adjoin-set`. `element-of-set?` is a predicate that determines whether a given element is a member of a set. `adjoin-set` takes an object and a set as arguments and returns a set that contains the elements of the original set and also the adjoined element. `union-set` computes the union of two sets, which is the set containing each element that appears in either argument. `intersection-set` computes the intersection of two sets, which is the set containing only elements that appear in both arguments. From the viewpoint of data abstraction, we are free to design any representation that implements these operations in a way consistent with the interpretations given above.[72]

[72] If we want to be more formal, we can specify "consistent with the interpretations given above" to mean that the operations satisfy a collection of rules such as these:
• For any set `S` and any object `x`, `(element-of-set? x (adjoin-set x S))` is true (informally: "Adjoining an object to a set produces a set that contains the object").
• For any sets `S` and `T` and any object `x`, `(element-of-set? x (union-set S T))` is equal to `(or (element-of-set? x S) (element-of-set? x`

Sets as unordered lists

One way to represent a set is as a list of its elements in which no element appears more than once. The empty set is represented by the empty list. In this representation, `element-of-set?` is similar to the procedure `memq` of Section 2.3.1. It uses `equal?` instead of `eq?` so that the set elements need not be symbols:

```
(define (element-of-set? x set)
  (cond ((null? set) false)
        ((equal? x (car set)) true)
        (else (element-of-set? x (cdr set)))))
```

Using this, we can write `adjoin-set`. If the object to be adjoined is already in the set, we just return the set. Otherwise, we use `cons` to add the object to the list that represents the set:

```
(define (adjoin-set x set)
  (if (element-of-set? x set)
      set
      (cons x set)))
```

For `intersection-set` we can use a recursive strategy. If we know how to form the intersection of `set2` and the `cdr` of `set1`, we only need to decide whether to include the `car` of `set1` in this. But this depends on whether `(car set1)` is also in `set2`. Here is the resulting procedure:

```
(define (intersection-set set1 set2)
  (cond ((or (null? set1) (null? set2)) '())
        ((element-of-set? (car set1) set2)
         (cons (car set1) (intersection-set (cdr set1) set2)))
        (else (intersection-set (cdr set1) set2))))
```

`T))` (informally: "The elements of `(union S T)` are the elements that are in `S` or in `T`").
• For any object `x`, `(element-of-set? x '())` is false (informally: "No object is an element of the empty set").

In designing a representation, one of the issues we should be concerned with is efficiency. Consider the number of steps required by our set operations. Since they all use `element-of-set?`, the speed of this operation has a major impact on the efficiency of the set implementation as a whole. Now, in order to check whether an object is a member of a set, `element-of-set?` may have to scan the entire set. (In the worst case, the object turns out not to be in the set.) Hence, if the set has n elements, `element-of-set?` might take up to n steps. Thus, the number of steps required grows as $\Theta(n)$. The number of steps required by `adjoin-set`, which uses this operation, also grows as $\Theta(n)$. For `intersection-set`, which does an `element-of-set?` check for each element of `set1`, the number of steps required grows as the product of the sizes of the sets involved, or $\Theta(n^2)$ for two sets of size n. The same will be true of `union-set`.

Exercise 2.59: Implement the `union-set` operation for the unordered-list representation of sets.

Exercise 2.60: We specified that a set would be represented as a list with no duplicates. Now suppose we allow duplicates. For instance, the set $\{1, 2, 3\}$ could be represented as the list `(2 3 2 1 3 2 2)`. Design procedures `element-of-set?`, `adjoin-set`, `union-set`, and `intersection-set` that operate on this representation. How does the efficiency of each compare with the corresponding procedure for the non-duplicate representation? Are there applications for which you would use this representation in preference to the non-duplicate one?

Sets as ordered lists

One way to speed up our set operations is to change the representation so that the set elements are listed in increasing order. To do this, we need some way to compare two objects so that we can say which is bigger. For example, we could compare symbols lexicographically, or we could agree on some method for assigning a unique number to an object and then compare the elements by comparing the corresponding numbers. To keep our discussion simple, we will consider only the case where the set elements are numbers, so that we can compare elements using $>$ and $<$. We will represent a set of numbers by listing its elements in increasing order. Whereas our first representation above allowed us to represent the set $\{1, 3, 6, 10\}$ by listing the elements in any order, our new representation allows only the list `(1 3 6 10)`.

One advantage of ordering shows up in `element-of-set?`: In checking for the presence of an item, we no longer have to scan the entire set. If we reach a set element that is larger than the item we are looking for, then we know that the item is not in the set:

```
(define (element-of-set? x set)
  (cond ((null? set) false)
        ((= x (car set)) true)
        ((< x (car set)) false)
        (else (element-of-set? x (cdr set)))))
```

How many steps does this save? In the worst case, the item we are looking for may be the largest one in the set, so the number of steps is the same as for the unordered representation. On the other hand, if we search for items of many different sizes we can expect that sometimes we will be able to stop searching at a point near the beginning of the list and that other times we will still need to examine most of the list. On the average we should expect to have to examine about half of the items in the set. Thus, the average number of steps required will be about $n/2$. This is still $\Theta(n)$ growth, but it does

save us, on the average, a factor of 2 in number of steps over the previous implementation.

We obtain a more impressive speedup with `intersection-set`. In the unordered representation this operation required $\Theta(n^2)$ steps, because we performed a complete scan of `set2` for each element of `set1`. But with the ordered representation, we can use a more clever method. Begin by comparing the initial elements, `x1` and `x2`, of the two sets. If `x1` equals `x2`, then that gives an element of the intersection, and the rest of the intersection is the intersection of the `cdr`-s of the two sets. Suppose, however, that `x1` is less than `x2`. Since `x2` is the smallest element in `set2`, we can immediately conclude that `x1` cannot appear anywhere in `set2` and hence is not in the intersection. Hence, the intersection is equal to the intersection of `set2` with the `cdr` of `set1`. Similarly, if `x2` is less than `x1`, then the intersection is given by the intersection of `set1` with the `cdr` of `set2`. Here is the procedure:

```
(define (intersection-set set1 set2)
  (if (or (null? set1) (null? set2))
      '()
      (let ((x1 (car set1)) (x2 (car set2)))
        (cond ((= x1 x2)
               (cons x1 (intersection-set (cdr set1)
                                          (cdr set2))))
              ((< x1 x2)
               (intersection-set (cdr set1) set2))
              ((< x2 x1)
               (intersection-set set1 (cdr set2)))))))
```

To estimate the number of steps required by this process, observe that at each step we reduce the intersection problem to computing intersections of smaller sets—removing the first element from `set1` or `set2` or both. Thus, the number of steps required is at most the sum of the sizes of `set1` and `set2`,

rather than the product of the sizes as with the unordered representation. This is $\Theta(n)$ growth rather than $\Theta(n^2)$—a considerable speedup, even for sets of moderate size.

> **Exercise 2.61:** Give an implementation of `adjoin-set` using the ordered representation. By analogy with `element-of-set?` show how to take advantage of the ordering to produce a procedure that requires on the average about half as many steps as with the unordered representation.

> **Exercise 2.62:** Give a $\Theta(n)$ implementation of `union-set` for sets represented as ordered lists.

Sets as binary trees

We can do better than the ordered-list representation by arranging the set elements in the form of a tree. Each node of the tree holds one element of the set, called the "entry" at that node, and a link to each of two other (possibly empty) nodes. The "left" link points to elements smaller than the one at the node, and the "right" link to elements greater than the one at the node. Figure 2.16 shows some trees that represent the set $\{1, 3, 5, 7, 9, 11\}$. The same set may be represented by a tree in a number of different ways. The only thing we require for a valid representation is that all elements in the left subtree be smaller than the node entry and that all elements in the right subtree be larger.

The advantage of the tree representation is this: Suppose we want to check whether a number x is contained in a set. We begin by comparing x with the entry in the top node. If x is less than this, we know that we need only search the left subtree; if x is greater, we need only search the right subtree. Now, if the tree is "balanced," each of these subtrees will be about half the size of the original. Thus, in one step we have reduced the problem of searching a tree




Figure 2.16: Various binary trees that represent the set $\{1, 3, 5, 7, 9, 11\}$.

of size n to searching a tree of size $n/2$. Since the size of the tree is halved at each step, we should expect that the number of steps needed to search a tree of size n grows as $\Theta(\log n)$.[73] For large sets, this will be a significant speedup over the previous representations.

We can represent trees by using lists. Each node will be a list of three items: the entry at the node, the left subtree, and the right subtree. A left or a right subtree of the empty list will indicate that there is no subtree connected there. We can describe this representation by the following procedures:[74]

```
(define (entry tree) (car tree))
(define (left-branch tree) (cadr tree))
(define (right-branch tree) (caddr tree))
```

[73] Halving the size of the problem at each step is the distinguishing characteristic of logarithmic growth, as we saw with the fast-exponentiation algorithm of Section 1.2.4 and the half-interval search method of Section 1.3.3.

[74] We are representing sets in terms of trees, and trees in terms of lists—in effect, a data abstraction built upon a data abstraction. We can regard the procedures `entry`, `left-branch`, `right-branch`, and `make-tree` as a way of isolating the abstraction of a "binary tree" from the particular way we might wish to represent such a tree in terms of list structure.

```
(define (make-tree entry left right)
  (list entry left right))
```

Now we can write the `element-of-set?` procedure using the strategy described above:

```
(define (element-of-set? x set)
  (cond ((null? set) false)
        ((= x (entry set)) true)
        ((< x (entry set))
         (element-of-set? x (left-branch set)))
        ((> x (entry set))
         (element-of-set? x (right-branch set)))))
```

Adjoining an item to a set is implemented similarly and also requires $\Theta(\log n)$ steps. To adjoin an item `x`, we compare `x` with the node entry to determine whether `x` should be added to the right or to the left branch, and having adjoined `x` to the appropriate branch we piece this newly constructed branch together with the original entry and the other branch. If `x` is equal to the entry, we just return the node. If we are asked to adjoin `x` to an empty tree, we generate a tree that has `x` as the entry and empty right and left branches. Here is the procedure:

```
(define (adjoin-set x set)
  (cond ((null? set) (make-tree x '() '()))
        ((= x (entry set)) set)
        ((< x (entry set))
         (make-tree (entry set)
                    (adjoin-set x (left-branch set))
                    (right-branch set)))
        ((> x (entry set))
         (make-tree (entry set) (left-branch set)
                    (adjoin-set x (right-branch set))))))
```

The above claim that searching the tree can be performed in a logarithmic number of steps rests on the assumption that the tree is "balanced," i.e., that the left and the right subtree of every tree have approximately the same number of elements, so that each subtree contains about half the elements of its parent. But how can we be certain that the trees we construct will be balanced? Even if we start with a balanced tree, adding elements with `adjoin-set` may produce an unbalanced result. Since the position of a newly adjoined element depends on how the element compares with the items already in the set, we can expect that if we add elements "randomly" the tree will tend to be balanced on the average. But this is not a guarantee. For example, if we start with an empty set and adjoin the numbers 1 through 7 in sequence we end up with the highly unbalanced tree shown in Figure 2.17. In this tree all the left subtrees are empty, so it has no advantage over a simple ordered list. One way to solve this problem is to define an operation that transforms an arbitrary tree into a balanced tree with the same elements. Then we can perform this transformation after every few `adjoin-set` operations to keep our set in balance. There are also other ways to solve this problem, most of which involve designing new data structures for which searching and insertion both can be done in $\Theta(\log n)$ steps.[75]

Exercise 2.63: Each of the following two procedures converts a binary tree to a list.

```
(define (tree->list-1 tree)
  (if (null? tree)
      '()
      (append (tree->list-1 (left-branch tree))
              (cons (entry tree)
                    (tree->list-1
```

[75] Examples of such structures include *B-trees* and *red-black trees*. There is a large literature on data structures devoted to this problem. See Cormen et al. 1990.




Figure 2.17: Unbalanced tree produced by adjoining 1 through 7 in sequence.

```
                        (right-branch tree))))))
(define (tree->list-2 tree)
  (define (copy-to-list tree result-list)
    (if (null? tree)
        result-list
        (copy-to-list (left-branch tree)
                      (cons (entry tree)
                            (copy-to-list
                              (right-branch tree)
                              result-list)))))
  (copy-to-list tree '()))
```

a. Do the two procedures produce the same result for every tree? If not, how do the results differ? What lists do the two procedures produce for the trees in Figure 2.16?

b. Do the two procedures have the same order of growth in the number of steps required to convert a balanced tree

with n elements to a list? If not, which one grows more slowly?

Exercise 2.64: The following procedure `list->tree` converts an ordered list to a balanced binary tree. The helper procedure `partial-tree` takes as arguments an integer n and list of at least n elements and constructs a balanced tree containing the first n elements of the list. The result returned by `partial-tree` is a pair (formed with `cons`) whose `car` is the constructed tree and whose `cdr` is the list of elements not included in the tree.

```
(define (list->tree elements)
  (car (partial-tree elements (length elements))))
(define (partial-tree elts n)
  (if (= n 0)
      (cons '() elts)
      (let ((left-size (quotient (- n 1) 2)))
        (let ((left-result
               (partial-tree elts left-size)))
          (let ((left-tree (car left-result))
                (non-left-elts (cdr left-result))
                (right-size (- n (+ left-size 1))))
            (let ((this-entry (car non-left-elts))
                  (right-result
                   (partial-tree
                    (cdr non-left-elts)
                    right-size)))
              (let ((right-tree (car right-result))
                    (remaining-elts
                     (cdr right-result)))
                (cons (make-tree this-entry
                                 left-tree
```

```
                                right-tree)
                        remaining-elts)))))))))
```

a. Write a short paragraph explaining as clearly as you can how `partial-tree` works. Draw the tree produced by `list->tree` for the list `(1 3 5 7 9 11)`.

b. What is the order of growth in the number of steps required by `list->tree` to convert a list of n elements?

Exercise 2.65: Use the results of Exercise 2.63 and Exercise 2.64 to give $\Theta(n)$ implementations of `union-set` and `intersection-set` for sets implemented as (balanced) binary trees.[76]

Sets and information retrieval

We have examined options for using lists to represent sets and have seen how the choice of representation for a data object can have a large impact on the performance of the programs that use the data. Another reason for concentrating on sets is that the techniques discussed here appear again and again in applications involving information retrieval.

Consider a data base containing a large number of individual records, such as the personnel files for a company or the transactions in an accounting system. A typical data-management system spends a large amount of time accessing or modifying the data in the records and therefore requires an efficient method for accessing records. This is done by identifying a part of each record to serve as an identifying *key*. A key can be anything that uniquely identifies the record. For a personnel file, it might be an employee's ID number. For an accounting system, it might be a transaction number. Whatever

[76] Exercise 2.63 through Exercise 2.65 are due to Paul Hilfinger.

the key is, when we define the record as a data structure we should include a `key` selector procedure that retrieves the key associated with a given record.

Now we represent the data base as a set of records. To locate the record with a given key we use a procedure `lookup`, which takes as arguments a key and a data base and which returns the record that has that key, or false if there is no such record. `lookup` is implemented in almost the same way as `element-of-set?`. For example, if the set of records is implemented as an unordered list, we could use

```
(define (lookup given-key set-of-records)
  (cond ((null? set-of-records) false)
        ((equal? given-key (key (car set-of-records)))
         (car set-of-records))
        (else (lookup given-key (cdr set-of-records)))))
```

Of course, there are better ways to represent large sets than as unordered lists. Information-retrieval systems in which records have to be "randomly accessed" are typically implemented by a tree-based method, such as the binary-tree representation discussed previously. In designing such a system the methodology of data abstraction can be a great help. The designer can create an initial implementation using a simple, straightforward representation such as unordered lists. This will be unsuitable for the eventual system, but it can be useful in providing a "quick and dirty" data base with which to test the rest of the system. Later on, the data representation can be modified to be more sophisticated. If the data base is accessed in terms of abstract selectors and constructors, this change in representation will not require any changes to the rest of the system.

> **Exercise 2.66:** Implement the `lookup` procedure for the case where the set of records is structured as a binary tree, ordered by the numerical values of the keys.

2.3.4 Example: Huffman Encoding Trees

This section provides practice in the use of list structure and data abstraction to manipulate sets and trees. The application is to methods for representing data as sequences of ones and zeros (bits). For example, the ASCII standard code used to represent text in computers encodes each character as a sequence of seven bits. Using seven bits allows us to distinguish 2^7, or 128, possible different characters. In general, if we want to distinguish n different symbols, we will need to use $\log_2 n$ bits per symbol. If all our messages are made up of the eight symbols A, B, C, D, E, F, G, and H, we can choose a code with three bits per character, for example

```
A 000    C 010    E 100    G 110
B 001    D 011    F 101    H 111
```

With this code, the message

```
BACADAEAFABBAAAGAH
```

is encoded as the string of 54 bits

```
001000010000011000100000101000001001000000000110000111
```

Codes such as ASCII and the A-through-H code above are known as *fixed-length* codes, because they represent each symbol in the message with the same number of bits. It is sometimes advantageous to use *variable-length* codes, in which different symbols may be represented by different numbers of bits. For example, Morse code does not use the same number of dots and dashes for each letter of the alphabet. In particular, E, the most frequent letter, is represented by a single dot. In general, if our messages are such that some symbols appear very frequently and some very rarely, we can encode data more efficiently (i.e., using fewer bits per message) if we assign shorter

codes to the frequent symbols. Consider the following alternative code for the letters A through H:

```
A 0       C 1010    E 1100    G 1110
B 100     D 1011    F 1101    H 1111
```

With this code, the same message as above is encoded as the string

```
1000101001011011000110101001000000111001111
```

This string contains 42 bits, so it saves more than 20% in space in comparison with the fixed-length code shown above.

One of the difficulties of using a variable-length code is knowing when you have reached the end of a symbol in reading a sequence of zeros and ones. Morse code solves this problem by using a special *separator code* (in this case, a pause) after the sequence of dots and dashes for each letter. Another solution is to design the code in such a way that no complete code for any symbol is the beginning (or *prefix*) of the code for another symbol. Such a code is called a *prefix code*. In the example above, A is encoded by 0 and B is encoded by 100, so no other symbol can have a code that begins with 0 or with 100.

In general, we can attain significant savings if we use variable-length prefix codes that take advantage of the relative frequencies of the symbols in the messages to be encoded. One particular scheme for doing this is called the Huffman encoding method, after its discoverer, David Huffman. A Huffman code can be represented as a binary tree whose leaves are the symbols that are encoded. At each non-leaf node of the tree there is a set containing all the symbols in the leaves that lie below the node. In addition, each symbol at a leaf is assigned a weight (which is its relative frequency), and each non-leaf node contains a weight that is the sum of all the weights of the leaves lying below it. The weights are not used in the encoding or the decoding process. We will see below how they are used to help construct the tree.




Figure 2.18: A Huffman encoding tree.

Figure 2.18 shows the Huffman tree for the A-through-H code given above. The weights at the leaves indicate that the tree was designed for messages in which A appears with relative frequency 8, B with relative frequency 3, and the other letters each with relative frequency 1.

Given a Huffman tree, we can find the encoding of any symbol by starting at the root and moving down until we reach the leaf that holds the symbol. Each time we move down a left branch we add a 0 to the code, and each time we move down a right branch we add a 1. (We decide which branch to follow by testing to see which branch either is the leaf node for the symbol or contains the symbol in its set.) For example, starting from the root of the tree in Figure 2.18, we arrive at the leaf for D by following a right branch, then a left branch, then a right branch, then a right branch; hence, the code for D is 1011.

To decode a bit sequence using a Huffman tree, we begin at the root and use the successive zeros and ones of the bit sequence to determine whether

to move down the left or the right branch. Each time we come to a leaf, we have generated a new symbol in the message, at which point we start over from the root of the tree to find the next symbol. For example, suppose we are given the tree above and the sequence 10001010. Starting at the root, we move down the right branch, (since the first bit of the string is 1), then down the left branch (since the second bit is 0), then down the left branch (since the third bit is also 0). This brings us to the leaf for B, so the first symbol of the decoded message is B. Now we start again at the root, and we make a left move because the next bit in the string is 0. This brings us to the leaf for A. Then we start again at the root with the rest of the string 1010, so we move right, left, right, left and reach C. Thus, the entire message is BAC.

Generating Huffman trees

Given an "alphabet" of symbols and their relative frequencies, how do we construct the "best" code? (In other words, which tree will encode messages with the fewest bits?) Huffman gave an algorithm for doing this and showed that the resulting code is indeed the best variable-length code for messages where the relative frequency of the symbols matches the frequencies with which the code was constructed. We will not prove this optimality of Huffman codes here, but we will show how Huffman trees are constructed.[77]

The algorithm for generating a Huffman tree is very simple. The idea is to arrange the tree so that the symbols with the lowest frequency appear farthest away from the root. Begin with the set of leaf nodes, containing symbols and their frequencies, as determined by the initial data from which the code is to be constructed. Now find two leaves with the lowest weights and merge them to produce a node that has these two nodes as its left and right branches. The weight of the new node is the sum of the two weights. Remove the two leaves

[77] See Hamming 1980 for a discussion of the mathematical properties of Huffman codes.

from the original set and replace them by this new node. Now continue this process. At each step, merge two nodes with the smallest weights, removing them from the set and replacing them with a node that has these two as its left and right branches. The process stops when there is only one node left, which is the root of the entire tree. Here is how the Huffman tree of Figure 2.18 was generated:

```
Initial leaves  {(A 8) (B 3) (C 1) (D 1) (E 1) (F 1) (G 1)
         Merge  {(A 8) (B 3) ({C D} 2) (E 1) (F 1) (G 1) (H
         Merge  {(A 8) (B 3) ({C D} 2) ({E F} 2) (G 1) (H 1)
         Merge  {(A 8) (B 3) ({C D} 2) ({E F} 2) ({G H} 2)}
         Merge  {(A 8) (B 3) ({C D} 2) ({E F G H} 4)}
         Merge  {(A 8) ({B C D} 5) ({E F G H} 4)}
         Merge  {(A 8) ({B C D E F G H} 9)}
   Final merge  {({A B C D E F G H} 17)}
```

The algorithm does not always specify a unique tree, because there may not be unique smallest-weight nodes at each step. Also, the choice of the order in which the two nodes are merged (i.e., which will be the right branch and which will be the left branch) is arbitrary.

Representing Huffman trees

In the exercises below we will work with a system that uses Huffman trees to encode and decode messages and generates Huffman trees according to the algorithm outlined above. We will begin by discussing how trees are represented.

Leaves of the tree are represented by a list consisting of the symbol `leaf`, the symbol at the leaf, and the weight:

```
(define (make-leaf symbol weight) (list 'leaf symbol weight)
(define (leaf? object) (eq? (car object) 'leaf))
```

```
(define (symbol-leaf x) (cadr x))
(define (weight-leaf x) (caddr x))
```

A general tree will be a list of a left branch, a right branch, a set of symbols, and a weight. The set of symbols will be simply a list of the symbols, rather than some more sophisticated set representation. When we make a tree by merging two nodes, we obtain the weight of the tree as the sum of the weights of the nodes, and the set of symbols as the union of the sets of symbols for the nodes. Since our symbol sets are represented as lists, we can form the union by using the `append` procedure we defined in Section 2.2.1:

```
(define (make-code-tree left right)
  (list left
        right
        (append (symbols left) (symbols right))
        (+ (weight left) (weight right))))
```

If we make a tree in this way, we have the following selectors:

```
(define (left-branch  tree) (car  tree))
(define (right-branch tree) (cadr tree))
(define (symbols tree)
  (if (leaf? tree)
      (list (symbol-leaf tree))
      (caddr tree)))
(define (weight tree)
  (if (leaf? tree)
      (weight-leaf tree)
      (cadddr tree)))
```

The procedures `symbols` and `weight` must do something slightly different depending on whether they are called with a leaf or a general tree. These are simple examples of *generic procedures* (procedures that can handle more than one kind of data), which we will have much more to say about in Section 2.4 and Section 2.5.

The decoding procedure

The following procedure implements the decoding algorithm. It takes as arguments a list of zeros and ones, together with a Huffman tree.

```
(define (decode bits tree)
  (define (decode-1 bits current-branch)
    (if (null? bits)
        '()
        (let ((next-branch
               (choose-branch (car bits) current-branch)))
          (if (leaf? next-branch)
              (cons (symbol-leaf next-branch)
                    (decode-1 (cdr bits) tree))
              (decode-1 (cdr bits) next-branch)))))
  (decode-1 bits tree))
(define (choose-branch bit branch)
  (cond ((= bit 0) (left-branch branch))
        ((= bit 1) (right-branch branch))
        (else (error "bad bit: CHOOSE-BRANCH" bit))))
```

The procedure `decode-1` takes two arguments: the list of remaining bits and the current position in the tree. It keeps moving "down" the tree, choosing a left or a right branch according to whether the next bit in the list is a zero or a one. (This is done with the procedure `choose-branch`.) When it reaches a leaf, it returns the symbol at that leaf as the next symbol in the message by `cons`ing it onto the result of decoding the rest of the message, starting at the root of the tree. Note the error check in the final clause of `choose-branch`, which complains if the procedure finds something other than a zero or a one in the input data.

Sets of weighted elements

In our representation of trees, each non-leaf node contains a set of symbols, which we have represented as a simple list. However, the tree-generating algorithm discussed above requires that we also work with sets of leaves and trees, successively merging the two smallest items. Since we will be required to repeatedly find the smallest item in a set, it is convenient to use an ordered representation for this kind of set.

We will represent a set of leaves and trees as a list of elements, arranged in increasing order of weight. The following `adjoin-set` procedure for constructing sets is similar to the one described in Exercise 2.61; however, items are compared by their weights, and the element being added to the set is never already in it.

```
(define (adjoin-set x set)
  (cond ((null? set) (list x))
        ((< (weight x) (weight (car set))) (cons x set))
        (else (cons (car set)
                    (adjoin-set x (cdr set))))))
```

The following procedure takes a list of symbol-frequency pairs such as `((A 4) (B 2) (C 1) (D 1))` and constructs an initial ordered set of leaves, ready to be merged according to the Huffman algorithm:

```
(define (make-leaf-set pairs)
  (if (null? pairs)
      '()
      (let ((pair (car pairs)))
        (adjoin-set (make-leaf (car pair)     ; symbol
                               (cadr pair))   ; frequency
                    (make-leaf-set (cdr pairs))))))
```

Exercise 2.67: Define an encoding tree and a sample message:

```
(define sample-tree
  (make-code-tree (make-leaf 'A 4)
                  (make-code-tree
                   (make-leaf 'B 2)
                   (make-code-tree
                    (make-leaf 'D 1)
                    (make-leaf 'C 1)))))
(define sample-message '(0 1 1 0 0 1 0 1 0 1 1 1 0))
```

Use the `decode` procedure to decode the message, and give the result.

Exercise 2.68: The `encode` procedure takes as arguments a message and a tree and produces the list of bits that gives the encoded message.

```
(define (encode message tree)
  (if (null? message)
      '()
      (append (encode-symbol (car message) tree)
              (encode (cdr message) tree))))
```

`encode-symbol` is a procedure, which you must write, that returns the list of bits that encodes a given symbol according to a given tree. You should design `encode-symbol` so that it signals an error if the symbol is not in the tree at all. Test your procedure by encoding the result you obtained in Exercise 2.67 with the sample tree and seeing whether it is the same as the original sample message.

Exercise 2.69: The following procedure takes as its argument a list of symbol-frequency pairs (where no symbol appears in more

than one pair) and generates a Huffman encoding tree according to the Huffman algorithm.

```
(define (generate-huffman-tree pairs)
  (successive-merge (make-leaf-set pairs)))
```

`make-leaf-set` is the procedure given above that transforms the list of pairs into an ordered set of leaves. `successive-merge` is the procedure you must write, using `make-code-tree` to successively merge the smallest-weight elements of the set until there is only one element left, which is the desired Huffman tree. (This procedure is slightly tricky, but not really complicated. If you find yourself designing a complex procedure, then you are almost certainly doing something wrong. You can take significant advantage of the fact that we are using an ordered set representation.)

Exercise 2.70: The following eight-symbol alphabet with associated relative frequencies was designed to efficiently encode the lyrics of 1950s rock songs. (Note that the "symbols" of an "alphabet" need not be individual letters.)

```
A    2   GET 2   SHA 3   WAH 1
BOOM 1   JOB 2   NA 16   YIP 9
```

Use `generate-huffman-tree` (Exercise 2.69) to generate a corresponding Huffman tree, and use `encode` (Exercise 2.68) to encode the following message:

```
Get a job
Sha na na na na na na na
```

```
Get a job
Sha na na na na na na na na
Wah yip yip yip yip yip yip yip yip yip
Sha boom
```

How many bits are required for the encoding? What is the smallest number of bits that would be needed to encode this song if we used a fixed-length code for the eight-symbol alphabet?

Exercise 2.71: Suppose we have a Huffman tree for an alphabet of n symbols, and that the relative frequencies of the symbols are $1, 2, 4, \ldots, 2^{n-1}$. Sketch the tree for $n = 5$; for $n = 10$. In such a tree (for general n) how many bits are required to encode the most frequent symbol? The least frequent symbol?

Exercise 2.72: Consider the encoding procedure that you designed in Exercise 2.68. What is the order of growth in the number of steps needed to encode a symbol? Be sure to include the number of steps needed to search the symbol list at each node encountered. To answer this question in general is difficult. Consider the special case where the relative frequencies of the n symbols are as described in Exercise 2.71, and give the order of growth (as a function of n) of the number of steps needed to encode the most frequent and least frequent symbols in the alphabet.

2.4 Multiple Representations for Abstract Data

We have introduced data abstraction, a methodology for structuring systems in such a way that much of a program can be specified independent of the choices

involved in implementing the data objects that the program manipulates. For example, we saw in Section 2.1.1 how to separate the task of designing a program that uses rational numbers from the task of implementing rational numbers in terms of the computer language's primitive mechanisms for constructing compound data. The key idea was to erect an abstraction barrier —in this case, the selectors and constructors for rational numbers (`make-rat`, `numer`, `denom`)—that isolates the way rational numbers are used from their underlying representation in terms of list structure. A similar abstraction barrier isolates the details of the procedures that perform rational arithmetic (`add-rat`, `sub-rat`, `mul-rat`, and `div-rat`) from the "higher-level" procedures that use rational numbers. The resulting program has the structure shown in Figure 2.1.

These data-abstraction barriers are powerful tools for controlling complexity. By isolating the underlying representations of data objects, we can divide the task of designing a large program into smaller tasks that can be performed separately. But this kind of data abstraction is not yet powerful enough, because it may not always make sense to speak of "the underlying representation" for a data object.

For one thing, there might be more than one useful representation for a data object, and we might like to design systems that can deal with multiple representations. To take a simple example, complex numbers may be represented in two almost equivalent ways: in rectangular form (real and imaginary parts) and in polar form (magnitude and angle). Sometimes rectangular form is more appropriate and sometimes polar form is more appropriate. Indeed, it is perfectly plausible to imagine a system in which complex numbers are represented in both ways, and in which the procedures for manipulating complex numbers work with either representation.

More importantly, programming systems are often designed by many people working over extended periods of time, subject to requirements that

change over time. In such an environment, it is simply not possible for everyone to agree in advance on choices of data representation. So in addition to the data-abstraction barriers that isolate representation from use, we need abstraction barriers that isolate different design choices from each other and permit different choices to coexist in a single program. Furthermore, since large programs are often created by combining pre-existing modules that were designed in isolation, we need conventions that permit programmers to incorporate modules into larger systems *additively*, that is, without having to redesign or reimplement these modules.

In this section, we will learn how to cope with data that may be represented in different ways by different parts of a program. This requires constructing *generic procedures*—procedures that can operate on data that may be represented in more than one way. Our main technique for building generic procedures will be to work in terms of data objects that have *type tags*, that is, data objects that include explicit information about how they are to be processed. We will also discuss *data-directed* programming, a powerful and convenient implementation strategy for additively assembling systems with generic operations.

We begin with the simple complex-number example. We will see how type tags and data-directed style enable us to design separate rectangular and polar representations for complex numbers while maintaining the notion of an abstract "complex-number" data object. We will accomplish this by defining arithmetic procedures for complex numbers (`add-complex`, `sub-complex`, `mul-complex`, and `div-complex`) in terms of generic selectors that access parts of a complex number independent of how the number is represented. The resulting complex-number system, as shown in Figure 2.19, contains two different kinds of abstraction barriers. The "horizontal" abstraction barriers play the same role as the ones in Figure 2.1. They isolate "higher-level" operations from "lower-level" representations. In addition,




Figure 2.19: Data-abstraction barriers in the complex-number system.

there is a "vertical" barrier that gives us the ability to separately design and install alternative representations.

In Section 2.5 we will show how to use type tags and data-directed style to develop a generic arithmetic package. This provides procedures (`add`, `mul`, and so on) that can be used to manipulate all sorts of "numbers" and can be easily extended when a new kind of number is needed. In Section 2.5.3, we'll show how to use generic arithmetic in a system that performs symbolic algebra.

2.4.1 Representations for Complex Numbers

We will develop a system that performs arithmetic operations on complex numbers as a simple but unrealistic example of a program that uses generic operations. We begin by discussing two plausible representations for complex numbers as ordered pairs: rectangular form (real part and imaginary part)

and polar form (magnitude and angle).[78] Section 2.4.2 will show how both representations can be made to coexist in a single system through the use of type tags and generic operations.

Like rational numbers, complex numbers are naturally represented as ordered pairs. The set of complex numbers can be thought of as a two-dimensional space with two orthogonal axes, the "real" axis and the "imaginary" axis. (See Figure 2.20.) From this point of view, the complex number $z = x + iy$ (where $i^2 = -1$) can be thought of as the point in the plane whose real coordinate is x and whose imaginary coordinate is y. Addition of complex numbers reduces in this representation to addition of coordinates:

$$\begin{aligned} \text{Real-part}(z_1 + z_2) &= \text{Real-part}(z_1) + \text{Real-part}(z_2), \\ \text{Imaginary-part}(z_1 + z_2) &= \text{Imaginary-part}(z_1) + \text{Imaginary-part}(z_2). \end{aligned}$$

When multiplying complex numbers, it is more natural to think in terms of representing a complex number in polar form, as a magnitude and an angle (r and A in Figure 2.20). The product of two complex numbers is the vector obtained by stretching one complex number by the length of the other and then rotating it through the angle of the other:

$$\begin{aligned} \text{Magnitude}(z_1 \cdot z_2) &= \text{Magnitude}(z_1) \cdot \text{Magnitude}(z_2), \\ \text{Angle}(z_1 \cdot z_2) &= \text{Angle}(z_1) + \text{Angle}(z_2). \end{aligned}$$

Thus, there are two different representations for complex numbers, which are appropriate for different operations. Yet, from the viewpoint of someone

[78] In actual computational systems, rectangular form is preferable to polar form most of the time because of roundoff errors in conversion between rectangular and polar form. This is why the complex-number example is unrealistic. Nevertheless, it provides a clear illustration of the design of a system using generic operations and a good introduction to the more substantial systems to be developed later in this chapter.




Figure 2.20: Complex numbers as points in the plane.

writing a program that uses complex numbers, the principle of data abstraction suggests that all the operations for manipulating complex numbers should be available regardless of which representation is used by the computer. For example, it is often useful to be able to find the magnitude of a complex number that is specified by rectangular coordinates. Similarly, it is often useful to be able to determine the real part of a complex number that is specified by polar coordinates.

To design such a system, we can follow the same data-abstraction strategy we followed in designing the rational-number package in Section 2.1.1. Assume that the operations on complex numbers are implemented in terms of four selectors: `real-part`, `imag-part`, `magnitude` and `angle`. Also assume that we have two procedures for constructing complex numbers: `make-from-real-imag` returns a complex number with specified real and imaginary parts, and `make-from-mag-ang` returns a complex number with specified magnitude and angle. These procedures have the property that, for any complex number `z`, both

```
(make-from-real-imag (real-part z) (imag-part z))
```

and

```
(make-from-mag-ang (magnitude z) (angle z))
```

produce complex numbers that are equal to `z`.

Using these constructors and selectors, we can implement arithmetic on complex numbers using the "abstract data" specified by the constructors and selectors, just as we did for rational numbers in Section 2.1.1. As shown in the formulas above, we can add and subtract complex numbers in terms of real and imaginary parts while multiplying and dividing complex numbers in terms of magnitudes and angles:

```
(define (add-complex z1 z2)
  (make-from-real-imag (+ (real-part z1) (real-part z2))
                       (+ (imag-part z1) (imag-part z2))))
(define (sub-complex z1 z2)
  (make-from-real-imag (- (real-part z1) (real-part z2))
                       (- (imag-part z1) (imag-part z2))))
(define (mul-complex z1 z2)
  (make-from-mag-ang (* (magnitude z1) (magnitude z2))
                     (+ (angle z1) (angle z2))))
(define (div-complex z1 z2)
  (make-from-mag-ang (/ (magnitude z1) (magnitude z2))
                     (- (angle z1) (angle z2))))
```

To complete the complex-number package, we must choose a representation and we must implement the constructors and selectors in terms of primitive numbers and primitive list structure. There are two obvious ways to do this: We can represent a complex number in "rectangular form" as a pair (real part, imaginary part) or in "polar form" as a pair (magnitude, angle). Which shall we choose?

In order to make the different choices concrete, imagine that there are two programmers, Ben Bitdiddle and Alyssa P. Hacker, who are independently designing representations for the complex-number system. Ben chooses to represent complex numbers in rectangular form. With this choice, selecting the real and imaginary parts of a complex number is straightforward, as is constructing a complex number with given real and imaginary parts. To find the magnitude and the angle, or to construct a complex number with a given magnitude and angle, he uses the trigonometric relations

$$\begin{aligned} x &= r\cos A, & r &= \sqrt{x^2+y^2},\\ y &= r\sin A, & A &= \arctan(y,x), \end{aligned}$$

which relate the real and imaginary parts (x, y) to the magnitude and the angle (r, A).[79] Ben's representation is therefore given by the following selectors and constructors:

```
(define (real-part z) (car z))
(define (imag-part z) (cdr z))
(define (magnitude z)
  (sqrt (+ (square (real-part z))
           (square (imag-part z)))))
(define (angle z)
  (atan (imag-part z) (real-part z)))
(define (make-from-real-imag x y) (cons x y))
(define (make-from-mag-ang r a)
  (cons (* r (cos a)) (* r (sin a))))
```

Alyssa, in contrast, chooses to represent complex numbers in polar form. For her, selecting the magnitude and angle is straightforward, but she has to use

[79] The arctangent function referred to here, computed by Scheme's `atan` procedure, is defined so as to take two arguments y and x and to return the angle whose tangent is y/x. The signs of the arguments determine the quadrant of the angle.

the trigonometric relations to obtain the real and imaginary parts. Alyssa's representation is:

```
(define (real-part z) (* (magnitude z) (cos (angle z))))
(define (imag-part z) (* (magnitude z) (sin (angle z))))
(define (magnitude z) (car z))
(define (angle z) (cdr z))
(define (make-from-real-imag x y)
  (cons (sqrt (+ (square x) (square y)))
        (atan y x)))
(define (make-from-mag-ang r a) (cons r a))
```

The discipline of data abstraction ensures that the same implementation of `add-complex`, `sub-complex`, `mul-complex`, and `div-complex` will work with either Ben's representation or Alyssa's representation.

2.4.2 Tagged data

One way to view data abstraction is as an application of the "principle of least commitment." In implementing the complex-number system in Section 2.4.1, we can use either Ben's rectangular representation or Alyssa's polar representation. The abstraction barrier formed by the selectors and constructors permits us to defer to the last possible moment the choice of a concrete representation for our data objects and thus retain maximum flexibility in our system design.

The principle of least commitment can be carried to even further extremes. If we desire, we can maintain the ambiguity of representation even *after* we have designed the selectors and constructors, and elect to use both Ben's representation *and* Alyssa's representation. If both representations are included in a single system, however, we will need some way to distinguish data in polar form from data in rectangular form. Otherwise, if we were asked, for instance, to find the `magnitude` of the pair (3, 4), we wouldn't

know whether to answer 5 (interpreting the number in rectangular form) or 3 (interpreting the number in polar form). A straightforward way to accomplish this distinction is to include a *type tag*—the symbol `rectangular` or `polar`—as part of each complex number. Then when we need to manipulate a complex number we can use the tag to decide which selector to apply.

In order to manipulate tagged data, we will assume that we have procedures `type-tag` and `contents` that extract from a data object the tag and the actual contents (the polar or rectangular coordinates, in the case of a complex number). We will also postulate a procedure `attach-tag` that takes a tag and contents and produces a tagged data object. A straightforward way to implement this is to use ordinary list structure:

```
(define (attach-tag type-tag contents)
  (cons type-tag contents))
(define (type-tag datum)
  (if (pair? datum)
      (car datum)
      (error "Bad tagged datum: TYPE-TAG" datum)))
(define (contents datum)
  (if (pair? datum)
      (cdr datum)
      (error "Bad tagged datum: CONTENTS" datum)))
```

Using these procedures, we can define predicates `rectangular?` and `polar?`, which recognize rectangular and polar numbers, respectively:

```
(define (rectangular? z)
  (eq? (type-tag z) 'rectangular))
(define (polar? z) (eq? (type-tag z) 'polar))
```

With type tags, Ben and Alyssa can now modify their code so that their two different representations can coexist in the same system. Whenever Ben con-

structs a complex number, he tags it as rectangular. Whenever Alyssa constructs a complex number, she tags it as polar. In addition, Ben and Alyssa must make sure that the names of their procedures do not conflict. One way to do this is for Ben to append the suffix `rectangular` to the name of each of his representation procedures and for Alyssa to append `polar` to the names of hers. Here is Ben's revised rectangular representation from Section 2.4.1:

```
(define (real-part-rectangular z) (car z))
(define (imag-part-rectangular z) (cdr z))
(define (magnitude-rectangular z)
  (sqrt (+ (square (real-part-rectangular z))
           (square (imag-part-rectangular z)))))
(define (angle-rectangular z)
  (atan (imag-part-rectangular z)
        (real-part-rectangular z)))
(define (make-from-real-imag-rectangular x y)
  (attach-tag 'rectangular (cons x y)))
(define (make-from-mag-ang-rectangular r a)
  (attach-tag 'rectangular
              (cons (* r (cos a)) (* r (sin a)))))
```

and here is Alyssa's revised polar representation:

```
(define (real-part-polar z)
  (* (magnitude-polar z) (cos (angle-polar z))))
(define (imag-part-polar z)
  (* (magnitude-polar z) (sin (angle-polar z))))
(define (magnitude-polar z) (car z))
(define (angle-polar z) (cdr z))
(define (make-from-real-imag-polar x y)
  (attach-tag 'polar
              (cons (sqrt (+ (square x) (square y)))
                    (atan y x))))
```

```
(define (make-from-mag-ang-polar r a)
  (attach-tag 'polar (cons r a)))
```

Each generic selector is implemented as a procedure that checks the tag of its argument and calls the appropriate procedure for handling data of that type. For example, to obtain the real part of a complex number, `real-part` examines the tag to determine whether to use Ben's `real-part-rectangular` or Alyssa's `real-part-polar`. In either case, we use `contents` to extract the bare, untagged datum and send this to the rectangular or polar procedure as required:

```
(define (real-part z)
  (cond ((rectangular? z)
         (real-part-rectangular (contents z)))
        ((polar? z)
         (real-part-polar (contents z)))
        (else (error "Unknown type: REAL-PART" z))))
(define (imag-part z)
  (cond ((rectangular? z)
         (imag-part-rectangular (contents z)))
        ((polar? z)
         (imag-part-polar (contents z)))
        (else (error "Unknown type: IMAG-PART" z))))
(define (magnitude z)
  (cond ((rectangular? z)
         (magnitude-rectangular (contents z)))
        ((polar? z)
         (magnitude-polar (contents z)))
        (else (error "Unknown type: MAGNITUDE" z))))
(define (angle z)
  (cond ((rectangular? z)
         (angle-rectangular (contents z)))
        ((polar? z)
```

```
         (angle-polar (contents z)))
        (else (error "Unknown type: ANGLE" z))))
```

To implement the complex-number arithmetic operations, we can use the same procedures `add-complex`, `sub-complex`, `mul-complex`, and `div-complex` from Section 2.4.1, because the selectors they call are generic, and so will work with either representation. For example, the procedure `add-complex` is still

```
(define (add-complex z1 z2)
  (make-from-real-imag (+ (real-part z1) (real-part z2))
                       (+ (imag-part z1) (imag-part z2))))
```

Finally, we must choose whether to construct complex numbers using Ben's representation or Alyssa's representation. One reasonable choice is to construct rectangular numbers whenever we have real and imaginary parts and to construct polar numbers whenever we have magnitudes and angles:

```
(define (make-from-real-imag x y)
  (make-from-real-imag-rectangular x y))
(define (make-from-mag-ang r a)
  (make-from-mag-ang-polar r a))
```

The resulting complex-number system has the structure shown in Figure 2.21. The system has been decomposed into three relatively independent parts: the complex-number-arithmetic operations, Alyssa's polar implementation, and Ben's rectangular implementation. The polar and rectangular implementations could have been written by Ben and Alyssa working separately, and both of these can be used as underlying representations by a third programmer implementing the complex-arithmetic procedures in terms of the abstract constructor/selector interface.

Since each data object is tagged with its type, the selectors operate on the data in a generic manner. That is, each selector is defined to have a behavior




Figure 2.21: Structure of the generic complex-arithmetic system.

that depends upon the particular type of data it is applied to. Notice the general mechanism for interfacing the separate representations: Within a given representation implementation (say, Alyssa's polar package) a complex number is an untyped pair (magnitude, angle). When a generic selector operates on a number of `polar` type, it strips off the tag and passes the contents on to Alyssa's code. Conversely, when Alyssa constructs a number for general use, she tags it with a type so that it can be appropriately recognized by the higher-level procedures. This discipline of stripping off and attaching tags as data objects are passed from level to level can be an important organizational strategy, as we shall see in Section 2.5.

2.4.3 Data-Directed Programming and Additivity

The general strategy of checking the type of a datum and calling an appropriate procedure is called *dispatching on type*. This is a powerful strategy for obtaining modularity in system design. On the other hand, implementing

the dispatch as in Section 2.4.2 has two significant weaknesses. One weakness is that the generic interface procedures (`real-part`, `imag-part`, `magnitude`, and `angle`) must know about all the different representations. For instance, suppose we wanted to incorporate a new representation for complex numbers into our complex-number system. We would need to identify this new representation with a type, and then add a clause to each of the generic interface procedures to check for the new type and apply the appropriate selector for that representation.

Another weakness of the technique is that even though the individual representations can be designed separately, we must guarantee that no two procedures in the entire system have the same name. This is why Ben and Alyssa had to change the names of their original procedures from Section 2.4.1.

The issue underlying both of these weaknesses is that the technique for implementing generic interfaces is not *additive*. The person implementing the generic selector procedures must modify those procedures each time a new representation is installed, and the people interfacing the individual representations must modify their code to avoid name conflicts. In each of these cases, the changes that must be made to the code are straightforward, but they must be made nonetheless, and this is a source of inconvenience and error. This is not much of a problem for the complex-number system as it stands, but suppose there were not two but hundreds of different representations for complex numbers. And suppose that there were many generic selectors to be maintained in the abstract-data interface. Suppose, in fact, that no one programmer knew all the interface procedures or all the representations. The problem is real and must be addressed in such programs as large-scale database-management systems.

What we need is a means for modularizing the system design even further. This is provided by the programming technique known as *data-directed*

programming. To understand how data-directed programming works, begin with the observation that whenever we deal with a set of generic operations that are common to a set of different types we are, in effect, dealing with a two-dimensional table that contains the possible operations on one axis and the possible types on the other axis. The entries in the table are the procedures that implement each operation for each type of argument presented. In the complex-number system developed in the previous section, the correspondence between operation name, data type, and actual procedure was spread out among the various conditional clauses in the generic interface procedures. But the same information could have been organized in a table, as shown in Figure 2.22.

Data-directed programming is the technique of designing programs to work with such a table directly. Previously, we implemented the mechanism that interfaces the complex-arithmetic code with the two representation packages as a set of procedures that each perform an explicit dispatch on type. Here we will implement the interface as a single procedure that looks up the combination of the operation name and argument type in the table to find the correct procedure to apply, and then applies it to the contents of the argument. If we do this, then to add a new representation package to the system we need not change any existing procedures; we need only add new entries to the table.

To implement this plan, assume that we have two procedures, `put` and `get`, for manipulating the operation-and-type table:

- `(put` ⟨*op*⟩ ⟨*type*⟩ ⟨*item*⟩`)` installs the ⟨*item*⟩ in the table, indexed by the ⟨*op*⟩ and the ⟨*type*⟩.
- `(get` ⟨*op*⟩ ⟨*type*⟩`)` looks up the ⟨*op*⟩, ⟨*type*⟩ entry in the table and returns the item found there. If no item is found, `get` returns false.

For now, we can assume that `put` and `get` are included in our language.




Figure 2.22: Table of operations for the complex-number system.

In Chapter 3 (Section 3.3.3) we will see how to implement these and other operations for manipulating tables.

Here is how data-directed programming can be used in the complex-number system. Ben, who developed the rectangular representation, implements his code just as he did originally. He defines a collection of procedures, or a *package*, and interfaces these to the rest of the system by adding entries to the table that tell the system how to operate on rectangular numbers. This is accomplished by calling the following procedure:

```
(define (install-rectangular-package)
  ;; internal procedures
  (define (real-part z) (car z))
  (define (imag-part z) (cdr z))
  (define (make-from-real-imag x y) (cons x y))
  (define (magnitude z)
    (sqrt (+ (square (real-part z))
             (square (imag-part z)))))
  (define (angle z)
    (atan (imag-part z) (real-part z)))
  (define (make-from-mag-ang r a)
    (cons (* r (cos a)) (* r (sin a)))))
```

```
  ;; interface to the rest of the system
  (define (tag x) (attach-tag 'rectangular x))
  (put 'real-part '(rectangular) real-part)
  (put 'imag-part '(rectangular) imag-part)
  (put 'magnitude '(rectangular) magnitude)
  (put 'angle '(rectangular) angle)
  (put 'make-from-real-imag 'rectangular
       (lambda (x y) (tag (make-from-real-imag x y))))
  (put 'make-from-mag-ang 'rectangular
       (lambda (r a) (tag (make-from-mag-ang r a))))
  'done)
```

Notice that the internal procedures here are the same procedures from Section 2.4.1 that Ben wrote when he was working in isolation. No changes are necessary in order to interface them to the rest of the system. Moreover, since these procedure definitions are internal to the installation procedure, Ben needn't worry about name conflicts with other procedures outside the rectangular package. To interface these to the rest of the system, Ben installs his `real-part` procedure under the operation name `real-part` and the type `(rectangular)`, and similarly for the other selectors.[80] The interface also defines the constructors to be used by the external system.[81] These are identical to Ben's internally defined constructors, except that they attach the tag.

Alyssa's polar package is analogous:

```
(define (install-polar-package)
  ;; internal procedures
  (define (magnitude z) (car z))
```

[80] We use the list `(rectangular)` rather than the symbol `rectangular` to allow for the possibility of operations with multiple arguments, not all of the same type.

[81] The type the constructors are installed under needn't be a list because a constructor is always used to make an object of one particular type.

```
(define (angle z) (cdr z))
(define (make-from-mag-ang r a) (cons r a))
(define (real-part z) (* (magnitude z) (cos (angle z))))
(define (imag-part z) (* (magnitude z) (sin (angle z))))
(define (make-from-real-imag x y)
  (cons (sqrt (+ (square x) (square y)))
        (atan y x)))
;; interface to the rest of the system
(define (tag x) (attach-tag 'polar x))
(put 'real-part '(polar) real-part)
(put 'imag-part '(polar) imag-part)
(put 'magnitude '(polar) magnitude)
(put 'angle '(polar) angle)
(put 'make-from-real-imag 'polar
     (lambda (x y) (tag (make-from-real-imag x y))))
(put 'make-from-mag-ang 'polar
     (lambda (r a) (tag (make-from-mag-ang r a))))
'done)
```

Even though Ben and Alyssa both still use their original procedures defined with the same names as each other's (e.g., `real-part`), these definitions are now internal to different procedures (see Section 1.1.8), so there is no name conflict.

The complex-arithmetic selectors access the table by means of a general "operation" procedure called `apply-generic`, which applies a generic operation to some arguments. `apply-generic` looks in the table under the name of the operation and the types of the arguments and applies the resulting procedure if one is present:[82]

[82] `apply-generic` uses the dotted-tail notation described in Exercise 2.20, because different generic operations may take different numbers of arguments. In `apply-generic`, `op` has as its value the first argument to `apply-generic` and `args` has as its value a list of the remaining arguments.

```
(define (apply-generic op . args)
  (let ((type-tags (map type-tag args)))
    (let ((proc (get op type-tags)))
      (if proc
          (apply proc (map contents args))
          (error
            "No method for these types: APPLY-GENERIC"
            (list op type-tags))))))
```

Using `apply-generic`, we can define our generic selectors as follows:

```
(define (real-part z) (apply-generic 'real-part z))
(define (imag-part z) (apply-generic 'imag-part z))
(define (magnitude z) (apply-generic 'magnitude z))
(define (angle z) (apply-generic 'angle z))
```

Observe that these do not change at all if a new representation is added to the system.

We can also extract from the table the constructors to be used by the programs external to the packages in making complex numbers from real and imaginary parts and from magnitudes and angles. As in Section 2.4.2, we construct rectangular numbers whenever we have real and imaginary parts, and polar numbers whenever we have magnitudes and angles:

```
(define (make-from-real-imag x y)
  ((get 'make-from-real-imag 'rectangular) x y))
(define (make-from-mag-ang r a)
  ((get 'make-from-mag-ang 'polar) r a))
```

`apply-generic` also uses the primitive procedure `apply`, which takes two arguments, a procedure and a list. `apply` applies the procedure, using the elements in the list as arguments. For example,

```
(apply + (list 1 2 3 4))
```

returns 10.

Exercise 2.73: Section 2.3.2 described a program that performs symbolic differentiation:

```
(define (deriv exp var)
  (cond ((number? exp) 0)
        ((variable? exp)
         (if (same-variable? exp var) 1 0))
        ((sum? exp)
         (make-sum (deriv (addend exp) var)
                   (deriv (augend exp) var)))
        ((product? exp)
         (make-sum (make-product
                    (multiplier exp)
                    (deriv (multiplicand exp) var))
                   (make-product
                    (deriv (multiplier exp) var)
                    (multiplicand exp))))
        ⟨more rules can be added here⟩
        (else (error "unknown expression type:
                      DERIV" exp))))
```

We can regard this program as performing a dispatch on the type of the expression to be differentiated. In this situation the "type tag" of the datum is the algebraic operator symbol (such as +) and the operation being performed is `deriv`. We can transform this program into data-directed style by rewriting the basic derivative procedure as

```
(define (deriv exp var)
  (cond ((number? exp) 0)
        ((variable? exp) (if (same-variable? exp var) 1
        (else ((get 'deriv (operator exp))
               (operands exp) var))))
(define (operator exp) (car exp))
```

```
(define (operands exp) (cdr exp))
```

a. Explain what was done above. Why can't we assimilate the predicates `number?` and `variable?` into the data-directed dispatch?

b. Write the procedures for derivatives of sums and products, and the auxiliary code required to install them in the table used by the program above.

c. Choose any additional differentiation rule that you like, such as the one for exponents (Exercise 2.56), and install it in this data-directed system.

d. In this simple algebraic manipulator the type of an expression is the algebraic operator that binds it together. Suppose, however, we indexed the procedures in the opposite way, so that the dispatch line in `deriv` looked like

```
((get (operator exp) 'deriv) (operands exp) var)
```

What corresponding changes to the derivative system are required?

Exercise 2.74: Insatiable Enterprises, Inc., is a highly decentralized conglomerate company consisting of a large number of independent divisions located all over the world. The company's computer facilities have just been interconnected by means of a clever network-interfacing scheme that makes the entire network appear to any user to be a single computer. Insatiable's president, in her first attempt to exploit the ability of the network to extract administrative information from division files, is dismayed to discover that, although all the division files have

been implemented as data structures in Scheme, the particular data structure used varies from division to division. A meeting of division managers is hastily called to search for a strategy to integrate the files that will satisfy headquarters' needs while preserving the existing autonomy of the divisions.

Show how such a strategy can be implemented with data-directed programming. As an example, suppose that each division's personnel records consist of a single file, which contains a set of records keyed on employees' names. The structure of the set varies from division to division. Furthermore, each employee's record is itself a set (structured differently from division to division) that contains information keyed under identifiers such as `address` and `salary`. In particular:

a. Implement for headquarters a `get-record` procedure that retrieves a specified employee's record from a specified personnel file. The procedure should be applicable to any division's file. Explain how the individual divisions' files should be structured. In particular, what type information must be supplied?

b. Implement for headquarters a `get-salary` procedure that returns the salary information from a given employee's record from any division's personnel file. How should the record be structured in order to make this operation work?

c. Implement for headquarters a `find-employee-record` procedure. This should search all the divisions' files for the record of a given employee and return the record. Assume that this procedure takes as arguments an employee's name and a list of all the divisions' files.

d. When Insatiable takes over a new company, what changes must be made in order to incorporate the new personnel information into the central system?

Message passing

The key idea of data-directed programming is to handle generic operations in programs by dealing explicitly with operation-and-type tables, such as the table in Figure 2.22. The style of programming we used in Section 2.4.2 organized the required dispatching on type by having each operation take care of its own dispatching. In effect, this decomposes the operation-and-type table into rows, with each generic operation procedure representing a row of the table.

An alternative implementation strategy is to decompose the table into columns and, instead of using "intelligent operations" that dispatch on data types, to work with "intelligent data objects" that dispatch on operation names. We can do this by arranging things so that a data object, such as a rectangular number, is represented as a procedure that takes as input the required operation name and performs the operation indicated. In such a discipline, `make-from-real-imag` could be written as

```
(define (make-from-real-imag x y)
  (define (dispatch op)
    (cond ((eq? op 'real-part) x)
          ((eq? op 'imag-part) y)
          ((eq? op 'magnitude) (sqrt (+ (square x) (square y
          ((eq? op 'angle) (atan y x))
          (else (error "Unknown op: MAKE-FROM-REAL-IMAG" op)
  dispatch)
```

The corresponding `apply-generic` procedure, which applies a generic operation to an argument, now simply feeds the operation's name to the data

object and lets the object do the work:[83]

```
(define (apply-generic op arg) (arg op))
```

Note that the value returned by `make-from-real-imag` is a procedure —the internal `dispatch` procedure. This is the procedure that is invoked when `apply-generic` requests an operation to be performed.

This style of programming is called *message passing*. The name comes from the image that a data object is an entity that receives the requested operation name as a "message." We have already seen an example of message passing in Section 2.1.3, where we saw how `cons`, `car`, and `cdr` could be defined with no data objects but only procedures. Here we see that message passing is not a mathematical trick but a useful technique for organizing systems with generic operations. In the remainder of this chapter we will continue to use data-directed programming, rather than message passing, to discuss generic arithmetic operations. In Chapter 3 we will return to message passing, and we will see that it can be a powerful tool for structuring simulation programs.

Exercise 2.75: Implement the constructor `make-from-mag-ang` in message-passing style. This procedure should be analogous to the `make-from-real-imag` procedure given above.

Exercise 2.76: As a large system with generic operations evolves, new types of data objects or new operations may be needed. For each of the three strategies—generic operations with explicit dispatch, data-directed style, and message-passing-style—describe the changes that must be made to a system in order to add new types or new operations. Which organization would be most appropriate for a system in which new types must often be

[83] One limitation of this organization is it permits only generic procedures of one argument.

added? Which would be most appropriate for a system in which new operations must often be added?

2.5 Systems with Generic Operations

In the previous section, we saw how to design systems in which data objects can be represented in more than one way. The key idea is to link the code that specifies the data operations to the several representations by means of generic interface procedures. Now we will see how to use this same idea not only to define operations that are generic over different representations but also to define operations that are generic over different kinds of arguments. We have already seen several different packages of arithmetic operations: the primitive arithmetic (+, −, *, /) built into our language, the rational-number arithmetic (`add-rat`, `sub-rat`, `mul-rat`, `div-rat`) of Section 2.1.1, and the complex-number arithmetic that we implemented in Section 2.4.3. We will now use data-directed techniques to construct a package of arithmetic operations that incorporates all the arithmetic packages we have already constructed.

Figure 2.23 shows the structure of the system we shall build. Notice the abstraction barriers. From the perspective of someone using "numbers," there is a single procedure `add` that operates on whatever numbers are supplied. `add` is part of a generic interface that allows the separate ordinary-arithmetic, rational-arithmetic, and complex-arithmetic packages to be accessed uniformly by programs that use numbers. Any individual arithmetic package (such as the complex package) may itself be accessed through generic procedures (such as `add-complex`) that combine packages designed for different representations (such as rectangular and polar). Moreover, the structure of the system is additive, so that one can design the individual arithmetic packages separately and combine them to produce a generic arithmetic sys-




Figure 2.23: Generic arithmetic system.

tem.

2.5.1 Generic Arithmetic Operations

The task of designing generic arithmetic operations is analogous to that of designing the generic complex-number operations. We would like, for instance, to have a generic addition procedure `add` that acts like ordinary primitive addition `+` on ordinary numbers, like `add-rat` on rational numbers, and like `add-complex` on complex numbers. We can implement `add`, and the other generic arithmetic operations, by following the same strategy we used in Section 2.4.3 to implement the generic selectors for complex numbers. We will attach a type tag to each kind of number and cause the generic procedure to dispatch to an appropriate package according to the data type of its arguments.

The generic arithmetic procedures are defined as follows:

```
(define (add x y) (apply-generic 'add x y))
(define (sub x y) (apply-generic 'sub x y))
(define (mul x y) (apply-generic 'mul x y))
(define (div x y) (apply-generic 'div x y))
```

We begin by installing a package for handling *ordinary* numbers, that is, the primitive numbers of our language. We will tag these with the symbol `scheme-number`. The arithmetic operations in this package are the primitive arithmetic procedures (so there is no need to define extra procedures to handle the untagged numbers). Since these operations each take two arguments, they are installed in the table keyed by the list `(scheme-number scheme-number)`:

```
(define (install-scheme-number-package)
  (define (tag x) (attach-tag 'scheme-number x))
  (put 'add '(scheme-number scheme-number)
       (lambda (x y) (tag (+ x y))))
  (put 'sub '(scheme-number scheme-number)
       (lambda (x y) (tag (- x y))))
  (put 'mul '(scheme-number scheme-number)
       (lambda (x y) (tag (* x y))))
  (put 'div '(scheme-number scheme-number)
       (lambda (x y) (tag (/ x y))))
  (put 'make 'scheme-number (lambda (x) (tag x)))
  'done)
```

Users of the Scheme-number package will create (tagged) ordinary numbers by means of the procedure:

```
(define (make-scheme-number n)
  ((get 'make 'scheme-number) n))
```

Now that the framework of the generic arithmetic system is in place, we can readily include new kinds of numbers. Here is a package that performs rational arithmetic. Notice that, as a benefit of additivity, we can use without modification the rational-number code from Section 2.1.1 as the internal procedures in the package:

```
(define (install-rational-package)
  ;; internal procedures
  (define (numer x) (car x))
  (define (denom x) (cdr x))
  (define (make-rat n d)
    (let ((g (gcd n d)))
      (cons (/ n g) (/ d g))))
  (define (add-rat x y)
    (make-rat (+ (* (numer x) (denom y))
                 (* (numer y) (denom x)))
              (* (denom x) (denom y))))
  (define (sub-rat x y)
    (make-rat (- (* (numer x) (denom y))
                 (* (numer y) (denom x)))
              (* (denom x) (denom y))))
  (define (mul-rat x y)
    (make-rat (* (numer x) (numer y))
              (* (denom x) (denom y))))
  (define (div-rat x y)
    (make-rat (* (numer x) (denom y))
              (* (denom x) (numer y))))
  ;; interface to rest of the system
  (define (tag x) (attach-tag 'rational x))
  (put 'add '(rational rational)
       (lambda (x y) (tag (add-rat x y))))
  (put 'sub '(rational rational)
       (lambda (x y) (tag (sub-rat x y))))
```

```
  (put 'mul '(rational rational)
       (lambda (x y) (tag (mul-rat x y))))
  (put 'div '(rational rational)
       (lambda (x y) (tag (div-rat x y))))
  (put 'make 'rational
       (lambda (n d) (tag (make-rat n d))))
  'done)
(define (make-rational n d)
  ((get 'make 'rational) n d))
```

We can install a similar package to handle complex numbers, using the tag `complex`. In creating the package, we extract from the table the operations `make-from-real-imag` and `make-from-mag-ang` that were defined by the rectangular and polar packages. Additivity permits us to use, as the internal operations, the same `add-complex`, `sub-complex`, `mul-complex`, and `div-complex` procedures from Section 2.4.1.

```
(define (install-complex-package)
  ;; imported procedures from rectangular and polar packages
  (define (make-from-real-imag x y)
    ((get 'make-from-real-imag 'rectangular) x y))
  (define (make-from-mag-ang r a)
    ((get 'make-from-mag-ang 'polar) r a))
  ;; internal procedures
  (define (add-complex z1 z2)
    (make-from-real-imag (+ (real-part z1) (real-part z2))
                         (+ (imag-part z1) (imag-part z2))))
  (define (sub-complex z1 z2)
    (make-from-real-imag (- (real-part z1) (real-part z2))
                         (- (imag-part z1) (imag-part z2))))
  (define (mul-complex z1 z2)
    (make-from-mag-ang (* (magnitude z1) (magnitude z2))
                       (+ (angle z1) (angle z2))))
  (define (div-complex z1 z2)
```

```
    (make-from-mag-ang (/ (magnitude z1) (magnitude z2))
                       (- (angle z1) (angle z2))))
  ;; interface to rest of the system
  (define (tag z) (attach-tag 'complex z))
  (put 'add '(complex complex)
       (lambda (z1 z2) (tag (add-complex z1 z2))))
  (put 'sub '(complex complex)
       (lambda (z1 z2) (tag (sub-complex z1 z2))))
  (put 'mul '(complex complex)
       (lambda (z1 z2) (tag (mul-complex z1 z2))))
  (put 'div '(complex complex)
       (lambda (z1 z2) (tag (div-complex z1 z2))))
  (put 'make-from-real-imag 'complex
       (lambda (x y) (tag (make-from-real-imag x y))))
  (put 'make-from-mag-ang 'complex
       (lambda (r a) (tag (make-from-mag-ang r a))))
  'done)
```

Programs outside the complex-number package can construct complex numbers either from real and imaginary parts or from magnitudes and angles. Notice how the underlying procedures, originally defined in the rectangular and polar packages, are exported to the complex package, and exported from there to the outside world.

```
(define (make-complex-from-real-imag x y)
  ((get 'make-from-real-imag 'complex) x y))
(define (make-complex-from-mag-ang r a)
  ((get 'make-from-mag-ang 'complex) r a))
```

What we have here is a two-level tag system. A typical complex number, such as $3 + 4i$ in rectangular form, would be represented as shown in Figure 2.24. The outer tag (`complex`) is used to direct the number to the complex package. Once within the complex package, the next tag (`rectangular`) is used to direct the number to the rectangular package. In a large and com-




Figure 2.24: Representation of $3 + 4i$ in rectangular form.

plicated system there might be many levels, each interfaced with the next by means of generic operations. As a data object is passed "downward," the outer tag that is used to direct it to the appropriate package is stripped off (by applying `contents`) and the next level of tag (if any) becomes visible to be used for further dispatching.

In the above packages, we used `add-rat`, `add-complex`, and the other arithmetic procedures exactly as originally written. Once these definitions are internal to different installation procedures, however, they no longer need names that are distinct from each other: we could simply name them `add`, `sub`, `mul`, and `div` in both packages.

> **Exercise 2.77:** Louis Reasoner tries to evaluate the expression `(magnitude z)` where `z` is the object shown in Figure 2.24. To his surprise, instead of the answer 5 he gets an error message from `apply-generic`, saying there is no method for the operation `magnitude` on the types `(complex)`. He shows this interaction to Alyssa P. Hacker, who says "The problem is that the complex-number selectors were never defined for `complex` numbers, just for `polar` and `rectangular` numbers. All you have to do to make this work is add the following to the `complex` package:"
>
> ```
> (put 'real-part '(complex) real-part)
> ```

```
(put 'imag-part '(complex) imag-part)
(put 'magnitude '(complex) magnitude)
(put 'angle '(complex) angle)
```

Describe in detail why this works. As an example, trace through all the procedures called in evaluating the expression `(magnitude z)` where `z` is the object shown in Figure 2.24. In particular, how many times is `apply-generic` invoked? What procedure is dispatched to in each case?

Exercise 2.78: The internal procedures in the `scheme-number` package are essentially nothing more than calls to the primitive procedures +, −, etc. It was not possible to use the primitives of the language directly because our type-tag system requires that each data object have a type attached to it. In fact, however, all Lisp implementations do have a type system, which they use internally. Primitive predicates such as `symbol?` and `number?` determine whether data objects have particular types. Modify the definitions of `type-tag`, `contents`, and `attach-tag` from Section 2.4.2 so that our generic system takes advantage of Scheme's internal type system. That is to say, the system should work as before except that ordinary numbers should be represented simply as Scheme numbers rather than as pairs whose `car` is the symbol `scheme-number`.

Exercise 2.79: Define a generic equality predicate `equ?` that tests the equality of two numbers, and install it in the generic arithmetic package. This operation should work for ordinary numbers, rational numbers, and complex numbers.

Exercise 2.80: Define a generic predicate `=zero?` that tests if its argument is zero, and install it in the generic arithmetic package. This operation should work for ordinary numbers, rational numbers, and complex numbers.

2.5.2 Combining Data of Different Types

We have seen how to define a unified arithmetic system that encompasses ordinary numbers, complex numbers, rational numbers, and any other type of number we might decide to invent, but we have ignored an important issue. The operations we have defined so far treat the different data types as being completely independent. Thus, there are separate packages for adding, say, two ordinary numbers, or two complex numbers. What we have not yet considered is the fact that it is meaningful to define operations that cross the type boundaries, such as the addition of a complex number to an ordinary number. We have gone to great pains to introduce barriers between parts of our programs so that they can be developed and understood separately. We would like to introduce the cross-type operations in some carefully controlled way, so that we can support them without seriously violating our module boundaries.

One way to handle cross-type operations is to design a different procedure for each possible combination of types for which the operation is valid. For example, we could extend the complex-number package so that it provides a procedure for adding complex numbers to ordinary numbers and installs this in the table using the tag `(complex scheme-number)`:[84]

```
;; to be included in the complex package
(define (add-complex-to-schemenum z x)
```

[84] We also have to supply an almost identical procedure to handle the types `(scheme-number complex)`.

```
  (make-from-real-imag (+ (real-part z) x) (imag-part z)))
(put 'add '(complex scheme-number)
     (lambda (z x) (tag (add-complex-to-schemenum z x))))
```

This technique works, but it is cumbersome. With such a system, the cost of introducing a new type is not just the construction of the package of procedures for that type but also the construction and installation of the procedures that implement the cross-type operations. This can easily be much more code than is needed to define the operations on the type itself. The method also undermines our ability to combine separate packages additively, or at least to limit the extent to which the implementors of the individual packages need to take account of other packages. For instance, in the example above, it seems reasonable that handling mixed operations on complex numbers and ordinary numbers should be the responsibility of the complex-number package. Combining rational numbers and complex numbers, however, might be done by the complex package, by the rational package, or by some third package that uses operations extracted from these two packages. Formulating coherent policies on the division of responsibility among packages can be an overwhelming task in designing systems with many packages and many cross-type operations.

Coercion

In the general situation of completely unrelated operations acting on completely unrelated types, implementing explicit cross-type operations, cumbersome though it may be, is the best that one can hope for. Fortunately, we can usually do better by taking advantage of additional structure that may be latent in our type system. Often the different data types are not completely independent, and there may be ways by which objects of one type may be viewed as being of another type. This process is called *coercion*. For example, if we are asked to arithmetically combine an ordinary number with a complex number, we can view the ordinary number as a complex number

whose imaginary part is zero. This transforms the problem to that of combining two complex numbers, which can be handled in the ordinary way by the complex-arithmetic package.

In general, we can implement this idea by designing coercion procedures that transform an object of one type into an equivalent object of another type. Here is a typical coercion procedure, which transforms a given ordinary number to a complex number with that real part and zero imaginary part:

```
(define (scheme-number->complex n)
  (make-complex-from-real-imag (contents n) 0))
```

We install these coercion procedures in a special coercion table, indexed under the names of the two types:

```
(put-coercion 'scheme-number
              'complex
              scheme-number->complex)
```

(We assume that there are `put-coercion` and `get-coercion` procedures available for manipulating this table.) Generally some of the slots in the table will be empty, because it is not generally possible to coerce an arbitrary data object of each type into all other types. For example, there is no way to coerce an arbitrary complex number to an ordinary number, so there will be no general `complex->scheme-number` procedure included in the table.

Once the coercion table has been set up, we can handle coercion in a uniform manner by modifying the `apply-generic` procedure of Section 2.4.3. When asked to apply an operation, we first check whether the operation is defined for the arguments' types, just as before. If so, we dispatch to the procedure found in the operation-and-type table. Otherwise, we try coercion. For simplicity, we consider only the case where there are two arguments.[85]

[85] See Exercise 2.82 for generalizations.

We check the coercion table to see if objects of the first type can be coerced to the second type. If so, we coerce the first argument and try the operation again. If objects of the first type cannot in general be coerced to the second type, we try the coercion the other way around to see if there is a way to coerce the second argument to the type of the first argument. Finally, if there is no known way to coerce either type to the other type, we give up. Here is the procedure:

```
(define (apply-generic op . args)
  (let ((type-tags (map type-tag args)))
    (let ((proc (get op type-tags)))
      (if proc
          (apply proc (map contents args))
          (if (= (length args) 2)
              (let ((type1 (car type-tags))
                    (type2 (cadr type-tags))
                    (a1 (car args))
                    (a2 (cadr args)))
                (let ((t1->t2 (get-coercion type1 type2))
                      (t2->t1 (get-coercion type2 type1)))
                  (cond (t1->t2
                         (apply-generic op (t1->t2 a1) a2))
                        (t2->t1
                         (apply-generic op a1 (t2->t1 a2)))
                        (else (error "No method for these ty
                                     (list op type-tags))))))
              (error "No method for these types"
                     (list op type-tags)))))))
```

This coercion scheme has many advantages over the method of defining explicit cross-type operations, as outlined above. Although we still need to write coercion procedures to relate the types (possibly n^2 procedures for a system with n types), we need to write only one procedure for each pair of types

rather than a different procedure for each collection of types and each generic operation.[86] What we are counting on here is the fact that the appropriate transformation between types depends only on the types themselves, not on the operation to be applied.

On the other hand, there may be applications for which our coercion scheme is not general enough. Even when neither of the objects to be combined can be converted to the type of the other it may still be possible to perform the operation by converting both objects to a third type. In order to deal with such complexity and still preserve modularity in our programs, it is usually necessary to build systems that take advantage of still further structure in the relations among types, as we discuss next.

Hierarchies of types

The coercion scheme presented above relied on the existence of natural relations between pairs of types. Often there is more "global" structure in how the different types relate to each other. For instance, suppose we are building a generic arithmetic system to handle integers, rational numbers, real numbers, and complex numbers. In such a system, it is quite natural to regard an integer as a special kind of rational number, which is in turn a special kind of real number, which is in turn a special kind of complex number. What we actually have is a so-called *hierarchy of types*, in which, for example, integers are a *subtype* of rational numbers (i.e., any operation that can be applied to a

[86] If we are clever, we can usually get by with fewer than n^2 coercion procedures. For instance, if we know how to convert from type 1 to type 2 and from type 2 to type 3, then we can use this knowledge to convert from type 1 to type 3. This can greatly decrease the number of coercion procedures we need to supply explicitly when we add a new type to the system. If we are willing to build the required amount of sophistication into our system, we can have it search the "graph" of relations among types and automatically generate those coercion procedures that can be inferred from the ones that are supplied explicitly.




Figure 2.25: A tower of types.

rational number can automatically be applied to an integer). Conversely, we say that rational numbers form a *supertype* of integers. The particular hierarchy we have here is of a very simple kind, in which each type has at most one supertype and at most one subtype. Such a structure, called a *tower*, is illustrated in Figure 2.25.

If we have a tower structure, then we can greatly simplify the problem of adding a new type to the hierarchy, for we need only specify how the new type is embedded in the next supertype above it and how it is the supertype of the type below it. For example, if we want to add an integer to a complex number, we need not explicitly define a special coercion procedure `integer->complex`. Instead, we define how an integer can be transformed into a rational number, how a rational number is transformed into a real number, and how a real number is transformed into a complex number. We then allow the system to transform the integer into a complex number through these steps and then add the two complex numbers.

We can redesign our `apply-generic` procedure in the following way: For each type, we need to supply a `raise` procedure, which "raises" objects of that type one level in the tower. Then when the system is required to operate on objects of different types it can successively raise the lower

types until all the objects are at the same level in the tower. (Exercise 2.83 and Exercise 2.84 concern the details of implementing such a strategy.)

Another advantage of a tower is that we can easily implement the notion that every type "inherits" all operations defined on a supertype. For instance, if we do not supply a special procedure for finding the real part of an integer, we should nevertheless expect that `real-part` will be defined for integers by virtue of the fact that integers are a subtype of complex numbers. In a tower, we can arrange for this to happen in a uniform way by modifying `apply-generic`. If the required operation is not directly defined for the type of the object given, we raise the object to its supertype and try again. We thus crawl up the tower, transforming our argument as we go, until we either find a level at which the desired operation can be performed or hit the top (in which case we give up).

Yet another advantage of a tower over a more general hierarchy is that it gives us a simple way to "lower" a data object to the simplest representation. For example, if we add $2+3i$ to $4-3i$, it would be nice to obtain the answer as the integer 6 rather than as the complex number $6+0i$. Exercise 2.85 discusses a way to implement such a lowering operation. (The trick is that we need a general way to distinguish those objects that can be lowered, such as $6+0i$, from those that cannot, such as $6+2i$.)

Inadequacies of hierarchies

If the data types in our system can be naturally arranged in a tower, this greatly simplifies the problems of dealing with generic operations on different types, as we have seen. Unfortunately, this is usually not the case. Figure 2.26 illustrates a more complex arrangement of mixed types, this one showing relations among different types of geometric figures. We see that, in general, a type may have more than one subtype. Triangles and quadrilaterals, for instance, are both subtypes of polygons. In addition, a type may have more than one supertype. For example, an isosceles right triangle may be regarded




Figure 2.26: Relations among types of geometric figures.

either as an isosceles triangle or as a right triangle. This multiple-supertypes issue is particularly thorny, since it means that there is no unique way to "raise" a type in the hierarchy. Finding the "correct" supertype in which to apply an operation to an object may involve considerable searching through the entire type network on the part of a procedure such as `apply-generic`. Since there generally are multiple subtypes for a type, there is a similar problem in coercing a value "down" the type hierarchy. Dealing with large numbers of interrelated types while still preserving modularity in the design of large systems is very difficult, and is an area of much current research.[87]

[87]This statement, which also appears in the first edition of this book, is just as true now as it was when we wrote it twelve years ago. Developing a useful, general framework for expressing the relations among different types of entities (what philosophers call "ontology") seems intractably difficult. The main difference between the confusion that existed ten years ago and the confusion that exists now is that now a variety of inadequate ontological theories

Exercise 2.81: Louis Reasoner has noticed that `apply-generic` may try to coerce the arguments to each other's type even if they already have the same type. Therefore, he reasons, we need to put procedures in the coercion table to *coerce* arguments of each type to their own type. For example, in addition to the `scheme-number->complex` coercion shown above, he would do:

```
(define (scheme-number->scheme-number n) n)
(define (complex->complex z) z)
(put-coercion 'scheme-number
              'scheme-number
              scheme-number->scheme-number)
(put-coercion 'complex 'complex complex->complex)
```

a. With Louis's coercion procedures installed, what happens if `apply-generic` is called with two arguments of type `scheme-number` or two arguments of type `complex` for an operation that is not found in the table for those types? For example, assume that we've defined a generic exponentiation operation:

```
(define (exp x y) (apply-generic 'exp x y))
```

have been embodied in a plethora of correspondingly inadequate programming languages. For example, much of the complexity of object-oriented programming languages—and the subtle and confusing differences among contemporary object-oriented languages—centers on the treatment of generic operations on interrelated types. Our own discussion of computational objects in Chapter 3 avoids these issues entirely. Readers familiar with object-oriented programming will notice that we have much to say in chapter 3 about local state, but we do not even mention "classes" or "inheritance." In fact, we suspect that these problems cannot be adequately addressed in terms of computer-language design alone, without also drawing on work in knowledge representation and automated reasoning.

and have put a procedure for exponentiation in the Scheme-number package but not in any other package:

```
;; following added to Scheme-number package
(put 'exp '(scheme-number scheme-number)
     (lambda (x y) (tag (expt x y))))
     ; using primitive expt
```

What happens if we call `exp` with two complex numbers as arguments?

b. Is Louis correct that something had to be done about coercion with arguments of the same type, or does `apply-generic` work correctly as is?

c. Modify `apply-generic` so that it doesn't try coercion if the two arguments have the same type.

Exercise 2.82: Show how to generalize `apply-generic` to handle coercion in the general case of multiple arguments. One strategy is to attempt to coerce all the arguments to the type of the first argument, then to the type of the second argument, and so on. Give an example of a situation where this strategy (and likewise the two-argument version given above) is not sufficiently general. (Hint: Consider the case where there are some suitable mixed-type operations present in the table that will not be tried.)

Exercise 2.83: Suppose you are designing a generic arithmetic system for dealing with the tower of types shown in Figure 2.25: integer, rational, real, complex. For each type (except complex), design a procedure that raises objects of that type one level in the tower. Show how to install a generic `raise` operation that will work for each type (except complex).

Exercise 2.84: Using the `raise` operation of Exercise 2.83, modify the `apply-generic` procedure so that it coerces its arguments to have the same type by the method of successive raising, as discussed in this section. You will need to devise a way to test which of two types is higher in the tower. Do this in a manner that is "compatible" with the rest of the system and will not lead to problems in adding new levels to the tower.

Exercise 2.85: This section mentioned a method for "simplifying" a data object by lowering it in the tower of types as far as possible. Design a procedure `drop` that accomplishes this for the tower described in Exercise 2.83. The key is to decide, in some general way, whether an object can be lowered. For example, the complex number $1.5 + 0i$ can be lowered as far as `real`, the complex number $1 + 0i$ can be lowered as far as `integer`, and the complex number $2 + 3i$ cannot be lowered at all. Here is a plan for determining whether an object can be lowered: Begin by defining a generic operation `project` that "pushes" an object down in the tower. For example, projecting a complex number would involve throwing away the imaginary part. Then a number can be dropped if, when we `project` it and `raise` the result back to the type we started with, we end up with something equal to what we started with. Show how to implement this idea in detail, by writing a `drop` procedure that drops an object as far as possible. You will need to design the various projection operations[88] and install `project` as a generic operation in the system. You will also need to make use of a generic equality predicate, such as described in Exercise

[88] A real number can be projected to an integer using the `round` primitive, which returns the closest integer to its argument.

2.79. Finally, use `drop` to rewrite `apply-generic` from Exercise 2.84 so that it "simplifies" its answers.

Exercise 2.86: Suppose we want to handle complex numbers whose real parts, imaginary parts, magnitudes, and angles can be either ordinary numbers, rational numbers, or other numbers we might wish to add to the system. Describe and implement the changes to the system needed to accommodate this. You will have to define operations such as `sine` and `cosine` that are generic over ordinary numbers and rational numbers.

2.5.3 Example: Symbolic Algebra

The manipulation of symbolic algebraic expressions is a complex process that illustrates many of the hardest problems that occur in the design of large-scale systems. An algebraic expression, in general, can be viewed as a hierarchical structure, a tree of operators applied to operands. We can construct algebraic expressions by starting with a set of primitive objects, such as constants and variables, and combining these by means of algebraic operators, such as addition and multiplication. As in other languages, we form abstractions that enable us to refer to compound objects in simple terms. Typical abstractions in symbolic algebra are ideas such as linear combination, polynomial, rational function, or trigonometric function. We can regard these as compound "types," which are often useful for directing the processing of expressions. For example, we could describe the expression

$$x^2 \sin(y^2 + 1) + x \cos 2y + \cos(y^3 - 2y^2)$$

as a polynomial in x with coefficients that are trigonometric functions of polynomials in y whose coefficients are integers.

We will not attempt to develop a complete algebraic-manipulation system here. Such systems are exceedingly complex programs, embodying deep algebraic knowledge and elegant algorithms. What we will do is look at a simple but important part of algebraic manipulation: the arithmetic of polynomials. We will illustrate the kinds of decisions the designer of such a system faces, and how to apply the ideas of abstract data and generic operations to help organize this effort.

Arithmetic on polynomials

Our first task in designing a system for performing arithmetic on polynomials is to decide just what a polynomial is. Polynomials are normally defined relative to certain variables (the *indeterminates* of the polynomial). For simplicity, we will restrict ourselves to polynomials having just one indeterminate (*univariate polynomials*).[89] We will define a polynomial to be a sum of terms, each of which is either a coefficient, a power of the indeterminate, or a product of a coefficient and a power of the indeterminate. A coefficient is defined as an algebraic expression that is not dependent upon the indeterminate of the polynomial. For example,

$$5x^2 + 3x + 7$$

is a simple polynomial in x, and

$$(y^2 + 1)x^3 + (2y)x + 1$$

is a polynomial in x whose coefficients are polynomials in y.

[89] On the other hand, we will allow polynomials whose coefficients are themselves polynomials in other variables. This will give us essentially the same representational power as a full multivariate system, although it does lead to coercion problems, as discussed below.

Already we are skirting some thorny issues. Is the first of these polynomials the same as the polynomial $5y^2 + 3y + 7$, or not? A reasonable answer might be "yes, if we are considering a polynomial purely as a mathematical function, but no, if we are considering a polynomial to be a syntactic form." The second polynomial is algebraically equivalent to a polynomial in y whose coefficients are polynomials in x. Should our system recognize this, or not? Furthermore, there are other ways to represent a polynomial—for example, as a product of factors, or (for a univariate polynomial) as the set of roots, or as a listing of the values of the polynomial at a specified set of points.[90] We can finesse these questions by deciding that in our algebraic-manipulation system a "polynomial" will be a particular syntactic form, not its underlying mathematical meaning.

Now we must consider how to go about doing arithmetic on polynomials. In this simple system, we will consider only addition and multiplication. Moreover, we will insist that two polynomials to be combined must have the same indeterminate.

We will approach the design of our system by following the familiar discipline of data abstraction. We will represent polynomials using a data structure called a *poly*, which consists of a variable and a collection of terms. We assume that we have selectors `variable` and `term-list` that extract those parts from a poly and a constructor `make-poly` that assembles a poly from a given variable and a term list. A variable will be just a symbol, so we can use the `same-variable?` procedure of Section 2.3.2 to compare variables. The following procedures define addition and multiplication

[90] For univariate polynomials, giving the value of a polynomial at a given set of points can be a particularly good representation. This makes polynomial arithmetic extremely simple. To obtain, for example, the sum of two polynomials represented in this way, we need only add the values of the polynomials at corresponding points. To transform back to a more familiar representation, we can use the Lagrange interpolation formula, which shows how to recover the coefficients of a polynomial of degree n given the values of the polynomial at $n+1$ points.

of polys:

```
(define (add-poly p1 p2)
  (if (same-variable? (variable p1) (variable p2))
      (make-poly (variable p1)
                 (add-terms (term-list p1) (term-list p2)))
      (error "Polys not in same var: ADD-POLY" (list p1 p2))))
(define (mul-poly p1 p2)
  (if (same-variable? (variable p1) (variable p2))
      (make-poly (variable p1)
                 (mul-terms (term-list p1) (term-list p2)))
      (error "Polys not in same var: MUL-POLY" (list p1 p2))))
```

To incorporate polynomials into our generic arithmetic system, we need to supply them with type tags. We'll use the tag `polynomial`, and install appropriate operations on tagged polynomials in the operation table. We'll embed all our code in an installation procedure for the polynomial package, similar to the ones in Section 2.5.1:

```
(define (install-polynomial-package)
  ;; internal procedures
  ;; representation of poly
  (define (make-poly variable term-list) (cons variable term
  (define (variable p) (car p))
  (define (term-list p) (cdr p))
  ⟨procedures same-variable? and variable? from section
2.3.2⟩
  ;; representation of terms and term lists
  ⟨procedures adjoin-term ... coeff from text below⟩
  (define (add-poly p1 p2) ...)
  ⟨procedures used by add-poly⟩
  (define (mul-poly p1 p2) ...)
  ⟨procedures used by mul-poly⟩
  ;; interface to rest of the system
```

```
(define (tag p) (attach-tag 'polynomial p))
(put 'add '(polynomial polynomial)
     (lambda (p1 p2) (tag (add-poly p1 p2))))
(put 'mul '(polynomial polynomial)
     (lambda (p1 p2) (tag (mul-poly p1 p2))))
(put 'make 'polynomial
     (lambda (var terms) (tag (make-poly var terms))))
'done)
```

Polynomial addition is performed termwise. Terms of the same order (i.e., with the same power of the indeterminate) must be combined. This is done by forming a new term of the same order whose coefficient is the sum of the coefficients of the addends. Terms in one addend for which there are no terms of the same order in the other addend are simply accumulated into the sum polynomial being constructed.

In order to manipulate term lists, we will assume that we have a constructor `the-empty-termlist` that returns an empty term list and a constructor `adjoin-term` that adjoins a new term to a term list. We will also assume that we have a predicate `empty-termlist?` that tells if a given term list is empty, a selector `first-term` that extracts the highest-order term from a term list, and a selector `rest-terms` that returns all but the highest-order term. To manipulate terms, we will suppose that we have a constructor `make-term` that constructs a term with given order and coefficient, and selectors `order` and `coeff` that return, respectively, the order and the coefficient of the term. These operations allow us to consider both terms and term lists as data abstractions, whose concrete representations we can worry about separately.

Here is the procedure that constructs the term list for the sum of two polynomials:[91]

[91] This operation is very much like the ordered `union-set` operation we developed in

```
(define (add-terms L1 L2)
  (cond ((empty-termlist? L1) L2)
        ((empty-termlist? L2) L1)
        (else
         (let ((t1 (first-term L1))
               (t2 (first-term L2)))
           (cond ((> (order t1) (order t2))
                  (adjoin-term
                   t1 (add-terms (rest-terms L1) L2)))
                 ((< (order t1) (order t2))
                  (adjoin-term
                   t2 (add-terms L1 (rest-terms L2))))
                 (else
                  (adjoin-term
                   (make-term (order t1)
                              (add (coeff t1) (coeff t2)))
                   (add-terms (rest-terms L1)
                              (rest-terms L2)))))))))
```

The most important point to note here is that we used the generic addition procedure `add` to add together the coefficients of the terms being combined. This has powerful consequences, as we will see below.

In order to multiply two term lists, we multiply each term of the first list by all the terms of the other list, repeatedly using `mul-term-by-all-terms`, which multiplies a given term by all terms in a given term list. The resulting term lists (one for each term of the first list) are accumulated into a sum. Multiplying two terms forms a term whose order is the sum of the orders of the factors and whose coefficient is the product of the coefficients of the factors:

Exercise 2.62. In fact, if we think of the terms of the polynomial as a set ordered according to the power of the indeterminate, then the program that produces the term list for a sum is almost identical to `union-set`.

```
(define (mul-terms L1 L2)
  (if (empty-termlist? L1)
      (the-empty-termlist)
      (add-terms (mul-term-by-all-terms (first-term L1) L2)
                 (mul-terms (rest-terms L1) L2))))
(define (mul-term-by-all-terms t1 L)
  (if (empty-termlist? L)
      (the-empty-termlist)
      (let ((t2 (first-term L)))
        (adjoin-term
         (make-term (+ (order t1) (order t2))
                    (mul (coeff t1) (coeff t2)))
         (mul-term-by-all-terms t1 (rest-terms L))))))
```

This is really all there is to polynomial addition and multiplication. Notice that, since we operate on terms using the generic procedures `add` and `mul`, our polynomial package is automatically able to handle any type of coefficient that is known about by the generic arithmetic package. If we include a coercion mechanism such as one of those discussed in Section 2.5.2, then we also are automatically able to handle operations on polynomials of different coefficient types, such as

$$[3x^2 + (2 + 3i)x + 7] \cdot \left[x^4 + \frac{2}{3}x^2 + (5 + 3i)\right].$$

Because we installed the polynomial addition and multiplication procedures `add-poly` and `mul-poly` in the generic arithmetic system as the `add` and `mul` operations for type `polynomial`, our system is also automatically able to handle polynomial operations such as

$$\left[(y + 1)x^2 + (y^2 + 1)x + (y - 1)\right] \cdot \left[(y - 2)x + (y^3 + 7)\right].$$

The reason is that when the system tries to combine coefficients, it will dispatch through `add` and `mul`. Since the coefficients are themselves polynomials (in y), these will be combined using `add-poly` and `mul-poly`. The result is a kind of "data-directed recursion" in which, for example, a call to `mul-poly` will result in recursive calls to `mul-poly` in order to multiply the coefficients. If the coefficients of the coefficients were themselves polynomials (as might be used to represent polynomials in three variables), the data direction would ensure that the system would follow through another level of recursive calls, and so on through as many levels as the structure of the data dictates.[92]

Representing term lists

Finally, we must confront the job of implementing a good representation for term lists. A term list is, in effect, a set of coefficients keyed by the order of the term. Hence, any of the methods for representing sets, as discussed in Section 2.3.3, can be applied to this task. On the other hand, our procedures `add-terms` and `mul-terms` always access term lists sequentially from highest to lowest order. Thus, we will use some kind of ordered list representation.

How should we structure the list that represents a term list? One consideration is the "density" of the polynomials we intend to manipulate. A polynomial is said to be *dense* if it has nonzero coefficients in terms of most orders. If it has many zero terms it is said to be *sparse*. For example,

[92] To make this work completely smoothly, we should also add to our generic arithmetic system the ability to coerce a "number" to a polynomial by regarding it as a polynomial of degree zero whose coefficient is the number. This is necessary if we are going to perform operations such as

$$[x^2 + (y + 1)x + 5] + [x^2 + 2x + 1],$$

which requires adding the coefficient $y + 1$ to the coefficient 2.

$$A: \quad x^5 + 2x^4 + 3x^2 - 2x - 5$$

is a dense polynomial, whereas

$$B: \quad x^{100} + 2x^2 + 1$$

is sparse.

The term lists of dense polynomials are most efficiently represented as lists of the coefficients. For example, A above would be nicely represented as `(1 2 0 3 -2 -5)`. The order of a term in this representation is the length of the sublist beginning with that term's coefficient, decremented by 1.[93] This would be a terrible representation for a sparse polynomial such as B: There would be a giant list of zeros punctuated by a few lonely nonzero terms. A more reasonable representation of the term list of a sparse polynomial is as a list of the nonzero terms, where each term is a list containing the order of the term and the coefficient for that order. In such a scheme, polynomial B is efficiently represented as `((100 1) (2 2) (0 1))`. As most polynomial manipulations are performed on sparse polynomials, we will use this method. We will assume that term lists are represented as lists of terms, arranged from highest-order to lowest-order term. Once we have made this decision, implementing the selectors and constructors for terms and term lists is straightforward:[94]

[93] In these polynomial examples, we assume that we have implemented the generic arithmetic system using the type mechanism suggested in Exercise 2.78. Thus, coefficients that are ordinary numbers will be represented as the numbers themselves rather than as pairs whose `car` is the symbol `scheme-number`.

[94] Although we are assuming that term lists are ordered, we have implemented `adjoin-term` to simply `cons` the new term onto the existing term list. We can get away with this so long as we guarantee that the procedures (such as `add-terms`) that use `adjoin-term` always call it with a higher-order term than appears in the list. If we did not want to make such

```
(define (adjoin-term term term-list)
  (if (=zero? (coeff term))
      term-list
      (cons term term-list)))
(define (the-empty-termlist) '())
(define (first-term term-list) (car term-list))
(define (rest-terms term-list) (cdr term-list))
(define (empty-termlist? term-list) (null? term-list))
(define (make-term order coeff) (list order coeff))
(define (order term) (car term))
(define (coeff term) (cadr term))
```

where `=zero?` is as defined in Exercise 2.80. (See also Exercise 2.87 below.)

Users of the polynomial package will create (tagged) polynomials by means of the procedure:

```
(define (make-polynomial var terms)
  ((get 'make 'polynomial) var terms))
```

Exercise 2.87: Install `=zero?` for polynomials in the generic arithmetic package. This will allow `adjoin-term` to work for polynomials with coefficients that are themselves polynomials.

Exercise 2.88: Extend the polynomial system to include subtraction of polynomials. (Hint: You may find it helpful to define a generic negation operation.)

---

a guarantee, we could have implemented `adjoin-term` to be similar to the `adjoin-set` constructor for the ordered-list representation of sets (Exercise 2.61).

Exercise 2.89: Define procedures that implement the term-list representation described above as appropriate for dense polynomials.

Exercise 2.90: Suppose we want to have a polynomial system that is efficient for both sparse and dense polynomials. One way to do this is to allow both kinds of term-list representations in our system. The situation is analogous to the complex-number example of Section 2.4, where we allowed both rectangular and polar representations. To do this we must distinguish different types of term lists and make the operations on term lists generic. Redesign the polynomial system to implement this generalization. This is a major effort, not a local change.

Exercise 2.91: A univariate polynomial can be divided by another one to produce a polynomial quotient and a polynomial remainder. For example,

$$\frac{x^5 - 1}{x^2 - 1} = x^3 + x, \text{ remainder } x - 1.$$

Division can be performed via long division. That is, divide the highest-order term of the dividend by the highest-order term of the divisor. The result is the first term of the quotient. Next, multiply the result by the divisor, subtract that from the dividend, and produce the rest of the answer by recursively dividing the difference by the divisor. Stop when the order of the divisor exceeds the order of the dividend and declare the dividend to be the remainder. Also, if the dividend ever becomes zero, return zero as both quotient and remainder.

We can design a `div-poly` procedure on the model of `add-poly` and `mul-poly`. The procedure checks to see if the two polys have the same variable. If so, `div-poly` strips off the variable and passes the problem to `div-terms`, which performs the division operation on term lists. `div-poly` finally reattaches the variable to the result supplied by `div-terms`. It is convenient to design `div-terms` to compute both the quotient and the remainder of a division. `div-terms` can take two term lists as arguments and return a list of the quotient term list and the remainder term list.

Complete the following definition of `div-terms` by filling in the missing expressions. Use this to implement `div-poly`, which takes two polys as arguments and returns a list of the quotient and remainder polys.

```
(define (div-terms L1 L2)
  (if (empty-termlist? L1)
      (list (the-empty-termlist) (the-empty-termlist))
      (let ((t1 (first-term L1))
            (t2 (first-term L2)))
        (if (> (order t2) (order t1))
            (list (the-empty-termlist) L1)
            (let ((new-c (div (coeff t1) (coeff t2)))
                  (new-o (- (order t1) (order t2))))
              (let ((rest-of-result
                     ⟨compute rest of result recursively⟩ ))
                ⟨form complete result⟩ ))))))
```

Hierarchies of types in symbolic algebra

Our polynomial system illustrates how objects of one type (polynomials) may in fact be complex objects that have objects of many different types as parts.

This poses no real difficulty in defining generic operations. We need only install appropriate generic operations for performing the necessary manipulations of the parts of the compound types. In fact, we saw that polynomials form a kind of "recursive data abstraction," in that parts of a polynomial may themselves be polynomials. Our generic operations and our data-directed programming style can handle this complication without much trouble.

On the other hand, polynomial algebra is a system for which the data types cannot be naturally arranged in a tower. For instance, it is possible to have polynomials in x whose coefficients are polynomials in y. It is also possible to have polynomials in y whose coefficients are polynomials in x. Neither of these types is "above" the other in any natural way, yet it is often necessary to add together elements from each set. There are several ways to do this. One possibility is to convert one polynomial to the type of the other by expanding and rearranging terms so that both polynomials have the same principal variable. One can impose a towerlike structure on this by ordering the variables and thus always converting any polynomial to a "canonical form" with the highest-priority variable dominant and the lower-priority variables buried in the coefficients. This strategy works fairly well, except that the conversion may expand a polynomial unnecessarily, making it hard to read and perhaps less efficient to work with. The tower strategy is certainly not natural for this domain or for any domain where the user can invent new types dynamically using old types in various combining forms, such as trigonometric functions, power series, and integrals.

It should not be surprising that controlling coercion is a serious problem in the design of large-scale algebraic-manipulation systems. Much of the complexity of such systems is concerned with relationships among diverse types. Indeed, it is fair to say that we do not yet completely understand coercion. In fact, we do not yet completely understand the concept of a data type. Nevertheless, what we know provides us with powerful structuring and modularity

principles to support the design of large systems.

> **Exercise 2.92:** By imposing an ordering on variables, extend the polynomial package so that addition and multiplication of polynomials works for polynomials in different variables. (This is not easy!)

Extended exercise: Rational functions

We can extend our generic arithmetic system to include *rational functions*. These are "fractions" whose numerator and denominator are polynomials, such as

$$\frac{x+1}{x^3-1}.$$

The system should be able to add, subtract, multiply, and divide rational functions, and to perform such computations as

$$\frac{x+1}{x^3-1}+\frac{x}{x^2-1}=\frac{x^3+2x^2+3x+1}{x^4+x^3-x-1}.$$

(Here the sum has been simplified by removing common factors. Ordinary "cross multiplication" would have produced a fourth-degree polynomial over a fifth-degree polynomial.)

If we modify our rational-arithmetic package so that it uses generic operations, then it will do what we want, except for the problem of reducing fractions to lowest terms.

> **Exercise 2.93:** Modify the rational-arithmetic package to use generic operations, but change `make-rat` so that it does not attempt to reduce fractions to lowest terms. Test your system by calling `make-rational` on two polynomials to produce a rational function:

```
(define p1 (make-polynomial 'x '((2 1) (0 1))))
(define p2 (make-polynomial 'x '((3 1) (0 1))))
(define rf (make-rational p2 p1))
```

Now add `rf` to itself, using `add`. You will observe that this addition procedure does not reduce fractions to lowest terms.

We can reduce polynomial fractions to lowest terms using the same idea we used with integers: modifying `make-rat` to divide both the numerator and the denominator by their greatest common divisor. The notion of "greatest common divisor" makes sense for polynomials. In fact, we can compute the GCD of two polynomials using essentially the same Euclid's Algorithm that works for integers.[95] The integer version is

```
(define (gcd a b)
  (if (= b 0)
      a
      (gcd b (remainder a b))))
```

Using this, we could make the obvious modification to define a GCD operation that works on term lists:

```
(define (gcd-terms a b)
  (if (empty-termlist? b)
      a
      (gcd-terms b (remainder-terms a b))))
```

[95] The fact that Euclid's Algorithm works for polynomials is formalized in algebra by saying that polynomials form a kind of algebraic domain called a *Euclidean ring*. A Euclidean ring is a domain that admits addition, subtraction, and commutative multiplication, together with a way of assigning to each element x of the ring a positive integer "measure" $m(x)$ with the properties that $m(xy) \geq m(x)$ for any nonzero x and y and that, given any x and y, there exists a q such that $y = qx + r$ and either $r = 0$ or $m(r) < m(x)$. From an abstract point of view, this is what is needed to prove that Euclid's Algorithm works. For the domain of integers, the measure m of an integer is the absolute value of the integer itself. For the domain of polynomials, the measure of a polynomial is its degree.

where `remainder-terms` picks out the remainder component of the list returned by the term-list division operation `div-terms` that was implemented in Exercise 2.91.

Exercise 2.94: Using `div-terms`, implement the procedure `remainder-terms` and use this to define `gcd-terms` as above. Now write a procedure `gcd-poly` that computes the polynomial GCD of two polys. (The procedure should signal an error if the two polys are not in the same variable.) Install in the system a generic operation `greatest-common-divisor` that reduces to `gcd-poly` for polynomials and to ordinary `gcd` for ordinary numbers. As a test, try

```
(define p1 (make-polynomial
            'x '((4 1) (3 -1) (2 -2) (1 2))))
(define p2 (make-polynomial 'x '((3 1) (1 -1))))
(greatest-common-divisor p1 p2)
```

and check your result by hand.

Exercise 2.95: Define P_1, P_2, and P_3 to be the polynomials

$$\begin{aligned} P_1 &: \quad x^2 - 2x + 1, \\ P_2 &: \quad 11x^2 + 7, \\ P_3 &: \quad 13x + 5. \end{aligned}$$

Now define Q_1 to be the product of P_1 and P_2 and Q_2 to be the product of P_1 and P_3, and use `greatest-common-divisor` (Exercise 2.94) to compute the GCD of Q_1 and Q_2. Note that the answer is not the same as P_1. This example introduces noninteger operations into the computation, causing dif-

ficulties with the GCD algorithm.[96] To understand what is happening, try tracing `gcd-terms` while computing the GCD or try performing the division by hand.

We can solve the problem exhibited in Exercise 2.95 if we use the following modification of the GCD algorithm (which really works only in the case of polynomials with integer coefficients). Before performing any polynomial division in the GCD computation, we multiply the dividend by an integer constant factor, chosen to guarantee that no fractions will arise during the division process. Our answer will thus differ from the actual GCD by an integer constant factor, but this does not matter in the case of reducing rational functions to lowest terms; the GCD will be used to divide both the numerator and denominator, so the integer constant factor will cancel out.

More precisely, if P and Q are polynomials, let O_1 be the order of P (i.e., the order of the largest term of P) and let O_2 be the order of Q. Let c be the leading coefficient of Q. Then it can be shown that, if we multiply P by the *integerizing factor* $c^{1+O_1-O_2}$, the resulting polynomial can be divided by Q by using the `div-terms` algorithm without introducing any fractions. The operation of multiplying the dividend by this constant and then dividing is sometimes called the *pseudodivision* of P by Q. The remainder of the division is called the *pseudoremainder*.

Exercise 2.96:

a. Implement the procedure `pseudoremainder-terms`, which is just like `remainder-terms` except that it multiplies the dividend by the integerizing factor described above before calling `div-terms`. Modify `gcd-terms`

[96] In an implementation like MIT Scheme, this produces a polynomial that is indeed a divisor of Q_1 and Q_2, but with rational coefficients. In many other Scheme systems, in which division of integers can produce limited-precision decimal numbers, we may fail to get a valid divisor.

to use `pseudoremainder-terms`, and verify that `greatest-common-divisor` now produces an answer with integer coefficients on the example in Exercise 2.95.

b. The GCD now has integer coefficients, but they are larger than those of P_1. Modify `gcd-terms` so that it removes common factors from the coefficients of the answer by dividing all the coefficients by their (integer) greatest common divisor.

Thus, here is how to reduce a rational function to lowest terms:

- Compute the GCD of the numerator and denominator, using the version of `gcd-terms` from Exercise 2.96.
- When you obtain the GCD, multiply both numerator and denominator by the same integerizing factor before dividing through by the GCD, so that division by the GCD will not introduce any noninteger coefficients. As the factor you can use the leading coefficient of the GCD raised to the power $1 + O_1 - O_2$, where O_2 is the order of the GCD and O_1 is the maximum of the orders of the numerator and denominator. This will ensure that dividing the numerator and denominator by the GCD will not introduce any fractions.
- The result of this operation will be a numerator and denominator with integer coefficients. The coefficients will normally be very large because of all of the integerizing factors, so the last step is to remove the redundant factors by computing the (integer) greatest common divisor of all the coefficients of the numerator and the denominator and dividing through by this factor.

Exercise 2.97:

a. Implement this algorithm as a procedure `reduce-terms` that takes two term lists `n` and `d` as arguments and returns a list `nn`, `dd`, which are `n` and `d` reduced to lowest terms via the algorithm given above. Also write a procedure `reduce-poly`, analogous to `add-poly`, that checks to see if the two polys have the same variable. If so, `reduce-poly` strips off the variable and passes the problem to `reduce-terms`, then reattaches the variable to the two term lists supplied by `reduce-terms`.

b. Define a procedure analogous to `reduce-terms` that does what the original `make-rat` did for integers:

```
(define (reduce-integers n d)
  (let ((g (gcd n d)))
    (list (/ n g) (/ d g))))
```

and define `reduce` as a generic operation that calls `apply-generic` to dispatch to either `reduce-poly` (for `polynomial` arguments) or `reduce-integers` (for `scheme-number` arguments). You can now easily make the rational-arithmetic package reduce fractions to lowest terms by having `make-rat` call `reduce` before combining the given numerator and denominator to form a rational number. The system now handles rational expressions in either integers or polynomials. To test your program, try the example at the beginning of this extended exercise:

```
(define p1 (make-polynomial 'x '((1 1) (0
1))))
```

```
(define  p2 (make-polynomial 'x '((3 1) (0 -1))))
(define  p3 (make-polynomial 'x '((1 1))))
(define  p4 (make-polynomial 'x '((2 1) (0 -1))))
(define rf1 (make-rational p1 p2))
(define rf2 (make-rational p3 p4))
(add rf1 rf2)
```

See if you get the correct answer, correctly reduced to lowest terms.

The GCD computation is at the heart of any system that does operations on rational functions. The algorithm used above, although mathematically straightforward, is extremely slow. The slowness is due partly to the large number of division operations and partly to the enormous size of the intermediate coefficients generated by the pseudodivisions. One of the active areas in the development of algebraic-manipulation systems is the design of better algorithms for computing polynomial GCDs.[97]

[97] One extremely efficient and elegant method for computing polynomial GCDs was discovered by Richard Zippel (1979). The method is a probabilistic algorithm, as is the fast test for primality that we discussed in Chapter 1. Zippel's book (Zippel 1993) describes this method, together with other ways to compute polynomial GCDs.

3

Modularity, Objects, and State

> Μεταβάλλον ἀναπαύεται
> (Even while it changes, it stands still.)
> —Heraclitus
>
> Plus ça change, plus c'est la même chose.
> —Alphonse Karr

The preceding chapters introduced the basic elements from which programs are made. We saw how primitive procedures and primitive data are combined to construct compound entities, and we learned that abstraction is vital in helping us to cope with the complexity of large systems. But these tools are not sufficient for designing programs. Effective program synthesis also requires organizational principles that can guide us in formulating the overall design of a program. In particular, we need strategies to help us structure large systems so that they will be *modular*, that is, so that they can be divided "naturally" into coherent parts that can be separately developed and maintained.

One powerful design strategy, which is particularly appropriate to the construction of programs for modeling physical systems, is to base the structure of our programs on the structure of the system being modeled. For each object in the system, we construct a corresponding computational object. For each system action, we define a symbolic operation in our computational model. Our hope in using this strategy is that extending the model to accommodate new objects or new actions will require no strategic changes to the program, only the addition of the new symbolic analogs of those objects or actions. If we have been successful in our system organization, then to add a new feature or debug an old one we will have to work on only a localized part of the system.

To a large extent, then, the way we organize a large program is dictated by our perception of the system to be modeled. In this chapter we will investigate two prominent organizational strategies arising from two rather different "world views" of the structure of systems. The first organizational strategy concentrates on *objects*, viewing a large system as a collection of distinct objects whose behaviors may change over time. An alternative organizational strategy concentrates on the *streams* of information that flow in the system, much as an electrical engineer views a signal-processing system.

Both the object-based approach and the stream-processing approach raise significant linguistic issues in programming. With objects, we must be concerned with how a computational object can change and yet maintain its identity. This will force us to abandon our old substitution model of computation (Section 1.1.5) in favor of a more mechanistic but less theoretically tractable *environment model* of computation. The difficulties of dealing with objects, change, and identity are a fundamental consequence of the need to grapple with time in our computational models. These difficulties become even greater when we allow the possibility of concurrent execution of programs. The stream approach can be most fully exploited when we decouple

simulated time in our model from the order of the events that take place in the computer during evaluation. We will accomplish this using a technique known as *delayed evaluation*.

3.1 Assignment and Local State

We ordinarily view the world as populated by independent objects, each of which has a state that changes over time. An object is said to "have state" if its behavior is influenced by its history. A bank account, for example, has state in that the answer to the question "Can I withdraw $100?" depends upon the history of deposit and withdrawal transactions. We can characterize an object's state by one or more *state variables*, which among them maintain enough information about history to determine the object's current behavior. In a simple banking system, we could characterize the state of an account by a current balance rather than by remembering the entire history of account transactions.

In a system composed of many objects, the objects are rarely completely independent. Each may influence the states of others through interactions, which serve to couple the state variables of one object to those of other objects. Indeed, the view that a system is composed of separate objects is most useful when the state variables of the system can be grouped into closely coupled subsystems that are only loosely coupled to other subsystems.

This view of a system can be a powerful framework for organizing computational models of the system. For such a model to be modular, it should be decomposed into computational objects that model the actual objects in the system. Each computational object must have its own *local state variables* describing the actual object's state. Since the states of objects in the system being modeled change over time, the state variables of the corresponding computational objects must also change. If we choose to model the flow of

time in the system by the elapsed time in the computer, then we must have a way to construct computational objects whose behaviors change as our programs run. In particular, if we wish to model state variables by ordinary symbolic names in the programming language, then the language must provide an *assignment operator* to enable us to change the value associated with a name.

3.1.1 Local State Variables

To illustrate what we mean by having a computational object with time-varying state, let us model the situation of withdrawing money from a bank account. We will do this using a procedure `withdraw`, which takes as argument an `amount` to be withdrawn. If there is enough money in the account to accommodate the withdrawal, then `withdraw` should return the balance remaining after the withdrawal. Otherwise, `withdraw` should return the message *Insufficient funds*. For example, if we begin with $100 in the account, we should obtain the following sequence of responses using `withdraw`:

```
(withdraw 25)
75
(withdraw 25)
50
(withdraw 60)
"Insufficient funds"
(withdraw 15)
35
```

Observe that the expression `(withdraw 25)`, evaluated twice, yields different values. This is a new kind of behavior for a procedure. Until now, all our procedures could be viewed as specifications for computing mathematical functions. A call to a procedure computed the value of the function applied

to the given arguments, and two calls to the same procedure with the same arguments always produced the same result.[1]

To implement `withdraw`, we can use a variable `balance` to indicate the balance of money in the account and define `withdraw` as a procedure that accesses `balance`. The `withdraw` procedure checks to see if `balance` is at least as large as the requested `amount`. If so, `withdraw` decrements `balance` by `amount` and returns the new value of `balance`. Otherwise, `withdraw` returns the *Insufficient funds* message. Here are the definitions of `balance` and `withdraw`:

```
(define balance 100)
(define (withdraw amount)
  (if (>= balance amount)
      (begin (set! balance (- balance amount))
             balance)
      "Insufficient funds"))
```

Decrementing `balance` is accomplished by the expression

```
(set! balance (- balance amount))
```

This uses the `set!` special form, whose syntax is

```
(set! ⟨name⟩ ⟨new-value⟩)
```

Here ⟨*name*⟩ is a symbol and ⟨*new-value*⟩ is any expression. `set!` changes ⟨*name*⟩ so that its value is the result obtained by evaluating ⟨*new-value*⟩. In the case at hand, we are changing `balance` so that its new value will be the

[1] Actually, this is not quite true. One exception was the random-number generator in Section 1.2.6. Another exception involved the operation/type tables we introduced in Section 2.4.3, where the values of two calls to `get` with the same arguments depended on intervening calls to `put`. On the other hand, until we introduce assignment, we have no way to create such procedures ourselves.

result of subtracting `amount` from the previous value of `balance`.[2]

`withdraw` also uses the `begin` special form to cause two expressions to be evaluated in the case where the `if` test is true: first decrementing `balance` and then returning the value of `balance`. In general, evaluating the expression

(**begin** $\langle exp_1 \rangle$ $\langle exp_2 \rangle$ ... $\langle exp_k \rangle$)

causes the expressions $\langle exp_1 \rangle$ through $\langle exp_k \rangle$ to be evaluated in sequence and the value of the final expression $\langle exp_k \rangle$ to be returned as the value of the entire `begin` form.[3]

Although `withdraw` works as desired, the variable `balance` presents a problem. As specified above, `balance` is a name defined in the global environment and is freely accessible to be examined or modified by any procedure. It would be much better if we could somehow make `balance` internal to `withdraw`, so that `withdraw` would be the only procedure that could access `balance` directly and any other procedure could access `balance` only indirectly (through calls to `withdraw`). This would more accurately model the notion that `balance` is a local state variable used by `withdraw` to keep track of the state of the account.

We can make `balance` internal to `withdraw` by rewriting the definition as follows:

```
(define new-withdraw
```

[2] The value of a `set!` expression is implementation-dependent. `set!` should be used only for its effect, not for its value.

The name `set!` reflects a naming convention used in Scheme: Operations that change the values of variables (or that change data structures, as we will see in Section 3.3) are given names that end with an exclamation point. This is similar to the convention of designating predicates by names that end with a question mark.

[3] We have already used `begin` implicitly in our programs, because in Scheme the body of a procedure can be a sequence of expressions. Also, the $\langle consequent \rangle$ part of each clause in a `cond` expression can be a sequence of expressions rather than a single expression.

```
(let ((balance 100))
  (lambda (amount)
    (if (>= balance amount)
        (begin (set! balance (- balance amount))
               balance)
        "Insufficient funds"))))
```

What we have done here is use `let` to establish an environment with a local variable `balance`, bound to the initial value 100. Within this local environment, we use `lambda` to create a procedure that takes `amount` as an argument and behaves like our previous `withdraw` procedure. This procedure—returned as the result of evaluating the `let` expression—is `new-withdraw`, which behaves in precisely the same way as `withdraw` but whose variable `balance` is not accessible by any other procedure.[4]

Combining `set!` with local variables is the general programming technique we will use for constructing computational objects with local state. Unfortunately, using this technique raises a serious problem: When we first introduced procedures, we also introduced the substitution model of evaluation (Section 1.1.5) to provide an interpretation of what procedure application means. We said that applying a procedure should be interpreted as evaluating the body of the procedure with the formal parameters replaced by their values. The trouble is that, as soon as we introduce assignment into our language, substitution is no longer an adequate model of procedure application. (We will see why this is so in Section 3.1.3.) As a consequence, we technically have at this point no way to understand why the `new-withdraw` procedure behaves as claimed above. In order to really understand a proce-

[4] In programming-language jargon, the variable `balance` is said to be *encapsulated* within the `new-withdraw` procedure. Encapsulation reflects the general system-design principle known as the *hiding principle*: One can make a system more modular and robust by protecting parts of the system from each other; that is, by providing information access only to those parts of the system that have a "need to know."

dure such as `new-withdraw`, we will need to develop a new model of procedure application. In Section 3.2 we will introduce such a model, together with an explanation of `set!` and local variables. First, however, we examine some variations on the theme established by `new-withdraw`.

The following procedure, `make-withdraw`, creates "withdrawal processors." The formal parameter `balance` in `make-withdraw` specifies the initial amount of money in the account.[5]

```
(define (make-withdraw balance)
  (lambda (amount)
    (if (>= balance amount)
        (begin (set! balance (- balance amount))
               balance)
        "Insufficient funds")))
```

`make-withdraw` can be used as follows to create two objects `W1` and `W2`:

```
(define W1 (make-withdraw 100))
(define W2 (make-withdraw 100))

(W1 50)
50
(W2 70)
30
(W2 40)
"Insufficient funds"
(W1 40)
10
```

[5] In contrast with `new-withdraw` above, we do not have to use `let` to make `balance` a local variable, since formal parameters are already local. This will be clearer after the discussion of the environment model of evaluation in Section 3.2. (See also Exercise 3.10.)

Observe that `W1` and `W2` are completely independent objects, each with its own local state variable `balance`. Withdrawals from one do not affect the other.

We can also create objects that handle deposits as well as withdrawals, and thus we can represent simple bank accounts. Here is a procedure that returns a "bank-account object" with a specified initial balance:

```
(define (make-account balance)
  (define (withdraw amount)
    (if (>= balance amount)
        (begin (set! balance (- balance amount))
               balance)
        "Insufficient funds"))
  (define (deposit amount)
    (set! balance (+ balance amount))
    balance)
  (define (dispatch m)
    (cond ((eq? m 'withdraw) withdraw)
          ((eq? m 'deposit) deposit)
          (else (error "Unknown request: MAKE-ACCOUNT"
                       m))))
  dispatch)
```

Each call to `make-account` sets up an environment with a local state variable `balance`. Within this environment, `make-account` defines procedures `deposit` and `withdraw` that access `balance` and an additional procedure `dispatch` that takes a "message" as input and returns one of the two local procedures. The `dispatch` procedure itself is returned as the value that represents the bank-account object. This is precisely the *message-passing* style of programming that we saw in Section 2.4.3, although here we are using it in conjunction with the ability to modify local variables.

`make-account` can be used as follows:

```
(define acc (make-account 100))
((acc 'withdraw) 50)
50
((acc 'withdraw) 60)
"Insufficient funds"
((acc 'deposit) 40)
90
((acc 'withdraw) 60)
30
```

Each call to `acc` returns the locally defined `deposit` or `withdraw` procedure, which is then applied to the specified `amount`. As was the case with `make-withdraw`, another call to `make-account`

```
(define acc2 (make-account 100))
```

will produce a completely separate account object, which maintains its own local `balance`.

> **Exercise 3.1:** An *accumulator* is a procedure that is called repeatedly with a single numeric argument and accumulates its arguments into a sum. Each time it is called, it returns the currently accumulated sum. Write a procedure `make-accumulator` that generates accumulators, each maintaining an independent sum. The input to `make-accumulator` should specify the initial value of the sum; for example
>
> ```
> (define A (make-accumulator 5))
> (A 10)
> 15
> (A 10)
> 25
> ```

Exercise 3.2: In software-testing applications, it is useful to be able to count the number of times a given procedure is called during the course of a computation. Write a procedure `make-monitored` that takes as input a procedure, `f`, that itself takes one input. The result returned by `make-monitored` is a third procedure, say `mf`, that keeps track of the number of times it has been called by maintaining an internal counter. If the input to `mf` is the special symbol `how-many-calls?`, then `mf` returns the value of the counter. If the input is the special symbol `reset-count`, then `mf` resets the counter to zero. For any other input, `mf` returns the result of calling `f` on that input and increments the counter. For instance, we could make a monitored version of the `sqrt` procedure:

```
(define s (make-monitored sqrt))
(s 100)
10
(s 'how-many-calls?)
1
```

Exercise 3.3: Modify the `make-account` procedure so that it creates password-protected accounts. That is, `make-account` should take a symbol as an additional argument, as in

```
(define acc (make-account 100 'secret-password))
```

The resulting account object should process a request only if it is accompanied by the password with which the account was created, and should otherwise return a complaint:

```
((acc 'secret-password 'withdraw) 40)
60
```

```
((acc 'some-other-password 'deposit) 50)
"Incorrect password"
```

Exercise 3.4: Modify the `make-account` procedure of Exercise 3.3 by adding another local state variable so that, if an account is accessed more than seven consecutive times with an incorrect password, it invokes the procedure `call-the-cops`.

3.1.2 The Benefits of Introducing Assignment

As we shall see, introducing assignment into our programming language leads us into a thicket of difficult conceptual issues. Nevertheless, viewing systems as collections of objects with local state is a powerful technique for maintaining a modular design. As a simple example, consider the design of a procedure `rand` that, whenever it is called, returns an integer chosen at random.

It is not at all clear what is meant by "chosen at random." What we presumably want is for successive calls to `rand` to produce a sequence of numbers that has statistical properties of uniform distribution. We will not discuss methods for generating suitable sequences here. Rather, let us assume that we have a procedure `rand-update` that has the property that if we start with a given number x_1 and form

```
x2 = (rand-update x1)
x3 = (rand-update x2)
```

then the sequence of values x_1, x_2, x_3, ... will have the desired statistical properties.[6]

[6] One common way to implement `rand-update` is to use the rule that x is updated to $ax + b$ modulo m, where a, b, and m are appropriately chosen integers. Chapter 3 of Knuth 1981 includes an extensive discussion of techniques for generating sequences of random numbers and establishing their statistical properties. Notice that the `rand-update` procedure

We can implement `rand` as a procedure with a local state variable `x` that is initialized to some fixed value `random-init`. Each call to `rand` computes `rand-update` of the current value of `x`, returns this as the random number, and also stores this as the new value of `x`.

```
(define rand (let ((x random-init))
               (lambda ()
                 (set! x (rand-update x))
                 x)))
```

Of course, we could generate the same sequence of random numbers without using assignment by simply calling `rand-update` directly. However, this would mean that any part of our program that used random numbers would have to explicitly remember the current value of `x` to be passed as an argument to `rand-update`. To realize what an annoyance this would be, consider using random numbers to implement a technique called *Monte Carlo simulation*.

The Monte Carlo method consists of choosing sample experiments at random from a large set and then making deductions on the basis of the probabilities estimated from tabulating the results of those experiments. For example, we can approximate π using the fact that $6/\pi^2$ is the probability that two integers chosen at random will have no factors in common; that is, that their greatest common divisor will be 1.[7] To obtain the approximation to π, we perform a large number of experiments. In each experiment we choose two

computes a mathematical function: Given the same input twice, it produces the same output. Therefore, the number sequence produced by `rand-update` certainly is not "random," if by "random" we insist that each number in the sequence is unrelated to the preceding number. The relation between "real randomness" and so-called *pseudo-random* sequences, which are produced by well-determined computations and yet have suitable statistical properties, is a complex question involving difficult issues in mathematics and philosophy. Kolmogorov, Solomonoff, and Chaitin have made great progress in clarifying these issues; a discussion can be found in Chaitin 1975.

[7] This theorem is due to E. Cesàro. See section 4.5.2 of Knuth 1981 for a discussion and a

integers at random and perform a test to see if their GCD is 1. The fraction of times that the test is passed gives us our estimate of $6/\pi^2$, and from this we obtain our approximation to π.

The heart of our program is a procedure `monte-carlo`, which takes as arguments the number of times to try an experiment, together with the experiment, represented as a no-argument procedure that will return either true or false each time it is run. `monte-carlo` runs the experiment for the designated number of trials and returns a number telling the fraction of the trials in which the experiment was found to be true.

```
(define (estimate-pi trials)
  (sqrt (/ 6 (monte-carlo trials cesaro-test))))
(define (cesaro-test)
   (= (gcd (rand) (rand)) 1))

(define (monte-carlo trials experiment)
  (define (iter trials-remaining trials-passed)
    (cond ((= trials-remaining 0)
           (/ trials-passed trials))
          ((experiment)
           (iter (- trials-remaining 1)
                 (+ trials-passed 1)))
          (else
           (iter (- trials-remaining 1)
                 trials-passed))))
  (iter trials 0))
```

Now let us try the same computation using `rand-update` directly rather than `rand`, the way we would be forced to proceed if we did not use assignment to model local state:

```
(define (estimate-pi trials)
```

proof.

```
  (sqrt (/ 6 (random-gcd-test trials random-init))))
(define (random-gcd-test trials initial-x)
  (define (iter trials-remaining trials-passed x)
    (let ((x1 (rand-update x)))
      (let ((x2 (rand-update x1)))
        (cond ((= trials-remaining 0)
               (/ trials-passed trials))
              ((= (gcd x1 x2) 1)
               (iter (- trials-remaining 1)
                     (+ trials-passed 1)
                     x2))
              (else
               (iter (- trials-remaining 1)
                     trials-passed
                     x2))))))
  (iter trials 0 initial-x))
```

While the program is still simple, it betrays some painful breaches of modularity. In our first version of the program, using `rand`, we can express the Monte Carlo method directly as a general `monte-carlo` procedure that takes as an argument an arbitrary `experiment` procedure. In our second version of the program, with no local state for the random-number generator, `random-gcd-test` must explicitly manipulate the random numbers `x1` and `x2` and recycle `x2` through the iterative loop as the new input to `rand-update`. This explicit handling of the random numbers intertwines the structure of accumulating test results with the fact that our particular experiment uses two random numbers, whereas other Monte Carlo experiments might use one random number or three. Even the top-level procedure `estimate-pi` has to be concerned with supplying an initial random number. The fact that the random-number generator's insides are leaking out into other parts of the program makes it difficult for us to isolate the Monte Carlo idea so that it can be applied to other tasks. In the first version of the

program, assignment encapsulates the state of the random-number generator within the `rand` procedure, so that the details of random-number generation remain independent of the rest of the program.

The general phenomenon illustrated by the Monte Carlo example is this: From the point of view of one part of a complex process, the other parts appear to change with time. They have hidden time-varying local state. If we wish to write computer programs whose structure reflects this decomposition, we make computational objects (such as bank accounts and random-number generators) whose behavior changes with time. We model state with local state variables, and we model the changes of state with assignments to those variables.

It is tempting to conclude this discussion by saying that, by introducing assignment and the technique of hiding state in local variables, we are able to structure systems in a more modular fashion than if all state had to be manipulated explicitly, by passing additional parameters. Unfortunately, as we shall see, the story is not so simple.

Exercise 3.5: *Monte Carlo integration* is a method of estimating definite integrals by means of Monte Carlo simulation. Consider computing the area of a region of space described by a predicate $P(x, y)$ that is true for points (x, y) in the region and false for points not in the region. For example, the region contained within a circle of radius 3 centered at (5, 7) is described by the predicate that tests whether $(x - 5)^2 + (y - 7)^2 \leq 3^2$. To estimate the area of the region described by such a predicate, begin by choosing a rectangle that contains the region. For example, a rectangle with diagonally opposite corners at (2, 4) and (8, 10) contains the circle above. The desired integral is the area of that portion of the rectangle that lies in the region. We can estimate the integral by picking, at random, points (x, y) that

lie in the rectangle, and testing $P(x, y)$ for each point to determine whether the point lies in the region. If we try this with many points, then the fraction of points that fall in the region should give an estimate of the proportion of the rectangle that lies in the region. Hence, multiplying this fraction by the area of the entire rectangle should produce an estimate of the integral.

Implement Monte Carlo integration as a procedure `estimate-integral` that takes as arguments a predicate `P`, upper and lower bounds `x1`, `x2`, `y1`, and `y2` for the rectangle, and the number of trials to perform in order to produce the estimate. Your procedure should use the same `monte-carlo` procedure that was used above to estimate π. Use your `estimate-integral` to produce an estimate of π by measuring the area of a unit circle.

You will find it useful to have a procedure that returns a number chosen at random from a given range. The following `random-in-range` procedure implements this in terms of the `random` procedure used in Section 1.2.6, which returns a nonnegative number less than its input.[8]

```
(define (random-in-range low high)
  (let ((range (- high low)))
    (+ low (random range))))
```

Exercise 3.6: It is useful to be able to reset a random-number generator to produce a sequence starting from a given value. Design a new `rand` procedure that is called with an argument that

[8] MIT Scheme provides such a procedure. If `random` is given an exact integer (as in Section 1.2.6) it returns an exact integer, but if it is given a decimal value (as in this exercise) it returns a decimal value.

is either the symbol `generate` or the symbol `reset` and behaves as follows: `(rand 'generate)` produces a new random number; `((rand 'reset)` ⟨*new-value*⟩`)` resets the internal state variable to the designated ⟨*new-value*⟩. Thus, by resetting the state, one can generate repeatable sequences. These are very handy to have when testing and debugging programs that use random numbers.

3.1.3 The Costs of Introducing Assignment

As we have seen, the `set!` operation enables us to model objects that have local state. However, this advantage comes at a price. Our programming language can no longer be interpreted in terms of the substitution model of procedure application that we introduced in Section 1.1.5. Moreover, no simple model with "nice" mathematical properties can be an adequate framework for dealing with objects and assignment in programming languages.

So long as we do not use assignments, two evaluations of the same procedure with the same arguments will produce the same result, so that procedures can be viewed as computing mathematical functions. Programming without any use of assignments, as we did throughout the first two chapters of this book, is accordingly known as *functional programming*.

To understand how assignment complicates matters, consider a simplified version of the `make-withdraw` procedure of Section 3.1.1 that does not bother to check for an insufficient amount:

```
(define (make-simplified-withdraw balance)
  (lambda (amount)
    (set! balance (- balance amount))
    balance))
(define W (make-simplified-withdraw 25))
(W 20)
```

```
5
(W 10)
-5
```

Compare this procedure with the following `make-decrementer` procedure, which does not use `set!`:

```
(define (make-decrementer balance)
  (lambda (amount)
    (- balance amount)))
```

`make-decrementer` returns a procedure that subtracts its input from a designated amount `balance`, but there is no accumulated effect over successive calls, as with `make-simplified-withdraw`:

```
(define D (make-decrementer 25))
(D 20)
5
(D 10)
15
```

We can use the substitution model to explain how `make-decrementer` works. For instance, let us analyze the evaluation of the expression

```
((make-decrementer 25) 20)
```

We first simplify the operator of the combination by substituting 25 for `balance` in the body of `make-decrementer`. This reduces the expression to

```
((lambda (amount) (- 25 amount)) 20)
```

Now we apply the operator by substituting 20 for `amount` in the body of the `lambda` expression:

```
(- 25 20)
```

The final answer is 5.

Observe, however, what happens if we attempt a similar substitution analysis with `make-simplified-withdraw`:

```
((make-simplified-withdraw 25) 20)
```

We first simplify the operator by substituting 25 for `balance` in the body of `make-simplified-withdraw`. This reduces the expression to[9]

```
((lambda (amount) (set! balance (- 25 amount)) 25) 20)
```

Now we apply the operator by substituting 20 for `amount` in the body of the `lambda` expression:

```
(set! balance (- 25 20)) 25
```

If we adhered to the substitution model, we would have to say that the meaning of the procedure application is to first set `balance` to 5 and then return 25 as the value of the expression. This gets the wrong answer. In order to get the correct answer, we would have to somehow distinguish the first occurrence of `balance` (before the effect of the `set!`) from the second occurrence of `balance` (after the effect of the `set!`), and the substitution model cannot do this.

The trouble here is that substitution is based ultimately on the notion that the symbols in our language are essentially names for values. But as soon as we introduce `set!` and the idea that the value of a variable can change, a variable can no longer be simply a name. Now a variable somehow refers to a place where a value can be stored, and the value stored at this place can change. In Section 3.2 we will see how environments play this role of "place" in our computational model.

[9] We don't substitute for the occurrence of `balance` in the `set!` expression because the ⟨*name*⟩ in a `set!` is not evaluated. If we did substitute for it, we would get `(set! 25 (- 25 amount))`, which makes no sense.

Sameness and change

The issue surfacing here is more profound than the mere breakdown of a particular model of computation. As soon as we introduce change into our computational models, many notions that were previously straightforward become problematical. Consider the concept of two things being "the same."

Suppose we call `make-decrementer` twice with the same argument to create two procedures:

```
(define D1 (make-decrementer 25))
(define D2 (make-decrementer 25))
```

Are `D1` and `D2` the same? An acceptable answer is yes, because `D1` and `D2` have the same computational behavior—each is a procedure that subtracts its input from 25. In fact, `D1` could be substituted for `D2` in any computation without changing the result.

Contrast this with making two calls to `make-simplified-withdraw`:

```
(define W1 (make-simplified-withdraw 25))
(define W2 (make-simplified-withdraw 25))
```

Are `W1` and `W2` the same? Surely not, because calls to `W1` and `W2` have distinct effects, as shown by the following sequence of interactions:

```
(W1 20)
5
(W1 20)
-15
(W2 20)
5
```

Even though `W1` and `W2` are "equal" in the sense that they are both created by evaluating the same expression, `(make-simplified-withdraw 25)`, it is not true that `W1` could be substituted for `W2` in any expression without changing the result of evaluating the expression.

A language that supports the concept that "equals can be substituted for equals" in an expression without changing the value of the expression is said to be *referentially transparent*. Referential transparency is violated when we include `set!` in our computer language. This makes it tricky to determine when we can simplify expressions by substituting equivalent expressions. Consequently, reasoning about programs that use assignment becomes drastically more difficult.

Once we forgo referential transparency, the notion of what it means for computational objects to be "the same" becomes difficult to capture in a formal way. Indeed, the meaning of "same" in the real world that our programs model is hardly clear in itself. In general, we can determine that two apparently identical objects are indeed "the same one" only by modifying one object and then observing whether the other object has changed in the same way. But how can we tell if an object has "changed" other than by observing the "same" object twice and seeing whether some property of the object differs from one observation to the next? Thus, we cannot determine "change" without some *a priori* notion of "sameness," and we cannot determine sameness without observing the effects of change.

As an example of how this issue arises in programming, consider the situation where Peter and Paul have a bank account with $100 in it. There is a substantial difference between modeling this as

```
(define peter-acc (make-account 100))
(define paul-acc (make-account 100))
```

and modeling it as

```
(define peter-acc (make-account 100))
(define paul-acc peter-acc)
```

In the first situation, the two bank accounts are distinct. Transactions made by Peter will not affect Paul's account, and vice versa. In the second situation,

however, we have defined `paul-acc` to be *the same thing* as `peter-acc`. In effect, Peter and Paul now have a joint bank account, and if Peter makes a withdrawal from `peter-acc` Paul will observe less money in `paul-acc`. These two similar but distinct situations can cause confusion in building computational models. With the shared account, in particular, it can be especially confusing that there is one object (the bank account) that has two different names (`peter-acc` and `paul-acc`); if we are searching for all the places in our program where `paul-acc` can be changed, we must remember to look also at things that change `peter-acc`.[10]

With reference to the above remarks on "sameness" and "change," observe that if Peter and Paul could only examine their bank balances, and could not perform operations that changed the balance, then the issue of whether the two accounts are distinct would be moot. In general, so long as we never modify data objects, we can regard a compound data object to be precisely the totality of its pieces. For example, a rational number is determined by giving its numerator and its denominator. But this view is no longer valid in the presence of change, where a compound data object has an "identity" that is something different from the pieces of which it is composed. A bank account is still "the same" bank account even if we change the balance by making a withdrawal; conversely, we could have two different bank accounts with the same state information. This complication is a consequence, not

[10]The phenomenon of a single computational object being accessed by more than one name is known as *aliasing*. The joint bank account situation illustrates a very simple example of an alias. In Section 3.3 we will see much more complex examples, such as "distinct" compound data structures that share parts. Bugs can occur in our programs if we forget that a change to an object may also, as a "side effect," change a "different" object because the two "different" objects are actually a single object appearing under different aliases. These so-called *side-effect bugs* are so difficult to locate and to analyze that some people have proposed that programming languages be designed in such a way as to not allow side effects or aliasing (Lampson et al. 1981; Morris et al. 1980).

of our programming language, but of our perception of a bank account as an object. We do not, for example, ordinarily regard a rational number as a changeable object with identity, such that we could change the numerator and still have "the same" rational number.

Pitfalls of imperative programming

In contrast to functional programming, programming that makes extensive use of assignment is known as *imperative programming*. In addition to raising complications about computational models, programs written in imperative style are susceptible to bugs that cannot occur in functional programs. For example, recall the iterative factorial program from Section 1.2.1:

```
(define (factorial n)
  (define (iter product counter)
    (if (> counter n)
        product
        (iter (* counter product) (+ counter 1))))
  (iter 1 1))
```

Instead of passing arguments in the internal iterative loop, we could adopt a more imperative style by using explicit assignment to update the values of the variables `product` and `counter`:

```
(define (factorial n)
  (let ((product 1)
        (counter 1))
    (define (iter)
      (if (> counter n)
          product
          (begin (set! product (* counter product))
                 (set! counter (+ counter 1))
                 (iter))))
    (iter)))
```

This does not change the results produced by the program, but it does introduce a subtle trap. How do we decide the order of the assignments? As it happens, the program is correct as written. But writing the assignments in the opposite order

```
(set! counter (+ counter 1))
(set! product (* counter product))
```

would have produced a different, incorrect result. In general, programming with assignment forces us to carefully consider the relative orders of the assignments to make sure that each statement is using the correct version of the variables that have been changed. This issue simply does not arise in functional programs.[11]

The complexity of imperative programs becomes even worse if we consider applications in which several processes execute concurrently. We will return to this in Section 3.4. First, however, we will address the issue of providing a computational model for expressions that involve assignment, and explore the uses of objects with local state in designing simulations.

> **Exercise 3.7:** Consider the bank account objects created by `make-account`, with the password modification described in Exercise 3.3. Suppose that our banking system requires the ability to make joint accounts. Define a procedure `make-joint` that accomplishes this. `make-joint` should take three arguments. The first is a password-protected account. The second

[11] In view of this, it is ironic that introductory programming is most often taught in a highly imperative style. This may be a vestige of a belief, common throughout the 1960s and 1970s, that programs that call procedures must inherently be less efficient than programs that perform assignments. (Steele 1977 debunks this argument.) Alternatively it may reflect a view that step-by-step assignment is easier for beginners to visualize than procedure call. Whatever the reason, it often saddles beginning programmers with "should I set this variable before or after that one" concerns that can complicate programming and obscure the important ideas.

argument must match the password with which the account was defined in order for the `make-joint` operation to proceed. The third argument is a new password. `make-joint` is to create an additional access to the original account using the new password. For example, if `peter-acc` is a bank account with password `open-sesame`, then

```
(define paul-acc
  (make-joint peter-acc 'open-sesame 'rosebud))
```

will allow one to make transactions on `peter-acc` using the name `paul-acc` and the password `rosebud`. You may wish to modify your solution to Exercise 3.3 to accommodate this new feature.

Exercise 3.8: When we defined the evaluation model in Section 1.1.3, we said that the first step in evaluating an expression is to evaluate its subexpressions. But we never specified the order in which the subexpressions should be evaluated (e.g., left to right or right to left). When we introduce assignment, the order in which the arguments to a procedure are evaluated can make a difference to the result. Define a simple procedure `f` such that evaluating

```
(+ (f 0) (f 1))
```

will return 0 if the arguments to + are evaluated from left to right but will return 1 if the arguments are evaluated from right to left.

3.2 The Environment Model of Evaluation

When we introduced compound procedures in Chapter 1, we used the substitution model of evaluation (Section 1.1.5) to define what is meant by applying a procedure to arguments:

- To apply a compound procedure to arguments, evaluate the body of the procedure with each formal parameter replaced by the corresponding argument.

Once we admit assignment into our programming language, such a definition is no longer adequate. In particular, Section 3.1.3 argued that, in the presence of assignment, a variable can no longer be considered to be merely a name for a value. Rather, a variable must somehow designate a "place" in which values can be stored. In our new model of evaluation, these places will be maintained in structures called *environments*.

An environment is a sequence of *frames*. Each frame is a table (possibly empty) of *bindings*, which associate variable names with their corresponding values. (A single frame may contain at most one binding for any variable.) Each frame also has a pointer to its *enclosing environment*, unless, for the purposes of discussion, the frame is considered to be *global*. The *value of a variable* with respect to an environment is the value given by the binding of the variable in the first frame in the environment that contains a binding for that variable. If no frame in the sequence specifies a binding for the variable, then the variable is said to be *unbound* in the environment.

Figure 3.1 shows a simple environment structure consisting of three frames, labeled I, II, and III. In the diagram, A, B, C, and D are pointers to environments. C and D point to the same environment. The variables `z` and `x` are bound in frame II, while `y` and `x` are bound in frame I. The value of `x` in environment D is 3. The value of `x` with respect to environment B is also 3.




Figure 3.1: A simple environment structure.

This is determined as follows: We examine the first frame in the sequence (frame III) and do not find a binding for `x`, so we proceed to the enclosing environment D and find the binding in frame I. On the other hand, the value of `x` in environment A is 7, because the first frame in the sequence (frame II) contains a binding of `x` to 7. With respect to environment A, the binding of `x` to 7 in frame II is said to *shadow* the binding of `x` to 3 in frame I.

The environment is crucial to the evaluation process, because it determines the context in which an expression should be evaluated. Indeed, one could say that expressions in a programming language do not, in themselves, have any meaning. Rather, an expression acquires a meaning only with respect to some environment in which it is evaluated. Even the interpretation of an expression as straightforward as `(+ 1 1)` depends on an understanding that one is operating in a context in which + is the symbol for addition. Thus, in our model of evaluation we will always speak of evaluating an expression with respect to some environment. To describe interactions with the interpreter, we will suppose that there is a global environment, consisting of a single frame (with no enclosing environment) that includes values for the

symbols associated with the primitive procedures. For example, the idea that + is the symbol for addition is captured by saying that the symbol + is bound in the global environment to the primitive addition procedure.

3.2.1 The Rules for Evaluation

The overall specification of how the interpreter evaluates a combination remains the same as when we first introduced it in Section 1.1.3:

- To evaluate a combination:

1. Evaluate the subexpressions of the combination.[12]
2. Apply the value of the operator subexpression to the values of the operand subexpressions.

The environment model of evaluation replaces the substitution model in specifying what it means to apply a compound procedure to arguments.

In the environment model of evaluation, a procedure is always a pair consisting of some code and a pointer to an environment. Procedures are created in one way only: by evaluating a λ-expression. This produces a procedure whose code is obtained from the text of the λ-expression and whose environment is the environment in which the λ-expression was evaluated to produce the procedure. For example, consider the procedure definition

[12] Assignment introduces a subtlety into step 1 of the evaluation rule. As shown in Exercise 3.8, the presence of assignment allows us to write expressions that will produce different values depending on the order in which the subexpressions in a combination are evaluated. Thus, to be precise, we should specify an evaluation order in step 1 (e.g., left to right or right to left). However, this order should always be considered to be an implementation detail, and one should never write programs that depend on some particular order. For instance, a sophisticated compiler might optimize a program by varying the order in which subexpressions are evaluated.

```
(define (square x)
  (* x x))
```

evaluated in the global environment. The procedure definition syntax is just syntactic sugar for an underlying implicit λ-expression. It would have been equivalent to have used

```
(define square
  (lambda (x) (* x x)))
```

which evaluates `(lambda (x) (* x x))` and binds `square` to the resulting value, all in the global environment.

Figure 3.2 shows the result of evaluating this `define` expression. The procedure object is a pair whose code specifies that the procedure has one formal parameter, namely `x`, and a procedure body `(* x x)`. The environment part of the procedure is a pointer to the global environment, since that is the environment in which the λ-expression was evaluated to produce the procedure. A new binding, which associates the procedure object with the symbol `square`, has been added to the global frame. In general, `define` creates definitions by adding bindings to frames.

Now that we have seen how procedures are created, we can describe how procedures are applied. The environment model specifies: To apply a procedure to arguments, create a new environment containing a frame that binds the parameters to the values of the arguments. The enclosing environment of this frame is the environment specified by the procedure. Now, within this new environment, evaluate the procedure body.

To show how this rule is followed, Figure 3.3 illustrates the environment structure created by evaluating the expression `(square 5)` in the global environment, where `square` is the procedure generated in Figure 3.2. Applying the procedure results in the creation of a new environment, labeled E1 in the figure, that begins with a frame in which `x`, the formal parameter for the procedure, is bound to the argument 5. The pointer leading upward




Figure 3.2: Environment structure produced by evaluating `(define (square x) (* x x))` in the global environment.

from this frame shows that the frame's enclosing environment is the global environment. The global environment is chosen here, because this is the environment that is indicated as part of the `square` procedure object. Within E1, we evaluate the body of the procedure, `(* x x)`. Since the value of `x` in E1 is 5, the result is `(* 5 5)`, or 25.

The environment model of procedure application can be summarized by two rules:

- A procedure object is applied to a set of arguments by constructing a frame, binding the formal parameters of the procedure to the arguments of the call, and then evaluating the body of the procedure in the context of the new environment constructed. The new frame has as its enclosing environment the environment part of the procedure object being applied.

- A procedure is created by evaluating a λ-expression relative to a given




Figure 3.3: Environment created by evaluating `(square 5)` in the global environment.

environment. The resulting procedure object is a pair consisting of the text of the λ-expression and a pointer to the environment in which the procedure was created.

We also specify that defining a symbol using `define` creates a binding in the current environment frame and assigns to the symbol the indicated value.[13] Finally, we specify the behavior of `set!`, the operation that forced us to introduce the environment model in the first place. Evaluating the expression `(set!` ⟨*variable*⟩ ⟨*value*⟩`)` in some environment locates the binding of the variable in the environment and changes that binding to indicate the new value. That is, one finds the first frame in the environment that contains a binding for the variable and modifies that frame. If the variable is unbound

[13] If there is already a binding for the variable in the current frame, then the binding is changed. This is convenient because it allows redefinition of symbols; however, it also means that `define` can be used to change values, and this brings up the issues of assignment without explicitly using `set!`. Because of this, some people prefer redefinitions of existing symbols to signal errors or warnings.

in the environment, then `set!` signals an error.

These evaluation rules, though considerably more complex than the substitution model, are still reasonably straightforward. Moreover, the evaluation model, though abstract, provides a correct description of how the interpreter evaluates expressions. In Chapter 4 we shall see how this model can serve as a blueprint for implementing a working interpreter. The following sections elaborate the details of the model by analyzing some illustrative programs.

3.2.2 Applying Simple Procedures

When we introduced the substitution model in Section 1.1.5 we showed how the combination `(f 5)` evaluates to 136, given the following procedure definitions:

```
(define (square x)
  (* x x))
(define (sum-of-squares x y)
  (+ (square x) (square y)))
(define (f a)
  (sum-of-squares (+ a 1) (* a 2)))
```

We can analyze the same example using the environment model. Figure 3.4 shows the three procedure objects created by evaluating the definitions of `f`, `square`, and `sum-of-squares` in the global environment. Each procedure object consists of some code, together with a pointer to the global environment.

In Figure 3.5 we see the environment structure created by evaluating the expression `(f 5)`. The call to `f` creates a new environment E1 beginning with a frame in which `a`, the formal parameter of `f`, is bound to the argument 5. In E1, we evaluate the body of `f`:

```
(sum-of-squares (+ a 1) (* a 2))
```




Figure 3.4: Procedure objects in the global frame.

To evaluate this combination, we first evaluate the subexpressions. The first subexpression, `sum-of-squares`, has a value that is a procedure object. (Notice how this value is found: We first look in the first frame of E1, which contains no binding for `sum-of-squares`. Then we proceed to the enclosing environment, i.e. the global environment, and find the binding shown in Figure 3.4.) The other two subexpressions are evaluated by applying the primitive operations `+` and `*` to evaluate the two combinations `(+ a 1)` and `(* a 2)` to obtain 6 and 10, respectively.

Now we apply the procedure object `sum-of-squares` to the arguments 6 and 10. This results in a new environment E2 in which the formal parameters `x` and `y` are bound to the arguments. Within E2 we evaluate the combination `(+ (square x) (square y))`. This leads us to evaluate `(square x)`, where `square` is found in the global frame and `x` is 6. Once again, we set up a new environment, E3, in which `x` is bound to 6, and within this we evaluate the body of `square`, which is `(* x x)`. Also as part of applying `sum-of-squares`, we must evaluate the subexpression `(square y)`, where `y` is 10. This second call to `square` creates




Figure 3.5: Environments created by evaluating `(f 5)` using the procedures in Figure 3.4.

another environment, E4, in which `x`, the formal parameter of `square`, is bound to 10. And within E4 we must evaluate `(* x x)`.

The important point to observe is that each call to `square` creates a new environment containing a binding for `x`. We can see here how the different frames serve to keep separate the different local variables all named `x`. Notice that each frame created by `square` points to the global environment, since this is the environment indicated by the `square` procedure object.

After the subexpressions are evaluated, the results are returned. The values generated by the two calls to `square` are added by `sum-of-squares`, and this result is returned by `f`. Since our focus here is on the environment structures, we will not dwell on how these returned values are passed from call to call; however, this is also an important aspect of the evaluation process, and we will return to it in detail in Chapter 5.

Exercise 3.9: In Section 1.2.1 we used the substitution model to analyze two procedures for computing factorials, a recursive

version

```
(define (factorial n)
  (if (= n 1) 1 (* n (factorial (- n 1)))))
```

and an iterative version

```
(define (factorial n) (fact-iter 1 1 n))
(define (fact-iter product counter max-count)
  (if (> counter max-count)
      product
      (fact-iter (* counter product)
                 (+ counter 1)
                 max-count)))
```

Show the environment structures created by evaluating `(factorial 6)` using each version of the `factorial` procedure.[14]

3.2.3 Frames as the Repository of Local State

We can turn to the environment model to see how procedures and assignment can be used to represent objects with local state. As an example, consider the "withdrawal processor" from Section 3.1.1 created by calling the procedure

```
(define (make-withdraw balance)
  (lambda (amount)
    (if (>= balance amount)
        (begin (set! balance (- balance amount))
               balance)
        "Insufficient funds")))
```

[14] The environment model will not clarify our claim in Section 1.2.1 that the interpreter can execute a procedure such as `fact-iter` in a constant amount of space using tail recursion. We will discuss tail recursion when we deal with the control structure of the interpreter in Section 5.4.




Figure 3.6: Result of defining `make-withdraw` in the global environment.

Let us describe the evaluation of

```
(define W1 (make-withdraw 100))
```

followed by

```
(W1 50)
50
```

Figure 3.6 shows the result of defining the `make-withdraw` procedure in the global environment. This produces a procedure object that contains a pointer to the global environment. So far, this is no different from the examples we have already seen, except that the body of the procedure is itself a λ-expression.

The interesting part of the computation happens when we apply the procedure `make-withdraw` to an argument:

```
(define W1 (make-withdraw 100))
```




Figure 3.7: Result of evaluating `(define W1 (make-withdraw 100))`.

We begin, as usual, by setting up an environment E1 in which the formal parameter `balance` is bound to the argument 100. Within this environment, we evaluate the body of `make-withdraw`, namely the λ-expression. This constructs a new procedure object, whose code is as specified by the `lambda` and whose environment is E1, the environment in which the `lambda` was evaluated to produce the procedure. The resulting procedure object is the value returned by the call to `make-withdraw`. This is bound to `W1` in the global environment, since the `define` itself is being evaluated in the global environment. Figure 3.7 shows the resulting environment structure.

Now we can analyze what happens when `W1` is applied to an argument:

```
(W1 50)
50
```

We begin by constructing a frame in which `amount`, the formal param-




Figure 3.8: Environments created by applying the procedure object `W1`.

eter of `W1`, is bound to the argument 50. The crucial point to observe is that this frame has as its enclosing environment not the global environment, but rather the environment E1, because this is the environment that is specified by the `W1` procedure object. Within this new environment, we evaluate the body of the procedure:

```
(if (>= balance amount)
    (begin (set! balance (- balance amount))
           balance)
    "Insufficient funds")
```

The resulting environment structure is shown in Figure 3.8. The expression being evaluated references both `amount` and `balance`. `amount` will be found in the first frame in the environment, while `balance` will be found by following the enclosing-environment pointer to E1.




Figure 3.9: Environments after the call to `W1`.

When the `set!` is executed, the binding of `balance` in E1 is changed. At the completion of the call to `W1`, `balance` is 50, and the frame that contains `balance` is still pointed to by the procedure object `W1`. The frame that binds `amount` (in which we executed the code that changed `balance`) is no longer relevant, since the procedure call that constructed it has terminated, and there are no pointers to that frame from other parts of the environment. The next time `W1` is called, this will build a new frame that binds `amount` and whose enclosing environment is E1. We see that E1 serves as the "place" that holds the local state variable for the procedure object `W1`. Figure 3.9 shows the situation after the call to `W1`.

Observe what happens when we create a second "withdraw" object by making another call to `make-withdraw`:

```
(define W2 (make-withdraw 100))
```

This produces the environment structure of Figure 3.10, which shows that `W2` is a procedure object, that is, a pair with some code and an environment. The environment E2 for `W2` was created by the call to `make-withdraw`.




Figure 3.10: Using `(define W2 (make-withdraw 100))` to create a second object.

It contains a frame with its own local binding for `balance`. On the other hand, `W1` and `W2` have the same code: the code specified by the λ-expression in the body of `make-withdraw`.[15] We see here why `W1` and `W2` behave as independent objects. Calls to `W1` reference the state variable `balance` stored in E1, whereas calls to `W2` reference the `balance` stored in E2. Thus, changes to the local state of one object do not affect the other object.

> **Exercise 3.10:** In the `make-withdraw` procedure, the local variable `balance` is created as a parameter of `make-withdraw`. We could also create the local state variable explicitly, using `let`, as follows:

[15] Whether `W1` and `W2` share the same physical code stored in the computer, or whether they each keep a copy of the code, is a detail of the implementation. For the interpreter we implement in Chapter 4, the code is in fact shared.

```
(define (make-withdraw initial-amount)
  (let ((balance initial-amount))
    (lambda (amount)
      (if (>= balance amount)
          (begin (set! balance (- balance amount))
                 balance)
          "Insufficient funds"))))
```

Recall from Section 1.3.2 that `let` is simply syntactic sugar for a procedure call:

```
(let ((⟨var⟩ ⟨exp⟩)) ⟨body⟩)
```

is interpreted as an alternate syntax for

```
((lambda (⟨var⟩) ⟨body⟩) ⟨exp⟩)
```

Use the environment model to analyze this alternate version of `make-withdraw`, drawing figures like the ones above to illustrate the interactions

```
(define W1 (make-withdraw 100))
(W1 50)
(define W2 (make-withdraw 100))
```

Show that the two versions of `make-withdraw` create objects with the same behavior. How do the environment structures differ for the two versions?

3.2.4 Internal Definitions

Section 1.1.8 introduced the idea that procedures can have internal definitions, thus leading to a block structure as in the following procedure to compute square roots:

```
(define (sqrt x)
  (define (good-enough? guess)
    (< (abs (- (square guess) x)) 0.001))
  (define (improve guess)
    (average guess (/ x guess)))
  (define (sqrt-iter guess)
    (if (good-enough? guess)
        guess
        (sqrt-iter (improve guess))))
  (sqrt-iter 1.0))
```

Now we can use the environment model to see why these internal definitions behave as desired. Figure 3.11 shows the point in the evaluation of the expression `(sqrt 2)` where the internal procedure `good-enough?` has been called for the first time with `guess` equal to 1.

Observe the structure of the environment. `sqrt` is a symbol in the global environment that is bound to a procedure object whose associated environment is the global environment. When `sqrt` was called, a new environment E1 was formed, subordinate to the global environment, in which the parameter `x` is bound to 2. The body of `sqrt` was then evaluated in E1. Since the first expression in the body of `sqrt` is

```
(define (good-enough? guess)
  (< (abs (- (square guess) x)) 0.001))
```

evaluating this expression defined the procedure `good-enough?` in the environment E1. To be more precise, the symbol `good-enough?` was added to the first frame of E1, bound to a procedure object whose associated environment is E1. Similarly, `improve` and `sqrt-iter` were defined as procedures in E1. For conciseness, Figure 3.11 shows only the procedure object for `good-enough?`.

After the local procedures were defined, the expression `(sqrt-iter 1.0)` was evaluated, still in environment E1. So the procedure object bound




Figure 3.11: `sqrt` procedure with internal definitions.

to `sqrt-iter` in E1 was called with 1 as an argument. This created an environment E2 in which `guess`, the parameter of `sqrt-iter`, is bound to 1. `sqrt-iter` in turn called `good-enough?` with the value of `guess` (from E2) as the argument for `good-enough?`. This set up another environment, E3, in which `guess` (the parameter of `good-enough?`) is bound to 1. Although `sqrt-iter` and `good-enough?` both have a parameter named `guess`, these are two distinct local variables located in different frames. Also, E2 and E3 both have E1 as their enclosing environment, because the `sqrt-iter` and `good-enough?` procedures

both have E1 as their environment part. One consequence of this is that the symbol `x` that appears in the body of `good-enough?` will reference the binding of `x` that appears in E1, namely the value of `x` with which the original `sqrt` procedure was called.

The environment model thus explains the two key properties that make local procedure definitions a useful technique for modularizing programs:

- The names of the local procedures do not interfere with names external to the enclosing procedure, because the local procedure names will be bound in the frame that the procedure creates when it is run, rather than being bound in the global environment.
- The local procedures can access the arguments of the enclosing procedure, simply by using parameter names as free variables. This is because the body of the local procedure is evaluated in an environment that is subordinate to the evaluation environment for the enclosing procedure.

Exercise 3.11: In Section 3.2.3 we saw how the environment model described the behavior of procedures with local state. Now we have seen how internal definitions work. A typical message-passing procedure contains both of these aspects. Consider the bank account procedure of Section 3.1.1:

```
(define (make-account balance)
  (define (withdraw amount)
    (if (>= balance amount)
        (begin (set! balance (- balance amount))
               balance)
        "Insufficient funds"))
  (define (deposit amount)
    (set! balance (+ balance amount))
```

```
    balance)
  (define (dispatch m)
    (cond ((eq? m 'withdraw) withdraw)
          ((eq? m 'deposit) deposit)
          (else
           (error "Unknown request: MAKE-ACCOUNT"
                  m))))
  dispatch)
```

Show the environment structure generated by the sequence of interactions

```
(define acc (make-account 50))
((acc 'deposit) 40)
90
((acc 'withdraw) 60)
30
```

Where is the local state for `acc` kept? Suppose we define another account

```
(define acc2 (make-account 100))
```

How are the local states for the two accounts kept distinct? Which parts of the environment structure are shared between `acc` and `acc2`?

3.3 Modeling with Mutable Data

Chapter 2 dealt with compound data as a means for constructing computational objects that have several parts, in order to model real-world objects that have several aspects. In that chapter we introduced the discipline of data

abstraction, according to which data structures are specified in terms of constructors, which create data objects, and selectors, which access the parts of compound data objects. But we now know that there is another aspect of data that Chapter 2 did not address. The desire to model systems composed of objects that have changing state leads us to the need to modify compound data objects, as well as to construct and select from them. In order to model compound objects with changing state, we will design data abstractions to include, in addition to selectors and constructors, operations called *mutators*, which modify data objects. For instance, modeling a banking system requires us to change account balances. Thus, a data structure for representing bank accounts might admit an operation

`(set-balance!` ⟨*account*⟩ ⟨*new-value*⟩`)`

that changes the balance of the designated account to the designated new value. Data objects for which mutators are defined are known as *mutable data objects*.

Chapter 2 introduced pairs as a general-purpose "glue" for synthesizing compound data. We begin this section by defining basic mutators for pairs, so that pairs can serve as building blocks for constructing mutable data objects. These mutators greatly enhance the representational power of pairs, enabling us to build data structures other than the sequences and trees that we worked with in Section 2.2. We also present some examples of simulations in which complex systems are modeled as collections of objects with local state.

3.3.1 Mutable List Structure

The basic operations on pairs—`cons`, `car`, and `cdr`—can be used to construct list structure and to select parts from list structure, but they are incapable of modifying list structure. The same is true of the list operations we have used so far, such as `append` and `list`, since these can be defined

in terms of `cons`, `car`, and `cdr`. To modify list structures we need new operations.

The primitive mutators for pairs are `set-car!` and `set-cdr!`. `set-car!` takes two arguments, the first of which must be a pair. It modifies this pair, replacing the `car` pointer by a pointer to the second argument of `set-car!`.[16]

As an example, suppose that `x` is bound to the list `((a b) c d)` and `y` to the list `(e f)` as illustrated in Figure 3.12. Evaluating the expression `(set-car! x y)` modifies the pair to which `x` is bound, replacing its `car` by the value of `y`. The result of the operation is shown in Figure 3.13. The structure `x` has been modified and would now be printed as `((e f) c d)`. The pairs representing the list `(a b)`, identified by the pointer that was replaced, are now detached from the original structure.[17]

Compare Figure 3.13 with Figure 3.14, which illustrates the result of executing `(define z (cons y (cdr x)))` with `x` and `y` bound to the original lists of Figure 3.12. The variable `z` is now bound to a new pair created by the `cons` operation; the list to which `x` is bound is unchanged.

The `set-cdr!` operation is similar to `set-car!`. The only difference is that the `cdr` pointer of the pair, rather than the `car` pointer, is replaced. The effect of executing `(set-cdr! x y)` on the lists of Figure 3.12 is shown in Figure 3.15. Here the `cdr` pointer of `x` has been replaced by the pointer to `(e f)`. Also, the list `(c d)`, which used to be the `cdr` of `x`, is now detached from the structure.

`cons` builds new list structure by creating new pairs, while `set-car!` and `set-cdr!` modify existing pairs. Indeed, we could implement `cons` in terms of the two mutators, together with a procedure `get-new-pair`,

[16] `set-car!` and `set-cdr!` return implementation-dependent values. Like `set!`, they should be used only for their effect.

[17] We see from this that mutation operations on lists can create "garbage" that is not part of any accessible structure. We will see in Section 5.3.2 that Lisp memory-management systems include a *garbage collector*, which identifies and recycles the memory space used by unneeded pairs.




Figure 3.12: Lists `x`: `((a b) c d)` and `y`: `(e f)`.




Figure 3.13: Effect of `(set-car! x y)` on the lists in Figure 3.12.




Figure 3.14: Effect of `(define z (cons y (cdr x)))` on the lists in Figure 3.12.




Figure 3.15: Effect of `(set-cdr! x y)` on the lists in Figure 3.12.

which returns a new pair that is not part of any existing list structure. We obtain the new pair, set its `car` and `cdr` pointers to the designated objects, and return the new pair as the result of the `cons`.[18]

```
(define (cons x y)
  (let ((new (get-new-pair)))
    (set-car! new x)
    (set-cdr! new y)
    new))
```

Exercise 3.12: The following procedure for appending lists was introduced in Section 2.2.1:

```
(define (append x y)
  (if (null? x)
      y
      (cons (car x) (append (cdr x) y))))
```

`append` forms a new list by successively `cons`ing the elements of `x` onto `y`. The procedure `append!` is similar to `append`, but it is a mutator rather than a constructor. It appends the lists by splicing them together, modifying the final pair of `x` so that its `cdr` is now `y`. (It is an error to call `append!` with an empty `x`.)

```
(define (append! x y)
  (set-cdr! (last-pair x) y)
  x)
```

Here `last-pair` is a procedure that returns the last pair in its argument:

[18] `get-new-pair` is one of the operations that must be implemented as part of the memory management required by a Lisp implementation. We will discuss this in Section 5.3.1.

```
(define (last-pair x)
  (if (null? (cdr x)) x (last-pair (cdr x))))
```

Consider the interaction

```
(define x (list 'a 'b))
(define y (list 'c 'd))
(define z (append x y))
z
(a b c d)
(cdr x)
⟨response⟩
(define w (append! x y))
w
(a b c d)
(cdr x)
⟨response⟩
```

What are the missing ⟨*response*⟩s? Draw box-and-pointer diagrams to explain your answer.

Exercise 3.13: Consider the following `make-cycle` procedure, which uses the `last-pair` procedure defined in Exercise 3.12:

```
(define (make-cycle x)
  (set-cdr! (last-pair x) x)
  x)
```

Draw a box-and-pointer diagram that shows the structure `z` created by

```
(define z (make-cycle (list 'a 'b 'c)))
```

What happens if we try to compute `(last-pair z)`?

Exercise 3.14: The following procedure is quite useful, although obscure:

```
(define (mystery x)
  (define (loop x y)
    (if (null? x)
        y
        (let ((temp (cdr x)))
          (set-cdr! x y)
          (loop temp x))))
  (loop x '()))
```

`loop` uses the "temporary" variable `temp` to hold the old value of the `cdr` of `x`, since the `set-cdr!` on the next line destroys the `cdr`. Explain what `mystery` does in general. Suppose `v` is defined by `(define v (list 'a 'b 'c 'd))`. Draw the box-and-pointer diagram that represents the list to which `v` is bound. Suppose that we now evaluate `(define w (mystery v))`. Draw box-and-pointer diagrams that show the structures `v` and `w` after evaluating this expression. What would be printed as the values of `v` and `w`?

Sharing and identity

We mentioned in Section 3.1.3 the theoretical issues of "sameness" and "change" raised by the introduction of assignment. These issues arise in practice when individual pairs are *shared* among different data objects. For example, consider the structure formed by

```
(define x (list 'a 'b))
(define z1 (cons x x))
```




Figure 3.16: The list `z1` formed by `(cons x x)`.

As shown in Figure 3.16, `z1` is a pair whose `car` and `cdr` both point to the same pair `x`. This sharing of `x` by the `car` and `cdr` of `z1` is a consequence of the straightforward way in which `cons` is implemented. In general, using `cons` to construct lists will result in an interlinked structure of pairs in which many individual pairs are shared by many different structures.

In contrast to Figure 3.16, Figure 3.17 shows the structure created by

```
(define z2 (cons (list 'a 'b) (list 'a 'b)))
```

In this structure, the pairs in the two `(a b)` lists are distinct, although the actual symbols are shared.[19]

When thought of as a list, `z1` and `z2` both represent "the same" list, `((a b) a b)`. In general, sharing is completely undetectable if we operate on lists using only `cons`, `car`, and `cdr`. However, if we allow mutators on list structure, sharing becomes significant. As an example of the difference that sharing can make, consider the following procedure, which modifies the `car` of the structure to which it is applied:

[19]The two pairs are distinct because each call to `cons` returns a new pair. The symbols are shared; in Scheme there is a unique symbol with any given name. Since Scheme provides no way to mutate a symbol, this sharing is undetectable. Note also that the sharing is what enables us to compare symbols using `eq?`, which simply checks equality of pointers.




Figure 3.17: The list `z2` formed by `(cons (list 'a 'b) (list 'a 'b))`.

```
(define (set-to-wow! x) (set-car! (car x) 'wow) x)
```

Even though `z1` and `z2` are "the same" structure, applying `set-to-wow!` to them yields different results. With `z1`, altering the `car` also changes the `cdr`, because in `z1` the `car` and the `cdr` are the same pair. With `z2`, the `car` and `cdr` are distinct, so `set-to-wow!` modifies only the `car`:

```
z1
((a b) a b)
(set-to-wow! z1)
((wow b) wow b)
z2
((a b) a b)
(set-to-wow! z2)
((wow b) a b)
```

One way to detect sharing in list structures is to use the predicate `eq?`, which we introduced in Section 2.3.1 as a way to test whether two symbols are equal. More generally, `(eq? x y)` tests whether `x` and `y` are the same object (that is, whether `x` and `y` are equal as pointers). Thus, with `z1` and `z2` as defined in Figure 3.16 and Figure 3.17, `(eq? (car z1) (cdr z1))` is true and `(eq? (car z2) (cdr z2))` is false.

As will be seen in the following sections, we can exploit sharing to greatly extend the repertoire of data structures that can be represented by pairs. On the other hand, sharing can also be dangerous, since modifications made to structures will also affect other structures that happen to share the modified parts. The mutation operations `set-car!` and `set-cdr!` should be used with care; unless we have a good understanding of how our data objects are shared, mutation can have unanticipated results.[20]

Exercise 3.15: Draw box-and-pointer diagrams to explain the effect of `set-to-wow!` on the structures `z1` and `z2` above.

Exercise 3.16: Ben Bitdiddle decides to write a procedure to count the number of pairs in any list structure. "It's easy," he reasons. "The number of pairs in any structure is the number in the `car` plus the number in the `cdr` plus one more to count the current pair." So Ben writes the following procedure:

```
(define (count-pairs x)
  (if (not (pair? x))
      0
      (+ (count-pairs (car x))
         (count-pairs (cdr x))
         1)))
```

[20]The subtleties of dealing with sharing of mutable data objects reflect the underlying issues of "sameness" and "change" that were raised in Section 3.1.3. We mentioned there that admitting change to our language requires that a compound object must have an "identity" that is something different from the pieces from which it is composed. In Lisp, we consider this "identity" to be the quality that is tested by `eq?`, i.e., by equality of pointers. Since in most Lisp implementations a pointer is essentially a memory address, we are "solving the problem" of defining the identity of objects by stipulating that a data object "itself" is the information stored in some particular set of memory locations in the computer. This suffices for simple Lisp programs, but is hardly a general way to resolve the issue of "sameness" in computational models.

Show that this procedure is not correct. In particular, draw box-and-pointer diagrams representing list structures made up of exactly three pairs for which Ben's procedure would return 3; return 4; return 7; never return at all.

Exercise 3.17: Devise a correct version of the `count-pairs` procedure of Exercise 3.16 that returns the number of distinct pairs in any structure. (Hint: Traverse the structure, maintaining an auxiliary data structure that is used to keep track of which pairs have already been counted.)

Exercise 3.18: Write a procedure that examines a list and determines whether it contains a cycle, that is, whether a program that tried to find the end of the list by taking successive `cdr`s would go into an infinite loop. Exercise 3.13 constructed such lists.

Exercise 3.19: Redo Exercise 3.18 using an algorithm that takes only a constant amount of space. (This requires a very clever idea.)

Mutation is just assignment

When we introduced compound data, we observed in Section 2.1.3 that pairs can be represented purely in terms of procedures:

```
(define (cons x y)
  (define (dispatch m)
    (cond ((eq? m 'car) x)
          ((eq? m 'cdr) y)
          (else (error "Undefined operation: CONS" m))))
  dispatch)
```

```
(define (car z) (z 'car))
(define (cdr z) (z 'cdr))
```

The same observation is true for mutable data. We can implement mutable data objects as procedures using assignment and local state. For instance, we can extend the above pair implementation to handle `set-car!` and `set-cdr!` in a manner analogous to the way we implemented bank accounts using `make-account` in Section 3.1.1:

```
(define (cons x y)
  (define (set-x! v) (set! x v))
  (define (set-y! v) (set! y v))
  (define (dispatch m)
    (cond ((eq? m 'car) x)
          ((eq? m 'cdr) y)
          ((eq? m 'set-car!) set-x!)
          ((eq? m 'set-cdr!) set-y!)
          (else
           (error "Undefined operation: CONS" m))))
  dispatch)
(define (car z) (z 'car))
(define (cdr z) (z 'cdr))
(define (set-car! z new-value)
  ((z 'set-car!) new-value) z)
(define (set-cdr! z new-value)
  ((z 'set-cdr!) new-value) z)
```

Assignment is all that is needed, theoretically, to account for the behavior of mutable data. As soon as we admit `set!` to our language, we raise all the issues, not only of assignment, but of mutable data in general.[21]

[21] On the other hand, from the viewpoint of implementation, assignment requires us to modify the environment, which is itself a mutable data structure. Thus, assignment and mutation are equipotent: Each can be implemented in terms of the other.

Exercise 3.20: Draw environment diagrams to illustrate the evaluation of the sequence of expressions

```
(define x (cons 1 2))
(define z (cons x x))
(set-car! (cdr z) 17)
(car x)
17
```

using the procedural implementation of pairs given above. (Compare Exercise 3.11.)

3.3.2 Representing Queues

The mutators `set-car!` and `set-cdr!` enable us to use pairs to construct data structures that cannot be built with `cons`, `car`, and `cdr` alone. This section shows how to use pairs to represent a data structure called a queue. Section 3.3.3 will show how to represent data structures called tables.

A *queue* is a sequence in which items are inserted at one end (called the *rear* of the queue) and deleted from the other end (the *front*). Figure 3.18 shows an initially empty queue in which the items `a` and `b` are inserted. Then `a` is removed, `c` and `d` are inserted, and `b` is removed. Because items are always removed in the order in which they are inserted, a queue is sometimes called a *FIFO* (first in, first out) buffer.

In terms of data abstraction, we can regard a queue as defined by the following set of operations:

- a constructor: `(make-queue)` returns an empty queue (a queue containing no items).
- two selectors:

  `(empty-queue?` ⟨*queue*⟩`)` tests if the queue is empty.

Operation	Resulting Queue
(define q (make-queue))	
(insert-queue! q 'a)	a
(insert-queue! q 'b)	a b
(delete-queue! q)	b
(insert-queue! q 'c)	b c
(insert-queue! q 'd)	b c d
(delete-queue! q)	c d

Figure 3.18: Queue operations.

`(front-queue` ⟨*queue*⟩`)` returns the object at the front of the queue, signaling an error if the queue is empty; it does not modify the queue.

- two mutators:

  `(insert-queue!` ⟨*queue*⟩ ⟨*item*⟩`)` inserts the item at the rear of the queue and returns the modified queue as its value.

  `(delete-queue!` ⟨*queue*⟩`)` removes the item at the front of the queue and returns the modified queue as its value, signaling an error if the queue is empty before the deletion.

Because a queue is a sequence of items, we could certainly represent it as an ordinary list; the front of the queue would be the `car` of the list, inserting an item in the queue would amount to appending a new element at the end of the list, and deleting an item from the queue would just be taking the `cdr` of the list. However, this representation is inefficient, because in order to insert an item we must scan the list until we reach the end. Since the only method we have for scanning a list is by successive `cdr` operations, this scanning requires $\Theta(n)$ steps for a list of n items. A simple modification to the list




Figure 3.19: Implementation of a queue as a list with front and rear pointers.

representation overcomes this disadvantage by allowing the queue operations to be implemented so that they require $\Theta(1)$ steps; that is, so that the number of steps needed is independent of the length of the queue.

The difficulty with the list representation arises from the need to scan to find the end of the list. The reason we need to scan is that, although the standard way of representing a list as a chain of pairs readily provides us with a pointer to the beginning of the list, it gives us no easily accessible pointer to the end. The modification that avoids the drawback is to represent the queue as a list, together with an additional pointer that indicates the final pair in the list. That way, when we go to insert an item, we can consult the rear pointer and so avoid scanning the list.

A queue is represented, then, as a pair of pointers, `front-ptr` and `rear-ptr`, which indicate, respectively, the first and last pairs in an ordinary list. Since we would like the queue to be an identifiable object, we can use `cons` to combine the two pointers. Thus, the queue itself will be the `cons` of the two pointers. Figure 3.19 illustrates this representation.

To define the queue operations we use the following procedures, which enable us to select and to modify the front and rear pointers of a queue:

```
(define (front-ptr queue) (car queue))
(define (rear-ptr  queue) (cdr queue))
(define (set-front-ptr! queue item)
  (set-car! queue item))
(define (set-rear-ptr!  queue item)
  (set-cdr! queue item))
```

Now we can implement the actual queue operations. We will consider a queue to be empty if its front pointer is the empty list:

```
(define (empty-queue? queue)
  (null? (front-ptr queue)))
```

The `make-queue` constructor returns, as an initially empty queue, a pair whose `car` and `cdr` are both the empty list:

```
(define (make-queue) (cons '() '()))
```

To select the item at the front of the queue, we return the `car` of the pair indicated by the front pointer:

```
(define (front-queue queue)
  (if (empty-queue? queue)
      (error "FRONT called with an empty queue" queue)
      (car (front-ptr queue))))
```

To insert an item in a queue, we follow the method whose result is indicated in Figure 3.20. We first create a new pair whose `car` is the item to be inserted and whose `cdr` is the empty list. If the queue was initially empty, we set the front and rear pointers of the queue to this new pair. Otherwise, we modify the final pair in the queue to point to the new pair, and also set the rear pointer to the new pair.

```
(define (insert-queue! queue item)
  (let ((new-pair (cons item '())))
    (cond ((empty-queue? queue)
```




Figure 3.20: Result of using `(insert-queue! q 'd)` on the queue of Figure 3.19.

```
        (set-front-ptr! queue new-pair)
        (set-rear-ptr! queue new-pair)
        queue)
       (else
        (set-cdr! (rear-ptr queue) new-pair)
        (set-rear-ptr! queue new-pair)
        queue))))
```

To delete the item at the front of the queue, we merely modify the front pointer so that it now points at the second item in the queue, which can be found by following the `cdr` pointer of the first item (see Figure 3.21):[22]

```
(define (delete-queue! queue)
  (cond ((empty-queue? queue)
         (error "DELETE! called with an empty queue" queue))
        (else (set-front-ptr! queue (cdr (front-ptr queue)))
              queue)))
```

[22] If the first item is the final item in the queue, the front pointer will be the empty list after the deletion, which will mark the queue as empty; we needn't worry about updating the rear pointer, which will still point to the deleted item, because `empty-queue?` looks only at the front pointer.




Figure 3.21: Result of using `(delete-queue! q)` on the queue of Figure 3.20.

Exercise 3.21: Ben Bitdiddle decides to test the queue implementation described above. He types in the procedures to the Lisp interpreter and proceeds to try them out:

```
(define q1 (make-queue))
(insert-queue! q1 'a)
((a) a)
(insert-queue! q1 'b)
((a b) b)
(delete-queue! q1)
((b) b)
(delete-queue! q1)
(() b)
```

"It's all wrong!" he complains. "The interpreter's response shows that the last item is inserted into the queue twice. And when I delete both items, the second `b` is still there, so the queue isn't empty, even though it's supposed to be." Eva Lu Ator suggests that Ben has misunderstood what is happening. "It's not that the items are going into the queue twice," she explains. "It's

just that the standard Lisp printer doesn't know how to make sense of the queue representation. If you want to see the queue printed correctly, you'll have to define your own print procedure for queues." Explain what Eva Lu is talking about. In particular, show why Ben's examples produce the printed results that they do. Define a procedure `print-queue` that takes a queue as input and prints the sequence of items in the queue.

Exercise 3.22: Instead of representing a queue as a pair of pointers, we can build a queue as a procedure with local state. The local state will consist of pointers to the beginning and the end of an ordinary list. Thus, the `make-queue` procedure will have the form

```
(define (make-queue)
  (let ((front-ptr ... )
        (rear-ptr ... ))
    ⟨definitions of internal procedures⟩
    (define (dispatch m) ...)
    dispatch))
```

Complete the definition of `make-queue` and provide implementations of the queue operations using this representation.

Exercise 3.23: A *deque* ("double-ended queue") is a sequence in which items can be inserted and deleted at either the front or the rear. Operations on deques are the constructor `make-deque`, the predicate `empty-deque?`, selectors `front-deque` and `rear-deque`, mutators `front-insert-deque!`, `rear-insert-deque!`, `front-delete-deque!`, and `rear-delete-deque!`. Show how to represent de-




Figure 3.22: A table represented as a headed list.

ques using pairs, and give implementations of the operations.[23] All operations should be accomplished in $\Theta(1)$ steps.

3.3.3 Representing Tables

When we studied various ways of representing sets in Chapter 2, we mentioned in Section 2.3.3 the task of maintaining a table of records indexed by identifying keys. In the implementation of data-directed programming in Section 2.4.3, we made extensive use of two-dimensional tables, in which information is stored and retrieved using two keys. Here we see how to build tables as mutable list structures.

We first consider a one-dimensional table, in which each value is stored under a single key. We implement the table as a list of records, each of which is implemented as a pair consisting of a key and the associated value. The records are glued together to form a list by pairs whose `cars` point to successive records. These gluing pairs are called the *backbone* of the table.

[23] Be careful not to make the interpreter try to print a structure that contains cycles. (See Exercise 3.13.)

In order to have a place that we can change when we add a new record to the table, we build the table as a *headed list*. A headed list has a special backbone pair at the beginning, which holds a dummy "record"—in this case the arbitrarily chosen symbol `*table*`. Figure 3.22 shows the box-and-pointer diagram for the table

```
a:  1
b:  2
c:  3
```

To extract information from a table we use the `lookup` procedure, which takes a key as argument and returns the associated value (or false if there is no value stored under that key). `lookup` is defined in terms of the `assoc` operation, which expects a key and a list of records as arguments. Note that `assoc` never sees the dummy record. `assoc` returns the record that has the given key as its `car`.[24] `lookup` then checks to see that the resulting record returned by `assoc` is not false, and returns the value (the `cdr`) of the record.

```
(define (lookup key table)
  (let ((record (assoc key (cdr table))))
    (if record
        (cdr record)
        false)))
(define (assoc key records)
  (cond ((null? records) false)
        ((equal? key (caar records)) (car records))
        (else (assoc key (cdr records)))))
```

To insert a value in a table under a specified key, we first use `assoc` to see if there is already a record in the table with this key. If not, we form a new

[24] Because `assoc` uses `equal?`, it can recognize keys that are symbols, numbers, or list structure.

record by `cons`ing the key with the value, and insert this at the head of the table's list of records, after the dummy record. If there already is a record with this key, we set the `cdr` of this record to the designated new value. The header of the table provides us with a fixed location to modify in order to insert the new record.[25]

```
(define (insert! key value table)
  (let ((record (assoc key (cdr table))))
    (if record
        (set-cdr! record value)
        (set-cdr! table
                  (cons (cons key value)
                        (cdr table)))))
  'ok)
```

To construct a new table, we simply create a list containing the symbol `*table*`:

```
(define (make-table)
  (list '*table*))
```

Two-dimensional tables

In a two-dimensional table, each value is indexed by two keys. We can construct such a table as a one-dimensional table in which each key identifies a subtable. Figure 3.23 shows the box-and-pointer diagram for the table

```
math:     +:  43        letters:    a:  97
          -:  45                    b:  98
          *:  42
```

[25] Thus, the first backbone pair is the object that represents the table "itself"; that is, a pointer to the table is a pointer to this pair. This same backbone pair always starts the table. If we did not arrange things in this way, `insert!` would have to return a new value for the start of the table when it added a new record.

which has two subtables. (The subtables don't need a special header symbol, since the key that identifies the subtable serves this purpose.)

When we look up an item, we use the first key to identify the correct subtable. Then we use the second key to identify the record within the subtable.

```
(define (lookup key-1 key-2 table)
  (let ((subtable
         (assoc key-1 (cdr table))))
    (if subtable
        (let ((record
               (assoc key-2 (cdr subtable))))
          (if record
              (cdr record)
              false))
        false)))
```

To insert a new item under a pair of keys, we use `assoc` to see if there is a subtable stored under the first key. If not, we build a new subtable containing the single record (`key-2`, `value`) and insert it into the table under the first key. If a subtable already exists for the first key, we insert the new record into this subtable, using the insertion method for one-dimensional tables described above:

```
(define (insert! key-1 key-2 value table)
  (let ((subtable (assoc key-1 (cdr table))))
    (if subtable
        (let ((record (assoc key-2 (cdr subtable))))
          (if record
              (set-cdr! record value)
              (set-cdr! subtable
                        (cons (cons key-2 value)
                              (cdr subtable)))))
        (set-cdr! table
                  (cons (list key-1
```




Figure 3.23: A two-dimensional table.

```
                                (cons key-2 value))
                          (cdr table)))))
  'ok)
```

Creating local tables

The `lookup` and `insert!` operations defined above take the table as an argument. This enables us to use programs that access more than one table.

Another way to deal with multiple tables is to have separate `lookup` and `insert!` procedures for each table. We can do this by representing a table procedurally, as an object that maintains an internal table as part of its local state. When sent an appropriate message, this "table object" supplies the procedure with which to operate on the internal table. Here is a generator for two-dimensional tables represented in this fashion:

```
(define (make-table)
  (let ((local-table (list '*table*)))
    (define (lookup key-1 key-2)
      (let ((subtable
             (assoc key-1 (cdr local-table))))
        (if subtable
            (let ((record
                   (assoc key-2 (cdr subtable))))
              (if record (cdr record) false))
            false)))
    (define (insert! key-1 key-2 value)
      (let ((subtable
             (assoc key-1 (cdr local-table))))
        (if subtable
            (let ((record
                   (assoc key-2 (cdr subtable))))
              (if record
                  (set-cdr! record value)
                  (set-cdr! subtable
                            (cons (cons key-2 value)
                                  (cdr subtable)))))
            (set-cdr! local-table
                      (cons (list key-1 (cons key-2 value))
                            (cdr local-table)))))
      'ok)
    (define (dispatch m)
```

```
      (cond ((eq? m 'lookup-proc) lookup)
            ((eq? m 'insert-proc!) insert!)
            (else (error "Unknown operation: TABLE" m))))
    dispatch))
```

Using `make-table`, we could implement the `get` and `put` operations used in Section 2.4.3 for data-directed programming, as follows:

```
(define operation-table (make-table))
(define get (operation-table 'lookup-proc))
(define put (operation-table 'insert-proc!))
```

`get` takes as arguments two keys, and `put` takes as arguments two keys and a value. Both operations access the same local table, which is encapsulated within the object created by the call to `make-table`.

Exercise 3.24: In the table implementations above, the keys are tested for equality using `equal?` (called by `assoc`). This is not always the appropriate test. For instance, we might have a table with numeric keys in which we don't need an exact match to the number we're looking up, but only a number within some tolerance of it. Design a table constructor `make-table` that takes as an argument a `same-key?` procedure that will be used to test "equality" of keys. `make-table` should return a `dispatch` procedure that can be used to access appropriate `lookup` and `insert!` procedures for a local table.

Exercise 3.25: Generalizing one- and two-dimensional tables, show how to implement a table in which values are stored under an arbitrary number of keys and different values may be stored under different numbers of keys. The `lookup` and `insert!` procedures should take as input a list of keys used to access the table.

Exercise 3.26: To search a table as implemented above, one needs to scan through the list of records. This is basically the unordered list representation of Section 2.3.3. For large tables, it may be more efficient to structure the table in a different manner. Describe a table implementation where the (key, value) records are organized using a binary tree, assuming that keys can be ordered in some way (e.g., numerically or alphabetically). (Compare Exercise 2.66 of Chapter 2.)

Exercise 3.27: *Memoization* (also called *tabulation*) is a technique that enables a procedure to record, in a local table, values that have previously been computed. This technique can make a vast difference in the performance of a program. A memoized procedure maintains a table in which values of previous calls are stored using as keys the arguments that produced the values. When the memoized procedure is asked to compute a value, it first checks the table to see if the value is already there and, if so, just returns that value. Otherwise, it computes the new value in the ordinary way and stores this in the table. As an example of memoization, recall from Section 1.2.2 the exponential process for computing Fibonacci numbers:

```
(define (fib n)
  (cond ((= n 0) 0)
        ((= n 1) 1)
        (else (+ (fib (- n 1)) (fib (- n 2))))))
```

The memoized version of the same procedure is

```
(define memo-fib
  (memoize
   (lambda (n)
```

```
(cond ((= n 0) 0)
      ((= n 1) 1)
      (else (+ (memo-fib (- n 1))
               (memo-fib (- n 2))))))))
```

where the memoizer is defined as

```
(define (memoize f)
  (let ((table (make-table)))
    (lambda (x)
      (let ((previously-computed-result
             (lookup x table)))
        (or previously-computed-result
            (let ((result (f x)))
              (insert! x result table)
              result))))))
```

Draw an environment diagram to analyze the computation of `(memo-fib 3)`. Explain why `memo-fib` computes the nth Fibonacci number in a number of steps proportional to n. Would the scheme still work if we had simply defined `memo-fib` to be `(memoize fib)`?

3.3.4 A Simulator for Digital Circuits

Designing complex digital systems, such as computers, is an important engineering activity. Digital systems are constructed by interconnecting simple elements. Although the behavior of these individual elements is simple, networks of them can have very complex behavior. Computer simulation of proposed circuit designs is an important tool used by digital systems engineers. In this section we design a system for performing digital logic simulations. This system typifies a kind of program called an *event-driven simulation*, in which




Figure 3.24: Primitive functions in the digital logic simulator.

actions ("events") trigger further events that happen at a later time, which in turn trigger more events, and so on.

Our computational model of a circuit will be composed of objects that correspond to the elementary components from which the circuit is constructed. There are *wires*, which carry *digital signals*. A digital signal may at any moment have only one of two possible values, 0 and 1. There are also various types of digital *function boxes*, which connect wires carrying input signals to other output wires. Such boxes produce output signals computed from their input signals. The output signal is delayed by a time that depends on the type of the function box. For example, an *inverter* is a primitive function box that inverts its input. If the input signal to an inverter changes to 0, then one inverter-delay later the inverter will change its output signal to 1. If the input signal to an inverter changes to 1, then one inverter-delay later the inverter will change its output signal to 0. We draw an inverter symbolically as in Figure 3.24. An *and-gate*, also shown in Figure 3.24, is a primitive function box with two inputs and one output. It drives its output signal to a value that is the *logical and* of the inputs. That is, if both of its input signals become 1, then one and-gate-delay time later the and-gate will force its output signal to be 1; otherwise the output will be 0. An *or-gate* is a similar two-input primitive function box that drives its output signal to a value that is the *logical or* of the inputs. That is, the output will become 1 if at least one of the input signals is 1; otherwise the output will become 0.

We can connect primitive functions together to construct more complex




Figure 3.25: A half-adder circuit.

functions. To accomplish this we wire the outputs of some function boxes to the inputs of other function boxes. For example, the *half-adder* circuit shown in Figure 3.25 consists of an or-gate, two and-gates, and an inverter. It takes two input signals, A and B, and has two output signals, S and C. S will become 1 whenever precisely one of A and B is 1, and C will become 1 whenever A and B are both 1. We can see from the figure that, because of the delays involved, the outputs may be generated at different times. Many of the difficulties in the design of digital circuits arise from this fact.

We will now build a program for modeling the digital logic circuits we wish to study. The program will construct computational objects modeling the wires, which will "hold" the signals. Function boxes will be modeled by procedures that enforce the correct relationships among the signals.

One basic element of our simulation will be a procedure `make-wire`, which constructs wires. For example, we can construct six wires as follows:

```
(define a (make-wire))
(define b (make-wire))
(define c (make-wire))
(define d (make-wire))
(define e (make-wire))
(define s (make-wire))
```

We attach a function box to a set of wires by calling a procedure that constructs that kind of box. The arguments to the constructor procedure are the wires to be attached to the box. For example, given that we can construct and-gates, or-gates, and inverters, we can wire together the half-adder shown in Figure 3.25:

```
(or-gate a b d)
ok
(and-gate a b c)
ok
(inverter c e)
ok
(and-gate d e s)
ok
```

Better yet, we can explicitly name this operation by defining a procedure `half-adder` that constructs this circuit, given the four external wires to be attached to the half-adder:

```
(define (half-adder a b s c)
  (let ((d (make-wire)) (e (make-wire)))
    (or-gate a b d)
    (and-gate a b c)
    (inverter c e)
    (and-gate d e s)
    'ok))
```

The advantage of making this definition is that we can use `half-adder` itself as a building block in creating more complex circuits. Figure 3.26, for example, shows a *full-adder* composed of two half-adders and an or-gate.[26]

[26] A full-adder is a basic circuit element used in adding two binary numbers. Here A and B are the bits at corresponding positions in the two numbers to be added, and C_{in} is the carry bit from the addition one place to the right. The circuit generates SUM, which is the sum bit in the corresponding position, and C_{out}, which is the carry bit to be propagated to the left.




Figure 3.26: A full-adder circuit.

We can construct a full-adder as follows:

```
(define (full-adder a b c-in sum c-out)
  (let ((s (make-wire)) (c1 (make-wire)) (c2 (make-wire)))
    (half-adder b c-in s c1)
    (half-adder a s sum c2)
    (or-gate c1 c2 c-out)
    'ok))
```

Having defined `full-adder` as a procedure, we can now use it as a building block for creating still more complex circuits. (For example, see Exercise 3.30.)

In essence, our simulator provides us with the tools to construct a language of circuits. If we adopt the general perspective on languages with which we approached the study of Lisp in Section 1.1, we can say that the primitive function boxes form the primitive elements of the language, that wiring boxes together provides a means of combination, and that specifying wiring patterns as procedures serves as a means of abstraction.

Primitive function boxes

The primitive function boxes implement the "forces" by which a change in the signal on one wire influences the signals on other wires. To build function

boxes, we use the following operations on wires:

- `(get-signal` ⟨*wire*⟩`)`

  returns the current value of the signal on the wire.

- `(set-signal!` ⟨*wire*⟩ ⟨*new value*⟩`)`

  changes the value of the signal on the wire to the new value.

- `(add-action!` ⟨*wire*⟩ ⟨*procedure of no arguments*⟩`)`

  asserts that the designated procedure should be run whenever the signal on the wire changes value. Such procedures are the vehicles by which changes in the signal value on the wire are communicated to other wires.

In addition, we will make use of a procedure `after-delay` that takes a time delay and a procedure to be run and executes the given procedure after the given delay.

Using these procedures, we can define the primitive digital logic functions. To connect an input to an output through an inverter, we use `add-action!` to associate with the input wire a procedure that will be run whenever the signal on the input wire changes value. The procedure computes the `logical-not` of the input signal, and then, after one `inverter-delay`, sets the output signal to be this new value:

```
(define (inverter input output)
  (define (invert-input)
    (let ((new-value (logical-not (get-signal input))))
      (after-delay inverter-delay
                   (lambda () (set-signal! output new-value)
  (add-action! input invert-input) 'ok)
(define (logical-not s)
```

```
  (cond ((= s 0) 1)
        ((= s 1) 0)
        (else (error "Invalid signal" s))))
```

An and-gate is a little more complex. The action procedure must be run if either of the inputs to the gate changes. It computes the `logical-and` (using a procedure analogous to `logical-not`) of the values of the signals on the input wires and sets up a change to the new value to occur on the output wire after one `and-gate-delay`.

```
(define (and-gate a1 a2 output)
  (define (and-action-procedure)
    (let ((new-value
           (logical-and (get-signal a1) (get-signal a2))))
      (after-delay
       and-gate-delay
       (lambda () (set-signal! output new-value)))))
  (add-action! a1 and-action-procedure)
  (add-action! a2 and-action-procedure)
  'ok)
```

Exercise 3.28: Define an or-gate as a primitive function box. Your `or-gate` constructor should be similar to `and-gate`.

Exercise 3.29: Another way to construct an or-gate is as a compound digital logic device, built from and-gates and inverters. Define a procedure `or-gate` that accomplishes this. What is the delay time of the or-gate in terms of `and-gate-delay` and `inverter-delay`?

Exercise 3.30: Figure 3.27 shows a *ripple-carry adder* formed by stringing together n full-adders. This is the simplest form




Figure 3.27: A ripple-carry adder for n-bit numbers.

of parallel adder for adding two n-bit binary numbers. The inputs A_1, A_2, A_3, ..., A_n and B_1, B_2, B_3, ..., B_n are the two binary numbers to be added (each A_k and B_k is a 0 or a 1). The circuit generates S_1, S_2, S_3, ..., S_n, the n bits of the sum, and C, the carry from the addition. Write a procedure `ripple-carry-adder` that generates this circuit. The procedure should take as arguments three lists of n wires each —the A_k, the B_k, and the S_k—and also another wire C. The major drawback of the ripple-carry adder is the need to wait for the carry signals to propagate. What is the delay needed to obtain the complete output from an n-bit ripple-carry adder, expressed in terms of the delays for and-gates, or-gates, and inverters?

Representing wires

A wire in our simulation will be a computational object with two local state variables: a `signal-value` (initially taken to be 0) and a collection of `action-procedures` to be run when the signal changes value. We implement the wire, using message-passing style, as a collection of local procedures together with a `dispatch` procedure that selects the appropriate

local operation, just as we did with the simple bank-account object in Section 3.1.1:

```
(define (make-wire)
  (let ((signal-value 0) (action-procedures '()))
    (define (set-my-signal! new-value)
      (if (not (= signal-value new-value))
          (begin (set! signal-value new-value)
                 (call-each action-procedures))
          'done))
    (define (accept-action-procedure! proc)
      (set! action-procedures
            (cons proc action-procedures))
      (proc))
    (define (dispatch m)
      (cond ((eq? m 'get-signal) signal-value)
            ((eq? m 'set-signal!) set-my-signal!)
            ((eq? m 'add-action!) accept-action-procedure!)
            (else (error "Unknown operation: WIRE" m))))
    dispatch))
```

The local procedure `set-my-signal!` tests whether the new signal value changes the signal on the wire. If so, it runs each of the action procedures, using the following procedure `call-each`, which calls each of the items in a list of no-argument procedures:

```
(define (call-each procedures)
  (if (null? procedures)
      'done
      (begin ((car procedures))
             (call-each (cdr procedures)))))
```

The local procedure `accept-action-procedure!` adds the given procedure to the list of procedures to be run, and then runs the new procedure once. (See Exercise 3.31.)

With the local `dispatch` procedure set up as specified, we can provide the following procedures to access the local operations on wires:[27]

```
(define (get-signal wire) (wire 'get-signal))
(define (set-signal! wire new-value)
  ((wire 'set-signal!) new-value))
(define (add-action! wire action-procedure)
  ((wire 'add-action!) action-procedure))
```

Wires, which have time-varying signals and may be incrementally attached to devices, are typical of mutable objects. We have modeled them as procedures with local state variables that are modified by assignment. When a new wire is created, a new set of state variables is allocated (by the `let` expression in `make-wire`) and a new `dispatch` procedure is constructed and returned, capturing the environment with the new state variables.

The wires are shared among the various devices that have been connected to them. Thus, a change made by an interaction with one device will affect all the other devices attached to the wire. The wire communicates the change to its neighbors by calling the action procedures provided to it when the connections were established.

[27] These procedures are simply syntactic sugar that allow us to use ordinary procedural syntax to access the local procedures of objects. It is striking that we can interchange the role of "procedures" and "data" in such a simple way. For example, if we write `(wire 'get-signal)` we think of `wire` as a procedure that is called with the message `get-signal` as input. Alternatively, writing `(get-signal wire)` encourages us to think of `wire` as a data object that is the input to a procedure `get-signal`. The truth of the matter is that, in a language in which we can deal with procedures as objects, there is no fundamental difference between "procedures" and "data," and we can choose our syntactic sugar to allow us to program in whatever style we choose.

The agenda

The only thing needed to complete the simulator is `after-delay`. The idea here is that we maintain a data structure, called an *agenda*, that contains a schedule of things to do. The following operations are defined for agendas:

- `(make-agenda)` returns a new empty agenda.
- `(empty-agenda?` ⟨*agenda*⟩`)` is true if the specified agenda is empty.
- `(first-agenda-item` ⟨*agenda*⟩`)` returns the first item on the agenda.
- `(remove-first-agenda-item!` ⟨*agenda*⟩`)` modifies the agenda by removing the first item.
- `(add-to-agenda!` ⟨*time*⟩ ⟨*action*⟩ ⟨*agenda*⟩`)` modifies the agenda by adding the given action procedure to be run at the specified time.
- `(current-time` ⟨*agenda*⟩`)` returns the current simulation time.

The particular agenda that we use is denoted by `the-agenda`. The procedure `after-delay` adds new elements to `the-agenda`:

```
(define (after-delay delay action)
  (add-to-agenda! (+ delay (current-time the-agenda))
                  action
                  the-agenda))
```

The simulation is driven by the procedure `propagate`, which operates on `the-agenda`, executing each procedure on the agenda in sequence. In

general, as the simulation runs, new items will be added to the agenda, and `propagate` will continue the simulation as long as there are items on the agenda:

```
(define (propagate)
  (if (empty-agenda? the-agenda)
      'done
      (let ((first-item (first-agenda-item the-agenda)))
        (first-item)
        (remove-first-agenda-item! the-agenda)
        (propagate))))
```

A sample simulation

The following procedure, which places a "probe" on a wire, shows the simulator in action. The probe tells the wire that, whenever its signal changes value, it should print the new signal value, together with the current time and a name that identifies the wire:

```
(define (probe name wire)
  (add-action! wire
               (lambda ()
                 (newline)
                 (display name) (display " ")
                 (display (current-time the-agenda))
                 (display "  New-value = ")
                 (display (get-signal wire)))))
```

We begin by initializing the agenda and specifying delays for the primitive function boxes:

```
(define the-agenda (make-agenda))
(define inverter-delay 2)
(define and-gate-delay 3)
```

```
(define or-gate-delay 5)
```

Now we define four wires, placing probes on two of them:

```
(define input-1 (make-wire))
(define input-2 (make-wire))
(define sum (make-wire))
(define carry (make-wire))

(probe 'sum sum)
sum 0 New-value = 0

(probe 'carry carry)
carry 0 New-value = 0
```

Next we connect the wires in a half-adder circuit (as in Figure 3.25), set the signal on `input-1` to 1, and run the simulation:

```
(half-adder input-1 input-2 sum carry)
ok

(set-signal! input-1 1)
done

(propagate)
sum 8 New-value = 1
done
```

The `sum` signal changes to 1 at time 8. We are now eight time units from the beginning of the simulation. At this point, we can set the signal on `input-2` to 1 and allow the values to propagate:

```
(set-signal! input-2 1)
done
```

```
(propagate)
carry 11 New-value = 1
sum 16 New-value = 0
done
```

The `carry` changes to 1 at time 11 and the `sum` changes to 0 at time 16.

> **Exercise 3.31:** The internal procedure `accept-action-procedure!` defined in `make-wire` specifies that when a new action procedure is added to a wire, the procedure is immediately run. Explain why this initialization is necessary. In particular, trace through the half-adder example in the paragraphs above and say how the system's response would differ if we had defined `accept-action-procedure!` as
>
> ```
> (define (accept-action-procedure! proc)
>   (set! action-procedures
>         (cons proc action-procedures)))
> ```

Implementing the agenda

Finally, we give details of the agenda data structure, which holds the procedures that are scheduled for future execution.

The agenda is made up of *time segments*. Each time segment is a pair consisting of a number (the time) and a queue (see Exercise 3.32) that holds the procedures that are scheduled to be run during that time segment.

```
(define (make-time-segment time queue)
  (cons time queue))
(define (segment-time s) (car s))
(define (segment-queue s) (cdr s))
```

We will operate on the time-segment queues using the queue operations described in Section 3.3.2.

The agenda itself is a one-dimensional table of time segments. It differs from the tables described in Section 3.3.3 in that the segments will be sorted in order of increasing time. In addition, we store the *current time* (i.e., the time of the last action that was processed) at the head of the agenda. A newly constructed agenda has no time segments and has a current time of 0:[28]

```
(define (make-agenda) (list 0))
(define (current-time agenda) (car agenda))
(define (set-current-time! agenda time)
  (set-car! agenda time))
(define (segments agenda) (cdr agenda))
(define (set-segments! agenda segments)
  (set-cdr! agenda segments))
(define (first-segment agenda) (car (segments agenda)))
(define (rest-segments agenda) (cdr (segments agenda)))
```

An agenda is empty if it has no time segments:

```
(define (empty-agenda? agenda)
  (null? (segments agenda)))
```

To add an action to an agenda, we first check if the agenda is empty. If so, we create a time segment for the action and install this in the agenda. Otherwise, we scan the agenda, examining the time of each segment. If we find a segment for our appointed time, we add the action to the associated queue. If we reach a time later than the one to which we are appointed, we insert a new time segment into the agenda just before it. If we reach the end of the agenda, we must create a new time segment at the end.

```
(define (add-to-agenda! time action agenda)
  (define (belongs-before? segments)
```

[28] The agenda is a headed list, like the tables in Section 3.3.3, but since the list is headed by the time, we do not need an additional dummy header (such as the `*table*` symbol used with tables).

```
    (or (null? segments)
        (< time (segment-time (car segments)))))
  (define (make-new-time-segment time action)
    (let ((q (make-queue)))
      (insert-queue! q action)
      (make-time-segment time q)))
  (define (add-to-segments! segments)
    (if (= (segment-time (car segments)) time)
        (insert-queue! (segment-queue (car segments))
                       action)
        (let ((rest (cdr segments)))
          (if (belongs-before? rest)
              (set-cdr!
               segments
               (cons (make-new-time-segment time action)
                     (cdr segments)))
              (add-to-segments! rest)))))
  (let ((segments (segments agenda)))
    (if (belongs-before? segments)
        (set-segments!
         agenda
         (cons (make-new-time-segment time action)
               segments))
        (add-to-segments! segments))))
```

The procedure that removes the first item from the agenda deletes the item at the front of the queue in the first time segment. If this deletion makes the time segment empty, we remove it from the list of segments:[29]

```
(define (remove-first-agenda-item! agenda)
```

[29] Observe that the `if` expression in this procedure has no ⟨*alternative*⟩ expression. Such a "one-armed `if` statement" is used to decide whether to do something, rather than to select between two expressions. An `if` expression returns an unspecified value if the predicate is false and there is no ⟨*alternative*⟩.

```
  (let ((q (segment-queue (first-segment agenda))))
    (delete-queue! q)
    (if (empty-queue? q)
        (set-segments! agenda (rest-segments agenda)))))
```

The first agenda item is found at the head of the queue in the first time segment. Whenever we extract an item, we also update the current time:[30]

```
(define (first-agenda-item agenda)
  (if (empty-agenda? agenda)
      (error "Agenda is empty: FIRST-AGENDA-ITEM")
      (let ((first-seg (first-segment agenda)))
        (set-current-time! agenda
                           (segment-time first-seg))
        (front-queue (segment-queue first-seg)))))
```

Exercise 3.32: The procedures to be run during each time segment of the agenda are kept in a queue. Thus, the procedures for each segment are called in the order in which they were added to the agenda (first in, first out). Explain why this order must be used. In particular, trace the behavior of an and-gate whose inputs change from 0, 1 to 1, 0 in the same segment and say how the behavior would differ if we stored a segment's procedures in an ordinary list, adding and removing procedures only at the front (last in, first out).

3.3.5 Propagation of Constraints

Computer programs are traditionally organized as one-directional computations, which perform operations on prespecified arguments to produce de-

[30] In this way, the current time will always be the time of the action most recently processed. Storing this time at the head of the agenda ensures that it will still be available even if the associated time segment has been deleted.

sired outputs. On the other hand, we often model systems in terms of relations among quantities. For example, a mathematical model of a mechanical structure might include the information that the deflection d of a metal rod is related to the force F on the rod, the length L of the rod, the cross-sectional area A, and the elastic modulus E via the equation

$$dAE = FL.$$

Such an equation is not one-directional. Given any four of the quantities, we can use it to compute the fifth. Yet translating the equation into a traditional computer language would force us to choose one of the quantities to be computed in terms of the other four. Thus, a procedure for computing the area A could not be used to compute the deflection d, even though the computations of A and d arise from the same equation.[31]

In this section, we sketch the design of a language that enables us to work in terms of relations themselves. The primitive elements of the language are *primitive constraints*, which state that certain relations hold between quantities. For example, `(adder a b c)` specifies that the quantities a, b, and c must be related by the equation $a + b = c$, `(multiplier x y z)` expresses the constraint $xy = z$, and `(constant 3.14 x)` says that the value of x must be 3.14.

Our language provides a means of combining primitive constraints in order to express more complex relations. We combine constraints by constructing *constraint networks*, in which constraints are joined by *connectors*. A connector is an object that "holds" a value that may participate in one or more

[31] Constraint propagation first appeared in the incredibly forward-looking SKETCHPAD system of Ivan Sutherland (1963). A beautiful constraint-propagation system based on the Smalltalk language was developed by Alan Borning (1977) at Xerox Palo Alto Research Center. Sussman, Stallman, and Steele applied constraint propagation to electrical circuit analysis (Sussman and Stallman 1975; Sussman and Steele 1980). TK!Solver (Konopasek and Jayaraman 1984) is an extensive modeling environment based on constraints.




Figure 3.28: The relation $9C = 5(F - 32)$ expressed as a constraint network.

constraints. For example, we know that the relationship between Fahrenheit and Celsius temperatures is

$$9C = 5(F - 32).$$

Such a constraint can be thought of as a network consisting of primitive adder, multiplier, and constant constraints (Figure 3.28). In the figure, we see on the left a multiplier box with three terminals, labeled $m1$, $m2$, and p. These connect the multiplier to the rest of the network as follows: The $m1$ terminal is linked to a connector C, which will hold the Celsius temperature. The $m2$ terminal is linked to a connector w, which is also linked to a constant box that holds 9. The p terminal, which the multiplier box constrains to be the product of $m1$ and $m2$, is linked to the p terminal of another multiplier box, whose $m2$ is connected to a constant 5 and whose $m1$ is connected to one of the terms in a sum.

Computation by such a network proceeds as follows: When a connector is given a value (by the user or by a constraint box to which it is linked), it awakens all of its associated constraints (except for the constraint that just awakened it) to inform them that it has a value. Each awakened constraint box then polls its connectors to see if there is enough information to determine a

value for a connector. If so, the box sets that connector, which then awakens all of its associated constraints, and so on. For instance, in conversion between Celsius and Fahrenheit, w, x, and y are immediately set by the constant boxes to 9, 5, and 32, respectively. The connectors awaken the multipliers and the adder, which determine that there is not enough information to proceed. If the user (or some other part of the network) sets C to a value (say 25), the leftmost multiplier will be awakened, and it will set u to $25 \cdot 9 = 225$. Then u awakens the second multiplier, which sets v to 45, and v awakens the adder, which sets f to 77.

Using the constraint system

To use the constraint system to carry out the temperature computation outlined above, we first create two connectors, `C` and `F`, by calling the constructor `make-connector`, and link `C` and `F` in an appropriate network:

```
(define C (make-connector))
(define F (make-connector))
(celsius-fahrenheit-converter C F)
ok
```

The procedure that creates the network is defined as follows:

```
(define (celsius-fahrenheit-converter c f)
  (let ((u (make-connector))
        (v (make-connector))
        (w (make-connector))
        (x (make-connector))
        (y (make-connector)))
    (multiplier c w u)
    (multiplier v x u)
    (adder v y f)
    (constant 9 w)
```

```
    (constant 5 x)
    (constant 32 y)
    'ok))
```

This procedure creates the internal connectors `u`, `v`, `w`, `x`, and `y`, and links them as shown in Figure 3.28 using the primitive constraint constructors `adder`, `multiplier`, and `constant`. Just as with the digital-circuit simulator of Section 3.3.4, expressing these combinations of primitive elements in terms of procedures automatically provides our language with a means of abstraction for compound objects.

To watch the network in action, we can place probes on the connectors `C` and `F`, using a `probe` procedure similar to the one we used to monitor wires in Section 3.3.4. Placing a probe on a connector will cause a message to be printed whenever the connector is given a value:

```
(probe "Celsius temp" C)
(probe "Fahrenheit temp" F)
```

Next we set the value of `C` to 25. (The third argument to `set-value!` tells `C` that this directive comes from the `user`.)

```
(set-value! C 25 'user)
Probe: Celsius temp = 25
Probe: Fahrenheit temp = 77
done
```

The probe on `C` awakens and reports the value. `C` also propagates its value through the network as described above. This sets `F` to 77, which is reported by the probe on `F`.

Now we can try to set `F` to a new value, say 212:

```
(set-value! F 212 'user)
Error! Contradiction (77 212)
```

The connector complains that it has sensed a contradiction: Its value is 77, and someone is trying to set it to 212. If we really want to reuse the network with new values, we can tell C to forget its old value:

```
(forget-value! C 'user)
Probe: Celsius temp = ?
Probe: Fahrenheit temp = ?
done
```

C finds that the user, who set its value originally, is now retracting that value, so C agrees to lose its value, as shown by the probe, and informs the rest of the network of this fact. This information eventually propagates to F, which now finds that it has no reason for continuing to believe that its own value is 77. Thus, F also gives up its value, as shown by the probe.

Now that F has no value, we are free to set it to 212:

```
(set-value! F 212 'user)
Probe: Fahrenheit temp = 212
Probe: Celsius temp = 100
done
```

This new value, when propagated through the network, forces C to have a value of 100, and this is registered by the probe on C. Notice that the very same network is being used to compute C given F and to compute F given C. This nondirectionality of computation is the distinguishing feature of constraint-based systems.

Implementing the constraint system

The constraint system is implemented via procedural objects with local state, in a manner very similar to the digital-circuit simulator of Section 3.3.4. Although the primitive objects of the constraint system are somewhat more complex, the overall system is simpler, since there is no concern about agendas and logic delays.

The basic operations on connectors are the following:

- `(has-value?` ⟨*connector*⟩`)` tells whether the connector has a value.
- `(get-value` ⟨*connector*⟩`)` returns the connector's current value.
- `(set-value!` ⟨*connector*⟩ ⟨*new-value*⟩ ⟨*informant*⟩`)` indicates that the informant is requesting the connector to set its value to the new value.
- `(forget-value!` ⟨*connector*⟩ ⟨*retractor*⟩`)` tells the connector that the retractor is requesting it to forget its value.
- `(connect` ⟨*connector*⟩ ⟨*new-constraint*⟩`)` tells the connector to participate in the new constraint.

The connectors communicate with the constraints by means of the procedures `inform-about-value`, which tells the given constraint that the connector has a value, and `inform-about-no-value`, which tells the constraint that the connector has lost its value.

`adder` constructs an adder constraint among summand connectors `a1` and `a2` and a `sum` connector. An adder is implemented as a procedure with local state (the procedure `me` below):

```
(define (adder a1 a2 sum)
  (define (process-new-value)
    (cond ((and (has-value? a1) (has-value? a2))
           (set-value! sum
                       (+ (get-value a1) (get-value a2))
                       me))
          ((and (has-value? a1) (has-value? sum))
           (set-value! a2
```

```
                    (- (get-value sum) (get-value a1))
                    me))
          ((and (has-value? a2) (has-value? sum))
           (set-value! a1
                    (- (get-value sum) (get-value a2))
                    me))))
  (define (process-forget-value)
    (forget-value! sum me)
    (forget-value! a1 me)
    (forget-value! a2 me)
    (process-new-value))
  (define (me request)
    (cond ((eq? request 'I-have-a-value)  (process-new-value
          ((eq? request 'I-lost-my-value) (process-forget-va
          (else (error "Unknown request: ADDER" request))))
  (connect a1 me)
  (connect a2 me)
  (connect sum me)
  me)
```

`adder` connects the new adder to the designated connectors and returns it as its value. The procedure `me`, which represents the adder, acts as a dispatch to the local procedures. The following "syntax interfaces" (see Footnote 27 in Section 3.3.4) are used in conjunction with the dispatch:

```
(define (inform-about-value constraint)
  (constraint 'I-have-a-value))
(define (inform-about-no-value constraint)
  (constraint 'I-lost-my-value))
```

The adder's local procedure `process-new-value` is called when the adder is informed that one of its connectors has a value. The adder first checks to see if both `a1` and `a2` have values. If so, it tells `sum` to set its value to the sum of the two addends. The `informant` argument to `set-value!` is

me, which is the adder object itself. If a1 and a2 do not both have values, then the adder checks to see if perhaps a1 and sum have values. If so, it sets a2 to the difference of these two. Finally, if a2 and sum have values, this gives the adder enough information to set a1. If the adder is told that one of its connectors has lost a value, it requests that all of its connectors now lose their values. (Only those values that were set by this adder are actually lost.) Then it runs process-new-value. The reason for this last step is that one or more connectors may still have a value (that is, a connector may have had a value that was not originally set by the adder), and these values may need to be propagated back through the adder.

A multiplier is very similar to an adder. It will set its product to 0 if either of the factors is 0, even if the other factor is not known.

```
(define (multiplier m1 m2 product)
  (define (process-new-value)
    (cond ((or (and (has-value? m1) (= (get-value m1) 0))
               (and (has-value? m2) (= (get-value m2) 0)))
           (set-value! product 0 me))
          ((and (has-value? m1) (has-value? m2))
           (set-value! product
                       (* (get-value m1) (get-value m2))
                       me))
          ((and (has-value? product) (has-value? m1))
           (set-value! m2
                       (/ (get-value product)
                          (get-value m1))
                       me))
          ((and (has-value? product) (has-value? m2))
           (set-value! m1
                       (/ (get-value product)
                          (get-value m2))
                       me))))
```

```
  (define (process-forget-value)
    (forget-value! product me)
    (forget-value! m1 me)
    (forget-value! m2 me)
    (process-new-value))
  (define (me request)
    (cond ((eq? request 'I-have-a-value)  (process-new-value
          ((eq? request 'I-lost-my-value) (process-forget-va
          (else (error "Unknown request: MULTIPLIER"
                       request))))
  (connect m1 me)
  (connect m2 me)
  (connect product me)
  me)
```

A `constant` constructor simply sets the value of the designated connector. Any `I-have-a-value` or `I-lost-my-value` message sent to the constant box will produce an error.

```
(define (constant value connector)
  (define (me request)
    (error "Unknown request: CONSTANT" request))
  (connect connector me)
  (set-value! connector value me)
  me)
```

Finally, a probe prints a message about the setting or unsetting of the designated connector:

```
(define (probe name connector)
  (define (print-probe value)
    (newline) (display "Probe: ") (display name)
    (display " = ") (display value))
  (define (process-new-value)
    (print-probe (get-value connector)))
```

```
  (define (process-forget-value) (print-probe "?"))
  (define (me request)
    (cond ((eq? request 'I-have-a-value)  (process-new-value
          ((eq? request 'I-lost-my-value) (process-forget-va
          (else (error "Unknown request: PROBE" request))))
  (connect connector me)
  me)
```

Representing connectors

A connector is represented as a procedural object with local state variables `value`, the current value of the connector; `informant`, the object that set the connector's value; and `constraints`, a list of the constraints in which the connector participates.

```
(define (make-connector)
  (let ((value false) (informant false) (constraints '()))
    (define (set-my-value newval setter)
      (cond ((not (has-value? me))
             (set! value newval)
             (set! informant setter)
             (for-each-except setter
                              inform-about-value
                              constraints))
            ((not (= value newval))
             (error "Contradiction" (list value newval)))
            (else 'ignored)))
    (define (forget-my-value retractor)
      (if (eq? retractor informant)
          (begin (set! informant false)
                 (for-each-except retractor
                                  inform-about-no-value
                                  constraints))
```

```
        'ignored))
    (define (connect new-constraint)
      (if (not (memq new-constraint constraints))
          (set! constraints
                (cons new-constraint constraints)))
      (if (has-value? me)
          (inform-about-value new-constraint))
      'done)
    (define (me request)
      (cond ((eq? request 'has-value?)
             (if informant true false))
            ((eq? request 'value) value)
            ((eq? request 'set-value!) set-my-value)
            ((eq? request 'forget) forget-my-value)
            ((eq? request 'connect) connect)
            (else (error "Unknown operation: CONNECTOR"
                         request))))
    me))
```

The connector's local procedure `set-my-value` is called when there is a request to set the connector's value. If the connector does not currently have a value, it will set its value and remember as `informant` the constraint that requested the value to be set.[32] Then the connector will notify all of its participating constraints except the constraint that requested the value to be set. This is accomplished using the following iterator, which applies a designated procedure to all items in a list except a given one:

```
(define (for-each-except exception procedure list)
  (define (loop items)
    (cond ((null? items) 'done)
          ((eq? (car items) exception) (loop (cdr items)))
```

[32]The `setter` might not be a constraint. In our temperature example, we used `user` as the `setter`.

```
          (else (procedure (car items))
                (loop (cdr items)))))
  (loop list))
```

If a connector is asked to forget its value, it runs the local procedure `forget-my-value`, which first checks to make sure that the request is coming from the same object that set the value originally. If so, the connector informs its associated constraints about the loss of the value.

The local procedure `connect` adds the designated new constraint to the list of constraints if it is not already in that list. Then, if the connector has a value, it informs the new constraint of this fact.

The connector's procedure `me` serves as a dispatch to the other internal procedures and also represents the connector as an object. The following procedures provide a syntax interface for the dispatch:

```
(define (has-value? connector)
  (connector 'has-value?))
(define (get-value connector)
  (connector 'value))
(define (set-value! connector new-value informant)
  ((connector 'set-value!) new-value informant))
(define (forget-value! connector retractor)
  ((connector 'forget) retractor))
(define (connect connector new-constraint)
  ((connector 'connect) new-constraint))
```

Exercise 3.33: Using primitive multiplier, adder, and constant constraints, define a procedure `averager` that takes three connectors `a`, `b`, and `c` as inputs and establishes the constraint that the value of `c` is the average of the values of `a` and `b`.

Exercise 3.34: Louis Reasoner wants to build a squarer, a constraint device with two terminals such that the value of connector

b on the second terminal will always be the square of the value a on the first terminal. He proposes the following simple device made from a multiplier:

```
(define (squarer a b)
  (multiplier a a b))
```

There is a serious flaw in this idea. Explain.

Exercise 3.35: Ben Bitdiddle tells Louis that one way to avoid the trouble in Exercise 3.34 is to define a squarer as a new primitive constraint. Fill in the missing portions in Ben's outline for a procedure to implement such a constraint:

```
(define (squarer a b)
  (define (process-new-value)
    (if (has-value? b)
        (if (< (get-value b) 0)
            (error "square less than 0: SQUARER"
                   (get-value b))
            ⟨alternative1⟩)
        ⟨alternative2⟩))
  (define (process-forget-value) ⟨body1⟩)
  (define (me request) ⟨body2⟩)
  ⟨rest of definition⟩
  me)
```

Exercise 3.36: Suppose we evaluate the following sequence of expressions in the global environment:

```
(define a (make-connector))
(define b (make-connector))
(set-value! a 10 'user)
```

At some time during evaluation of the `set-value!`, the following expression from the connector's local procedure is evaluated:

```
(for-each-except
  setter inform-about-value constraints)
```

Draw an environment diagram showing the environment in which the above expression is evaluated.

Exercise 3.37: The `celsius-fahrenheit-converter` procedure is cumbersome when compared with a more expression-oriented style of definition, such as

```
(define (celsius-fahrenheit-converter x)
  (c+ (c* (c/ (cv 9) (cv 5))
          x)
      (cv 32)))
(define C (make-connector))
(define F (celsius-fahrenheit-converter C))
```

Here `c+`, `c*`, etc. are the "constraint" versions of the arithmetic operations. For example, `c+` takes two connectors as arguments and returns a connector that is related to these by an adder constraint:

```
(define (c+ x y)
  (let ((z (make-connector)))
    (adder x y z)
    z))
```

Define analogous procedures `c-`, `c*`, `c/`, and `cv` (constant value) that enable us to define compound constraints as in the converter example above.[33]

[33] The expression-oriented format is convenient because it avoids the need to name the in-

3.4 Concurrency: Time Is of the Essence

We've seen the power of computational objects with local state as tools for modeling. Yet, as Section 3.1.3 warned, this power extracts a price: the loss of referential transparency, giving rise to a thicket of questions about sameness and change, and the need to abandon the substitution model of evaluation in favor of the more intricate environment model.

The central issue lurking beneath the complexity of state, sameness, and

---

termediate expressions in a computation. Our original formulation of the constraint language is cumbersome in the same way that many languages are cumbersome when dealing with operations on compound data. For example, if we wanted to compute the product $(a+b)\cdot(c+d)$, where the variables represent vectors, we could work in "imperative style," using procedures that set the values of designated vector arguments but do not themselves return vectors as values:

```
(v-sum a b temp1)
(v-sum c d temp2)
(v-prod temp1 temp2 answer)
```

Alternatively, we could deal with expressions, using procedures that return vectors as values, and thus avoid explicitly mentioning `temp1` and `temp2`:

```
(define answer (v-prod (v-sum a b) (v-sum c d)))
```

Since Lisp allows us to return compound objects as values of procedures, we can transform our imperative-style constraint language into an expression-oriented style as shown in this exercise. In languages that are impoverished in handling compound objects, such as Algol, Basic, and Pascal (unless one explicitly uses Pascal pointer variables), one is usually stuck with the imperative style when manipulating compound objects. Given the advantage of the expression-oriented format, one might ask if there is any reason to have implemented the system in imperative style, as we did in this section. One reason is that the non-expression-oriented constraint language provides a handle on constraint objects (e.g., the value of the `adder` procedure) as well as on connector objects. This is useful if we wish to extend the system with new operations that communicate with constraints directly rather than only indirectly via operations on connectors. Although it is easy to implement the expression-oriented style in terms of the imperative implementation, it is very difficult to do the converse.

change is that by introducing assignment we are forced to admit *time* into our computational models. Before we introduced assignment, all our programs were timeless, in the sense that any expression that has a value always has the same value. In contrast, recall the example of modeling withdrawals from a bank account and returning the resulting balance, introduced at the beginning of Section 3.1.1:

```
(withdraw 25)
75
(withdraw 25)
50
```

Here successive evaluations of the same expression yield different values. This behavior arises from the fact that the execution of assignment statements (in this case, assignments to the variable `balance`) delineates *moments in time* when values change. The result of evaluating an expression depends not only on the expression itself, but also on whether the evaluation occurs before or after these moments. Building models in terms of computational objects with local state forces us to confront time as an essential concept in programming.

We can go further in structuring computational models to match our perception of the physical world. Objects in the world do not change one at a time in sequence. Rather we perceive them as acting *concurrently*—all at once. So it is often natural to model systems as collections of computational processes that execute concurrently. Just as we can make our programs modular by organizing models in terms of objects with separate local state, it is often appropriate to divide computational models into parts that evolve separately and concurrently. Even if the programs are to be executed on a sequential computer, the practice of writing programs as if they were to be executed concurrently forces the programmer to avoid inessential timing constraints and thus makes programs more modular.

In addition to making programs more modular, concurrent computation

can provide a speed advantage over sequential computation. Sequential computers execute only one operation at a time, so the amount of time it takes to perform a task is proportional to the total number of operations performed.[34] However, if it is possible to decompose a problem into pieces that are relatively independent and need to communicate only rarely, it may be possible to allocate pieces to separate computing processors, producing a speed advantage proportional to the number of processors available.

Unfortunately, the complexities introduced by assignment become even more problematic in the presence of concurrency. The fact of concurrent execution, either because the world operates in parallel or because our computers do, entails additional complexity in our understanding of time.

3.4.1 The Nature of Time in Concurrent Systems

On the surface, time seems straightforward. It is an ordering imposed on events.[35] For any events A and B, either A occurs before B, A and B are simultaneous, or A occurs after B. For instance, returning to the bank account example, suppose that Peter withdraws \$10 and Paul withdraws \$25 from a joint account that initially contains \$100, leaving \$65 in the account. Depending on the order of the two withdrawals, the sequence of balances in the account is either $\$100 \rightarrow \$90 \rightarrow \$65$ or $\$100 \rightarrow \$75 \rightarrow \$65$. In a computer implementation of the banking system, this changing sequence of balances could be modeled by successive assignments to a variable `balance`.

In complex situations, however, such a view can be problematic. Suppose

[34] Most real processors actually execute a few operations at a time, following a strategy called *pipelining*. Although this technique greatly improves the effective utilization of the hardware, it is used only to speed up the execution of a sequential instruction stream, while retaining the behavior of the sequential program.

[35] To quote some graffiti seen on a Cambridge building wall: "Time is a device that was invented to keep everything from happening at once."

that Peter and Paul, and other people besides, are accessing the same bank account through a network of banking machines distributed all over the world. The actual sequence of balances in the account will depend critically on the detailed timing of the accesses and the details of the communication among the machines.

This indeterminacy in the order of events can pose serious problems in the design of concurrent systems. For instance, suppose that the withdrawals made by Peter and Paul are implemented as two separate processes sharing a common variable `balance`, each process specified by the procedure given in Section 3.1.1:

```
(define (withdraw amount)
  (if (>= balance amount)
      (begin
        (set! balance (- balance amount))
        balance)
      "Insufficient funds"))
```

If the two processes operate independently, then Peter might test the balance and attempt to withdraw a legitimate amount. However, Paul might withdraw some funds in between the time that Peter checks the balance and the time Peter completes the withdrawal, thus invalidating Peter's test.

Things can be worse still. Consider the expression

```
(set! balance (- balance amount))
```

executed as part of each withdrawal process. This consists of three steps: (1) accessing the value of the `balance` variable; (2) computing the new balance; (3) setting `balance` to this new value. If Peter and Paul's withdrawals execute this statement concurrently, then the two withdrawals might interleave the order in which they access `balance` and set it to the new value.




Figure 3.29: Timing diagram showing how interleaving the order of events in two banking withdrawals can lead to an incorrect final balance.

The timing diagram in Figure 3.29 depicts an order of events where `balance` starts at 100, Peter withdraws 10, Paul withdraws 25, and yet the final value of `balance` is 75. As shown in the diagram, the reason for this anomaly is that Paul's assignment of 75 to `balance` is made under the assumption that the value of `balance` to be decremented is 100. That assumption, however, became invalid when Peter changed `balance` to 90. This is a catastrophic failure for the banking system, because the total amount of money in the system is not conserved. Before the transactions, the total amount of money was $100. Afterwards, Peter has $10, Paul has $25, and the bank has $75.[36]

The general phenomenon illustrated here is that several processes may share a common state variable. What makes this complicated is that more than one process may be trying to manipulate the shared state at the same time. For the bank account example, during each transaction, each customer should be able to act as if the other customers did not exist. When a customer changes the balance in a way that depends on the balance, he must be able to assume that, just before the moment of change, the balance is still what he thought it was.

[36] An even worse failure for this system could occur if the two `set!` operations attempt to change the balance simultaneously, in which case the actual data appearing in memory might end up being a random combination of the information being written by the two processes. Most computers have interlocks on the primitive memory-write operations, which protect against such simultaneous access. Even this seemingly simple kind of protection, however, raises implementation challenges in the design of multiprocessing computers, where elaborate *cache-coherence* protocols are required to ensure that the various processors will maintain a consistent view of memory contents, despite the fact that data may be replicated ("cached") among the different processors to increase the speed of memory access.

Correct behavior of concurrent programs

The above example typifies the subtle bugs that can creep into concurrent programs. The root of this complexity lies in the assignments to variables that are shared among the different processes. We already know that we must be careful in writing programs that use `set!`, because the results of a computation depend on the order in which the assignments occur.[37] With concurrent processes we must be especially careful about assignments, because we may not be able to control the order of the assignments made by the different processes. If several such changes might be made concurrently (as with two depositors accessing a joint account) we need some way to ensure that our system behaves correctly. For example, in the case of withdrawals from a joint bank account, we must ensure that money is conserved. To make concurrent programs behave correctly, we may have to place some restrictions on concurrent execution.

One possible restriction on concurrency would stipulate that no two operations that change any shared state variables can occur at the same time. This is an extremely stringent requirement. For distributed banking, it would require the system designer to ensure that only one transaction could proceed at a time. This would be both inefficient and overly conservative. Figure 3.30 shows Peter and Paul sharing a bank account, where Paul has a private account as well. The diagram illustrates two withdrawals from the shared account (one by Peter and one by Paul) and a deposit to Paul's private account.[38] The two withdrawals from the shared account must not be concurrent (since both access and update the same account), and Paul's deposit and withdrawal

[37] The factorial program in Section 3.1.3 illustrates this for a single sequential process.

[38] The columns show the contents of Peter's wallet, the joint account (in Bank1), Paul's wallet, and Paul's private account (in Bank2), before and after each withdrawal (W) and deposit (D). Peter withdraws $10 from Bank1; Paul deposits $5 in Bank2, then withdraws $25 from Bank1.




Figure 3.30: Concurrent deposits and withdrawals from a joint account in Bank1 and a private account in Bank2.

must not be concurrent (since both access and update the amount in Paul's wallet). But there should be no problem permitting Paul's deposit to his private account to proceed concurrently with Peter's withdrawal from the shared account.

A less stringent restriction on concurrency would ensure that a concurrent system produces the same result as if the processes had run sequentially in some order. There are two important aspects to this requirement. First, it does not require the processes to actually run sequentially, but only to produce results that are the same *as if* they had run sequentially. For the example in Figure 3.30, the designer of the bank account system can safely allow Paul's

deposit and Peter's withdrawal to happen concurrently, because the net result will be the same as if the two operations had happened sequentially. Second, there may be more than one possible "correct" result produced by a concurrent program, because we require only that the result be the same as for *some* sequential order. For example, suppose that Peter and Paul's joint account starts out with $100, and Peter deposits $40 while Paul concurrently withdraws half the money in the account. Then sequential execution could result in the account balance being either $70 or $90 (see Exercise 3.38).[39]

There are still weaker requirements for correct execution of concurrent programs. A program for simulating diffusion (say, the flow of heat in an object) might consist of a large number of processes, each one representing a small volume of space, that update their values concurrently. Each process repeatedly changes its value to the average of its own value and its neighbors' values. This algorithm converges to the right answer independent of the order in which the operations are done; there is no need for any restrictions on concurrent use of the shared values.

Exercise 3.38: Suppose that Peter, Paul, and Mary share a joint bank account that initially contains $100. Concurrently, Peter deposits $10, Paul withdraws $20, and Mary withdraws half the money in the account, by executing the following commands:

```
Peter: (set! balance (+ balance 10))
Paul:  (set! balance (- balance 20))
Mary:  (set! balance (- balance (/ balance 2)))
```

[39] A more formal way to express this idea is to say that concurrent programs are inherently *nondeterministic*. That is, they are described not by single-valued functions, but by functions whose results are sets of possible values. In Section 4.3 we will study a language for expressing nondeterministic computations.

a. List all the different possible values for `balance` after these three transactions have been completed, assuming that the banking system forces the three processes to run sequentially in some order.

b. What are some other values that could be produced if the system allows the processes to be interleaved? Draw timing diagrams like the one in Figure 3.29 to explain how these values can occur.

3.4.2 Mechanisms for Controlling Concurrency

We've seen that the difficulty in dealing with concurrent processes is rooted in the need to consider the interleaving of the order of events in the different processes. For example, suppose we have two processes, one with three ordered events (a, b, c) and one with three ordered events (x, y, z). If the two processes run concurrently, with no constraints on how their execution is interleaved, then there are 20 different possible orderings for the events that are consistent with the individual orderings for the two processes:

```
(a,b,c,x,y,z)   (a,x,b,y,c,z)   (x,a,b,c,y,z)   (x,a,y,z,b,c)
(a,b,x,c,y,z)   (a,x,b,y,z,c)   (x,a,b,y,c,z)   (x,y,a,b,c,z)
(a,b,x,y,c,z)   (a,x,y,b,c,z)   (x,a,b,y,z,c)   (x,y,a,b,z,c)
(a,b,x,y,z,c)   (a,x,y,b,z,c)   (x,a,y,b,c,z)   (x,y,a,z,b,c)
(a,x,b,c,y,z)   (a,x,y,z,b,c)   (x,a,y,b,z,c)   (x,y,z,a,b,c)
```

As programmers designing this system, we would have to consider the effects of each of these 20 orderings and check that each behavior is acceptable. Such an approach rapidly becomes unwieldy as the numbers of processes and events increase.

A more practical approach to the design of concurrent systems is to devise general mechanisms that allow us to constrain the interleaving of concurrent

processes so that we can be sure that the program behavior is correct. Many mechanisms have been developed for this purpose. In this section, we describe one of them, the *serializer*.

Serializing access to shared state

Serialization implements the following idea: Processes will execute concurrently, but there will be certain collections of procedures that cannot be executed concurrently. More precisely, serialization creates distinguished sets of procedures such that only one execution of a procedure in each serialized set is permitted to happen at a time. If some procedure in the set is being executed, then a process that attempts to execute any procedure in the set will be forced to wait until the first execution has finished.

We can use serialization to control access to shared variables. For example, if we want to update a shared variable based on the previous value of that variable, we put the access to the previous value of the variable and the assignment of the new value to the variable in the same procedure. We then ensure that no other procedure that assigns to the variable can run concurrently with this procedure by serializing all of these procedures with the same serializer. This guarantees that the value of the variable cannot be changed between an access and the corresponding assignment.

Serializers in Scheme

To make the above mechanism more concrete, suppose that we have extended Scheme to include a procedure called `parallel-execute`:

`(parallel-execute` $\langle p_1 \rangle$ $\langle p_2 \rangle$ ... $\langle p_k \rangle$`)`

Each $\langle p \rangle$ must be a procedure of no arguments. `parallel-execute` creates a separate process for each $\langle p \rangle$, which applies $\langle p \rangle$ (to no arguments).

These processes all run concurrently.[40]

As an example of how this is used, consider

```
(define x 10)
(parallel-execute
 (lambda () (set! x (* x x)))
 (lambda () (set! x (+ x 1))))
```

This creates two concurrent processes—P_1, which sets `x` to `x` times `x`, and P_2, which increments `x`. After execution is complete, `x` will be left with one of five possible values, depending on the interleaving of the events of P_1 and P_2:

`101:` P_1 sets `x` to 100 and then P_2 increments `x` to 101.
`121:` P_2 increments `x` to 11 and then P_1 sets `x` to `x * x`.
`110:` P_2 changes `x` from 10 to 11 between the two times that P_1 accesses the value of `x` during the evaluation of `(* x x)`.
`11:` P_2 accesses `x`, then P_1 sets `x` to 100, then P_2 sets `x`.
`100:` P_1 accesses `x` (twice), then P_2 sets `x` to 11, then P_1 sets `x`.

We can constrain the concurrency by using serialized procedures, which are created by *serializers*. Serializers are constructed by `make-serializer`, whose implementation is given below. A serializer takes a procedure as argument and returns a serialized procedure that behaves like the original procedure. All calls to a given serializer return serialized procedures in the same set.

Thus, in contrast to the example above, executing

```
(define x 10)
```

[40] `parallel-execute` is not part of standard Scheme, but it can be implemented in MIT Scheme. In our implementation, the new concurrent processes also run concurrently with the original Scheme process. Also, in our implementation, the value returned by `parallel-execute` is a special control object that can be used to halt the newly created processes.

```
(define s (make-serializer))
(parallel-execute
 (s (lambda () (set! x (* x x))))
 (s (lambda () (set! x (+ x 1)))))
```

can produce only two possible values for x, 101 or 121. The other possibilities are eliminated, because the execution of P_1 and P_2 cannot be interleaved.

Here is a version of the `make-account` procedure from Section 3.1.1, where the deposits and withdrawals have been serialized:

```
(define (make-account balance)
  (define (withdraw amount)
    (if (>= balance amount)
        (begin (set! balance (- balance amount))
               balance)
        "Insufficient funds"))
  (define (deposit amount)
    (set! balance (+ balance amount))
    balance)
  (let ((protected (make-serializer)))
    (define (dispatch m)
      (cond ((eq? m 'withdraw) (protected withdraw))
            ((eq? m 'deposit) (protected deposit))
            ((eq? m 'balance) balance)
            (else (error "Unknown request: MAKE-ACCOUNT"
                         m))))
    dispatch))
```

With this implementation, two processes cannot be withdrawing from or depositing into a single account concurrently. This eliminates the source of the error illustrated in Figure 3.29, where Peter changes the account balance between the times when Paul accesses the balance to compute the new value and when Paul actually performs the assignment. On the other hand, each account has its own serializer, so that deposits and withdrawals for different accounts

can proceed concurrently.

Exercise 3.39: Which of the five possibilities in the parallel execution shown above remain if we instead serialize execution as follows:

```
(define x 10)
(define s (make-serializer))
(parallel-execute
 (lambda () (set! x ((s (lambda () (* x x))))))
 (s (lambda () (set! x (+ x 1)))))
```

Exercise 3.40: Give all possible values of `x` that can result from executing

```
(define x 10)
(parallel-execute (lambda () (set! x (* x x)))
                  (lambda () (set! x (* x x x))))
```

Which of these possibilities remain if we instead use serialized procedures:

```
(define x 10)
(define s (make-serializer))
(parallel-execute (s (lambda () (set! x (* x x))))
                  (s (lambda () (set! x (* x x x)))))
```

Exercise 3.41: Ben Bitdiddle worries that it would be better to implement the bank account as follows (where the commented line has been changed):

```
(define (make-account balance)
  (define (withdraw amount)
    (if (>= balance amount)
```

```
          (begin (set! balance
                       (- balance amount))
                 balance)
          "Insufficient funds"))
    (define (deposit amount)
      (set! balance (+ balance amount))
      balance)
    (let ((protected (make-serializer)))
      (define (dispatch m)
        (cond ((eq? m 'withdraw) (protected withdraw))
              ((eq? m 'deposit) (protected deposit))
              ((eq? m 'balance)
               ((protected
                 (lambda () balance)))) ;serial-
ized
              (else
               (error "Unknown request: MAKE-ACCOUNT"
                      m))))
      dispatch))
```

because allowing unserialized access to the bank balance can result in anomalous behavior. Do you agree? Is there any scenario that demonstrates Ben's concern?

Exercise 3.42: Ben Bitdiddle suggests that it's a waste of time to create a new serialized procedure in response to every `withdraw` and `deposit` message. He says that `make-account` could be changed so that the calls to `protected` are done outside the `dispatch` procedure. That is, an account would return the same serialized procedure (which was created at the same time as the account) each time it is asked for a withdrawal procedure.

```
(define (make-account balance)
  (define (withdraw amount)
    (if (>= balance amount)
        (begin (set! balance (- balance amount))
               balance)
        "Insufficient funds"))
  (define (deposit amount)
    (set! balance (+ balance amount))
    balance)
  (let ((protected (make-serializer)))
    (let ((protected-withdraw (protected withdraw))
          (protected-deposit (protected deposit)))
      (define (dispatch m)
        (cond ((eq? m 'withdraw) protected-withdraw)
              ((eq? m 'deposit) protected-deposit)
              ((eq? m 'balance) balance)
              (else
               (error "Unknown request: MAKE-ACCOUNT"
                      m))))
      dispatch)))
```

Is this a safe change to make? In particular, is there any difference in what concurrency is allowed by these two versions of `make-account`?

Complexity of using multiple shared resources

Serializers provide a powerful abstraction that helps isolate the complexities of concurrent programs so that they can be dealt with carefully and (hopefully) correctly. However, while using serializers is relatively straightforward when there is only a single shared resource (such as a single bank account), concurrent programming can be treacherously difficult when there are multiple

shared resources.

To illustrate one of the difficulties that can arise, suppose we wish to swap the balances in two bank accounts. We access each account to find the balance, compute the difference between the balances, withdraw this difference from one account, and deposit it in the other account. We could implement this as follows:[41]

```
(define (exchange account1 account2)
  (let ((difference (- (account1 'balance)
                       (account2 'balance))))
    ((account1 'withdraw) difference)
    ((account2 'deposit) difference)))
```

This procedure works well when only a single process is trying to do the exchange. Suppose, however, that Peter and Paul both have access to accounts $a1$, $a2$, and $a3$, and that Peter exchanges $a1$ and $a2$ while Paul concurrently exchanges $a1$ and $a3$. Even with account deposits and withdrawals serialized for individual accounts (as in the `make-account` procedure shown above in this section), `exchange` can still produce incorrect results. For example, Peter might compute the difference in the balances for $a1$ and $a2$, but then Paul might change the balance in $a1$ before Peter is able to complete the exchange.[42] For correct behavior, we must arrange for the `exchange` procedure to lock out any other concurrent accesses to the accounts during the entire time of the exchange.

One way we can accomplish this is by using both accounts' serializers to serialize the entire `exchange` procedure. To do this, we will arrange for access to an account's serializer. Note that we are deliberately breaking the

[41] We have simplified `exchange` by exploiting the fact that our `deposit` message accepts negative amounts. (This is a serious bug in our banking system!)

[42] If the account balances start out as $10, $20, and $30, then after any number of concurrent exchanges, the balances should still be $10, $20, and $30 in some order. Serializing the deposits to individual accounts is not sufficient to guarantee this. See Exercise 3.43.

modularity of the bank-account object by exposing the serializer. The following version of `make-account` is identical to the original version given in Section 3.1.1, except that a serializer is provided to protect the balance variable, and the serializer is exported via message passing:

```
(define (make-account-and-serializer balance)
  (define (withdraw amount)
    (if (>= balance amount)
        (begin (set! balance (- balance amount))
               balance)
        "Insufficient funds"))
  (define (deposit amount)
    (set! balance (+ balance amount))
    balance)
  (let ((balance-serializer (make-serializer)))
    (define (dispatch m)
      (cond ((eq? m 'withdraw) withdraw)
            ((eq? m 'deposit) deposit)
            ((eq? m 'balance) balance)
            ((eq? m 'serializer) balance-serializer)
            (else (error "Unknown request: MAKE-ACCOUNT" m))))
    dispatch))
```

We can use this to do serialized deposits and withdrawals. However, unlike our earlier serialized account, it is now the responsibility of each user of bank-account objects to explicitly manage the serialization, for example as follows:[43]

```
(define (deposit account amount)
  (let ((s (account 'serializer))
        (d (account 'deposit)))
    ((s d) amount)))
```

[43] Exercise 3.45 investigates why deposits and withdrawals are no longer automatically serialized by the account.

Exporting the serializer in this way gives us enough flexibility to implement a serialized exchange program. We simply serialize the original `exchange` procedure with the serializers for both accounts:

```
(define (serialized-exchange account1 account2)
  (let ((serializer1 (account1 'serializer))
        (serializer2 (account2 'serializer)))
    ((serializer1 (serializer2 exchange))
     account1
     account2)))
```

Exercise 3.43: Suppose that the balances in three accounts start out as $10, $20, and $30, and that multiple processes run, exchanging the balances in the accounts. Argue that if the processes are run sequentially, after any number of concurrent exchanges, the account balances should be $10, $20, and $30 in some order. Draw a timing diagram like the one in Figure 3.29 to show how this condition can be violated if the exchanges are implemented using the first version of the account-exchange program in this section. On the other hand, argue that even with this `exchange` program, the sum of the balances in the accounts will be preserved. Draw a timing diagram to show how even this condition would be violated if we did not serialize the transactions on individual accounts.

Exercise 3.44: Consider the problem of transferring an amount from one account to another. Ben Bitdiddle claims that this can be accomplished with the following procedure, even if there are multiple people concurrently transferring money among multiple accounts, using any account mechanism that serializes deposit and withdrawal transactions, for example, the version of `make-account` in the text above.

```
(define (transfer from-account to-account amount)
  ((from-account 'withdraw) amount)
  ((to-account 'deposit) amount))
```

Louis Reasoner claims that there is a problem here, and that we need to use a more sophisticated method, such as the one required for dealing with the exchange problem. Is Louis right? If not, what is the essential difference between the transfer problem and the exchange problem? (You should assume that the balance in `from-account` is at least `amount`.)

Exercise 3.45: Louis Reasoner thinks our bank-account system is unnecessarily complex and error-prone now that deposits and withdrawals aren't automatically serialized. He suggests that `make-account-and-serializer` should have exported the serializer (for use by such procedures as `serialized-exchange`) in addition to (rather than instead of) using it to serialize accounts and deposits as `make-account` did. He proposes to redefine accounts as follows:

```
(define (make-account-and-serializer balance)
  (define (withdraw amount)
    (if (>= balance amount)
        (begin (set! balance (- balance amount)) balance)
        "Insufficient funds"))
  (define (deposit amount)
    (set! balance (+ balance amount)) balance)
  (let ((balance-serializer (make-serializer)))
    (define (dispatch m)
      (cond ((eq? m 'withdraw) (balance-serializer withdraw))
            ((eq? m 'deposit) (balance-serializer deposit))
            ((eq? m 'balance) balance)
            ((eq? m 'serializer) balance-serializer)
            (else (error "Unknown request: MAKE-ACCOUNT" m)))
```

```
    dispatch))
```

Then deposits are handled as with the original `make-account`:

```
(define (deposit account amount)
  ((account 'deposit) amount))
```

Explain what is wrong with Louis's reasoning. In particular, consider what happens when `serialized-exchange` is called.

Implementing serializers

We implement serializers in terms of a more primitive synchronization mechanism called a *mutex*. A mutex is an object that supports two operations—the mutex can be *acquired*, and the mutex can be *released*. Once a mutex has been acquired, no other acquire operations on that mutex may proceed until the mutex is released.[44] In our implementation, each serializer has an associated mutex. Given a procedure `p`, the serializer returns a procedure that acquires the mutex, runs `p`, and then releases the mutex. This ensures that only one of the procedures produced by the serializer can be running at once, which is precisely the serialization property that we need to guarantee.

[44]The term "mutex" is an abbreviation for *mutual exclusion*. The general problem of arranging a mechanism that permits concurrent processes to safely share resources is called the mutual exclusion problem. Our mutex is a simple variant of the *semaphore* mechanism (see Exercise 3.47), which was introduced in the "THE" Multiprogramming System developed at the Technological University of Eindhoven and named for the university's initials in Dutch (Dijkstra 1968a). The acquire and release operations were originally called P and V, from the Dutch words *passeren* (to pass) and *vrijgeven* (to release), in reference to the semaphores used on railroad systems. Dijkstra's classic exposition (Dijkstra 1968b) was one of the first to clearly present the issues of concurrency control, and showed how to use semaphores to handle a variety of concurrency problems.

```
(define (make-serializer)
  (let ((mutex (make-mutex)))
    (lambda (p)
      (define (serialized-p . args)
        (mutex 'acquire)
        (let ((val (apply p args)))
          (mutex 'release)
          val))
      serialized-p)))
```

The mutex is a mutable object (here we'll use a one-element list, which we'll refer to as a *cell*) that can hold the value true or false. When the value is false, the mutex is available to be acquired. When the value is true, the mutex is unavailable, and any process that attempts to acquire the mutex must wait.

Our mutex constructor `make-mutex` begins by initializing the cell contents to false. To acquire the mutex, we test the cell. If the mutex is available, we set the cell contents to true and proceed. Otherwise, we wait in a loop, attempting to acquire over and over again, until we find that the mutex is available.[45] To release the mutex, we set the cell contents to false.

```
(define (make-mutex)
  (let ((cell (list false)))
    (define (the-mutex m)
      (cond ((eq? m 'acquire)
             (if (test-and-set! cell)
                 (the-mutex 'acquire))) ; retry
            ((eq? m 'release) (clear! cell))))
    the-mutex))
(define (clear! cell) (set-car! cell false))
```

[45] In most time-shared operating systems, processes that are blocked by a mutex do not waste time "busy-waiting" as above. Instead, the system schedules another process to run while the first is waiting, and the blocked process is awakened when the mutex becomes available.

`test-and-set!` tests the cell and returns the result of the test. In addition, if the test was false, `test-and-set!` sets the cell contents to true before returning false. We can express this behavior as the following procedure:

```
(define (test-and-set! cell)
  (if (car cell) true (begin (set-car! cell true) false)))
```

However, this implementation of `test-and-set!` does not suffice as it stands. There is a crucial subtlety here, which is the essential place where concurrency control enters the system: The `test-and-set!` operation must be performed *atomically*. That is, we must guarantee that, once a process has tested the cell and found it to be false, the cell contents will actually be set to true before any other process can test the cell. If we do not make this guarantee, then the mutex can fail in a way similar to the bank-account failure in Figure 3.29. (See Exercise 3.46.)

The actual implementation of `test-and-set!` depends on the details of how our system runs concurrent processes. For example, we might be executing concurrent processes on a sequential processor using a time-slicing mechanism that cycles through the processes, permitting each process to run for a short time before interrupting it and moving on to the next process. In that case, `test-and-set!` can work by disabling time slicing during the testing and setting.[46] Alternatively, multiprocessing computers provide

[46] In MIT Scheme for a single processor, which uses a time-slicing model, `test-and-set!` can be implemented as follows:

```
(define (test-and-set! cell)
  (without-interrupts
   (lambda ()
     (if (car cell)
         true
         (begin (set-car! cell true)
```

instructions that support atomic operations directly in hardware.[47]

Exercise 3.46: Suppose that we implement `test-and-set!` using an ordinary procedure as shown in the text, without attempting to make the operation atomic. Draw a timing diagram like the one in Figure 3.29 to demonstrate how the mutex implementation can fail by allowing two processes to acquire the mutex at the same time.

Exercise 3.47: A semaphore (of size n) is a generalization of a mutex. Like a mutex, a semaphore supports acquire and release operations, but it is more general in that up to n processes can acquire it concurrently. Additional processes that attempt to acquire the semaphore must wait for release operations. Give implementations of semaphores

a. in terms of mutexes

```
                    false)))))
```

`without-interrupts` disables time-slicing interrupts while its procedure argument is being executed.

[47] There are many variants of such instructions—including test-and-set, test-and-clear, swap, compare-and-exchange, load-reserve, and store-conditional—whose design must be carefully matched to the machine's processor-memory interface. One issue that arises here is to determine what happens if two processes attempt to acquire the same resource at exactly the same time by using such an instruction. This requires some mechanism for making a decision about which process gets control. Such a mechanism is called an *arbiter*. Arbiters usually boil down to some sort of hardware device. Unfortunately, it is possible to prove that one cannot physically construct a fair arbiter that works 100% of the time unless one allows the arbiter an arbitrarily long time to make its decision. The fundamental phenomenon here was originally observed by the fourteenth-century French philosopher Jean Buridan in his commentary on Aristotle's *De caelo*. Buridan argued that a perfectly rational dog placed between two equally attractive sources of food will starve to death, because it is incapable of deciding which to go to first.

b. in terms of atomic `test-and-set!` operations.

Deadlock

Now that we have seen how to implement serializers, we can see that account exchanging still has a problem, even with the `serialized-exchange` procedure above. Imagine that Peter attempts to exchange $a1$ with $a2$ while Paul concurrently attempts to exchange $a2$ with $a1$. Suppose that Peter's process reaches the point where it has entered a serialized procedure protecting $a1$ and, just after that, Paul's process enters a serialized procedure protecting $a2$. Now Peter cannot proceed (to enter a serialized procedure protecting $a2$) until Paul exits the serialized procedure protecting $a2$. Similarly, Paul cannot proceed until Peter exits the serialized procedure protecting $a1$. Each process is stalled forever, waiting for the other. This situation is called a *deadlock*. Deadlock is always a danger in systems that provide concurrent access to multiple shared resources.

One way to avoid the deadlock in this situation is to give each account a unique identification number and rewrite `serialized-exchange` so that a process will always attempt to enter a procedure protecting the lowest-numbered account first. Although this method works well for the exchange problem, there are other situations that require more sophisticated deadlock-avoidance techniques, or where deadlock cannot be avoided at all. (See Exercise 3.48 and Exercise 3.49.)[48]

> **Exercise 3.48:** Explain in detail why the deadlock-avoidance method described above, (i.e., the accounts are numbered, and

[48] The general technique for avoiding deadlock by numbering the shared resources and acquiring them in order is due to Havender (1968). Situations where deadlock cannot be avoided require *deadlock-recovery* methods, which entail having processes "back out" of the deadlocked state and try again. Deadlock-recovery mechanisms are widely used in database management systems, a topic that is treated in detail in Gray and Reuter 1993.

each process attempts to acquire the smaller-numbered account first) avoids deadlock in the exchange problem. Rewrite `serialized-exchange` to incorporate this idea. (You will also need to modify `make-account` so that each account is created with a number, which can be accessed by sending an appropriate message.)

Exercise 3.49: Give a scenario where the deadlock-avoidance mechanism described above does not work. (Hint: In the exchange problem, each process knows in advance which accounts it will need to get access to. Consider a situation where a process must get access to some shared resources before it can know which additional shared resources it will require.)

Concurrency, time, and communication

We've seen how programming concurrent systems requires controlling the ordering of events when different processes access shared state, and we've seen how to achieve this control through judicious use of serializers. But the problems of concurrency lie deeper than this, because, from a fundamental point of view, it's not always clear what is meant by "shared state."

Mechanisms such as `test-and-set!` require processes to examine a global shared flag at arbitrary times. This is problematic and inefficient to implement in modern high-speed processors, where due to optimization techniques such as pipelining and cached memory, the contents of memory may not be in a consistent state at every instant. In contemporary multiprocessing systems, therefore, the serializer paradigm is being supplanted by new approaches to concurrency control.[49]

[49] One such alternative to serialization is called *barrier synchronization*. The programmer permits concurrent processes to execute as they please, but establishes certain synchronization

The problematic aspects of shared state also arise in large, distributed systems. For instance, imagine a distributed banking system where individual branch banks maintain local values for bank balances and periodically compare these with values maintained by other branches. In such a system the value of "the account balance" would be undetermined, except right after synchronization. If Peter deposits money in an account he holds jointly with Paul, when should we say that the account balance has changed—when the balance in the local branch changes, or not until after the synchronization? And if Paul accesses the account from a different branch, what are the reasonable constraints to place on the banking system such that the behavior is "correct"? The only thing that might matter for correctness is the behavior observed by Peter and Paul individually and the "state" of the account immediately after synchronization. Questions about the "real" account balance or the order of events between synchronizations may be irrelevant or meaningless.[50]

The basic phenomenon here is that synchronizing different processes, establishing shared state, or imposing an order on events requires communication among the processes. In essence, any notion of time in concurrency control must be intimately tied to communication.[51] It is intriguing that a

points ("barriers") through which no process can proceed until all the processes have reached the barrier. Modern processors provide machine instructions that permit programmers to establish synchronization points at places where consistency is required. The PowerPC, for example, includes for this purpose two instructions called SYNC and EIEIO (Enforced In-order Execution of Input/Output).

[50] This may seem like a strange point of view, but there are systems that work this way. International charges to credit-card accounts, for example, are normally cleared on a per-country basis, and the charges made in different countries are periodically reconciled. Thus the account balance may be different in different countries.

[51] For distributed systems, this perspective was pursued by Lamport (1978), who showed how to use communication to establish "global clocks" that can be used to establish orderings on events in distributed systems.

similar connection between time and communication also arises in the Theory of Relativity, where the speed of light (the fastest signal that can be used to synchronize events) is a fundamental constant relating time and space. The complexities we encounter in dealing with time and state in our computational models may in fact mirror a fundamental complexity of the physical universe.

3.5 Streams

We've gained a good understanding of assignment as a tool in modeling, as well as an appreciation of the complex problems that assignment raises. It is time to ask whether we could have gone about things in a different way, so as to avoid some of these problems. In this section, we explore an alternative approach to modeling state, based on data structures called *streams*. As we shall see, streams can mitigate some of the complexity of modeling state.

Let's step back and review where this complexity comes from. In an attempt to model real-world phenomena, we made some apparently reasonable decisions: We modeled real-world objects with local state by computational objects with local variables. We identified time variation in the real world with time variation in the computer. We implemented the time variation of the states of the model objects in the computer with assignments to the local variables of the model objects.

Is there another approach? Can we avoid identifying time in the computer with time in the modeled world? Must we make the model change with time in order to model phenomena in a changing world? Think about the issue in terms of mathematical functions. We can describe the time-varying behavior of a quantity x as a function of time $x(t)$. If we concentrate on x instant by instant, we think of it as a changing quantity. Yet if we concentrate on the entire time history of values, we do not emphasize change—the function

itself does not change.[52]

If time is measured in discrete steps, then we can model a time function as a (possibly infinite) sequence. In this section, we will see how to model change in terms of sequences that represent the time histories of the systems being modeled. To accomplish this, we introduce new data structures called *streams*. From an abstract point of view, a stream is simply a sequence. However, we will find that the straightforward implementation of streams as lists (as in Section 2.2.1) doesn't fully reveal the power of stream processing. As an alternative, we introduce the technique of *delayed evaluation*, which enables us to represent very large (even infinite) sequences as streams.

Stream processing lets us model systems that have state without ever using assignment or mutable data. This has important implications, both theoretical and practical, because we can build models that avoid the drawbacks inherent in introducing assignment. On the other hand, the stream framework raises difficulties of its own, and the question of which modeling technique leads to more modular and more easily maintained systems remains open.

3.5.1 Streams Are Delayed Lists

As we saw in Section 2.2.3, sequences can serve as standard interfaces for combining program modules. We formulated powerful abstractions for manipulating sequences, such as `map`, `filter`, and `accumulate`, that capture a wide variety of operations in a manner that is both succinct and elegant.

Unfortunately, if we represent sequences as lists, this elegance is bought at the price of severe inefficiency with respect to both the time and space required by our computations. When we represent manipulations on sequences

[52] Physicists sometimes adopt this view by introducing the "world lines" of particles as a device for reasoning about motion. We've also already mentioned (Section 2.2.3) that this is the natural way to think about signal-processing systems. We will explore applications of streams to signal processing in Section 3.5.3.

as transformations of lists, our programs must construct and copy data structures (which may be huge) at every step of a process.

To see why this is true, let us compare two programs for computing the sum of all the prime numbers in an interval. The first program is written in standard iterative style:[53]

```
(define (sum-primes a b)
  (define (iter count accum)
    (cond ((> count b) accum)
          ((prime? count)
             (iter (+ count 1) (+ count accum)))
          (else (iter (+ count 1) accum))))
  (iter a 0))
```

The second program performs the same computation using the sequence operations of Section 2.2.3:

```
(define (sum-primes a b)
  (accumulate +
              0
              (filter prime?
                      (enumerate-interval a b))))
```

In carrying out the computation, the first program needs to store only the sum being accumulated. In contrast, the filter in the second program cannot do any testing until `enumerate-interval` has constructed a complete list of the numbers in the interval. The filter generates another list, which in turn is passed to `accumulate` before being collapsed to form a sum. Such large intermediate storage is not needed by the first program, which we can think of as enumerating the interval incrementally, adding each prime to the sum as it is generated.

[53] Assume that we have a predicate `prime?` (e.g., as in Section 1.2.6) that tests for primality.

The inefficiency in using lists becomes painfully apparent if we use the sequence paradigm to compute the second prime in the interval from 10,000 to 1,000,000 by evaluating the expression

```
(car (cdr (filter prime?
                  (enumerate-interval 10000 1000000))))
```

This expression does find the second prime, but the computational overhead is outrageous. We construct a list of almost a million integers, filter this list by testing each element for primality, and then ignore almost all of the result. In a more traditional programming style, we would interleave the enumeration and the filtering, and stop when we reached the second prime.

Streams are a clever idea that allows one to use sequence manipulations without incurring the costs of manipulating sequences as lists. With streams we can achieve the best of both worlds: We can formulate programs elegantly as sequence manipulations, while attaining the efficiency of incremental computation. The basic idea is to arrange to construct a stream only partially, and to pass the partial construction to the program that consumes the stream. If the consumer attempts to access a part of the stream that has not yet been constructed, the stream will automatically construct just enough more of itself to produce the required part, thus preserving the illusion that the entire stream exists. In other words, although we will write programs as if we were processing complete sequences, we design our stream implementation to automatically and transparently interleave the construction of the stream with its use.

On the surface, streams are just lists with different names for the procedures that manipulate them. There is a constructor, `cons-stream`, and two selectors, `stream-car` and `stream-cdr`, which satisfy the constraints

```
(stream-car (cons-stream x y)) = x
(stream-cdr (cons-stream x y)) = y
```

There is a distinguishable object, `the-empty-stream`, which cannot be the result of any `cons-stream` operation, and which can be identified with the predicate `stream-null?`.[54] Thus we can make and use streams, in just the same way as we can make and use lists, to represent aggregate data arranged in a sequence. In particular, we can build stream analogs of the list operations from Chapter 2, such as `list-ref`, `map`, and `for-each`:[55]

```
(define (stream-ref s n)
  (if (= n 0)
      (stream-car s)
      (stream-ref (stream-cdr s) (- n 1))))
(define (stream-map proc s)
  (if (stream-null? s)
      the-empty-stream
      (cons-stream (proc (stream-car s))
                   (stream-map proc (stream-cdr s)))))
(define (stream-for-each proc s)
  (if (stream-null? s)
      'done
      (begin (proc (stream-car s))
             (stream-for-each proc (stream-cdr s)))))
```

`stream-for-each` is useful for viewing streams:

```
(define (display-stream s)
  (stream-for-each display-line s))
(define (display-line x) (newline) (display x))
```

[54] In the MIT implementation, `the-empty-stream` is the same as the empty list `'()`, and `stream-null?` is the same as `null?`.

[55] This should bother you. The fact that we are defining such similar procedures for streams and lists indicates that we are missing some underlying abstraction. Unfortunately, in order to exploit this abstraction, we will need to exert finer control over the process of evaluation than we can at present. We will discuss this point further at the end of Section 3.5.4. In Section 4.2, we'll develop a framework that unifies lists and streams.

To make the stream implementation automatically and transparently interleave the construction of a stream with its use, we will arrange for the `cdr` of a stream to be evaluated when it is accessed by the `stream-cdr` procedure rather than when the stream is constructed by `cons-stream`. This implementation choice is reminiscent of our discussion of rational numbers in Section 2.1.2, where we saw that we can choose to implement rational numbers so that the reduction of numerator and denominator to lowest terms is performed either at construction time or at selection time. The two rational-number implementations produce the same data abstraction, but the choice has an effect on efficiency. There is a similar relationship between streams and ordinary lists. As a data abstraction, streams are the same as lists. The difference is the time at which the elements are evaluated. With ordinary lists, both the `car` and the `cdr` are evaluated at construction time. With streams, the `cdr` is evaluated at selection time.

Our implementation of streams will be based on a special form called `delay`. Evaluating `(delay` ⟨*exp*⟩`)` does not evaluate the expression ⟨*exp*⟩, but rather returns a so-called *delayed object*, which we can think of as a "promise" to evaluate ⟨*exp*⟩ at some future time. As a companion to `delay`, there is a procedure called `force` that takes a delayed object as argument and performs the evaluation—in effect, forcing the `delay` to fulfill its promise. We will see below how `delay` and `force` can be implemented, but first let us use these to construct streams.

`cons-stream` is a special form defined so that

```
(cons-stream ⟨a⟩ ⟨b⟩)
```

is equivalent to

```
(cons ⟨a⟩ (delay ⟨b⟩))
```

What this means is that we will construct streams using pairs. However, rather than placing the value of the rest of the stream into the `cdr` of the pair we

will put there a promise to compute the rest if it is ever requested. `stream-car` and `stream-cdr` can now be defined as procedures:

```
(define (stream-car stream) (car stream))
(define (stream-cdr stream) (force (cdr stream)))
```

`stream-car` selects the `car` of the pair; `stream-cdr` selects the `cdr` of the pair and evaluates the delayed expression found there to obtain the rest of the stream.[56]

The stream implementation in action

To see how this implementation behaves, let us analyze the "outrageous" prime computation we saw above, reformulated in terms of streams:

```
(stream-car
 (stream-cdr
  (stream-filter prime?
                 (stream-enumerate-interval
                  10000 1000000))))
```

We will see that it does indeed work efficiently.

We begin by calling `stream-enumerate-interval` with the arguments 10,000 and 1,000,000. `stream-enumerate-interval` is the stream analog of `enumerate-interval` (Section 2.2.3):

```
(define (stream-enumerate-interval low high)
  (if (> low high)
      the-empty-stream
```

[56] Although `stream-car` and `stream-cdr` can be defined as procedures, `cons-stream` must be a special form. If `cons-stream` were a procedure, then, according to our model of evaluation, evaluating `(cons-stream` $\langle a \rangle$ $\langle b \rangle$`)` would automatically cause $\langle b \rangle$ to be evaluated, which is precisely what we do not want to happen. For the same reason, `delay` must be a special form, though `force` can be an ordinary procedure.

```
(cons-stream
 low
 (stream-enumerate-interval (+ low 1) high))))
```

and thus the result returned by `stream-enumerate-interval`, formed by the `cons-stream`, is[57]

```
(cons 10000
      (delay (stream-enumerate-interval 10001 1000000)))
```

That is, `stream-enumerate-interval` returns a stream represented as a pair whose `car` is 10,000 and whose `cdr` is a promise to enumerate more of the interval if so requested. This stream is now filtered for primes, using the stream analog of the `filter` procedure (Section 2.2.3):

```
(define (stream-filter pred stream)
  (cond ((stream-null? stream) the-empty-stream)
        ((pred (stream-car stream))
         (cons-stream (stream-car stream)
                      (stream-filter
                       pred
                       (stream-cdr stream))))
        (else (stream-filter pred (stream-cdr stream)))))
```

`stream-filter` tests the `stream-car` of the stream (the `car` of the pair, which is 10,000). Since this is not prime, `stream-filter` examines the `stream-cdr` of its input stream. The call to `stream-cdr` forces evaluation of the delayed `stream-enumerate-interval`, which now returns

```
(cons 10001
```

[57] The numbers shown here do not really appear in the delayed expression. What actually appears is the original expression, in an environment in which the variables are bound to the appropriate numbers. For example, `(+ low 1)` with `low` bound to 10,000 actually appears where `10001` is shown.

```
      (delay (stream-enumerate-interval 10002 1000000)))
```

`stream-filter` now looks at the `stream-car` of this stream, 10,001, sees that this is not prime either, forces another `stream-cdr`, and so on, until `stream-enumerate-interval` yields the prime 10,007, whereupon `stream-filter`, according to its definition, returns

```
(cons-stream (stream-car stream)
             (stream-filter pred (stream-cdr stream)))
```

which in this case is

```
(cons 10007
      (delay (stream-filter
              prime?
              (cons 10008
                    (delay (stream-enumerate-interval
                            10009
                            1000000))))))
```

This result is now passed to `stream-cdr` in our original expression. This forces the delayed `stream-filter`, which in turn keeps forcing the delayed `stream-enumerate-interval` until it finds the next prime, which is 10,009. Finally, the result passed to `stream-car` in our original expression is

```
(cons 10009
      (delay (stream-filter
              prime?
              (cons 10010
                    (delay (stream-enumerate-interval
                            10011
                            1000000))))))
```

`stream-car` returns 10,009, and the computation is complete. Only as many integers were tested for primality as were necessary to find the second

prime, and the interval was enumerated only as far as was necessary to feed the prime filter.

In general, we can think of delayed evaluation as "demand-driven" programming, whereby each stage in the stream process is activated only enough to satisfy the next stage. What we have done is to decouple the actual order of events in the computation from the apparent structure of our procedures. We write procedures as if the streams existed "all at once" when, in reality, the computation is performed incrementally, as in traditional programming styles.

Implementing `delay` and `force`

Although `delay` and `force` may seem like mysterious operations, their implementation is really quite straightforward. `delay` must package an expression so that it can be evaluated later on demand, and we can accomplish this simply by treating the expression as the body of a procedure. `delay` can be a special form such that

```
(delay ⟨exp⟩)
```

is syntactic sugar for

```
(lambda () ⟨exp⟩)
```

`force` simply calls the procedure (of no arguments) produced by `delay`, so we can implement `force` as a procedure:

```
(define (force delayed-object) (delayed-object))
```

This implementation suffices for `delay` and `force` to work as advertised, but there is an important optimization that we can include. In many applications, we end up forcing the same delayed object many times. This can lead to serious inefficiency in recursive programs involving streams. (See Exercise 3.57.) The solution is to build delayed objects so that the first time they are

forced, they store the value that is computed. Subsequent forcings will simply return the stored value without repeating the computation. In other words, we implement `delay` as a special-purpose memoized procedure similar to the one described in Exercise 3.27. One way to accomplish this is to use the following procedure, which takes as argument a procedure (of no arguments) and returns a memoized version of the procedure. The first time the memoized procedure is run, it saves the computed result. On subsequent evaluations, it simply returns the result.

```
(define (memo-proc proc)
  (let ((already-run? false) (result false))
    (lambda ()
      (if (not already-run?)
          (begin (set! result (proc))
                 (set! already-run? true)
                 result)
          result))))
```

`delay` is then defined so that `(delay` ⟨*exp*⟩`)` is equivalent to

`(memo-proc (lambda ()` ⟨*exp*⟩`))`

and `force` is as defined previously.[58]

> **Exercise 3.50:** Complete the following definition, which generalizes `stream-map` to allow procedures that take multiple arguments, analogous to `map` in Section 2.2.1, Footnote 12.

[58] There are many possible implementations of streams other than the one described in this section. Delayed evaluation, which is the key to making streams practical, was inherent in Algol 60's *call-by-name* parameter-passing method. The use of this mechanism to implement streams was first described by Landin (1965). Delayed evaluation for streams was introduced into Lisp by Friedman and Wise (1976). In their implementation, `cons` always delays evaluating its arguments, so that lists automatically behave as streams. The memoizing optimization is also known as *call-by-need*. The Algol community would refer to our original delayed objects as *call-by-name thunks* and to the optimized versions as *call-by-need thunks*.

```
(define (stream-map proc . argstreams)
  (if (⟨??⟩ (car argstreams))
      the-empty-stream
      (⟨??⟩
       (apply proc (map ⟨??⟩ argstreams))
       (apply stream-map
              (cons proc (map ⟨??⟩ argstreams))))))
```

Exercise 3.51: In order to take a closer look at delayed evaluation, we will use the following procedure, which simply returns its argument after printing it:

```
(define (show x)
  (display-line x)
  x)
```

What does the interpreter print in response to evaluating each expression in the following sequence?[59]

```
(define x
  (stream-map show
              (stream-enumerate-interval 0 10)))
(stream-ref x 5)
(stream-ref x 7)
```

[59] Exercises such as Exercise 3.51 and Exercise 3.52 are valuable for testing our understanding of how `delay` works. On the other hand, intermixing delayed evaluation with printing —and, even worse, with assignment—is extremely confusing, and instructors of courses on computer languages have traditionally tormented their students with examination questions such as the ones in this section. Needless to say, writing programs that depend on such subtleties is odious programming style. Part of the power of stream processing is that it lets us ignore the order in which events actually happen in our programs. Unfortunately, this is precisely what we cannot afford to do in the presence of assignment, which forces us to be concerned with time and change.

Exercise 3.52: Consider the sequence of expressions

```
(define sum 0)
(define (accum x) (set! sum (+ x sum)) sum)
(define seq
  (stream-map accum
              (stream-enumerate-interval 1 20)))
(define y (stream-filter even? seq))
(define z
  (stream-filter (lambda (x) (= (remainder x 5) 0))
                 seq))
(stream-ref y 7)
(display-stream z)
```

What is the value of `sum` after each of the above expressions is evaluated? What is the printed response to evaluating the `stream-ref` and `display-stream` expressions? Would these responses differ if we had implemented `(delay` ⟨*exp*⟩`)` simply as `(lambda () `⟨*exp*⟩`)` without using the optimization provided by `memo-proc`? Explain.

3.5.2 Infinite Streams

We have seen how to support the illusion of manipulating streams as complete entities even though, in actuality, we compute only as much of the stream as we need to access. We can exploit this technique to represent sequences efficiently as streams, even if the sequences are very long. What is more striking, we can use streams to represent sequences that are infinitely long. For instance, consider the following definition of the stream of positive integers:

```
(define (integers-starting-from n)
  (cons-stream n (integers-starting-from (+ n 1))))
(define integers (integers-starting-from 1))
```

This makes sense because `integers` will be a pair whose `car` is 1 and whose `cdr` is a promise to produce the integers beginning with 2. This is an infinitely long stream, but in any given time we can examine only a finite portion of it. Thus, our programs will never know that the entire infinite stream is not there.

Using `integers` we can define other infinite streams, such as the stream of integers that are not divisible by 7:

```
(define (divisible? x y) (= (remainder x y) 0))
(define no-sevens
  (stream-filter (lambda (x) (not (divisible? x 7)))
                 integers))
```

Then we can find integers not divisible by 7 simply by accessing elements of this stream:

```
(stream-ref no-sevens 100)
117
```

In analogy with `integers`, we can define the infinite stream of Fibonacci numbers:

```
(define (fibgen a b) (cons-stream a (fibgen b (+ a b))))
(define fibs (fibgen 0 1))
```

`fibs` is a pair whose `car` is 0 and whose `cdr` is a promise to evaluate `(fibgen 1 1)`. When we evaluate this delayed `(fibgen 1 1)`, it will produce a pair whose `car` is 1 and whose `cdr` is a promise to evaluate `(fibgen 1 2)`, and so on.

For a look at a more exciting infinite stream, we can generalize the `no-sevens` example to construct the infinite stream of prime numbers, using a method known as the *sieve of Eratosthenes*.[60] We start with the integers beginning with 2, which is the first prime. To get the rest of the primes,

[60] Eratosthenes, a third-century B.C. Alexandrian Greek philosopher, is famous for giving

we start by filtering the multiples of 2 from the rest of the integers. This leaves a stream beginning with 3, which is the next prime. Now we filter the multiples of 3 from the rest of this stream. This leaves a stream beginning with 5, which is the next prime, and so on. In other words, we construct the primes by a sieving process, described as follows: To sieve a stream `S`, form a stream whose first element is the first element of `S` and the rest of which is obtained by filtering all multiples of the first element of `S` out of the rest of `S` and sieving the result. This process is readily described in terms of stream operations:

```
(define (sieve stream)
  (cons-stream
   (stream-car stream)
   (sieve (stream-filter
           (lambda (x)
             (not (divisible? x (stream-car stream))))
           (stream-cdr stream)))))
(define primes (sieve (integers-starting-from 2)))
```

Now to find a particular prime we need only ask for it:

```
(stream-ref primes 50)
233
```

It is interesting to contemplate the signal-processing system set up by `sieve`, shown in the "Henderson diagram" in Figure 3.31.[61] The input stream feeds

---

the first accurate estimate of the circumference of the Earth, which he computed by observing shadows cast at noon on the day of the summer solstice. Eratosthenes's sieve method, although ancient, has formed the basis for special-purpose hardware "sieves" that, until recently, were the most powerful tools in existence for locating large primes. Since the 70s, however, these methods have been superseded by outgrowths of the probabilistic techniques discussed in Section 1.2.6.

[61] We have named these figures after Peter Henderson, who was the first person to show us diagrams of this sort as a way of thinking about stream processing. Each solid line represents




Figure 3.31: The prime sieve viewed as a signal-processing system.

into an "unconser" that separates the first element of the stream from the rest of the stream. The first element is used to construct a divisibility filter, through which the rest is passed, and the output of the filter is fed to another sieve box. Then the original first element is consed onto the output of the internal sieve to form the output stream. Thus, not only is the stream infinite, but the signal processor is also infinite, because the sieve contains a sieve within it.

Defining streams implicitly

The integers and fibs streams above were defined by specifying "generating" procedures that explicitly compute the stream elements one by one. An alternative way to specify streams is to take advantage of delayed evaluation to define streams implicitly. For example, the following expression defines the stream ones to be an infinite stream of ones:

```
(define ones (cons-stream 1 ones))
```

a stream of values being transmitted. The dashed line from the car to the cons and the filter indicates that this is a single value rather than a stream.

This works much like the definition of a recursive procedure: `ones` is a pair whose `car` is 1 and whose `cdr` is a promise to evaluate `ones`. Evaluating the `cdr` gives us again a 1 and a promise to evaluate `ones`, and so on.

We can do more interesting things by manipulating streams with operations such as `add-streams`, which produces the elementwise sum of two given streams:[62]

```
(define (add-streams s1 s2) (stream-map + s1 s2))
```

Now we can define the integers as follows:

```
(define integers
  (cons-stream 1 (add-streams ones integers)))
```

This defines `integers` to be a stream whose first element is 1 and the rest of which is the sum of `ones` and `integers`. Thus, the second element of `integers` is 1 plus the first element of `integers`, or 2; the third element of `integers` is 1 plus the second element of `integers`, or 3; and so on. This definition works because, at any point, enough of the `integers` stream has been generated so that we can feed it back into the definition to produce the next integer.

We can define the Fibonacci numbers in the same style:

```
(define fibs
  (cons-stream
   0
   (cons-stream 1 (add-streams (stream-cdr fibs) fibs))))
```

This definition says that `fibs` is a stream beginning with 0 and 1, such that the rest of the stream can be generated by adding `fibs` to itself shifted by one place:

```
      1  1  2  3  5  8   13  21  ...  =  (stream-cdr fibs)
```

[62] This uses the generalized version of `stream-map` from Exercise 3.50.

```
       0   1   1   2   3   5    8    13   ...   =   fibs
0   1  1   2   3   5   8   13   21   34   ...   =   fibs
```

`scale-stream` is another useful procedure in formulating such stream definitions. This multiplies each item in a stream by a given constant:

```
(define (scale-stream stream factor)
  (stream-map (lambda (x) (* x factor))
              stream))
```

For example,

```
(define double (cons-stream 1 (scale-stream double 2)))
```

produces the stream of powers of 2: 1, 2, 4, 8, 16, 32, ...

An alternate definition of the stream of primes can be given by starting with the integers and filtering them by testing for primality. We will need the first prime, 2, to get started:

```
(define primes
  (cons-stream
   2
   (stream-filter prime? (integers-starting-from 3))))
```

This definition is not so straightforward as it appears, because we will test whether a number n is prime by checking whether n is divisible by a prime (not by just any integer) less than or equal to $\sqrt{n}$:

```
(define (prime? n)
  (define (iter ps)
    (cond ((> (square (stream-car ps)) n) true)
          ((divisible? n (stream-car ps)) false)
          (else (iter (stream-cdr ps)))))
  (iter primes))
```

This is a recursive definition, since `primes` is defined in terms of the `prime?` predicate, which itself uses the `primes` stream. The reason this procedure

works is that, at any point, enough of the `primes` stream has been generated to test the primality of the numbers we need to check next. That is, for every n we test for primality, either n is not prime (in which case there is a prime already generated that divides it) or n is prime (in which case there is a prime already generated—i.e., a prime less than n—that is greater than $\sqrt{n}$).[63]

Exercise 3.53: Without running the program, describe the elements of the stream defined by

```
(define s (cons-stream 1 (add-streams s s)))
```

Exercise 3.54: Define a procedure `mul-streams`, analogous to `add-streams`, that produces the elementwise product of its two input streams. Use this together with the stream of `integers` to complete the following definition of the stream whose n^{th} element (counting from 0) is $n + 1$ factorial:

```
(define factorials
  (cons-stream 1 (mul-streams ⟨??⟩ ⟨??⟩)))
```

Exercise 3.55: Define a procedure `partial-sums` that takes as argument a stream S and returns the stream whose elements are S_0, S_0+S_1, $S_0+S_1+S_2$, ... For example, `(partial-sums integers)` should be the stream 1, 3, 6, 10, 15, ...

[63] This last point is very subtle and relies on the fact that $p_{n+1} \leq p_n^2$. (Here, p_k denotes the kth prime.) Estimates such as these are very difficult to establish. The ancient proof by Euclid that there are an infinite number of primes shows that $p_{n+1} \leq p_1 p_2 \cdots p_n + 1$, and no substantially better result was proved until 1851, when the Russian mathematician P. L. Chebyshev established that $p_{n+1} \leq 2p_n$ for all n. This result, originally conjectured in 1845, is known as *Bertrand's hypothesis*. A proof can be found in section 22.3 of Hardy and Wright 1960.

Exercise 3.56: A famous problem, first raised by R. Hamming, is to enumerate, in ascending order with no repetitions, all positive integers with no prime factors other than 2, 3, or 5. One obvious way to do this is to simply test each integer in turn to see whether it has any factors other than 2, 3, and 5. But this is very inefficient, since, as the integers get larger, fewer and fewer of them fit the requirement. As an alternative, let us call the required stream of numbers `S` and notice the following facts about it.

- `S` begins with 1.
- The elements of `(scale-stream S 2)` are also elements of `S`.
- The same is true for `(scale-stream S 3)` and `(scale-stream 5 S)`.
- These are all the elements of `S`.

Now all we have to do is combine elements from these sources. For this we define a procedure `merge` that combines two ordered streams into one ordered result stream, eliminating repetitions:

```
(define (merge s1 s2)
  (cond ((stream-null? s1) s2)
        ((stream-null? s2) s1)
        (else
         (let ((s1car (stream-car s1))
               (s2car (stream-car s2)))
           (cond ((< s1car s2car)
                  (cons-stream
                   s1car
```

```
      (merge (stream-cdr s1) s2)))
((> s1car s2car)
 (cons-stream
  s2car
  (merge s1 (stream-cdr s2))))
(else
 (cons-stream
  s1car
  (merge (stream-cdr s1)
         (stream-cdr s2)))))))))
```

Then the required stream may be constructed with `merge`, as follows:

```
(define S (cons-stream 1 (merge ⟨??⟩ ⟨??⟩)))
```

Fill in the missing expressions in the places marked ⟨??⟩ above.

Exercise 3.57: How many additions are performed when we compute the nth Fibonacci number using the definition of `fibs` based on the `add-streams` procedure? Show that the number of additions would be exponentially greater if we had implemented `(delay` ⟨*exp*⟩`)` simply as `(lambda () `⟨*exp*⟩`)`, without using the optimization provided by the `memo-proc` procedure described in Section 3.5.1.[64]

Exercise 3.58: Give an interpretation of the stream computed by the following procedure:

[64] This exercise shows how call-by-need is closely related to ordinary memoization as described in Exercise 3.27. In that exercise, we used assignment to explicitly construct a local table. Our call-by-need stream optimization effectively constructs such a table automatically, storing values in the previously forced parts of the stream.

```
(define (expand num den radix)
  (cons-stream
   (quotient (* num radix) den)
   (expand (remainder (* num radix) den) den radix)))
```

(`quotient` is a primitive that returns the integer quotient of two integers.) What are the successive elements produced by `(expand 1 7 10)`? What is produced by `(expand 3 8 10)`?

Exercise 3.59: In Section 2.5.3 we saw how to implement a polynomial arithmetic system representing polynomials as lists of terms. In a similar way, we can work with *power series*, such as

$$e^x = 1 + x + \frac{x^2}{2} + \frac{x^3}{3 \cdot 2} + \frac{x^4}{4 \cdot 3 \cdot 2} + \dots,$$

$$\cos x = 1 - \frac{x^2}{2} + \frac{x^4}{4 \cdot 3 \cdot 2} - \dots,$$

$$\sin x = x - \frac{x^3}{3 \cdot 2} + \frac{x^5}{5 \cdot 4 \cdot 3 \cdot 2} - \dots$$

represented as infinite streams. We will represent the series $a_0 + a_1 x + a_2 x^2 + a_3 x^3 + \dots$ as the stream whose elements are the coefficients a_0, a_1, a_2, a_3, ...

a. The integral of the series $a_0 + a_1 x + a_2 x^2 + a_3 x^3 + \dots$ is the series

$$c + a_0 x + \frac{1}{2} a_1 x^2 + \frac{1}{3} a_2 x^3 + \frac{1}{4} a_3 x^4 + \dots,$$

where c is any constant. Define a procedure `integrate-series` that takes as input a stream $a_0, a_1, a_2, \ldots$ representing a power series and returns the stream $a_0, \frac{1}{2}a_1, \frac{1}{3}a_2, \ldots$ of coefficients of the non-constant terms of the integral of the series. (Since the result has no constant term, it doesn't represent a power series; when we use `integrate-series`, we will `cons` on the appropriate constant.)

b. The function $x \mapsto e^x$ is its own derivative. This implies that e^x and the integral of e^x are the same series, except for the constant term, which is $e^0 = 1$. Accordingly, we can generate the series for e^x as

```
(define exp-series
  (cons-stream 1 (integrate-series exp-series)))
```

Show how to generate the series for sine and cosine, starting from the facts that the derivative of sine is cosine and the derivative of cosine is the negative of sine:

```
(define cosine-series (cons-stream 1 ⟨??⟩))
(define sine-series (cons-stream 0 ⟨??⟩))
```

Exercise 3.60: With power series represented as streams of coefficients as in Exercise 3.59, adding series is implemented by `add-streams`. Complete the definition of the following procedure for multiplying series:

```
(define (mul-series s1 s2)
  (cons-stream ⟨??⟩ (add-streams ⟨??⟩ ⟨??⟩)))
```

You can test your procedure by verifying that $\sin^2 x + \cos^2 x = 1$, using the series from Exercise 3.59.

Exercise 3.61: Let S be a power series (Exercise 3.59) whose constant term is 1. Suppose we want to find the power series $1/S$, that is, the series X such that $SX = 1$. Write $S = 1 + S_R$ where S_R is the part of S after the constant term. Then we can solve for X as follows:

$$\begin{aligned} S \cdot X &= 1, \\ (1 + S_R) \cdot X &= 1, \\ X + S_R \cdot X &= 1, \\ X &= 1 - S_R \cdot X. \end{aligned}$$

In other words, X is the power series whose constant term is 1 and whose higher-order terms are given by the negative of S_R times X. Use this idea to write a procedure `invert-unit-series` that computes $1/S$ for a power series S with constant term 1. You will need to use `mul-series` from Exercise 3.60.

Exercise 3.62: Use the results of Exercise 3.60 and Exercise 3.61 to define a procedure `div-series` that divides two power series. `div-series` should work for any two series, provided that the denominator series begins with a nonzero constant term. (If the denominator has a zero constant term, then `div-series` should signal an error.) Show how to use `div-series` together with the result of Exercise 3.59 to generate the power series for tangent.

3.5.3 Exploiting the Stream Paradigm

Streams with delayed evaluation can be a powerful modeling tool, providing many of the benefits of local state and assignment. Moreover, they avoid some

of the theoretical tangles that accompany the introduction of assignment into a programming language.

The stream approach can be illuminating because it allows us to build systems with different module boundaries than systems organized around assignment to state variables. For example, we can think of an entire time series (or signal) as a focus of interest, rather than the values of the state variables at individual moments. This makes it convenient to combine and compare components of state from different moments.

Formulating iterations as stream processes

In Section 1.2.1, we introduced iterative processes, which proceed by updating state variables. We know now that we can represent state as a "timeless" stream of values rather than as a set of variables to be updated. Let's adopt this perspective in revisiting the square-root procedure from Section 1.1.7. Recall that the idea is to generate a sequence of better and better guesses for the square root of x by applying over and over again the procedure that improves guesses:

```
(define (sqrt-improve guess x)
  (average guess (/ x guess)))
```

In our original `sqrt` procedure, we made these guesses be the successive values of a state variable. Instead we can generate the infinite stream of guesses, starting with an initial guess of 1:[65]

```
(define (sqrt-stream x)
  (define guesses
    (cons-stream
     1.0
```

[65] We can't use `let` to bind the local variable `guesses`, because the value of `guesses` depends on `guesses` itself. Exercise 3.63 addresses why we want a local variable here.

```
      (stream-map (lambda (guess) (sqrt-improve guess x))
                  guesses)))
  guesses)

(display-stream (sqrt-stream 2))
1.
1.5
1.4166666666666665
1.4142156862745097
1.4142135623746899
...
```

We can generate more and more terms of the stream to get better and better guesses. If we like, we can write a procedure that keeps generating terms until the answer is good enough. (See Exercise 3.64.)

Another iteration that we can treat in the same way is to generate an approximation to π, based upon the alternating series that we saw in Section 1.3.1:

$$\frac{\pi}{4} = 1 - \frac{1}{3} + \frac{1}{5} - \frac{1}{7} + \ldots .$$

We first generate the stream of summands of the series (the reciprocals of the odd integers, with alternating signs). Then we take the stream of sums of more and more terms (using the `partial-sums` procedure of Exercise 3.55) and scale the result by 4:

```
(define (pi-summands n)
  (cons-stream (/ 1.0 n)
               (stream-map - (pi-summands (+ n 2)))))
(define pi-stream
  (scale-stream (partial-sums (pi-summands 1)) 4))

(display-stream pi-stream)
```

```
4.
2.666666666666667
3.466666666666667
2.8952380952380956
3.3396825396825403
2.976046176046176 5
3.2837384837384844
3.017071817071818
...
```

This gives us a stream of better and better approximations to π, although the approximations converge rather slowly. Eight terms of the sequence bound the value of π between 3.284 and 3.017.

So far, our use of the stream of states approach is not much different from updating state variables. But streams give us an opportunity to do some interesting tricks. For example, we can transform a stream with a *sequence accelerator* that converts a sequence of approximations to a new sequence that converges to the same value as the original, only faster.

One such accelerator, due to the eighteenth-century Swiss mathematician Leonhard Euler, works well with sequences that are partial sums of alternating series (series of terms with alternating signs). In Euler's technique, if S_n is the nth term of the original sum sequence, then the accelerated sequence has terms

$$S_{n+1} - \frac{(S_{n+1} - S_n)^2}{S_{n-1} - 2S_n + S_{n+1}}\,.$$

Thus, if the original sequence is represented as a stream of values, the transformed sequence is given by

```
(define (euler-transform s)
  (let ((s0 (stream-ref s 0))      ;S_{n-1}
        (s1 (stream-ref s 1))      ;S_n
```

```
        (s2 (stream-ref s 2)))    ;S_{n+1}
    (cons-stream (- s2 (/ (square (- s2 s1))
                          (+ s0 (* -2 s1) s2)))
                 (euler-transform (stream-cdr s)))))
```

We can demonstrate Euler acceleration with our sequence of approximations to π:

```
(display-stream (euler-transform pi-stream))
3.166666666666667
3.1333333333333337
3.1452380952380956
3.13968253968254
3.1427128427128435
3.1408813408813416
3.142071817071818
3.1412548236077655
...
```

Even better, we can accelerate the accelerated sequence, and recursively accelerate that, and so on. Namely, we create a stream of streams (a structure we'll call a *tableau*) in which each stream is the transform of the preceding one:

```
(define (make-tableau transform s)
  (cons-stream s (make-tableau transform (transform s))))
```

The tableau has the form

$$\begin{array}{cccccc} s_{00} & s_{01} & s_{02} & s_{03} & s_{04} & \cdots \\ & s_{10} & s_{11} & s_{12} & s_{13} & \cdots \\ & & s_{20} & s_{21} & s_{22} & \cdots \\ & & & \cdots & & \end{array}$$

Finally, we form a sequence by taking the first term in each row of the tableau:

```
(define (accelerated-sequence transform s)
  (stream-map stream-car (make-tableau transform s)))
```

We can demonstrate this kind of "super-acceleration" of the π sequence:

```
(display-stream
 (accelerated-sequence euler-transform pi-stream))
4.
3.166666666666667
3.142105263157895
3.141599357319005
3.1415927140337785
3.1415926539752927
3.1415926535911765
3.141592653589778
...
```

The result is impressive. Taking eight terms of the sequence yields the correct value of π to 14 decimal places. If we had used only the original π sequence, we would need to compute on the order of 10^{13} terms (i.e., expanding the series far enough so that the individual terms are less than 10^{-13}) to get that much accuracy!

We could have implemented these acceleration techniques without using streams. But the stream formulation is particularly elegant and convenient because the entire sequence of states is available to us as a data structure that can be manipulated with a uniform set of operations.

> **Exercise 3.63:** Louis Reasoner asks why the `sqrt-stream` procedure was not written in the following more straightforward way, without the local variable `guesses`:
>
> ```
> (define (sqrt-stream x)
>   (cons-stream 1.0 (stream-map
>                     (lambda (guess)
> ```

```
                (sqrt-improve guess x))
              (sqrt-stream x))))
```

Alyssa P. Hacker replies that this version of the procedure is considerably less efficient because it performs redundant computation. Explain Alyssa's answer. Would the two versions still differ in efficiency if our implementation of `delay` used only `(lambda () ⟨exp⟩)` without using the optimization provided by `memo-proc` (Section 3.5.1)?

Exercise 3.64: Write a procedure `stream-limit` that takes as arguments a stream and a number (the tolerance). It should examine the stream until it finds two successive elements that differ in absolute value by less than the tolerance, and return the second of the two elements. Using this, we could compute square roots up to a given tolerance by

```
(define (sqrt x tolerance)
  (stream-limit (sqrt-stream x) tolerance))
```

Exercise 3.65: Use the series

$$\ln 2 = 1 - \frac{1}{2} + \frac{1}{3} - \frac{1}{4} + \dots$$

to compute three sequences of approximations to the natural logarithm of 2, in the same way we did above for π. How rapidly do these sequences converge?

Infinite streams of pairs

In Section 2.2.3, we saw how the sequence paradigm handles traditional nested loops as processes defined on sequences of pairs. If we generalize this technique to infinite streams, then we can write programs that are not easily represented as loops, because the "looping" must range over an infinite set.

For example, suppose we want to generalize the `prime-sum-pairs` procedure of Section 2.2.3 to produce the stream of pairs of *all* integers (i, j) with $i \leq j$ such that $i + j$ is prime. If `int-pairs` is the sequence of all pairs of integers (i, j) with $i \leq j$, then our required stream is simply[66]

```
(stream-filter
 (lambda (pair) (prime? (+ (car pair) (cadr pair))))
 int-pairs)
```

Our problem, then, is to produce the stream `int-pairs`. More generally, suppose we have two streams $S = (S_i)$ and $T = (T_j)$, and imagine the infinite rectangular array

$$\begin{array}{llll} (S_0, T_0) & (S_0, T_1) & (S_0, T_2) & \ldots \\ (S_1, T_0) & (S_1, T_1) & (S_1, T_2) & \ldots \\ (S_2, T_0) & (S_2, T_1) & (S_2, T_2) & \ldots \\ \ldots & & & \end{array}$$

We wish to generate a stream that contains all the pairs in the array that lie on or above the diagonal, i.e., the pairs

$$\begin{array}{llll} (S_0, T_0) & (S_0, T_1) & (S_0, T_2) & \ldots \\ & (S_1, T_1) & (S_1, T_2) & \ldots \\ & & (S_2, T_2) & \ldots \\ & & & \ldots \end{array}$$

[66] As in Section 2.2.3, we represent a pair of integers as a list rather than a Lisp pair.

(If we take both S and T to be the stream of integers, then this will be our desired stream `int-pairs`.)

Call the general stream of pairs `(pairs S T)`, and consider it to be composed of three parts: the pair (S_0, T_0), the rest of the pairs in the first row, and the remaining pairs:[67]

(S_0, T_0)	(S_0, T_1)	(S_0, T_2)	$\ldots$
	(S_1, T_1)	(S_1, T_2)	$\ldots$
		(S_2, T_2)	$\ldots$
			$\ldots$

Observe that the third piece in this decomposition (pairs that are not in the first row) is (recursively) the pairs formed from `(stream-cdr S)` and `(stream-cdr T)`. Also note that the second piece (the rest of the first row) is

```
(stream-map (lambda (x) (list (stream-car s) x))
            (stream-cdr t))
```

Thus we can form our stream of pairs as follows:

```
(define (pairs s t)
  (cons-stream
   (list (stream-car s) (stream-car t))
   (⟨combine-in-some-way⟩
     (stream-map (lambda (x) (list (stream-car s) x))
                 (stream-cdr t))
     (pairs (stream-cdr s) (stream-cdr t)))))
```

In order to complete the procedure, we must choose some way to combine the two inner streams. One idea is to use the stream analog of the `append` procedure from Section 2.2.1:

[67] See Exercise 3.68 for some insight into why we chose this decomposition.

```
(define (stream-append s1 s2)
  (if (stream-null? s1)
      s2
      (cons-stream (stream-car s1)
                   (stream-append (stream-cdr s1) s2))))
```

This is unsuitable for infinite streams, however, because it takes all the elements from the first stream before incorporating the second stream. In particular, if we try to generate all pairs of positive integers using

```
(pairs integers integers)
```

our stream of results will first try to run through all pairs with the first integer equal to 1, and hence will never produce pairs with any other value of the first integer.

To handle infinite streams, we need to devise an order of combination that ensures that every element will eventually be reached if we let our program run long enough. An elegant way to accomplish this is with the following `interleave` procedure:[68]

```
(define (interleave s1 s2)
  (if (stream-null? s1)
      s2
      (cons-stream (stream-car s1)
                   (interleave s2 (stream-cdr s1)))))
```

Since `interleave` takes elements alternately from the two streams, every element of the second stream will eventually find its way into the interleaved stream, even if the first stream is infinite.

[68] The precise statement of the required property on the order of combination is as follows: There should be a function f of two arguments such that the pair corresponding to element i of the first stream and element j of the second stream will appear as element number $f(i, j)$ of the output stream. The trick of using `interleave` to accomplish this was shown to us by David Turner, who employed it in the language KRC (Turner 1981).

We can thus generate the required stream of pairs as

```
(define (pairs s t)
  (cons-stream
   (list (stream-car s) (stream-car t))
   (interleave
    (stream-map (lambda (x) (list (stream-car s) x))
                (stream-cdr t))
    (pairs (stream-cdr s) (stream-cdr t)))))
```

Exercise 3.66: Examine the stream `(pairs integers integers)`. Can you make any general comments about the order in which the pairs are placed into the stream? For example, approximately how many pairs precede the pair (1, 100)? the pair (99, 100)? the pair (100, 100)? (If you can make precise mathematical statements here, all the better. But feel free to give more qualitative answers if you find yourself getting bogged down.)

Exercise 3.67: Modify the `pairs` procedure so that `(pairs integers integers)` will produce the stream of *all* pairs of integers (i, j) (without the condition $i \leq j$). Hint: You will need to mix in an additional stream.

Exercise 3.68: Louis Reasoner thinks that building a stream of pairs from three parts is unnecessarily complicated. Instead of separating the pair (S_0, T_0) from the rest of the pairs in the first row, he proposes to work with the whole first row, as follows:

```
(define (pairs s t)
  (interleave
   (stream-map (lambda (x) (list (stream-car s) x))
               t)
   (pairs (stream-cdr s) (stream-cdr t))))
```

Does this work? Consider what happens if we evaluate `(pairs integers integers)` using Louis's definition of `pairs`.

Exercise 3.69: Write a procedure `triples` that takes three infinite streams, S, T, and U, and produces the stream of triples (S_i, T_j, U_k) such that $i \leq j \leq k$. Use `triples` to generate the stream of all Pythagorean triples of positive integers, i.e., the triples (i, j, k) such that $i \leq j$ and $i^2 + j^2 = k^2$.

Exercise 3.70: It would be nice to be able to generate streams in which the pairs appear in some useful order, rather than in the order that results from an *ad hoc* interleaving process. We can use a technique similar to the `merge` procedure of Exercise 3.56, if we define a way to say that one pair of integers is "less than" another. One way to do this is to define a "weighting function" $W(i, j)$ and stipulate that (i_1, j_1) is less than (i_2, j_2) if $W(i_1, j_1) < W(i_2, j_2)$. Write a procedure `merge-weighted` that is like `merge`, except that `merge-weighted` takes an additional argument `weight`, which is a procedure that computes the weight of a pair, and is used to determine the order in which elements should appear in the resulting merged stream.[69] Using this, generalize `pairs` to a procedure `weighted-pairs` that takes two streams, together with a procedure that computes a weighting function, and generates the stream of pairs, ordered according to weight. Use your procedure to generate

a. the stream of all pairs of positive integers (i, j) with $i \leq j$ ordered according to the sum $i + j$,

[69] We will require that the weighting function be such that the weight of a pair increases as we move out along a row or down along a column of the array of pairs.

b. the stream of all pairs of positive integers (i, j) with $i \leq j$, where neither i nor j is divisible by 2, 3, or 5, and the pairs are ordered according to the sum $2i + 3j + 5ij$.

Exercise 3.71: Numbers that can be expressed as the sum of two cubes in more than one way are sometimes called *Ramanujan numbers*, in honor of the mathematician Srinivasa Ramanujan.[70] Ordered streams of pairs provide an elegant solution to the problem of computing these numbers. To find a number that can be written as the sum of two cubes in two different ways, we need only generate the stream of pairs of integers (i, j) weighted according to the sum $i^3 + j^3$ (see Exercise 3.70), then search the stream for two consecutive pairs with the same weight. Write a procedure to generate the Ramanujan numbers. The first such number is 1,729. What are the next five?

Exercise 3.72: In a similar way to Exercise 3.71 generate a stream of all numbers that can be written as the sum of two squares in three different ways (showing how they can be so written).

Streams as signals

We began our discussion of streams by describing them as computational analogs of the "signals" in signal-processing systems. In fact, we can use

[70] To quote from G. H. Hardy's obituary of Ramanujan (Hardy 1921): "It was Mr. Littlewood (I believe) who remarked that 'every positive integer was one of his friends.' I remember once going to see him when he was lying ill at Putney. I had ridden in taxi-cab No. 1729, and remarked that the number seemed to me a rather dull one, and that I hoped it was not an unfavorable omen. 'No,' he replied, 'it is a very interesting number; it is the smallest number expressible as the sum of two cubes in two different ways.' " The trick of using weighted pairs to generate the Ramanujan numbers was shown to us by Charles Leiserson.

streams to model signal-processing systems in a very direct way, representing the values of a signal at successive time intervals as consecutive elements of a stream. For instance, we can implement an *integrator* or *summer* that, for an input stream $x = (x_i)$, an initial value C, and a small increment dt, accumulates the sum

$$S_i = C + \sum_{j=1}^{i} x_j \, dt$$

and returns the stream of values $S = (S_i)$. The following `integral` procedure is reminiscent of the "implicit style" definition of the stream of integers (Section 3.5.2):

```
(define (integral integrand initial-value dt)
  (define int
    (cons-stream initial-value
                 (add-streams (scale-stream integrand dt)
                              int)))
  int)
```

Figure 3.32 is a picture of a signal-processing system that corresponds to the `integral` procedure. The input stream is scaled by dt and passed through an adder, whose output is passed back through the same adder. The self-reference in the definition of `int` is reflected in the figure by the feedback loop that connects the output of the adder to one of the inputs.

> **Exercise 3.73:** We can model electrical circuits using streams to represent the values of currents or voltages at a sequence of times. For instance, suppose we have an *RC circuit* consisting of a resistor of resistance R and a capacitor of capacitance C in series. The voltage response v of the circuit to an injected




Figure 3.32: The `integral` procedure viewed as a signal-processing system.

current i is determined by the formula in Figure 3.33, whose structure is shown by the accompanying signal-flow diagram.

Write a procedure `RC` that models this circuit. `RC` should take as inputs the values of R, C, and dt and should return a procedure that takes as inputs a stream representing the current i and an initial value for the capacitor voltage v_0 and produces as output the stream of voltages v. For example, you should be able to use `RC` to model an RC circuit with R = 5 ohms, C = 1 farad, and a 0.5-second time step by evaluating `(define RC1 (RC 5 1 0.5))`. This defines `RC1` as a procedure that takes a stream representing the time sequence of currents and an initial capacitor voltage and produces the output stream of voltages.

Exercise 3.74: Alyssa P. Hacker is designing a system to process signals coming from physical sensors. One important feature she wishes to produce is a signal that describes the *zero crossings* of the input signal. That is, the resulting signal should be $+1$ whenever the input signal changes from negative to positive, -1 whenever the input signal changes from positive to negative, and




Figure 3.33: An RC circuit and the associated signal-flow diagram.

0 otherwise. (Assume that the sign of a 0 input is positive.) For example, a typical input signal with its associated zero-crossing signal would be

```
... 1 2 1.5 1 0.5 -0.1 -2 -3 -2 -0.5 0.2 3 4 ...
... 0 0  0  0  0   -1   0  0  0   0   1  0 0 ...
```

In Alyssa's system, the signal from the sensor is represented as a stream `sense-data` and the stream `zero-crossings` is the corresponding stream of zero crossings. Alyssa first writes a procedure `sign-change-detector` that takes two values as arguments and compares the signs of the values to produce an appropriate 0, 1, or - 1. She then constructs her zero-crossing stream as follows:

```
(define (make-zero-crossings input-stream last-value)
  (cons-stream
   (sign-change-detector
```

```
     (stream-car input-stream)
     last-value)
    (make-zero-crossings
     (stream-cdr input-stream)
     (stream-car input-stream))))
(define zero-crossings
  (make-zero-crossings sense-data 0))
```

Alyssa's boss, Eva Lu Ator, walks by and suggests that this program is approximately equivalent to the following one, which uses the generalized version of `stream-map` from Exercise 3.50:

```
(define zero-crossings
  (stream-map sign-change-detector
              sense-data
              ⟨expression⟩))
```

Complete the program by supplying the indicated ⟨*expression*⟩.

Exercise 3.75: Unfortunately, Alyssa's zero-crossing detector in Exercise 3.74 proves to be insufficient, because the noisy signal from the sensor leads to spurious zero crossings. Lem E. Tweakit, a hardware specialist, suggests that Alyssa smooth the signal to filter out the noise before extracting the zero crossings. Alyssa takes his advice and decides to extract the zero crossings from the signal constructed by averaging each value of the sense data with the previous value. She explains the problem to her assistant, Louis Reasoner, who attempts to implement the idea, altering Alyssa's program as follows:

```
(define (make-zero-crossings input-stream last-value)
  (let ((avpt (/ (+ (stream-car input-stream)
```

```
                  last-value)
               2)))
    (cons-stream
     (sign-change-detector avpt last-value)
     (make-zero-crossings
      (stream-cdr input-stream) avpt))))
```

This does not correctly implement Alyssa's plan. Find the bug that Louis has installed and fix it without changing the structure of the program. (Hint: You will need to increase the number of arguments to `make-zero-crossings`.)

Exercise 3.76: Eva Lu Ator has a criticism of Louis's approach in Exercise 3.75. The program he wrote is not modular, because it intermixes the operation of smoothing with the zero-crossing extraction. For example, the extractor should not have to be changed if Alyssa finds a better way to condition her input signal. Help Louis by writing a procedure `smooth` that takes a stream as input and produces a stream in which each element is the average of two successive input stream elements. Then use `smooth` as a component to implement the zero-crossing detector in a more modular style.

3.5.4 Streams and Delayed Evaluation

The `integral` procedure at the end of the preceding section shows how we can use streams to model signal-processing systems that contain feedback loops. The feedback loop for the adder shown in Figure 3.32 is modeled by the fact that `integral`'s internal stream `int` is defined in terms of itself:

```
(define int
  (cons-stream
```




Figure 3.34: An "analog computer circuit" that solves the equation $dy/dt = f(y)$.

```
initial-value
(add-streams (scale-stream integrand dt)
             int)))
```

The interpreter's ability to deal with such an implicit definition depends on the `delay` that is incorporated into `cons-stream`. Without this `delay`, the interpreter could not construct `int` before evaluating both arguments to `cons-stream`, which would require that `int` already be defined. In general, `delay` is crucial for using streams to model signal-processing systems that contain loops. Without `delay`, our models would have to be formulated so that the inputs to any signal-processing component would be fully evaluated before the output could be produced. This would outlaw loops.

Unfortunately, stream models of systems with loops may require uses of `delay` beyond the "hidden" `delay` supplied by `cons-stream`. For instance, Figure 3.34 shows a signal-processing system for solving the differential equation $dy/dt = f(y)$ where f is a given function. The figure shows a mapping component, which applies f to its input signal, linked in a feedback loop to an integrator in a manner very similar to that of the analog computer circuits that are actually used to solve such equations.

Assuming we are given an initial value y_0 for y, we could try to model

this system using the procedure

```
(define (solve f y0 dt)
  (define y (integral dy y0 dt))
  (define dy (stream-map f y))
  y)
```

This procedure does not work, because in the first line of `solve` the call to `integral` requires that the input `dy` be defined, which does not happen until the second line of `solve`.

On the other hand, the intent of our definition does make sense, because we can, in principle, begin to generate the `y` stream without knowing `dy`. Indeed, `integral` and many other stream operations have properties similar to those of `cons-stream`, in that we can generate part of the answer given only partial information about the arguments. For `integral`, the first element of the output stream is the specified `initial-value`. Thus, we can generate the first element of the output stream without evaluating the integrand `dy`. Once we know the first element of `y`, the `stream-map` in the second line of `solve` can begin working to generate the first element of `dy`, which will produce the next element of `y`, and so on.

To take advantage of this idea, we will redefine `integral` to expect the integrand stream to be a *delayed argument*. `integral` will `force` the integrand to be evaluated only when it is required to generate more than the first element of the output stream:

```
(define (integral delayed-integrand initial-value dt)
  (define int
    (cons-stream
     initial-value
     (let ((integrand (force delayed-integrand)))
       (add-streams (scale-stream integrand dt) int))))
  int)
```

Now we can implement our `solve` procedure by delaying the evaluation of `dy` in the definition of `y`:[71]

```
(define (solve f y0 dt)
  (define y (integral (delay dy) y0 dt))
  (define dy (stream-map f y))
  y)
```

In general, every caller of `integral` must now `delay` the integrand argument. We can demonstrate that the `solve` procedure works by approximating $e \approx 2.718$ by computing the value at $y = 1$ of the solution to the differential equation $dy/dt = y$ with initial condition $y(0) = 1$:

```
(stream-ref (solve (lambda (y) y)
                   1
                   0.001)
            1000)
2.716924
```

> **Exercise 3.77:** The `integral` procedure used above was analogous to the "implicit" definition of the infinite stream of integers in Section 3.5.2. Alternatively, we can give a definition of `integral` that is more like `integers-starting-from` (also in Section 3.5.2):
>
> ```
> (define (integral integrand initial-value dt)
>   (cons-stream
>    initial-value
>    (if (stream-null? integrand)
>        the-empty-stream
> ```

[71] This procedure is not guaranteed to work in all Scheme implementations, although for any implementation there is a simple variation that will work. The problem has to do with subtle differences in the ways that Scheme implementations handle internal definitions. (See Section 4.1.6.)




Figure 3.35: Signal-flow diagram for the solution to a second-order linear differential equation.

```
(integral (stream-cdr integrand)
          (+ (* dt (stream-car integrand))
             initial-value)
          dt))))
```

When used in systems with loops, this procedure has the same problem as does our original version of `integral`. Modify the procedure so that it expects the `integrand` as a delayed argument and hence can be used in the `solve` procedure shown above.

Exercise 3.78: Consider the problem of designing a signal-processing system to study the homogeneous second-order linear differential equation




Figure 3.36: A series RLC circuit.

$$\frac{d^2y}{dt^2} - a\frac{dy}{dt} - by = 0.$$

The output stream, modeling y, is generated by a network that contains a loop. This is because the value of d^2y/dt^2 depends upon the values of y and dy/dt and both of these are determined by integrating d^2y/dt^2. The diagram we would like to encode is shown in Figure 3.35. Write a procedure `solve-2nd` that takes as arguments the constants a, b, and dt and the initial values y_0 and dy_0 for y and dy/dt and generates the stream of successive values of y.

Exercise 3.79: Generalize the `solve-2nd` procedure of Exercise 3.78 so that it can be used to solve general second-order differential equations $d^2y/dt^2 = f(dy/dt, y)$.

Exercise 3.80: A *series RLC circuit* consists of a resistor, a capacitor, and an inductor connected in series, as shown in Figure

3.36. If R, L, and C are the resistance, inductance, and capacitance, then the relations between voltage (v) and current (i) for the three components are described by the equations

$$v_R = i_R R, \qquad v_L = L\frac{di_L}{dt}, \qquad i_C = C\frac{dv_C}{dt},$$

and the circuit connections dictate the relations

$$i_R = i_L = -i_C, \qquad v_C = v_L + v_R.$$

Combining these equations shows that the state of the circuit (summarized by v_C, the voltage across the capacitor, and i_L, the current in the inductor) is described by the pair of differential equations

$$\frac{dv_C}{dt} = -\frac{i_L}{C}, \qquad \frac{di_L}{dt} = \frac{1}{L}v_C - \frac{R}{L}i_L.$$

The signal-flow diagram representing this system of differential equations is shown in Figure 3.37.

Write a procedure `RLC` that takes as arguments the parameters R, L, and C of the circuit and the time increment dt. In a manner similar to that of the `RC` procedure of Exercise 3.73, `RLC` should produce a procedure that takes the initial values of the state variables, v_{C_0} and i_{L_0}, and produces a pair (using `cons`) of the streams of states v_C and i_L. Using `RLC`, generate the pair of streams that models the behavior of a series RLC circuit with R = 1 ohm, C = 0.2 farad, L = 1 henry, dt = 0.1 second, and initial values i_{L_0} = 0 amps and v_{C_0} = 10 volts.




Figure 3.37: A signal-flow diagram for the solution to a series RLC circuit.

Normal-order evaluation

The examples in this section illustrate how the explicit use of `delay` and `force` provides great programming flexibility, but the same examples also show how this can make our programs more complex. Our new `integral` procedure, for instance, gives us the power to model systems with loops, but we must now remember that `integral` should be called with a delayed integrand, and every procedure that uses `integral` must be aware of this. In effect, we have created two classes of procedures: ordinary procedures and

procedures that take delayed arguments. In general, creating separate classes of procedures forces us to create separate classes of higher-order procedures as well.[72]

One way to avoid the need for two different classes of procedures is to make all procedures take delayed arguments. We could adopt a model of evaluation in which all arguments to procedures are automatically delayed and arguments are forced only when they are actually needed (for example, when they are required by a primitive operation). This would transform our language to use normal-order evaluation, which we first described when we introduced the substitution model for evaluation in Section 1.1.5. Converting to normal-order evaluation provides a uniform and elegant way to simplify the use of delayed evaluation, and this would be a natural strategy to adopt if we were concerned only with stream processing. In Section 4.2, after we have studied the evaluator, we will see how to transform our language in just this way. Unfortunately, including delays in procedure calls wreaks havoc with our ability to design programs that depend on the order of events, such as programs that use assignment, mutate data, or perform input or output. Even the

[72]This is a small reflection, in Lisp, of the difficulties that conventional strongly typed languages such as Pascal have in coping with higher-order procedures. In such languages, the programmer must specify the data types of the arguments and the result of each procedure: number, logical value, sequence, and so on. Consequently, we could not express an abstraction such as "map a given procedure `proc` over all the elements in a sequence" by a single higher-order procedure such as `stream-map`. Rather, we would need a different mapping procedure for each different combination of argument and result data types that might be specified for a `proc`. Maintaining a practical notion of "data type" in the presence of higher-order procedures raises many difficult issues. One way of dealing with this problem is illustrated by the language ML (Gordon et al. 1979), whose "polymorphic data types" include templates for higher-order transformations between data types. Moreover, data types for most procedures in ML are never explicitly declared by the programmer. Instead, ML includes a *type-inferencing* mechanism that uses information in the environment to deduce the data types for newly defined procedures.

single `delay` in `cons-stream` can cause great confusion, as illustrated by Exercise 3.51 and Exercise 3.52. As far as anyone knows, mutability and delayed evaluation do not mix well in programming languages, and devising ways to deal with both of these at once is an active area of research.

3.5.5 Modularity of Functional Programs and Modularity of Objects

As we saw in Section 3.1.2, one of the major benefits of introducing assignment is that we can increase the modularity of our systems by encapsulating, or "hiding," parts of the state of a large system within local variables. Stream models can provide an equivalent modularity without the use of assignment. As an illustration, we can reimplement the Monte Carlo estimation of π, which we examined in Section 3.1.2, from a stream-processing point of view.

The key modularity issue was that we wished to hide the internal state of a random-number generator from programs that used random numbers. We began with a procedure `rand-update`, whose successive values furnished our supply of random numbers, and used this to produce a random-number generator:

```
(define rand
  (let ((x random-init))
    (lambda ()
      (set! x (rand-update x))
      x)))
```

In the stream formulation there is no random-number generator *per se*, just a stream of random numbers produced by successive calls to `rand-update`:

```
(define random-numbers
  (cons-stream
   random-init
```

```
   (stream-map rand-update random-numbers)))
```

We use this to construct the stream of outcomes of the Cesàro experiment performed on consecutive pairs in the `random-numbers` stream:

```
(define cesaro-stream
  (map-successive-pairs
   (lambda (r1 r2) (= (gcd r1 r2) 1))
   random-numbers))
(define (map-successive-pairs f s)
  (cons-stream
   (f (stream-car s) (stream-car (stream-cdr s)))
   (map-successive-pairs f (stream-cdr (stream-cdr s)))))
```

The `cesaro-stream` is now fed to a `monte-carlo` procedure, which produces a stream of estimates of probabilities. The results are then converted into a stream of estimates of π. This version of the program doesn't need a parameter telling how many trials to perform. Better estimates of π (from performing more experiments) are obtained by looking farther into the `pi` stream:

```
(define (monte-carlo experiment-stream passed failed)
  (define (next passed failed)
    (cons-stream
     (/ passed (+ passed failed))
     (monte-carlo
      (stream-cdr experiment-stream) passed failed)))
  (if (stream-car experiment-stream)
      (next (+ passed 1) failed)
      (next passed (+ failed 1))))
(define pi
  (stream-map
   (lambda (p) (sqrt (/ 6 p)))
   (monte-carlo cesaro-stream 0 0)))
```

There is considerable modularity in this approach, because we still can formulate a general `monte-carlo` procedure that can deal with arbitrary experiments. Yet there is no assignment or local state.

> **Exercise 3.81:** Exercise 3.6 discussed generalizing the random-number generator to allow one to reset the random-number sequence so as to produce repeatable sequences of "random" numbers. Produce a stream formulation of this same generator that operates on an input stream of requests to `generate` a new random number or to `reset` the sequence to a specified value and that produces the desired stream of random numbers. Don't use assignment in your solution.

> **Exercise 3.82:** Redo Exercise 3.5 on Monte Carlo integration in terms of streams. The stream version of `estimate-integral` will not have an argument telling how many trials to perform. Instead, it will produce a stream of estimates based on successively more trials.

A functional-programming view of time

Let us now return to the issues of objects and state that were raised at the beginning of this chapter and examine them in a new light. We introduced assignment and mutable objects to provide a mechanism for modular construction of programs that model systems with state. We constructed computational objects with local state variables and used assignment to modify these variables. We modeled the temporal behavior of the objects in the world by the temporal behavior of the corresponding computational objects.

Now we have seen that streams provide an alternative way to model objects with local state. We can model a changing quantity, such as the local

state of some object, using a stream that represents the time history of successive states. In essence, we represent time explicitly, using streams, so that we decouple time in our simulated world from the sequence of events that take place during evaluation. Indeed, because of the presence of `delay` there may be little relation between simulated time in the model and the order of events during the evaluation.

In order to contrast these two approaches to modeling, let us reconsider the implementation of a "withdrawal processor" that monitors the balance in a bank account. In Section 3.1.3 we implemented a simplified version of such a processor:

```
(define (make-simplified-withdraw balance)
  (lambda (amount)
    (set! balance (- balance amount))
    balance))
```

Calls to `make-simplified-withdraw` produce computational objects, each with a local state variable `balance` that is decremented by successive calls to the object. The object takes an `amount` as an argument and returns the new balance. We can imagine the user of a bank account typing a sequence of inputs to such an object and observing the sequence of returned values shown on a display screen.

Alternatively, we can model a withdrawal processor as a procedure that takes as input a balance and a stream of amounts to withdraw and produces the stream of successive balances in the account:

```
(define (stream-withdraw balance amount-stream)
  (cons-stream
   balance
   (stream-withdraw (- balance (stream-car amount-stream))
                    (stream-cdr amount-stream))))
```

`stream-withdraw` implements a well-defined mathematical function whose output is fully determined by its input. Suppose, however, that the input `amount-stream` is the stream of successive values typed by the user and that the resulting stream of balances is displayed. Then, from the perspective of the user who is typing values and watching results, the stream process has the same behavior as the object created by `make-simplified-withdraw`. However, with the stream version, there is no assignment, no local state variable, and consequently none of the theoretical difficulties that we encountered in Section 3.1.3. Yet the system has state!

This is really remarkable. Even though `stream-withdraw` implements a well-defined mathematical function whose behavior does not change, the user's perception here is one of interacting with a system that has a changing state. One way to resolve this paradox is to realize that it is the user's temporal existence that imposes state on the system. If the user could step back from the interaction and think in terms of streams of balances rather than individual transactions, the system would appear stateless.[73]

From the point of view of one part of a complex process, the other parts appear to change with time. They have hidden time-varying local state. If we wish to write programs that model this kind of natural decomposition in our world (as we see it from our viewpoint as a part of that world) with structures in our computer, we make computational objects that are not functional—they must change with time. We model state with local state variables, and we model the changes of state with assignments to those variables. By doing this we make the time of execution of a computation model time in the world that we are part of, and thus we get "objects" in our computer.

Modeling with objects is powerful and intuitive, largely because this matches

[73] Similarly in physics, when we observe a moving particle, we say that the position (state) of the particle is changing. However, from the perspective of the particle's world line in space-time there is no change involved.

the perception of interacting with a world of which we are part. However, as we've seen repeatedly throughout this chapter, these models raise thorny problems of constraining the order of events and of synchronizing multiple processes. The possibility of avoiding these problems has stimulated the development of *functional programming languages*, which do not include any provision for assignment or mutable data. In such a language, all procedures implement well-defined mathematical functions of their arguments, whose behavior does not change. The functional approach is extremely attractive for dealing with concurrent systems.[74]

On the other hand, if we look closely, we can see time-related problems creeping into functional models as well. One particularly troublesome area arises when we wish to design interactive systems, especially ones that model interactions between independent entities. For instance, consider once more the implementation a banking system that permits joint bank accounts. In a conventional system using assignment and objects, we would model the fact that Peter and Paul share an account by having both Peter and Paul send their transaction requests to the same bank-account object, as we saw in Section 3.1.3. From the stream point of view, where there are no "objects" *per se*, we have already indicated that a bank account can be modeled as a process that operates on a stream of transaction requests to produce a stream of responses. Accordingly, we could model the fact that Peter and Paul have a joint bank account by merging Peter's stream of transaction requests with Paul's stream of requests and feeding the result to the bank-account stream process, as shown in Figure 3.38.

The trouble with this formulation is in the notion of *merge*. It will not do to

[74] John Backus, the inventor of Fortran, gave high visibility to functional programming when he was awarded the ACM Turing award in 1978. His acceptance speech (Backus 1978) strongly advocated the functional approach. A good overview of functional programming is given in Henderson 1980 and in Darlington et al. 1982.




Figure 3.38: A joint bank account, modeled by merging two streams of transaction requests.

merge the two streams by simply taking alternately one request from Peter and one request from Paul. Suppose Paul accesses the account only very rarely. We could hardly force Peter to wait for Paul to access the account before he could issue a second transaction. However such a merge is implemented, it must interleave the two transaction streams in some way that is constrained by "real time" as perceived by Peter and Paul, in the sense that, if Peter and Paul meet, they can agree that certain transactions were processed before the meeting, and other transactions were processed after the meeting.[75] This is precisely the same constraint that we had to deal with in Section 3.4.1, where we found the need to introduce explicit synchronization to ensure a "correct" order of events in concurrent processing of objects with state. Thus, in an attempt to support the functional style, the need to merge inputs from different agents reintroduces the same problems that the functional style was meant to eliminate.

We began this chapter with the goal of building computational models whose structure matches our perception of the real world we are trying to

[75] Observe that, for any two streams, there is in general more than one acceptable order of interleaving. Thus, technically, "merge" is a relation rather than a function—the answer is not a deterministic function of the inputs. We already mentioned (Footnote 39) that nondeterminism is essential when dealing with concurrency. The merge relation illustrates the same essential nondeterminism, from the functional perspective. In Section 4.3, we will look at nondeterminism from yet another point of view.

model. We can model the world as a collection of separate, time-bound, interacting objects with state, or we can model the world as a single, timeless, stateless unity. Each view has powerful advantages, but neither view alone is completely satisfactory. A grand unification has yet to emerge.[76]

[76]The object model approximates the world by dividing it into separate pieces. The functional model does not modularize along object boundaries. The object model is useful when the unshared state of the "objects" is much larger than the state that they share. An example of a place where the object viewpoint fails is quantum mechanics, where thinking of things as individual particles leads to paradoxes and confusions. Unifying the object view with the functional view may have little to do with programming, but rather with fundamental epistemological issues.

4

Metalinguistic Abstraction

> . . . It's in words that the magic is—Abracadabra, Open Sesame, and the rest—but the magic words in one story aren't magical in the next. The real magic is to understand which words work, and when, and for what; the trick is to learn the trick.
>
> . . . And those words are made from the letters of our alphabet: a couple-dozen squiggles we can draw with the pen. This is the key! And the treasure, too, if we can only get our hands on it! It's as if—as if the key to the treasure *is* the treasure!
>
> —John Barth, *Chimera*

In our study of program design, we have seen that expert programmers control the complexity of their designs with the same general techniques used by designers of all complex systems. They combine primitive elements to form compound objects, they abstract compound objects to form higher-level building blocks, and they preserve modularity by adopting appropriate large-scale views of system structure. In illustrating these techniques, we have

used Lisp as a language for describing processes and for constructing computational data objects and processes to model complex phenomena in the real world. However, as we confront increasingly complex problems, we will find that Lisp, or indeed any fixed programming language, is not sufficient for our needs. We must constantly turn to new languages in order to express our ideas more effectively. Establishing new languages is a powerful strategy for controlling complexity in engineering design; we can often enhance our ability to deal with a complex problem by adopting a new language that enables us to describe (and hence to think about) the problem in a different way, using primitives, means of combination, and means of abstraction that are particularly well suited to the problem at hand.[1]

Programming is endowed with a multitude of languages. There are physical languages, such as the machine languages for particular computers. These languages are concerned with the representation of data and control in terms of individual bits of storage and primitive machine instructions. The machine-language programmer is concerned with using the given hardware to erect sys-

[1]The same idea is pervasive throughout all of engineering. For example, electrical engineers use many different languages for describing circuits. Two of these are the language of electrical *networks* and the language of electrical *systems*. The network language emphasizes the physical modeling of devices in terms of discrete electrical elements. The primitive objects of the network language are primitive electrical components such as resistors, capacitors, inductors, and transistors, which are characterized in terms of physical variables called voltage and current. When describing circuits in the network language, the engineer is concerned with the physical characteristics of a design. In contrast, the primitive objects of the system language are signal-processing modules such as filters and amplifiers. Only the functional behavior of the modules is relevant, and signals are manipulated without concern for their physical realization as voltages and currents. The system language is erected on the network language, in the sense that the elements of signal-processing systems are constructed from electrical networks. Here, however, the concerns are with the large-scale organization of electrical devices to solve a given application problem; the physical feasibility of the parts is assumed. This layered collection of languages is another example of the stratified design technique illustrated by the picture language of Section 2.2.4.

tems and utilities for the efficient implementation of resource-limited computations. High-level languages, erected on a machine-language substrate, hide concerns about the representation of data as collections of bits and the representation of programs as sequences of primitive instructions. These languages have means of combination and abstraction, such as procedure definition, that are appropriate to the larger-scale organization of systems.

Metalinguistic abstraction—establishing new languages—plays an important role in all branches of engineering design. It is particularly important to computer programming, because in programming not only can we formulate new languages but we can also implement these languages by constructing evaluators. An *evaluator* (or *interpreter*) for a programming language is a procedure that, when applied to an expression of the language, performs the actions required to evaluate that expression.

It is no exaggeration to regard this as the most fundamental idea in programming:

> The evaluator, which determines the meaning of expressions in a programming language, is just another program.

To appreciate this point is to change our images of ourselves as programmers. We come to see ourselves as designers of languages, rather than only users of languages designed by others.

In fact, we can regard almost any program as the evaluator for some language. For instance, the polynomial manipulation system of Section 2.5.3 embodies the rules of polynomial arithmetic and implements them in terms of operations on list-structured data. If we augment this system with procedures to read and print polynomial expressions, we have the core of a special-purpose language for dealing with problems in symbolic mathematics. The digital-logic simulator of Section 3.3.4 and the constraint propagator of Section 3.3.5 are legitimate languages in their own right, each with its own prim-

itives, means of combination, and means of abstraction. Seen from this perspective, the technology for coping with large-scale computer systems merges with the technology for building new computer languages, and computer science itself becomes no more (and no less) than the discipline of constructing appropriate descriptive languages.

We now embark on a tour of the technology by which languages are established in terms of other languages. In this chapter we shall use Lisp as a base, implementing evaluators as Lisp procedures. Lisp is particularly well suited to this task, because of its ability to represent and manipulate symbolic expressions. We will take the first step in understanding how languages are implemented by building an evaluator for Lisp itself. The language implemented by our evaluator will be a subset of the Scheme dialect of Lisp that we use in this book. Although the evaluator described in this chapter is written for a particular dialect of Lisp, it contains the essential structure of an evaluator for any expression-oriented language designed for writing programs for a sequential machine. (In fact, most language processors contain, deep within them, a little "Lisp" evaluator.) The evaluator has been simplified for the purposes of illustration and discussion, and some features have been left out that would be important to include in a production-quality Lisp system. Nevertheless, this simple evaluator is adequate to execute most of the programs in this book.[2]

An important advantage of making the evaluator accessible as a Lisp program is that we can implement alternative evaluation rules by describing these as modifications to the evaluator program. One place where we can use this power to good effect is to gain extra control over the ways in which compu-

[2]The most important features that our evaluator leaves out are mechanisms for handling errors and supporting debugging. For a more extensive discussion of evaluators, see Friedman et al. 1992, which gives an exposition of programming languages that proceeds via a sequence of evaluators written in Scheme.

tational models embody the notion of time, which was so central to the discussion in Chapter 3. There, we mitigated some of the complexities of state and assignment by using streams to decouple the representation of time in the world from time in the computer. Our stream programs, however, were sometimes cumbersome, because they were constrained by the applicative-order evaluation of Scheme. In Section 4.2, we'll change the underlying language to provide for a more elegant approach, by modifying the evaluator to provide for *normal-order evaluation*.

Section 4.3 implements a more ambitious linguistic change, whereby expressions have many values, rather than just a single value. In this language of *nondeterministic computing*, it is natural to express processes that generate all possible values for expressions and then search for those values that satisfy certain constraints. In terms of models of computation and time, this is like having time branch into a set of "possible futures" and then searching for appropriate time lines. With our nondeterministic evaluator, keeping track of multiple values and performing searches are handled automatically by the underlying mechanism of the language.

In Section 4.4 we implement a *logic-programming* language in which knowledge is expressed in terms of relations, rather than in terms of computations with inputs and outputs. Even though this makes the language drastically different from Lisp, or indeed from any conventional language, we will see that the logic-programming evaluator shares the essential structure of the Lisp evaluator.

4.1 The Metacircular Evaluator

Our evaluator for Lisp will be implemented as a Lisp program. It may seem circular to think about evaluating Lisp programs using an evaluator that is itself implemented in Lisp. However, evaluation is a process, so it is ap-

propriate to describe the evaluation process using Lisp, which, after all, is our tool for describing processes.[3] An evaluator that is written in the same language that it evaluates is said to be *metacircular*.

The metacircular evaluator is essentially a Scheme formulation of the environment model of evaluation described in Section 3.2. Recall that the model has two basic parts:

1. To evaluate a combination (a compound expression other than a special form), evaluate the subexpressions and then apply the value of the operator subexpression to the values of the operand subexpressions.

2. To apply a compound procedure to a set of arguments, evaluate the body of the procedure in a new environment. To construct this environment, extend the environment part of the procedure object by a frame in which the formal parameters of the procedure are bound to the arguments to which the procedure is applied.

These two rules describe the essence of the evaluation process, a basic cycle in which expressions to be evaluated in environments are reduced to procedures to be applied to arguments, which in turn are reduced to new expressions to be evaluated in new environments, and so on, until we get down to symbols, whose values are looked up in the environment, and to primitive procedures, which are applied directly (see Figure 4.1).[4] This evaluation cycle will be em-

[3] Even so, there will remain important aspects of the evaluation process that are not elucidated by our evaluator. The most important of these are the detailed mechanisms by which procedures call other procedures and return values to their callers. We will address these issues in Chapter 5, where we take a closer look at the evaluation process by implementing the evaluator as a simple register machine.

[4] If we grant ourselves the ability to apply primitives, then what remains for us to implement in the evaluator? The job of the evaluator is not to specify the primitives of the language, but rather to provide the connective tissue—the means of combination and the means of abstrac-

bodied by the interplay between the two critical procedures in the evaluator, `eval` and `apply`, which are described in Section 4.1.1 (see Figure 4.1).

The implementation of the evaluator will depend upon procedures that define the *syntax* of the expressions to be evaluated. We will use data abstraction to make the evaluator independent of the representation of the language. For example, rather than committing to a choice that an assignment is to be represented by a list beginning with the symbol `set!` we use an abstract predicate `assignment?` to test for an assignment, and we use abstract selectors `assignment-variable` and `assignment-value` to access the parts of an assignment. Implementation of expressions will be described in detail in Section 4.1.2. There are also operations, described in Section 4.1.3, that specify the representation of procedures and environments. For example, `make-procedure` constructs compound procedures, `lookup-variable-value` accesses the values of variables, and `apply-primitive-procedure` applies a primitive procedure to a given list of arguments.

---

tion—that binds a collection of primitives to form a language. Specifically:

- The evaluator enables us to deal with nested expressions. For example, although simply applying primitives would suffice for evaluating the expression `(+ 1 6)`, it is not adequate for handling `(+ 1 (* 2 3))`. As far as the primitive procedure + is concerned, its arguments must be numbers, and it would choke if we passed it the expression `(* 2 3)` as an argument. One important role of the evaluator is to choreograph procedure composition so that `(* 2 3)` is reduced to 6 before being passed as an argument to +.
- The evaluator allows us to use variables. For example, the primitive procedure for addition has no way to deal with expressions such as `(+ x 1)`. We need an evaluator to keep track of variables and obtain their values before invoking the primitive procedures.
- The evaluator allows us to define compound procedures. This involves keeping track of procedure definitions, knowing how to use these definitions in evaluating expressions, and providing a mechanism that enables procedures to accept arguments.
- The evaluator provides the special forms, which must be evaluated differently from procedure calls.




Figure 4.1: The `eval-apply` cycle exposes the essence of a computer language.

4.1.1 The Core of the Evaluator

The evaluation process can be described as the interplay between two procedures: `eval` and `apply`.

Eval

`eval` takes as arguments an expression and an environment. It classifies the expression and directs its evaluation. `eval` is structured as a case analysis of the syntactic type of the expression to be evaluated. In order to keep the procedure general, we express the determination of the type of an expression abstractly, making no commitment to any particular representation for the various types of expressions. Each type of expression has a predicate that tests for it and an abstract means for selecting its parts. This *abstract syntax* makes it easy to see how we can change the syntax of the language by using the same evaluator, but with a different collection of syntax procedures.

Primitive expressions

- For self-evaluating expressions, such as numbers, `eval` returns the expression itself.
- `eval` must look up variables in the environment to find their values.

Special forms

- For quoted expressions, `eval` returns the expression that was quoted.
- An assignment to (or a definition of) a variable must recursively call `eval` to compute the new value to be associated with the variable. The environment must be modified to change (or create) the binding of the variable.
- An `if` expression requires special processing of its parts, so as to evaluate the consequent if the predicate is true, and otherwise to evaluate the alternative.
- A `lambda` expression must be transformed into an applicable procedure by packaging together the parameters and body specified by the `lambda` expression with the environment of the evaluation.
- A `begin` expression requires evaluating its sequence of expressions in the order in which they appear.
- A case analysis (`cond`) is transformed into a nest of `if` expressions and then evaluated.

Combinations

- For a procedure application, `eval` must recursively evaluate the operator part and the operands of the combination. The resulting procedure and arguments are passed to `apply`, which handles the actual procedure application.

Here is the definition of `eval`:

```
(define (eval exp env)
  (cond ((self-evaluating? exp) exp)
        ((variable? exp) (lookup-variable-value exp env))
        ((quoted? exp) (text-of-quotation exp))
        ((assignment? exp) (eval-assignment exp env))
        ((definition? exp) (eval-definition exp env))
        ((if? exp) (eval-if exp env))
        ((lambda? exp) (make-procedure (lambda-parameters ex
                                       (lambda-body exp)
                                       env))
        ((begin? exp)
         (eval-sequence (begin-actions exp) env))
        ((cond? exp) (eval (cond->if exp) env))
        ((application? exp)
         (apply (eval (operator exp) env)
                (list-of-values (operands exp) env)))
        (else
         (error "Unknown expression type: EVAL" exp))))
```

For clarity, `eval` has been implemented as a case analysis using `cond`. The disadvantage of this is that our procedure handles only a few distinguishable types of expressions, and no new ones can be defined without editing the definition of `eval`. In most Lisp implementations, dispatching on the type of an expression is done in a data-directed style. This allows a user to add new types of expressions that `eval` can distinguish, without modifying the definition of `eval` itself. (See Exercise 4.3.)

Apply

`apply` takes two arguments, a procedure and a list of arguments to which the procedure should be applied. `apply` classifies procedures into two kinds: It calls `apply-primitive-procedure` to apply primitives; it applies compound procedures by sequentially evaluating the expressions that make up the body of the procedure. The environment for the evaluation of the body of a compound procedure is constructed by extending the base environment carried by the procedure to include a frame that binds the parameters of the procedure to the arguments to which the procedure is to be applied. Here is the definition of `apply`:

```
(define (apply procedure arguments)
  (cond ((primitive-procedure? procedure)
         (apply-primitive-procedure procedure arguments))
        ((compound-procedure? procedure)
         (eval-sequence
           (procedure-body procedure)
           (extend-environment
             (procedure-parameters procedure)
             arguments
             (procedure-environment procedure))))
        (else
         (error
          "Unknown procedure type: APPLY" procedure))))
```

Procedure arguments

When `eval` processes a procedure application, it uses `list-of-values` to produce the list of arguments to which the procedure is to be applied. `list-of-values` takes as an argument the operands of the combination.

It evaluates each operand and returns a list of the corresponding values:[5]

```
(define (list-of-values exps env)
  (if (no-operands? exps)
      '()
      (cons (eval (first-operand exps) env)
            (list-of-values (rest-operands exps) env))))
```

Conditionals

`eval-if` evaluates the predicate part of an `if` expression in the given environment. If the result is true, `eval-if` evaluates the consequent, otherwise it evaluates the alternative:

```
(define (eval-if exp env)
  (if (true? (eval (if-predicate exp) env))
      (eval (if-consequent exp) env)
      (eval (if-alternative exp) env)))
```

The use of `true?` in `eval-if` highlights the issue of the connection between an implemented language and an implementation language. The `if-predicate` is evaluated in the language being implemented and thus yields a value in that language. The interpreter predicate `true?` translates that value into a value that can be tested by the `if` in the implementation language: The metacircular representation of truth might not be the same as that of the underlying Scheme.[6]

[5] We could have simplified the `application?` clause in `eval` by using `map` (and stipulating that `operands` returns a list) rather than writing an explicit `list-of-values` procedure. We chose not to use `map` here to emphasize the fact that the evaluator can be implemented without any use of higher-order procedures (and thus could be written in a language that doesn't have higher-order procedures), even though the language that it supports will include higher-order procedures.

[6] In this case, the language being implemented and the implementation language are the

Sequences

`eval-sequence` is used by `apply` to evaluate the sequence of expressions in a procedure body and by `eval` to evaluate the sequence of expressions in a `begin` expression. It takes as arguments a sequence of expressions and an environment, and evaluates the expressions in the order in which they occur. The value returned is the value of the final expression.

```
(define (eval-sequence exps env)
  (cond ((last-exp? exps)
         (eval (first-exp exps) env))
        (else
         (eval (first-exp exps) env)
         (eval-sequence (rest-exps exps) env))))
```

Assignments and definitions

The following procedure handles assignments to variables. It calls `eval` to find the value to be assigned and transmits the variable and the resulting value to `set-variable-value!` to be installed in the designated environment.

```
(define (eval-assignment exp env)
  (set-variable-value! (assignment-variable exp)
                       (eval (assignment-value exp) env)
                       env)
  'ok)
```

Definitions of variables are handled in a similar manner.[7]

same. Contemplation of the meaning of `true?` here yields expansion of consciousness without the abuse of substance.

[7] This implementation of `define` ignores a subtle issue in the handling of internal definitions, although it works correctly in most cases. We will see what the problem is and how to solve it in Section 4.1.6.

```
(define (eval-definition exp env)
  (define-variable! (definition-variable exp)
                    (eval (definition-value exp) env)
                    env)
  'ok)
```

We have chosen here to return the symbol `ok` as the value of an assignment or a definition.[8]

> **Exercise 4.1:** Notice that we cannot tell whether the metacircular evaluator evaluates operands from left to right or from right to left. Its evaluation order is inherited from the underlying Lisp: If the arguments to `cons` in `list-of-values` are evaluated from left to right, then `list-of-values` will evaluate operands from left to right; and if the arguments to `cons` are evaluated from right to left, then `list-of-values` will evaluate operands from right to left.
>
> Write a version of `list-of-values` that evaluates operands from left to right regardless of the order of evaluation in the underlying Lisp. Also write a version of `list-of-values` that evaluates operands from right to left.

4.1.2 Representing Expressions

The evaluator is reminiscent of the symbolic differentiation program discussed in Section 2.3.2. Both programs operate on symbolic expressions. In both programs, the result of operating on a compound expression is determined by operating recursively on the pieces of the expression and combining

[8] As we said when we introduced `define` and `set!`, these values are implementation-dependent in Scheme—that is, the implementor can choose what value to return.

the results in a way that depends on the type of the expression. In both programs we used data abstraction to decouple the general rules of operation from the details of how expressions are represented. In the differentiation program this meant that the same differentiation procedure could deal with algebraic expressions in prefix form, in infix form, or in some other form. For the evaluator, this means that the syntax of the language being evaluated is determined solely by the procedures that classify and extract pieces of expressions.

Here is the specification of the syntax of our language:

- The only self-evaluating items are numbers and strings:

```
(define (self-evaluating? exp)
  (cond ((number? exp) true)
        ((string? exp) true)
        (else false)))
```

- Variables are represented by symbols:

```
(define (variable? exp) (symbol? exp))
```

- Quotations have the form `(quote` ⟨*text-of-quotation*⟩`)`:[9]

```
(define (quoted? exp) (tagged-list? exp 'quote))
(define (text-of-quotation exp) (cadr exp))
```

  `quoted?` is defined in terms of the procedure `tagged-list?`, which identifies lists beginning with a designated symbol:

[9] As mentioned in Section 2.3.1, the evaluator sees a quoted expression as a list beginning with `quote`, even if the expression is typed with the quotation mark. For example, the expression `'a` would be seen by the evaluator as `(quote a)`. See Exercise 2.55.

```
(define (tagged-list? exp tag)
  (if (pair? exp)
      (eq? (car exp) tag)
      false))
```

- Assignments have the form `(set!` ⟨*var*⟩ ⟨*value*⟩`)`:

```
(define (assignment? exp) (tagged-list? exp 'set!))
(define (assignment-variable exp) (cadr exp))
(define (assignment-value exp) (caddr exp))
```

- Definitions have the form

```
(define ⟨var⟩ ⟨value⟩)
```

  or the form

```
(define (⟨var⟩ ⟨parameter_1⟩ ... ⟨parameter_n⟩)
  ⟨body⟩)
```

  The latter form (standard procedure definition) is syntactic sugar for

```
(define ⟨var⟩
  (lambda (⟨parameter_1⟩ ... ⟨parameter_n⟩)
    ⟨body⟩))
```

  The corresponding syntax procedures are the following:

```
(define (definition? exp) (tagged-list? exp 'define))
(define (definition-variable exp)
  (if (symbol? (cadr exp))
      (cadr exp)
      (caadr exp)))
(define (definition-value exp)
  (if (symbol? (cadr exp))
      (caddr exp)
```

```
(make-lambda (cdadr exp)        ; formal parameters
             (cddr exp))))      ; body
```

- `lambda` expressions are lists that begin with the symbol `lambda`:

```
(define (lambda? exp) (tagged-list? exp 'lambda))
(define (lambda-parameters exp) (cadr exp))
(define (lambda-body exp) (cddr exp))
```

We also provide a constructor for `lambda` expressions, which is used by `definition-value`, above:

```
(define (make-lambda parameters body)
  (cons 'lambda (cons parameters body)))
```

- Conditionals begin with `if` and have a predicate, a consequent, and an (optional) alternative. If the expression has no alternative part, we provide `false` as the alternative.[10]

```
(define (if? exp) (tagged-list? exp 'if))
(define (if-predicate exp) (cadr exp))
(define (if-consequent exp) (caddr exp))
(define (if-alternative exp)
  (if (not (null? (cdddr exp)))
      (cadddr exp)
      'false))
```

We also provide a constructor for `if` expressions, to be used by `cond->if` to transform `cond` expressions into `if` expressions:

[10] The value of an `if` expression when the predicate is false and there is no alternative is unspecified in Scheme; we have chosen here to make it false. We will support the use of the variables `true` and `false` in expressions to be evaluated by binding them in the global environment. See Section 4.1.4.

```
(define (make-if predicate consequent alternative)
  (list 'if predicate consequent alternative))
```

- `begin` packages a sequence of expressions into a single expression. We include syntax operations on `begin` expressions to extract the actual sequence from the `begin` expression, as well as selectors that return the first expression and the rest of the expressions in the sequence.[11]

```
(define (begin? exp) (tagged-list? exp 'begin))
(define (begin-actions exp) (cdr exp))
(define (last-exp? seq) (null? (cdr seq)))
(define (first-exp seq) (car seq))
(define (rest-exps seq) (cdr seq))
```

  We also include a constructor `sequence->exp` (for use by `cond->if`) that transforms a sequence into a single expression, using `begin` if necessary:

```
(define (sequence->exp seq)
  (cond ((null? seq) seq)
        ((last-exp? seq) (first-exp seq))
        (else (make-begin seq))))
(define (make-begin seq) (cons 'begin seq))
```

- A procedure application is any compound expression that is not one of the above expression types. The `car` of the expression is the operator, and the `cdr` is the list of operands:

[11] These selectors for a list of expressions—and the corresponding ones for a list of operands—are not intended as a data abstraction. They are introduced as mnemonic names for the basic list operations in order to make it easier to understand the explicit-control evaluator in Section 5.4.

```
(define (application? exp) (pair? exp))
(define (operator exp) (car exp))
(define (operands exp) (cdr exp))
(define (no-operands? ops) (null? ops))
(define (first-operand ops) (car ops))
(define (rest-operands ops) (cdr ops))
```

Derived expressions

Some special forms in our language can be defined in terms of expressions involving other special forms, rather than being implemented directly. One example is `cond`, which can be implemented as a nest of `if` expressions. For example, we can reduce the problem of evaluating the expression

```
(cond ((> x 0) x)
      ((= x 0) (display 'zero) 0)
      (else (- x)))
```

to the problem of evaluating the following expression involving `if` and `begin` expressions:

```
(if (> x 0)
    x
    (if (= x 0)
        (begin (display 'zero) 0)
        (- x)))
```

Implementing the evaluation of `cond` in this way simplifies the evaluator because it reduces the number of special forms for which the evaluation process must be explicitly specified.

We include syntax procedures that extract the parts of a `cond` expression, and a procedure `cond->if` that transforms `cond` expressions into `if` expressions. A case analysis begins with `cond` and has a list of predicate-

action clauses. A clause is an `else` clause if its predicate is the symbol `else`.[12]

```
(define (cond? exp) (tagged-list? exp 'cond))
(define (cond-clauses exp) (cdr exp))
(define (cond-else-clause? clause)
  (eq? (cond-predicate clause) 'else))
(define (cond-predicate clause) (car clause))
(define (cond-actions clause) (cdr clause))
(define (cond->if exp) (expand-clauses (cond-clauses exp)))
(define (expand-clauses clauses)
  (if (null? clauses)
      'false                          ; no else clause
      (let ((first (car clauses))
            (rest (cdr clauses)))
        (if (cond-else-clause? first)
            (if (null? rest)
                (sequence->exp (cond-actions first))
                (error "ELSE clause isn't last: COND->IF"
                       clauses))
            (make-if (cond-predicate first)
                     (sequence->exp (cond-actions first))
                     (expand-clauses rest))))))
```

Expressions (such as `cond`) that we choose to implement as syntactic transformations are called *derived expressions*. `let` expressions are also derived expressions (see Exercise 4.6).[13]

[12] The value of a `cond` expression when all the predicates are false and there is no `else` clause is unspecified in Scheme; we have chosen here to make it false.

[13] Practical Lisp systems provide a mechanism that allows a user to add new derived expressions and specify their implementation as syntactic transformations without modifying the evaluator. Such a user-defined transformation is called a *macro*. Although it is easy to add an elementary mechanism for defining macros, the resulting language has subtle name-conflict problems. There has been much research on mechanisms for macro definition that do not

Exercise 4.2: Louis Reasoner plans to reorder the `cond` clauses in `eval` so that the clause for procedure applications appears before the clause for assignments. He argues that this will make the interpreter more efficient: Since programs usually contain more applications than assignments, definitions, and so on, his modified `eval` will usually check fewer clauses than the original `eval` before identifying the type of an expression.

a. What is wrong with Louis's plan? (Hint: What will Louis's evaluator do with the expression `(define x 3)`?)

b. Louis is upset that his plan didn't work. He is willing to go to any lengths to make his evaluator recognize procedure applications before it checks for most other kinds of expressions. Help him by changing the syntax of the evaluated language so that procedure applications start with `call`. For example, instead of `(factorial 3)` we will now have to write `(call factorial 3)` and instead of `(+ 1 2)` we will have to write `(call + 1 2)`.

Exercise 4.3: Rewrite `eval` so that the dispatch is done in data-directed style. Compare this with the data-directed differentiation procedure of Exercise 2.73. (You may use the `car` of a compound expression as the type of the expression, as is appropriate for the syntax implemented in this section.)

Exercise 4.4: Recall the definitions of the special forms `and` and `or` from Chapter 1:

---

cause these difficulties. See, for example, Kohlbecker 1986, Clinger and Rees 1991, and Hanson 1991.

- `and`: The expressions are evaluated from left to right. If any expression evaluates to false, false is returned; any remaining expressions are not evaluated. If all the expressions evaluate to true values, the value of the last expression is returned. If there are no expressions then true is returned.
- `or`: The expressions are evaluated from left to right. If any expression evaluates to a true value, that value is returned; any remaining expressions are not evaluated. If all expressions evaluate to false, or if there are no expressions, then false is returned.

Install `and` and `or` as new special forms for the evaluator by defining appropriate syntax procedures and evaluation procedures `eval-and` and `eval-or`. Alternatively, show how to implement `and` and `or` as derived expressions.

Exercise 4.5: Scheme allows an additional syntax for `cond` clauses, (⟨*test*⟩ `=>` ⟨*recipient*⟩). If ⟨*test*⟩ evaluates to a true value, then ⟨*recipient*⟩ is evaluated. Its value must be a procedure of one argument; this procedure is then invoked on the value of the ⟨*test*⟩, and the result is returned as the value of the `cond` expression. For example

```
(cond ((assoc 'b '((a 1) (b 2))) => cadr)
      (else false))
```

returns 2. Modify the handling of `cond` so that it supports this extended syntax.

Exercise 4.6: `let` expressions are derived expressions, because

```
(let ((⟨var1⟩ ⟨exp1⟩) ... (⟨varn⟩ ⟨expn⟩))
  ⟨body⟩)
```

is equivalent to

```
((lambda (⟨var1⟩ ... ⟨varn⟩)
   ⟨body⟩)
 ⟨exp1⟩
 ...
 ⟨expn⟩)
```

Implement a syntactic transformation `let->combination` that reduces evaluating `let` expressions to evaluating combinations of the type shown above, and add the appropriate clause to `eval` to handle `let` expressions.

Exercise 4.7: `let*` is similar to `let`, except that the bindings of the `let*` variables are performed sequentially from left to right, and each binding is made in an environment in which all of the preceding bindings are visible. For example

```
(let* ((x 3)   (y (+ x 2))   (z (+ x y 5)))
  (* x z))
```

returns 39. Explain how a `let*` expression can be rewritten as a set of nested `let` expressions, and write a procedure `let*->nested-lets` that performs this transformation. If we have already implemented `let` (Exercise 4.6) and we want to extend the evaluator to handle `let*`, is it sufficient to add a clause to `eval` whose action is

```
(eval (let*->nested-lets exp) env)
```

or must we explicitly expand `let*` in terms of non-derived expressions?

Exercise 4.8: "Named `let`" is a variant of `let` that has the form

```
(let ⟨var⟩ ⟨bindings⟩ ⟨body⟩)
```

The ⟨*bindings*⟩ and ⟨*body*⟩ are just as in ordinary `let`, except that ⟨*var*⟩ is bound within ⟨*body*⟩ to a procedure whose body is ⟨*body*⟩ and whose parameters are the variables in the ⟨*bindings*⟩. Thus, one can repeatedly execute the ⟨*body*⟩ by invoking the procedure named ⟨*var*⟩. For example, the iterative Fibonacci procedure (Section 1.2.2) can be rewritten using named `let` as follows:

```
(define (fib n)
  (let fib-iter ((a 1)
                 (b 0)
                 (count n))
    (if (= count 0)
        b
        (fib-iter (+ a b) a (- count 1)))))
```

Modify `let->combination` of Exercise 4.6 to also support named `let`.

Exercise 4.9: Many languages support a variety of iteration constructs, such as `do`, `for`, `while`, and `until`. In Scheme, iterative processes can be expressed in terms of ordinary procedure calls, so special iteration constructs provide no essential gain in computational power. On the other hand, such constructs are often convenient. Design some iteration constructs, give examples of their use, and show how to implement them as derived expressions.

Exercise 4.10: By using data abstraction, we were able to write an `eval` procedure that is independent of the particular syntax of the language to be evaluated. To illustrate this, design and implement a new syntax for Scheme by modifying the procedures in this section, without changing `eval` or `apply`.

4.1.3 Evaluator Data Structures

In addition to defining the external syntax of expressions, the evaluator implementation must also define the data structures that the evaluator manipulates internally, as part of the execution of a program, such as the representation of procedures and environments and the representation of true and false.

Testing of predicates

For conditionals, we accept anything to be true that is not the explicit `false` object.

```
(define (true? x)  (not (eq? x false)))
(define (false? x) (eq? x false))
```

Representing procedures

To handle primitives, we assume that we have available the following procedures:

- `(apply-primitive-procedure` ⟨*proc*⟩ ⟨*args*⟩`)`
  applies the given primitive procedure to the argument values in the list ⟨*args*⟩ and returns the result of the application.
- `(primitive-procedure?` ⟨*proc*⟩`)`
  tests whether ⟨*proc*⟩ is a primitive procedure.

These mechanisms for handling primitives are further described in Section 4.1.4.

Compound procedures are constructed from parameters, procedure bodies, and environments using the constructor `make-procedure`:

```
(define (make-procedure parameters body env)
  (list 'procedure parameters body env))
(define (compound-procedure? p)
  (tagged-list? p 'procedure))
(define (procedure-parameters p) (cadr p))
(define (procedure-body p) (caddr p))
(define (procedure-environment p) (cadddr p))
```

Operations on Environments

The evaluator needs operations for manipulating environments. As explained in Section 3.2, an environment is a sequence of frames, where each frame is a table of bindings that associate variables with their corresponding values. We use the following operations for manipulating environments:

- `(lookup-variable-value` ⟨*var*⟩ ⟨*env*⟩`)`

  returns the value that is bound to the symbol ⟨*var*⟩ in the environment ⟨*env*⟩, or signals an error if the variable is unbound.

- `(extend-environment` ⟨*variables*⟩ ⟨*values*⟩ ⟨*base-env*⟩`)`

  returns a new environment, consisting of a new frame in which the symbols in the list ⟨*variables*⟩ are bound to the corresponding elements in the list ⟨*values*⟩, where the enclosing environment is the environment ⟨*base-env*⟩.

- `(define-variable!` ⟨*var*⟩ ⟨*value*⟩ ⟨*env*⟩`)`

  adds to the first frame in the environment ⟨*env*⟩ a new binding that associates the variable ⟨*var*⟩ with the value ⟨*value*⟩.

- `(set-variable-value!` ⟨*var*⟩ ⟨*value*⟩ ⟨*env*⟩`)`

  changes the binding of the variable ⟨*var*⟩ in the environment ⟨*env*⟩ so that the variable is now bound to the value ⟨*value*⟩, or signals an error if the variable is unbound.

To implement these operations we represent an environment as a list of frames. The enclosing environment of an environment is the `cdr` of the list. The empty environment is simply the empty list.

```
(define (enclosing-environment env) (cdr env))
(define (first-frame env) (car env))
(define the-empty-environment '())
```

Each frame of an environment is represented as a pair of lists: a list of the variables bound in that frame and a list of the associated values.[14]

```
(define (make-frame variables values)
  (cons variables values))
(define (frame-variables frame) (car frame))
(define (frame-values frame) (cdr frame))
(define (add-binding-to-frame! var val frame)
  (set-car! frame (cons var (car frame)))
  (set-cdr! frame (cons val (cdr frame))))
```

[14]Frames are not really a data abstraction in the following code: `set-variable-value!` and `define-variable!` use `set-car!` to directly modify the values in a frame. The purpose of the frame procedures is to make the environment-manipulation procedures easy to read.

To extend an environment by a new frame that associates variables with values, we make a frame consisting of the list of variables and the list of values, and we adjoin this to the environment. We signal an error if the number of variables does not match the number of values.

```
(define (extend-environment vars vals base-env)
  (if (= (length vars) (length vals))
      (cons (make-frame vars vals) base-env)
      (if (< (length vars) (length vals))
          (error "Too many arguments supplied" vars vals)
          (error "Too few arguments supplied" vars vals))))
```

To look up a variable in an environment, we scan the list of variables in the first frame. If we find the desired variable, we return the corresponding element in the list of values. If we do not find the variable in the current frame, we search the enclosing environment, and so on. If we reach the empty environment, we signal an "unbound variable" error.

```
(define (lookup-variable-value var env)
  (define (env-loop env)
    (define (scan vars vals)
      (cond ((null? vars)
             (env-loop (enclosing-environment env)))
            ((eq? var (car vars)) (car vals))
            (else (scan (cdr vars) (cdr vals)))))
    (if (eq? env the-empty-environment)
        (error "Unbound variable" var)
        (let ((frame (first-frame env)))
          (scan (frame-variables frame)
                (frame-values frame)))))
  (env-loop env))
```

To set a variable to a new value in a specified environment, we scan for the variable, just as in `lookup-variable-value`, and change the corre-

sponding value when we find it.

```
(define (set-variable-value! var val env)
  (define (env-loop env)
    (define (scan vars vals)
      (cond ((null? vars)
             (env-loop (enclosing-environment env)))
            ((eq? var (car vars)) (set-car! vals val))
            (else (scan (cdr vars) (cdr vals)))))
    (if (eq? env the-empty-environment)
        (error "Unbound variable: SET!" var)
        (let ((frame (first-frame env)))
          (scan (frame-variables frame)
                (frame-values frame)))))
  (env-loop env))
```

To define a variable, we search the first frame for a binding for the variable, and change the binding if it exists (just as in `set-variable-value!`). If no such binding exists, we adjoin one to the first frame.

```
(define (define-variable! var val env)
  (let ((frame (first-frame env)))
    (define (scan vars vals)
      (cond ((null? vars)
             (add-binding-to-frame! var val frame))
            ((eq? var (car vars)) (set-car! vals val))
            (else (scan (cdr vars) (cdr vals)))))
    (scan (frame-variables frame) (frame-values frame))))
```

The method described here is only one of many plausible ways to represent environments. Since we used data abstraction to isolate the rest of the evaluator from the detailed choice of representation, we could change the environment representation if we wanted to. (See Exercise 4.11.) In a production-quality Lisp system, the speed of the evaluator's environment operations—especially

that of variable lookup—has a major impact on the performance of the system. The representation described here, although conceptually simple, is not efficient and would not ordinarily be used in a production system.[15]

Exercise 4.11: Instead of representing a frame as a pair of lists, we can represent a frame as a list of bindings, where each binding is a name-value pair. Rewrite the environment operations to use this alternative representation.

Exercise 4.12: The procedures `set-variable-value!`, `define-variable!` and `lookup-variable-value` can be expressed in terms of more abstract procedures for traversing the environment structure. Define abstractions that capture the common patterns and redefine the three procedures in terms of these abstractions.

Exercise 4.13: Scheme allows us to create new bindings for variables by means of `define`, but provides no way to get rid of bindings. Implement for the evaluator a special form `make-unbound!` that removes the binding of a given symbol from the environment in which the `make-unbound!` expression is evaluated. This problem is not completely specified. For example, should we remove only the binding in the first frame of the environment? Complete the specification and justify any choices you make.

[15] The drawback of this representation (as well as the variant in Exercise 4.11) is that the evaluator may have to search through many frames in order to find the binding for a given variable. (Such an approach is referred to as *deep binding*.) One way to avoid this inefficiency is to make use of a strategy called *lexical addressing*, which will be discussed in Section 5.5.6.

4.1.4 Running the Evaluator as a Program

Given the evaluator, we have in our hands a description (expressed in Lisp) of the process by which Lisp expressions are evaluated. One advantage of expressing the evaluator as a program is that we can run the program. This gives us, running within Lisp, a working model of how Lisp itself evaluates expressions. This can serve as a framework for experimenting with evaluation rules, as we shall do later in this chapter.

Our evaluator program reduces expressions ultimately to the application of primitive procedures. Therefore, all that we need to run the evaluator is to create a mechanism that calls on the underlying Lisp system to model the application of primitive procedures.

There must be a binding for each primitive procedure name, so that when `eval` evaluates the operator of an application of a primitive, it will find an object to pass to `apply`. We thus set up a global environment that associates unique objects with the names of the primitive procedures that can appear in the expressions we will be evaluating. The global environment also includes bindings for the symbols `true` and `false`, so that they can be used as variables in expressions to be evaluated.

```
(define (setup-environment)
  (let ((initial-env
         (extend-environment (primitive-procedure-names)
                             (primitive-procedure-objects)
                             the-empty-environment)))
    (define-variable! 'true true initial-env)
    (define-variable! 'false false initial-env)
    initial-env))
(define the-global-environment (setup-environment))
```

It does not matter how we represent the primitive procedure objects, so long as `apply` can identify and apply them by using the procedures `primitive-`

`procedure?` and `apply-primitive-procedure`. We have chosen to represent a primitive procedure as a list beginning with the symbol `primitive` and containing a procedure in the underlying Lisp that implements that primitive.

```
(define (primitive-procedure? proc)
  (tagged-list? proc 'primitive))
(define (primitive-implementation proc) (cadr proc))
```

`setup-environment` will get the primitive names and implementation procedures from a list:[16]

```
(define primitive-procedures
  (list (list 'car car)
        (list 'cdr cdr)
        (list 'cons cons)
        (list 'null? null?)
        ⟨more primitives⟩ ))
(define (primitive-procedure-names)
  (map car primitive-procedures))
(define (primitive-procedure-objects)
  (map (lambda (proc) (list 'primitive (cadr proc)))
       primitive-procedures))
```

To apply a primitive procedure, we simply apply the implementation procedure to the arguments, using the underlying Lisp system:[17]

[16] Any procedure defined in the underlying Lisp can be used as a primitive for the metacircular evaluator. The name of a primitive installed in the evaluator need not be the same as the name of its implementation in the underlying Lisp; the names are the same here because the metacircular evaluator implements Scheme itself. Thus, for example, we could put `(list 'first car)` or `(list 'square (lambda (x) (* x x)))` in the list of `primitive-procedures`.

[17] `apply-in-underlying-scheme` is the `apply` procedure we have used in earlier chapters. The metacircular evaluator's `apply` procedure (Section 4.1.1) models the

```
(define (apply-primitive-procedure proc args)
  (apply-in-underlying-scheme
   (primitive-implementation proc) args))
```

For convenience in running the metacircular evaluator, we provide a *driver loop* that models the read-eval-print loop of the underlying Lisp system. It prints a *prompt*, reads an input expression, evaluates this expression in the global environment, and prints the result. We precede each printed result by an *output prompt* so as to distinguish the value of the expression from other output that may be printed.[18]

```
(define input-prompt  ";;; M-Eval input:")
(define output-prompt ";;; M-Eval value:")
(define (driver-loop)
  (prompt-for-input input-prompt)
  (let ((input (read)))
    (let ((output (eval input the-global-environment)))
      (announce-output output-prompt)
      (user-print output)))
  (driver-loop))
(define (prompt-for-input string)
  (newline) (newline) (display string) (newline))
```

---

working of this primitive. Having two different things called `apply` leads to a technical problem in running the metacircular evaluator, because defining the metacircular evaluator's `apply` will mask the definition of the primitive. One way around this is to rename the metacircular `apply` to avoid conflict with the name of the primitive procedure. We have assumed instead that we have saved a reference to the underlying `apply` by doing

```
(define apply-in-underlying-scheme apply)
```

before defining the metacircular `apply`. This allows us to access the original version of `apply` under a different name.

[18] The primitive procedure `read` waits for input from the user, and returns the next complete expression that is typed. For example, if the user types `(+ 23 x)`, `read` returns a three-element list containing the symbol +, the number 23, and the symbol `x`. If the user types `'x`, `read` returns a two-element list containing the symbol `quote` and the symbol `x`.

```
(define (announce-output string)
  (newline) (display string) (newline))
```

We use a special printing procedure, `user-print`, to avoid printing the environment part of a compound procedure, which may be a very long list (or may even contain cycles).

```
(define (user-print object)
  (if (compound-procedure? object)
      (display (list 'compound-procedure
                     (procedure-parameters object)
                     (procedure-body object)
                     '<procedure-env>))
      (display object)))
```

Now all we need to do to run the evaluator is to initialize the global environment and start the driver loop. Here is a sample interaction:

```
(define the-global-environment (setup-environment))
(driver-loop)

;;; M-Eval input:
(define (append x y)
  (if (null? x)
      y
      (cons (car x) (append (cdr x) y))))
;;; M-Eval value:
ok
;;; M-Eval input:
(append '(a b c) '(d e f))
;;; M-Eval value:
(a b c d e f)
```

Exercise 4.14: Eva Lu Ator and Louis Reasoner are each experimenting with the metacircular evaluator. Eva types in the def-

inition of `map`, and runs some test programs that use it. They work fine. Louis, in contrast, has installed the system version of `map` as a primitive for the metacircular evaluator. When he tries it, things go terribly wrong. Explain why Louis's `map` fails even though Eva's works.

4.1.5 Data as Programs

In thinking about a Lisp program that evaluates Lisp expressions, an analogy might be helpful. One operational view of the meaning of a program is that a program is a description of an abstract (perhaps infinitely large) machine. For example, consider the familiar program to compute factorials:

```
(define (factorial n)
  (if (= n 1) 1 (* (factorial (- n 1)) n)))
```

We may regard this program as the description of a machine containing parts that decrement, multiply, and test for equality, together with a two-position switch and another factorial machine. (The factorial machine is infinite because it contains another factorial machine within it.) Figure 4.2 is a flow diagram for the factorial machine, showing how the parts are wired together.

In a similar way, we can regard the evaluator as a very special machine that takes as input a description of a machine. Given this input, the evaluator configures itself to emulate the machine described. For example, if we feed our evaluator the definition of `factorial`, as shown in Figure 4.3, the evaluator will be able to compute factorials.

From this perspective, our evaluator is seen to be a *universal machine*. It mimics other machines when these are described as Lisp programs.[19] This

[19] The fact that the machines are described in Lisp is inessential. If we give our evaluator a Lisp program that behaves as an evaluator for some other language, say C, the Lisp evaluator will emulate the C evaluator, which in turn can emulate any machine described as a C program.




Figure 4.2: The factorial program, viewed as an abstract machine.

Similarly, writing a Lisp evaluator in C produces a C program that can execute any Lisp program. The deep idea here is that any evaluator can emulate any other. Thus, the notion of "what can in principle be computed" (ignoring practicalities of time and memory required) is independent of the language or the computer, and instead reflects an underlying notion of *computability*. This was first demonstrated in a clear way by Alan M. Turing (1912-1954), whose 1936 paper laid the foundations for theoretical computer science. In the paper, Turing presented a simple computational model—now known as a *Turing machine*—and argued that any "effective process" can be formulated as a program for such a machine. (This argument is known as the *Church-Turing thesis*.) Turing then implemented a universal machine, i.e., a Turing machine that behaves as an evaluator for Turing-machine programs. He used this framework to demonstrate that there are well-posed problems that cannot be computed by Turing machines (see Exercise 4.15), and so by implication cannot be formulated as "effective processes." Turing went on to make fundamental contributions to practical computer science as well. For example, he invented the idea of structuring programs using general-purpose subroutines. See Hodges 1983 for a biography of Turing.




Figure 4.3: The evaluator emulating a factorial machine.

is striking. Try to imagine an analogous evaluator for electrical circuits. This would be a circuit that takes as input a signal encoding the plans for some other circuit, such as a filter. Given this input, the circuit evaluator would then behave like a filter with the same description. Such a universal electrical circuit is almost unimaginably complex. It is remarkable that the program evaluator is a rather simple program.[20]

Another striking aspect of the evaluator is that it acts as a bridge between the data objects that are manipulated by our programming language and the programming language itself. Imagine that the evaluator program (implemented in Lisp) is running, and that a user is typing expressions to the evaluator and observing the results. From the perspective of the user, an input expression such as `(* x x)` is an expression in the programming language,

[20] Some people find it counterintuitive that an evaluator, which is implemented by a relatively simple procedure, can emulate programs that are more complex than the evaluator itself. The existence of a universal evaluator machine is a deep and wonderful property of computation. *Recursion theory*, a branch of mathematical logic, is concerned with logical limits of computation. Douglas Hofstadter's beautiful book *Gödel, Escher, Bach* explores some of these ideas (Hofstadter 1979).

which the evaluator should execute. From the perspective of the evaluator, however, the expression is simply a list (in this case, a list of three symbols: `*`, `x`, and `x`) that is to be manipulated according to a well-defined set of rules.

That the user's programs are the evaluator's data need not be a source of confusion. In fact, it is sometimes convenient to ignore this distinction, and to give the user the ability to explicitly evaluate a data object as a Lisp expression, by making `eval` available for use in programs. Many Lisp dialects provide a primitive `eval` procedure that takes as arguments an expression and an environment and evaluates the expression relative to the environment.[21] Thus,

```
(eval '(* 5 5) user-initial-environment)
```

and

```
(eval (cons '* (list 5 5)) user-initial-environment)
```

will both return 25.[22]

> **Exercise 4.15:** Given a one-argument procedure `p` and an object `a`, `p` is said to "halt" on `a` if evaluating the expression `(p a)` returns a value (as opposed to terminating with an error message or running forever). Show that it is impossible to write a procedure `halts?` that correctly determines whether `p` halts on `a` for any procedure `p` and object `a`. Use the following reasoning:

[21] Warning: This `eval` primitive is not identical to the `eval` procedure we implemented in Section 4.1.1, because it uses *actual* Scheme environments rather than the sample environment structures we built in Section 4.1.3. These actual environments cannot be manipulated by the user as ordinary lists; they must be accessed via `eval` or other special operations. Similarly, the `apply` primitive we saw earlier is not identical to the metacircular `apply`, because it uses actual Scheme procedures rather than the procedure objects we constructed in Section 4.1.3 and Section 4.1.4.

[22] The MIT implementation of Scheme includes `eval`, as well as a symbol `user-initial-environment` that is bound to the initial environment in which the user's input expressions are evaluated.

If you had such a procedure `halts?`, you could implement the following program:

```
(define (run-forever) (run-forever))
(define (try p)
  (if (halts? p p) (run-forever) 'halted))
```

Now consider evaluating the expression `(try try)` and show that any possible outcome (either halting or running forever) violates the intended behavior of `halts?`.[23]

4.1.6 Internal Definitions

Our environment model of evaluation and our metacircular evaluator execute definitions in sequence, extending the environment frame one definition at a time. This is particularly convenient for interactive program development, in which the programmer needs to freely mix the application of procedures with the definition of new procedures. However, if we think carefully about the internal definitions used to implement block structure (introduced in Section 1.1.8), we will find that name-by-name extension of the environment may not be the best way to define local variables.

Consider a procedure with internal definitions, such as

```
(define (f x)
  (define (even? n) (if (= n 0) true  (odd?  (- n 1))))
  (define (odd? n)  (if (= n 0) false (even? (- n 1))))
  ⟨rest of body of f⟩)
```

[23] Although we stipulated that `halts?` is given a procedure object, notice that this reasoning still applies even if `halts?` can gain access to the procedure's text and its environment. This is Turing's celebrated *Halting Theorem*, which gave the first clear example of a *non-computable* problem, i.e., a well-posed task that cannot be carried out as a computational procedure.

Our intention here is that the name `odd?` in the body of the procedure `even?` should refer to the procedure `odd?` that is defined after `even?`. The scope of the name `odd?` is the entire body of `f`, not just the portion of the body of `f` starting at the point where the `define` for `odd?` occurs. Indeed, when we consider that `odd?` is itself defined in terms of `even?`—so that `even?` and `odd?` are mutually recursive procedures—we see that the only satisfactory interpretation of the two `define`s is to regard them as if the names `even?` and `odd?` were being added to the environment simultaneously. More generally, in block structure, the scope of a local name is the entire procedure body in which the `define` is evaluated.

As it happens, our interpreter will evaluate calls to `f` correctly, but for an "accidental" reason: Since the definitions of the internal procedures come first, no calls to these procedures will be evaluated until all of them have been defined. Hence, `odd?` will have been defined by the time `even?` is executed. In fact, our sequential evaluation mechanism will give the same result as a mechanism that directly implements simultaneous definition for any procedure in which the internal definitions come first in a body and evaluation of the value expressions for the defined variables doesn't actually use any of the defined variables. (For an example of a procedure that doesn't obey these restrictions, so that sequential definition isn't equivalent to simultaneous definition, see Exercise 4.19.)[24]

There is, however, a simple way to treat definitions so that internally

[24] Wanting programs to not depend on this evaluation mechanism is the reason for the "management is not responsible" remark in Footnote 28 of Chapter 1. By insisting that internal definitions come first and do not use each other while the definitions are being evaluated, the IEEE standard for Scheme leaves implementors some choice in the mechanism used to evaluate these definitions. The choice of one evaluation rule rather than another here may seem like a small issue, affecting only the interpretation of "badly formed" programs. However, we will see in Section 5.5.6 that moving to a model of simultaneous scoping for internal definitions avoids some nasty difficulties that would otherwise arise in implementing a compiler.

defined names have truly simultaneous scope—just create all local variables that will be in the current environment before evaluating any of the value expressions. One way to do this is by a syntax transformation on `lambda` expressions. Before evaluating the body of a `lambda` expression, we "scan out" and eliminate all the internal definitions in the body. The internally defined variables will be created with a `let` and then set to their values by assignment. For example, the procedure

```
(lambda ⟨vars⟩
  (define u ⟨e1⟩)
  (define v ⟨e2⟩)
  ⟨e3⟩)
```

would be transformed into

```
(lambda ⟨vars⟩
  (let ((u '*unassigned*)
        (v '*unassigned*))
    (set! u ⟨e1⟩)
    (set! v ⟨e2⟩)
    ⟨e3⟩))
```

where `*unassigned*` is a special symbol that causes looking up a variable to signal an error if an attempt is made to use the value of the not-yet-assigned variable.

An alternative strategy for scanning out internal definitions is shown in Exercise 4.18. Unlike the transformation shown above, this enforces the restriction that the defined variables' values can be evaluated without using any of the variables' values.[25]

[25] The IEEE standard for Scheme allows for different implementation strategies by specifying that it is up to the programmer to obey this restriction, not up to the implementation to enforce it. Some Scheme implementations, including MIT Scheme, use the transformation shown above. Thus, some programs that don't obey this restriction will in fact run in such implementations.

Exercise 4.16: In this exercise we implement the method just described for interpreting internal definitions. We assume that the evaluator supports `let` (see Exercise 4.6).

a. Change `lookup-variable-value` (Section 4.1.3) to signal an error if the value it finds is the symbol `*unassigned*`.

b. Write a procedure `scan-out-defines` that takes a procedure body and returns an equivalent one that has no internal definitions, by making the transformation described above.

c. Install `scan-out-defines` in the interpreter, either in `make-procedure` or in `procedure-body` (see Section 4.1.3). Which place is better? Why?

Exercise 4.17: Draw diagrams of the environment in effect when evaluating the expression ⟨*e3*⟩ in the procedure in the text, comparing how this will be structured when definitions are interpreted sequentially with how it will be structured if definitions are scanned out as described. Why is there an extra frame in the transformed program? Explain why this difference in environment structure can never make a difference in the behavior of a correct program. Design a way to make the interpreter implement the "simultaneous" scope rule for internal definitions without constructing the extra frame.

Exercise 4.18: Consider an alternative strategy for scanning out definitions that translates the example in the text to

```
(lambda ⟨vars⟩
  (let ((u '*unassigned*) (v '*unassigned*))
    (let ((a ⟨e1⟩) (b ⟨e2⟩))
```

```
      (set! u a)
      (set! v b))
    ⟨e3⟩))
```

Here `a` and `b` are meant to represent new variable names, created by the interpreter, that do not appear in the user's program. Consider the `solve` procedure from Section 3.5.4:

```
(define (solve f y0 dt)
  (define  y (integral (delay dy) y0 dt))
  (define dy (stream-map f y))
  y)
```

Will this procedure work if internal definitions are scanned out as shown in this exercise? What if they are scanned out as shown in the text? Explain.

Exercise 4.19: Ben Bitdiddle, Alyssa P. Hacker, and Eva Lu Ator are arguing about the desired result of evaluating the expression

```
(let ((a 1))
  (define (f x)
    (define b (+ a x))
    (define a 5)
    (+ a b))
  (f 10))
```

Ben asserts that the result should be obtained using the sequential rule for `define`: `b` is defined to be 11, then `a` is defined to be 5, so the result is 16. Alyssa objects that mutual recursion requires the simultaneous scope rule for internal procedure definitions, and that it is unreasonable to treat procedure names differently from other names. Thus, she argues for the mechanism implemented in Exercise 4.16. This would lead to `a` being

unassigned at the time that the value for `b` is to be computed. Hence, in Alyssa's view the procedure should produce an error. Eva has a third opinion. She says that if the definitions of `a` and `b` are truly meant to be simultaneous, then the value 5 for `a` should be used in evaluating `b`. Hence, in Eva's view `a` should be 5, `b` should be 15, and the result should be 20. Which (if any) of these viewpoints do you support? Can you devise a way to implement internal definitions so that they behave as Eva prefers?[26]

Exercise 4.20: Because internal definitions look sequential but are actually simultaneous, some people prefer to avoid them entirely, and use the special form `letrec` instead. `letrec` looks like `let`, so it is not surprising that the variables it binds are bound simultaneously and have the same scope as each other. The sample procedure `f` above can be written without internal definitions, but with exactly the same meaning, as

```
(define (f x)
  (letrec
    ((even? (lambda (n)
              (if (= n 0) true  (odd?  (- n 1)))))
     (odd?  (lambda (n)
              (if (= n 0) false (even? (- n 1))))))
    ⟨rest of body of f⟩))
```

`letrec` expressions, which have the form

[26]The MIT implementors of Scheme support Alyssa on the following grounds: Eva is in principle correct—the definitions should be regarded as simultaneous. But it seems difficult to implement a general, efficient mechanism that does what Eva requires. In the absence of such a mechanism, it is better to generate an error in the difficult cases of simultaneous definitions (Alyssa's notion) than to produce an incorrect answer (as Ben would have it).

```
(letrec ((⟨var_1⟩ ⟨exp_1⟩) ... (⟨var_n⟩ ⟨exp_n⟩))
  ⟨body⟩)
```

are a variation on `let` in which the expressions $\langle exp_k \rangle$ that provide the initial values for the variables $\langle var_k \rangle$ are evaluated in an environment that includes all the `letrec` bindings. This permits recursion in the bindings, such as the mutual recursion of `even?` and `odd?` in the example above, or the evaluation of 10 factorial with

```
(letrec
  ((fact (lambda (n)
           (if (= n 1) 1 (* n (fact (- n 1)))))))
  (fact 10))
```

a. Implement `letrec` as a derived expression, by transforming a `letrec` expression into a `let` expression as shown in the text above or in Exercise 4.18. That is, the `letrec` variables should be created with a `let` and then be assigned their values with `set!`.

b. Louis Reasoner is confused by all this fuss about internal definitions. The way he sees it, if you don't like to use `define` inside a procedure, you can just use `let`. Illustrate what is loose about his reasoning by drawing an environment diagram that shows the environment in which the ⟨*rest of body of* `f`⟩ is evaluated during evaluation of the expression `(f 5)`, with `f` defined as in this exercise. Draw an environment diagram for the same evaluation, but with `let` in place of `letrec` in the definition of `f`.

Exercise 4.21: Amazingly, Louis's intuition in Exercise 4.20 is correct. It is indeed possible to specify recursive procedures without using `letrec` (or even `define`), although the method for accomplishing this is much more subtle than Louis imagined. The following expression computes 10 factorial by applying a recursive factorial procedure:[27]

```
((lambda (n)
   ((lambda (fact) (fact fact n))
    (lambda (ft k) (if (= k 1) 1 (* k (ft ft (- k 1))))))
 10)
```

a. Check (by evaluating the expression) that this really does compute factorials. Devise an analogous expression for computing Fibonacci numbers.

b. Consider the following procedure, which includes mutually recursive internal definitions:

```
(define (f x)
  (define (even? n)
    (if (= n 0) true  (odd?  (- n 1))))
  (define (odd? n)
    (if (= n 0) false (even? (- n 1))))
  (even? x))
```

Fill in the missing expressions to complete an alternative definition of `f`, which uses neither internal definitions nor `letrec`:

[27] This example illustrates a programming trick for formulating recursive procedures without using `define`. The most general trick of this sort is the Y *operator*, which can be used to give a "pure λ-calculus" implementation of recursion. (See Stoy 1977 for details on the λ-calculus, and Gabriel 1988 for an exposition of the Y operator in Scheme.)

```
(define (f x)
  ((lambda (even? odd?) (even? even? odd? x))
   (lambda (ev? od? n)
     (if (= n 0) true (od? ⟨??⟩ ⟨??⟩ ⟨??⟩))))
   (lambda (ev? od? n)
     (if (= n 0) false (ev? ⟨??⟩ ⟨??⟩ ⟨??⟩)))))
```

4.1.7 Separating Syntactic Analysis from Execution

The evaluator implemented above is simple, but it is very inefficient, because the syntactic analysis of expressions is interleaved with their execution. Thus if a program is executed many times, its syntax is analyzed many times. Consider, for example, evaluating `(factorial 4)` using the following definition of `factorial`:

```
(define (factorial n)
  (if (= n 1) 1 (* (factorial (- n 1)) n)))
```

Each time `factorial` is called, the evaluator must determine that the body is an `if` expression and extract the predicate. Only then can it evaluate the predicate and dispatch on its value. Each time it evaluates the expression `(* (factorial (- n 1)) n)`, or the subexpressions `(factorial (- n 1))` and `(- n 1)`, the evaluator must perform the case analysis in `eval` to determine that the expression is an application, and must extract its operator and operands. This analysis is expensive. Performing it repeatedly is wasteful.

We can transform the evaluator to be significantly more efficient by arranging things so that syntactic analysis is performed only once.[28] We split

[28] This technique is an integral part of the compilation process, which we shall discuss in Chapter 5. Jonathan Rees wrote a Scheme interpreter like this in about 1982 for the T project (Rees and Adams 1982). Marc Feeley (1986) (see also Feeley and Lapalme 1987) independently invented this technique in his master's thesis.

`eval`, which takes an expression and an environment, into two parts. The procedure `analyze` takes only the expression. It performs the syntactic analysis and returns a new procedure, the *execution procedure*, that encapsulates the work to be done in executing the analyzed expression. The execution procedure takes an environment as its argument and completes the evaluation. This saves work because `analyze` will be called only once on an expression, while the execution procedure may be called many times.

With the separation into analysis and execution, `eval` now becomes

```
(define (eval exp env) ((analyze exp) env))
```

The result of calling `analyze` is the execution procedure to be applied to the environment. The `analyze` procedure is the same case analysis as performed by the original `eval` of Section 4.1.1, except that the procedures to which we dispatch perform only analysis, not full evaluation:

```
(define (analyze exp)
  (cond ((self-evaluating? exp) (analyze-self-evaluating exp
        ((quoted? exp) (analyze-quoted exp))
        ((variable? exp) (analyze-variable exp))
        ((assignment? exp) (analyze-assignment exp))
        ((definition? exp) (analyze-definition exp))
        ((if? exp) (analyze-if exp))
        ((lambda? exp) (analyze-lambda exp))
        ((begin? exp) (analyze-sequence (begin-actions exp)))
        ((cond? exp) (analyze (cond->if exp)))
        ((application? exp) (analyze-application exp))
        (else (error "Unknown expression type: ANALYZE" exp))
```

Here is the simplest syntactic analysis procedure, which handles self-evaluating expressions. It returns an execution procedure that ignores its environment argument and just returns the expression:

```
(define (analyze-self-evaluating exp)
  (lambda (env) exp))
```

For a quoted expression, we can gain a little efficiency by extracting the text of the quotation only once, in the analysis phase, rather than in the execution phase.

```
(define (analyze-quoted exp)
  (let ((qval (text-of-quotation exp)))
    (lambda (env) qval)))
```

Looking up a variable value must still be done in the execution phase, since this depends upon knowing the environment.[29]

```
(define (analyze-variable exp)
  (lambda (env) (lookup-variable-value exp env)))
```

`analyze-assignment` also must defer actually setting the variable until the execution, when the environment has been supplied. However, the fact that the `assignment-value` expression can be analyzed (recursively) during analysis is a major gain in efficiency, because the `assignment-value` expression will now be analyzed only once. The same holds true for definitions.

```
(define (analyze-assignment exp)
  (let ((var (assignment-variable exp))
        (vproc (analyze (assignment-value exp))))
    (lambda (env)
      (set-variable-value! var (vproc env) env)
      'ok)))
(define (analyze-definition exp)
  (let ((var (definition-variable exp))
        (vproc (analyze (definition-value exp)))))
```

[29] There is, however, an important part of the variable search that *can* be done as part of the syntactic analysis. As we will show in Section 5.5.6, one can determine the position in the environment structure where the value of the variable will be found, thus obviating the need to scan the environment for the entry that matches the variable.

```
    (lambda (env)
      (define-variable! var (vproc env) env)
      'ok)))
```

For `if` expressions, we extract and analyze the predicate, consequent, and alternative at analysis time.

```
(define (analyze-if exp)
  (let ((pproc (analyze (if-predicate exp)))
        (cproc (analyze (if-consequent exp)))
        (aproc (analyze (if-alternative exp))))
    (lambda (env) (if (true? (pproc env))
                      (cproc env)
                      (aproc env)))))
```

Analyzing a `lambda` expression also achieves a major gain in efficiency: We analyze the `lambda` body only once, even though procedures resulting from evaluation of the `lambda` may be applied many times.

```
(define (analyze-lambda exp)
  (let ((vars (lambda-parameters exp))
        (bproc (analyze-sequence (lambda-body exp))))
    (lambda (env) (make-procedure vars bproc env))))
```

Analysis of a sequence of expressions (as in a `begin` or the body of a `lambda` expression) is more involved.[30] Each expression in the sequence is analyzed, yielding an execution procedure. These execution procedures are combined to produce an execution procedure that takes an environment as argument and sequentially calls each individual execution procedure with the environment as argument.

```
(define (analyze-sequence exps)
  (define (sequentially proc1 proc2)
```

[30] See Exercise 4.23 for some insight into the processing of sequences.

```
    (lambda (env) (proc1 env) (proc2 env)))
  (define (loop first-proc rest-procs)
    (if (null? rest-procs)
        first-proc
        (loop (sequentially first-proc (car rest-procs))
              (cdr rest-procs))))
  (let ((procs (map analyze exps)))
    (if (null? procs) (error "Empty sequence: ANALYZE"))
    (loop (car procs) (cdr procs))))
```

To analyze an application, we analyze the operator and operands and construct an execution procedure that calls the operator execution procedure (to obtain the actual procedure to be applied) and the operand execution procedures (to obtain the actual arguments). We then pass these to `execute-application`, which is the analog of `apply` in Section 4.1.1. `execute-application` differs from `apply` in that the procedure body for a compound procedure has already been analyzed, so there is no need to do further analysis. Instead, we just call the execution procedure for the body on the extended environment.

```
(define (analyze-application exp)
  (let ((fproc (analyze (operator exp)))
        (aprocs (map analyze (operands exp))))
    (lambda (env)
      (execute-application
       (fproc env)
       (map (lambda (aproc) (aproc env))
            aprocs)))))
(define (execute-application proc args)
  (cond ((primitive-procedure? proc)
         (apply-primitive-procedure proc args))
        ((compound-procedure? proc)
         ((procedure-body proc)
```

```
        (extend-environment
         (procedure-parameters proc)
         args
         (procedure-environment proc))))
       (else
        (error "Unknown procedure type: EXECUTE-APPLICATION
               proc))))
```

Our new evaluator uses the same data structures, syntax procedures, and run-time support procedures as in sections Section 4.1.2, Section 4.1.3, and Section 4.1.4.

Exercise 4.22: Extend the evaluator in this section to support the special form `let`. (See Exercise 4.6.)

Exercise 4.23: Alyssa P. Hacker doesn't understand why `analyze-sequence` needs to be so complicated. All the other analysis procedures are straightforward transformations of the corresponding evaluation procedures (or `eval` clauses) in Section 4.1.1. She expected `analyze-sequence` to look like this:

```
(define (analyze-sequence exps)
  (define (execute-sequence procs env)
    (cond ((null? (cdr procs))
           ((car procs) env))
          (else
           ((car procs) env)
           (execute-sequence (cdr procs) env))))
  (let ((procs (map analyze exps)))
    (if (null? procs)
        (error "Empty sequence: ANALYZE"))
    (lambda (env)
      (execute-sequence procs env))))
```

Eva Lu Ator explains to Alyssa that the version in the text does more of the work of evaluating a sequence at analysis time. Alyssa's sequence-execution procedure, rather than having the calls to the individual execution procedures built in, loops through the procedures in order to call them: In effect, although the individual expressions in the sequence have been analyzed, the sequence itself has not been.

Compare the two versions of `analyze-sequence`. For example, consider the common case (typical of procedure bodies) where the sequence has just one expression. What work will the execution procedure produced by Alyssa's program do? What about the execution procedure produced by the program in the text above? How do the two versions compare for a sequence with two expressions?

Exercise 4.24: Design and carry out some experiments to compare the speed of the original metacircular evaluator with the version in this section. Use your results to estimate the fraction of time that is spent in analysis versus execution for various procedures.

4.2 Variations on a Scheme — Lazy Evaluation

Now that we have an evaluator expressed as a Lisp program, we can experiment with alternative choices in language design simply by modifying the evaluator. Indeed, new languages are often invented by first writing an evaluator that embeds the new language within an existing high-level language. For example, if we wish to discuss some aspect of a proposed modification to Lisp with another member of the Lisp community, we can supply an evaluator

that embodies the change. The recipient can then experiment with the new evaluator and send back comments as further modifications. Not only does the high-level implementation base make it easier to test and debug the evaluator; in addition, the embedding enables the designer to snarf [31] features from the underlying language, just as our embedded Lisp evaluator uses primitives and control structure from the underlying Lisp. Only later (if ever) need the designer go to the trouble of building a complete implementation in a low-level language or in hardware. In this section and the next we explore some variations on Scheme that provide significant additional expressive power.

4.2.1 Normal Order and Applicative Order

In Section 1.1, where we began our discussion of models of evaluation, we noted that Scheme is an *applicative-order* language, namely, that all the arguments to Scheme procedures are evaluated when the procedure is applied. In contrast, *normal-order* languages delay evaluation of procedure arguments until the actual argument values are needed. Delaying evaluation of procedure arguments until the last possible moment (e.g., until they are required by a primitive operation) is called *lazy evaluation*.[32] Consider the procedure

```
(define (try a b) (if (= a 0) 1 b))
```

[31] Snarf: "To grab, especially a large document or file for the purpose of using it either with or without the owner's permission." Snarf down: "To snarf, sometimes with the connotation of absorbing, processing, or understanding." (These definitions were snarfed from Steele et al. 1983. See also Raymond 1993.)

[32] The difference between the "lazy" terminology and the "normal-order" terminology is somewhat fuzzy. Generally, "lazy" refers to the mechanisms of particular evaluators, while "normal-order" refers to the semantics of languages, independent of any particular evaluation strategy. But this is not a hard-and-fast distinction, and the two terminologies are often used interchangeably.

Evaluating `(try 0 (/ 1 0))` generates an error in Scheme. With lazy evaluation, there would be no error. Evaluating the expression would return 1, because the argument `(/ 1 0)` would never be evaluated.

An example that exploits lazy evaluation is the definition of a procedure `unless`

```
(define (unless condition usual-value exceptional-value)
  (if condition exceptional-value usual-value))
```

that can be used in expressions such as

```
(unless (= b 0)
        (/ a b)
        (begin (display "exception: returning 0") 0))
```

This won't work in an applicative-order language because both the usual value and the exceptional value will be evaluated before `unless` is called (compare Exercise 1.6). An advantage of lazy evaluation is that some procedures, such as `unless`, can do useful computation even if evaluation of some of their arguments would produce errors or would not terminate.

If the body of a procedure is entered before an argument has been evaluated we say that the procedure is *non-strict* in that argument. If the argument is evaluated before the body of the procedure is entered we say that the procedure is *strict* in that argument.[33] In a purely applicative-order language, all procedures are strict in each argument. In a purely normal-order language, all compound procedures are non-strict in each argument, and primitive procedures may be either strict or non-strict. There are also languages (see Exercise

[33] The "strict" versus "non-strict" terminology means essentially the same thing as "applicative-order" versus "normal-order," except that it refers to individual procedures and arguments rather than to the language as a whole. At a conference on programming languages you might hear someone say, "The normal-order language Hassle has certain strict primitives. Other procedures take their arguments by lazy evaluation."

4.31) that give programmers detailed control over the strictness of the procedures they define.

A striking example of a procedure that can usefully be made non-strict is `cons` (or, in general, almost any constructor for data structures). One can do useful computation, combining elements to form data structures and operating on the resulting data structures, even if the values of the elements are not known. It makes perfect sense, for instance, to compute the length of a list without knowing the values of the individual elements in the list. We will exploit this idea in Section 4.2.3 to implement the streams of Chapter 3 as lists formed of non-strict `cons` pairs.

Exercise 4.25: Suppose that (in ordinary applicative-order Scheme) we define `unless` as shown above and then define `factorial` in terms of `unless` as

```
(define (factorial n)
  (unless (= n 1)
          (* n (factorial (- n 1)))
          1))
```

What happens if we attempt to evaluate `(factorial 5)`? Will our definitions work in a normal-order language?

Exercise 4.26: Ben Bitdiddle and Alyssa P. Hacker disagree over the importance of lazy evaluation for implementing things such as `unless`. Ben points out that it's possible to implement `unless` in applicative order as a special form. Alyssa counters that, if one did that, `unless` would be merely syntax, not a procedure that could be used in conjunction with higher-order procedures. Fill in the details on both sides of the argument. Show how to implement `unless` as a derived expression (like `cond` or `let`), and give an example of a situation

where it might be useful to have `unless` available as a procedure, rather than as a special form.

4.2.2 An Interpreter with Lazy Evaluation

In this section we will implement a normal-order language that is the same as Scheme except that compound procedures are non-strict in each argument. Primitive procedures will still be strict. It is not difficult to modify the evaluator of Section 4.1.1 so that the language it interprets behaves this way. Almost all the required changes center around procedure application.

The basic idea is that, when applying a procedure, the interpreter must determine which arguments are to be evaluated and which are to be delayed. The delayed arguments are not evaluated; instead, they are transformed into objects called *thunks*.[34] The thunk must contain the information required to produce the value of the argument when it is needed, as if it had been evaluated at the time of the application. Thus, the thunk must contain the argument expression and the environment in which the procedure application is being evaluated.

The process of evaluating the expression in a thunk is called *forcing*.[35] In general, a thunk will be forced only when its value is needed: when it is passed to a primitive procedure that will use the value of the thunk; when it is the value of a predicate of a conditional; and when it is the value of an operator that is about to be applied as a procedure. One design choice we have available

[34] The word *thunk* was invented by an informal working group that was discussing the implementation of call-by-name in Algol 60. They observed that most of the analysis of ("thinking about") the expression could be done at compile time; thus, at run time, the expression would already have been "thunk" about (Ingerman et al. 1960).

[35] This is analogous to the use of `force` on the delayed objects that were introduced in Chapter 3 to represent streams. The critical difference between what we are doing here and what we did in Chapter 3 is that we are building delaying and forcing into the evaluator, and thus making this uniform and automatic throughout the language.

is whether or not to *memoize* thunks, as we did with delayed objects in Section 3.5.1. With memoization, the first time a thunk is forced, it stores the value that is computed. Subsequent forcings simply return the stored value without repeating the computation. We'll make our interpreter memoize, because this is more efficient for many applications. There are tricky considerations here, however.[36]

Modifying the evaluator

The main difference between the lazy evaluator and the one in Section 4.1 is in the handling of procedure applications in `eval` and `apply`.

The `application?` clause of `eval` becomes

```
((application? exp)
 (apply (actual-value (operator exp) env)
        (operands exp)
        env))
```

This is almost the same as the `application?` clause of `eval` in Section 4.1.1. For lazy evaluation, however, we call `apply` with the operand expressions, rather than the arguments produced by evaluating them. Since we will need the environment to construct thunks if the arguments are to be delayed, we must pass this as well. We still evaluate the operator, because `apply` needs the actual procedure to be applied in order to dispatch on its type (primitive versus compound) and apply it.

[36] Lazy evaluation combined with memoization is sometimes referred to as *call-by-need* argument passing, in contrast to *call-by-name* argument passing. (Call-by-name, introduced in Algol 60, is similar to non-memoized lazy evaluation.) As language designers, we can build our evaluator to memoize, not to memoize, or leave this an option for programmers (Exercise 4.31). As you might expect from Chapter 3, these choices raise issues that become both subtle and confusing in the presence of assignments. (See Exercise 4.27 and Exercise 4.29.) An excellent article by Clinger (1982) attempts to clarify the multiple dimensions of confusion that arise here.

Whenever we need the actual value of an expression, we use

```
(define (actual-value exp env)
  (force-it (eval exp env)))
```

instead of just `eval`, so that if the expression's value is a thunk, it will be forced.

Our new version of `apply` is also almost the same as the version in Section 4.1.1. The difference is that `eval` has passed in unevaluated operand expressions: For primitive procedures (which are strict), we evaluate all the arguments before applying the primitive; for compound procedures (which are non-strict) we delay all the arguments before applying the procedure.

```
(define (apply procedure arguments env)
  (cond ((primitive-procedure? procedure)
         (apply-primitive-procedure
          procedure
          (list-of-arg-values arguments env)))    ;changed
        ((compound-procedure? procedure)
         (eval-sequence
          (procedure-body procedure)
          (extend-environment
           (procedure-parameters procedure)
           (list-of-delayed-args arguments env)   ;changed
           (procedure-environment procedure))))
        (else (error "Unknown procedure type: APPLY"
                     procedure))))
```

The procedures that process the arguments are just like `list-of-values` from Section 4.1.1, except that `list-of-delayed-args` delays the arguments instead of evaluating them, and `list-of-arg-values` uses `actual-value` instead of `eval`:

```
(define (list-of-arg-values exps env)
  (if (no-operands? exps)
```

```
      '()
      (cons (actual-value (first-operand exps)
                          env)
            (list-of-arg-values (rest-operands exps)
                                env))))
(define (list-of-delayed-args exps env)
  (if (no-operands? exps)
      '()
      (cons (delay-it (first-operand exps)
                      env)
            (list-of-delayed-args (rest-operands exps)
                                  env))))
```

The other place we must change the evaluator is in the handling of `if`, where we must use `actual-value` instead of `eval` to get the value of the predicate expression before testing whether it is true or false:

```
(define (eval-if exp env)
  (if (true? (actual-value (if-predicate exp) env))
      (eval (if-consequent exp) env)
      (eval (if-alternative exp) env)))
```

Finally, we must change the `driver-loop` procedure (Section 4.1.4) to use `actual-value` instead of `eval`, so that if a delayed value is propagated back to the read-eval-print loop, it will be forced before being printed. We also change the prompts to indicate that this is the lazy evaluator:

```
(define input-prompt  ";;; L-Eval input:")
(define output-prompt ";;; L-Eval value:")
(define (driver-loop)
  (prompt-for-input input-prompt)
  (let ((input (read)))
    (let ((output
           (actual-value
            input the-global-environment)))
```

```
      (announce-output output-prompt)
      (user-print output)))
  (driver-loop))
```

With these changes made, we can start the evaluator and test it. The successful evaluation of the `try` expression discussed in Section 4.2.1 indicates that the interpreter is performing lazy evaluation:

```
(define the-global-environment (setup-environment))
(driver-loop)
;;; L-Eval input:
(define (try a b) (if (= a 0) 1 b))
;;; L-Eval value:
ok
;;; L-Eval input:
(try 0 (/ 1 0))
;;; L-Eval value:
1
```

Representing thunks

Our evaluator must arrange to create thunks when procedures are applied to arguments and to force these thunks later. A thunk must package an expression together with the environment, so that the argument can be produced later. To force the thunk, we simply extract the expression and environment from the thunk and evaluate the expression in the environment. We use `actual-value` rather than `eval` so that in case the value of the expression is itself a thunk, we will force that, and so on, until we reach something that is not a thunk:

```
(define (force-it obj)
  (if (thunk? obj)
      (actual-value (thunk-exp obj) (thunk-env obj))
```

```
      obj))
```

One easy way to package an expression with an environment is to make a list containing the expression and the environment. Thus, we create a thunk as follows:

```
(define (delay-it exp env)
  (list 'thunk exp env))
(define (thunk? obj)
  (tagged-list? obj 'thunk))
(define (thunk-exp thunk) (cadr  thunk))
(define (thunk-env thunk) (caddr thunk))
```

Actually, what we want for our interpreter is not quite this, but rather thunks that have been memoized. When a thunk is forced, we will turn it into an evaluated thunk by replacing the stored expression with its value and changing the `thunk` tag so that it can be recognized as already evaluated.[37]

```
(define (evaluated-thunk? obj)
  (tagged-list? obj 'evaluated-thunk))
(define (thunk-value evaluated-thunk)
  (cadr evaluated-thunk))
(define (force-it obj)
  (cond ((thunk? obj)
         (let ((result (actual-value (thunk-exp obj)
                                     (thunk-env obj))))
```

[37] Notice that we also erase the `env` from the thunk once the expression's value has been computed. This makes no difference in the values returned by the interpreter. It does help save space, however, because removing the reference from the thunk to the `env` once it is no longer needed allows this structure to be *garbage-collected* and its space recycled, as we will discuss in Section 5.3.

Similarly, we could have allowed unneeded environments in the memoized delayed objects of Section 3.5.1 to be garbage-collected, by having `memo-proc` do something like `(set! proc '())` to discard the procedure `proc` (which includes the environment in which the `delay` was evaluated) after storing its value.

```
        (set-car! obj 'evaluated-thunk)
        (set-car! (cdr obj)
                  result)       ; replace exp with its value
        (set-cdr! (cdr obj)
                  '())          ; forget unneeded env
        result))
    ((evaluated-thunk? obj) (thunk-value obj))
    (else obj)))
```

Notice that the same `delay-it` procedure works both with and without memoization.

Exercise 4.27: Suppose we type in the following definitions to the lazy evaluator:

```
(define count 0)
(define (id x) (set! count (+ count 1)) x)
```

Give the missing values in the following sequence of interactions, and explain your answers.[38]

```
(define w (id (id 10)))
;;; L-Eval input:
count
;;; L-Eval value:
⟨response⟩
;;; L-Eval input:
w
;;; L-Eval value:
⟨response⟩
;;; L-Eval input:
count
```

[38] This exercise demonstrates that the interaction between lazy evaluation and side effects can be very confusing. This is just what you might expect from the discussion in Chapter 3.

```
;;; L-Eval value:
⟨response⟩
```

Exercise 4.28: `eval` uses `actual-value` rather than `eval` to evaluate the operator before passing it to `apply`, in order to force the value of the operator. Give an example that demonstrates the need for this forcing.

Exercise 4.29: Exhibit a program that you would expect to run much more slowly without memoization than with memoization. Also, consider the following interaction, where the `id` procedure is defined as in Exercise 4.27 and `count` starts at 0:

```
(define (square x) (* x x))
;;; L-Eval input:
(square (id 10))
;;; L-Eval value:
⟨response⟩
;;; L-Eval input:
count
;;; L-Eval value:
⟨response⟩
```

Give the responses both when the evaluator memoizes and when it does not.

Exercise 4.30: Cy D. Fect, a reformed C programmer, is worried that some side effects may never take place, because the lazy evaluator doesn't force the expressions in a sequence. Since the value of an expression in a sequence other than the last one is not used (the expression is there only for its effect, such as assigning to a variable or printing), there can be no subsequent use of

this value (e.g., as an argument to a primitive procedure) that will cause it to be forced. Cy thus thinks that when evaluating sequences, we must force all expressions in the sequence except the final one. He proposes to modify `eval-sequence` from Section 4.1.1 to use `actual-value` rather than `eval`:

```
(define (eval-sequence exps env)
  (cond ((last-exp? exps) (eval (first-exp exps) env))
        (else (actual-value (first-exp exps) env)
              (eval-sequence (rest-exps exps) env))))
```

a. Ben Bitdiddle thinks Cy is wrong. He shows Cy the `for-each` procedure described in Exercise 2.23, which gives an important example of a sequence with side effects:

```
(define (for-each proc items)
  (if (null? items)
      'done
      (begin (proc (car items))
             (for-each proc (cdr items)))))
```

He claims that the evaluator in the text (with the original `eval-sequence`) handles this correctly:

```
;;; L-Eval input:
(for-each (lambda (x) (newline) (display x))
          (list 57 321 88))
57
321
88
;;; L-Eval value:
done
```

Explain why Ben is right about the behavior of `for-each`.

b. Cy agrees that Ben is right about the `for-each` example, but says that that's not the kind of program he was thinking about when he proposed his change to `eval-sequence`. He defines the following two procedures in the lazy evaluator:

```
(define (p1 x)
  (set! x (cons x '(2)))
  x)
(define (p2 x)
  (define (p e)
    e
    x)
  (p (set! x (cons x '(2)))))
```

What are the values of `(p1 1)` and `(p2 1)` with the original `eval-sequence`? What would the values be with Cy's proposed change to `eval-sequence`?

c. Cy also points out that changing `eval-sequence` as he proposes does not affect the behavior of the example in part a. Explain why this is true.

d. How do you think sequences ought to be treated in the lazy evaluator? Do you like Cy's approach, the approach in the text, or some other approach?

Exercise 4.31: The approach taken in this section is somewhat unpleasant, because it makes an incompatible change to Scheme. It might be nicer to implement lazy evaluation as an *upward-compatible extension*, that is, so that ordinary Scheme programs will work as before. We can do this by extending the syntax of procedure declarations to let the user control whether or not

arguments are to be delayed. While we're at it, we may as well also give the user the choice between delaying with and without memoization. For example, the definition

```
(define (f a (b lazy) c (d lazy-memo))
  ...)
```

would define `f` to be a procedure of four arguments, where the first and third arguments are evaluated when the procedure is called, the second argument is delayed, and the fourth argument is both delayed and memoized. Thus, ordinary procedure definitions will produce the same behavior as ordinary Scheme, while adding the `lazy-memo` declaration to each parameter of every compound procedure will produce the behavior of the lazy evaluator defined in this section. Design and implement the changes required to produce such an extension to Scheme. You will have to implement new syntax procedures to handle the new syntax for `define`. You must also arrange for `eval` or `apply` to determine when arguments are to be delayed, and to force or delay arguments accordingly, and you must arrange for forcing to memoize or not, as appropriate.

4.2.3 Streams as Lazy Lists

In Section 3.5.1, we showed how to implement streams as delayed lists. We introduced special forms `delay` and `cons-stream`, which allowed us to construct a "promise" to compute the `cdr` of a stream, without actually fulfilling that promise until later. We could use this general technique of introducing special forms whenever we need more control over the evaluation process, but this is awkward. For one thing, a special form is not a first-class object like a procedure, so we cannot use it together with higher-order pro-

cedures.[39] Additionally, we were forced to create streams as a new kind of data object similar but not identical to lists, and this required us to reimplement many ordinary list operations (`map`, `append`, and so on) for use with streams.

With lazy evaluation, streams and lists can be identical, so there is no need for special forms or for separate list and stream operations. All we need to do is to arrange matters so that `cons` is non-strict. One way to accomplish this is to extend the lazy evaluator to allow for non-strict primitives, and to implement `cons` as one of these. An easier way is to recall (Section 2.1.3) that there is no fundamental need to implement `cons` as a primitive at all. Instead, we can represent pairs as procedures:[40]

```
(define (cons x y) (lambda (m) (m x y)))
(define (car z) (z (lambda (p q) p)))
(define (cdr z) (z (lambda (p q) q)))
```

In terms of these basic operations, the standard definitions of the list operations will work with infinite lists (streams) as well as finite ones, and the stream operations can be implemented as list operations. Here are some examples:

```
(define (list-ref items n)
  (if (= n 0)
      (car items)
      (list-ref (cdr items) (- n 1))))
(define (map proc items)
  (if (null? items)
      '()
```

[39] This is precisely the issue with the `unless` procedure, as in Exercise 4.26.

[40] This is the procedural representation described in Exercise 2.4. Essentially any procedural representation (e.g., a message-passing implementation) would do as well. Notice that we can install these definitions in the lazy evaluator simply by typing them at the driver loop. If we had originally included `cons`, `car`, and `cdr` as primitives in the global environment, they will be redefined. (Also see Exercise 4.33 and Exercise 4.34.)

```
      (cons (proc (car items)) (map proc (cdr items)))))
(define (scale-list items factor)
  (map (lambda (x) (* x factor)) items))
(define (add-lists list1 list2)
  (cond ((null? list1) list2)
        ((null? list2) list1)
        (else (cons (+ (car list1) (car list2))
                    (add-lists (cdr list1) (cdr list2))))))
(define ones (cons 1 ones))
(define integers (cons 1 (add-lists ones integers)))
;;; L-Eval input:
(list-ref integers 17)
;;; L-Eval value:
18
```

Note that these lazy lists are even lazier than the streams of Chapter 3: The `car` of the list, as well as the `cdr`, is delayed.[41] In fact, even accessing the `car` or `cdr` of a lazy pair need not force the value of a list element. The value will be forced only when it is really needed—e.g., for use as the argument of a primitive, or to be printed as an answer.

Lazy pairs also help with the problem that arose with streams in Section 3.5.4, where we found that formulating stream models of systems with loops may require us to sprinkle our programs with explicit `delay` operations, beyond the ones supplied by `cons-stream`. With lazy evaluation, all arguments to procedures are delayed uniformly. For instance, we can implement procedures to integrate lists and solve differential equations as we originally intended in Section 3.5.4:

```
(define (integral integrand initial-value dt)
  (define int
```

[41] This permits us to create delayed versions of more general kinds of list structures, not just sequences. Hughes 1990 discusses some applications of "lazy trees."

```
    (cons initial-value
          (add-lists (scale-list integrand dt) int)))
  int)
(define (solve f y0 dt)
  (define  y (integral dy y0 dt))
  (define dy (map f y))
  y)
;;; L-Eval input:
(list-ref (solve (lambda (x) x) 1 0.001) 1000)
;;; L-Eval value:
2.716924
```

Exercise 4.32: Give some examples that illustrate the difference between the streams of Chapter 3 and the "lazier" lazy lists described in this section. How can you take advantage of this extra laziness?

Exercise 4.33: Ben Bitdiddle tests the lazy list implementation given above by evaluating the expression:

```
(car '(a b c))
```

To his surprise, this produces an error. After some thought, he realizes that the "lists" obtained by reading in quoted expressions are different from the lists manipulated by the new definitions of `cons`, `car`, and `cdr`. Modify the evaluator's treatment of quoted expressions so that quoted lists typed at the driver loop will produce true lazy lists.

Exercise 4.34: Modify the driver loop for the evaluator so that lazy pairs and lists will print in some reasonable way. (What are you going to do about infinite lists?) You may also need to

modify the representation of lazy pairs so that the evaluator can identify them in order to print them.

4.3 Variations on a Scheme — Nondeterministic Computing

In this section, we extend the Scheme evaluator to support a programming paradigm called *nondeterministic computing* by building into the evaluator a facility to support automatic search. This is a much more profound change to the language than the introduction of lazy evaluation in Section 4.2.

Nondeterministic computing, like stream processing, is useful for "generate and test" applications. Consider the task of starting with two lists of positive integers and finding a pair of integers—one from the first list and one from the second list—whose sum is prime. We saw how to handle this with finite sequence operations in Section 2.2.3 and with infinite streams in Section 3.5.3. Our approach was to generate the sequence of all possible pairs and filter these to select the pairs whose sum is prime. Whether we actually generate the entire sequence of pairs first as in Chapter 2, or interleave the generating and filtering as in Chapter 3, is immaterial to the essential image of how the computation is organized.

The nondeterministic approach evokes a different image. Imagine simply that we choose (in some way) a number from the first list and a number from the second list and require (using some mechanism) that their sum be prime. This is expressed by following procedure:

```
(define (prime-sum-pair list1 list2)
  (let ((a (an-element-of list1))
        (b (an-element-of list2)))
    (require (prime? (+ a b)))
    (list a b)))
```

It might seem as if this procedure merely restates the problem, rather than specifying a way to solve it. Nevertheless, this is a legitimate nondeterministic program.[42]

The key idea here is that expressions in a nondeterministic language can have more than one possible value. For instance, `an-element-of` might return any element of the given list. Our nondeterministic program evaluator will work by automatically choosing a possible value and keeping track of the choice. If a subsequent requirement is not met, the evaluator will try a different choice, and it will keep trying new choices until the evaluation succeeds, or until we run out of choices. Just as the lazy evaluator freed the programmer from the details of how values are delayed and forced, the nondeterministic program evaluator will free the programmer from the details of how choices are made.

It is instructive to contrast the different images of time evoked by nondeterministic evaluation and stream processing. Stream processing uses lazy evaluation to decouple the time when the stream of possible answers is assembled from the time when the actual stream elements are produced. The evaluator supports the illusion that all the possible answers are laid out before us in a timeless sequence. With nondeterministic evaluation, an expression represents the exploration of a set of possible worlds, each determined by a set of choices. Some of the possible worlds lead to dead ends, while others have useful values. The nondeterministic program evaluator supports the illusion

[42] We assume that we have previously defined a procedure `prime?` that tests whether numbers are prime. Even with `prime?` defined, the `prime-sum-pair` procedure may look suspiciously like the unhelpful "pseudo-Lisp" attempt to define the square-root function, which we described at the beginning of Section 1.1.7. In fact, a square-root procedure along those lines can actually be formulated as a nondeterministic program. By incorporating a search mechanism into the evaluator, we are eroding the distinction between purely declarative descriptions and imperative specifications of how to compute answers. We'll go even farther in this direction in Section 4.4.

that time branches, and that our programs have different possible execution histories. When we reach a dead end, we can revisit a previous choice point and proceed along a different branch.

The nondeterministic program evaluator implemented below is called the `amb` evaluator because it is based on a new special form called `amb`. We can type the above definition of `prime-sum-pair` at the `amb` evaluator driver loop (along with definitions of `prime?`, `an-element-of`, and `require`) and run the procedure as follows:

```
;;; Amb-Eval input:
(prime-sum-pair '(1 3 5 8) '(20 35 110))
;;; Starting a new problem
;;; Amb-Eval value:
(3 20)
```

The value returned was obtained after the evaluator repeatedly chose elements from each of the lists, until a successful choice was made.

Section 4.3.1 introduces `amb` and explains how it supports nondeterminism through the evaluator's automatic search mechanism. Section 4.3.2 presents examples of nondeterministic programs, and Section 4.3.3 gives the details of how to implement the `amb` evaluator by modifying the ordinary Scheme evaluator.

4.3.1 Amb and Search

To extend Scheme to support nondeterminism, we introduce a new special form called `amb`.[43] The expression

`(amb` $\langle e_1 \rangle$ $\langle e_2 \rangle$ ... $\langle e_n \rangle$`)`

[43] The idea of `amb` for nondeterministic programming was first described in 1961 by John McCarthy (see McCarthy 1963).

returns the value of one of the n expressions $\langle e_i \rangle$ "ambiguously." For example, the expression

```
(list (amb 1 2 3) (amb 'a 'b))
```

can have six possible values:

```
(1 a) (1 b) (2 a) (2 b) (3 a) (3 b)
```

`amb` with a single choice produces an ordinary (single) value.

`amb` with no choices—the expression `(amb)` —is an expression with no acceptable values. Operationally, we can think of `(amb)` as an expression that when evaluated causes the computation to "fail": The computation aborts and no value is produced. Using this idea, we can express the requirement that a particular predicate expression `p` must be true as follows:

```
(define (require p) (if (not p) (amb)))
```

With `amb` and `require`, we can implement the `an-element-of` procedure used above:

```
(define (an-element-of items)
  (require (not (null? items)))
  (amb (car items) (an-element-of (cdr items))))
```

`an-element-of` fails if the list is empty. Otherwise it ambiguously returns either the first element of the list or an element chosen from the rest of the list.

We can also express infinite ranges of choices. The following procedure potentially returns any integer greater than or equal to some given n:

```
(define (an-integer-starting-from n)
  (amb n (an-integer-starting-from (+ n 1))))
```

This is like the stream procedure `integers-starting-from` described in Section 3.5.2, but with an important difference: The stream proce-

dure returns an object that represents the sequence of all integers beginning with n, whereas the `amb` procedure returns a single integer.[44]

Abstractly, we can imagine that evaluating an `amb` expression causes time to split into branches, where the computation continues on each branch with one of the possible values of the expression. We say that `amb` represents a *nondeterministic choice point*. If we had a machine with a sufficient number of processors that could be dynamically allocated, we could implement the search in a straightforward way. Execution would proceed as in a sequential machine, until an `amb` expression is encountered. At this point, more processors would be allocated and initialized to continue all of the parallel executions implied by the choice. Each processor would proceed sequentially as if it were the only choice, until it either terminates by encountering a failure, or it further subdivides, or it finishes.[45]

On the other hand, if we have a machine that can execute only one process (or a few concurrent processes), we must consider the alternatives sequentially. One could imagine modifying an evaluator to pick at random a branch to follow whenever it encounters a choice point. Random choice, however, can easily lead to failing values. We might try running the evaluator over and over, making random choices and hoping to find a non-failing value, but it is

[44] In actuality, the distinction between nondeterministically returning a single choice and returning all choices depends somewhat on our point of view. From the perspective of the code that uses the value, the nondeterministic choice returns a single value. From the perspective of the programmer designing the code, the nondeterministic choice potentially returns all possible values, and the computation branches so that each value is investigated separately.

[45] One might object that this is a hopelessly inefficient mechanism. It might require millions of processors to solve some easily stated problem this way, and most of the time most of those processors would be idle. This objection should be taken in the context of history. Memory used to be considered just such an expensive commodity. In 1964 a megabyte of RAM cost about $400,000. Now every personal computer has many megabytes of RAM, and most of the time most of that RAM is unused. It is hard to underestimate the cost of mass-produced electronics.

better to *systematically search* all possible execution paths. The `amb` evaluator that we will develop and work with in this section implements a systematic search as follows: When the evaluator encounters an application of `amb`, it initially selects the first alternative. This selection may itself lead to a further choice. The evaluator will always initially choose the first alternative at each choice point. If a choice results in a failure, then the evaluator automagically[46] *backtracks* to the most recent choice point and tries the next alternative. If it runs out of alternatives at any choice point, the evaluator will back up to the previous choice point and resume from there. This process leads to a search strategy known as *depth-first search* or *chronological backtracking*.[47]

[46] Automagically: "Automatically, but in a way which, for some reason (typically because it is too complicated, or too ugly, or perhaps even too trivial), the speaker doesn't feel like explaining." (Steele et al. 1983, Raymond 1993)

[47] The integration of automatic search strategies into programming languages has had a long and checkered history. The first suggestions that nondeterministic algorithms might be elegantly encoded in a programming language with search and automatic backtracking came from Robert Floyd (1967). Carl Hewitt (1969) invented a programming language called Planner that explicitly supported automatic chronological backtracking, providing for a built-in depth-first search strategy. Sussman et al. (1971) implemented a subset of this language, called MicroPlanner, which was used to support work in problem solving and robot planning. Similar ideas, arising from logic and theorem proving, led to the genesis in Edinburgh and Marseille of the elegant language Prolog (which we will discuss in Section 4.4). After sufficient frustration with automatic search, McDermott and Sussman (1972) developed a language called Conniver, which included mechanisms for placing the search strategy under programmer control. This proved unwieldy, however, and Sussman and Stallman 1975 found a more tractable approach while investigating methods of symbolic analysis for electrical circuits. They developed a non-chronological backtracking scheme that was based on tracing out the logical dependencies connecting facts, a technique that has come to be known as *dependency-directed backtracking*. Although their method was complex, it produced reasonably efficient programs because it did little redundant search. Doyle (1979) and McAllester (1978; 1980) generalized and clarified the methods of Stallman and Sussman, developing a new paradigm for formulating search that is now called *truth maintenance*. Modern problem-solving systems all use some form of truth-maintenance system as a substrate. See Forbus and deKleer 1993 for a discus-

Driver loop

The driver loop for the `amb` evaluator has some unusual properties. It reads an expression and prints the value of the first non-failing execution, as in the `prime-sum-pair` example shown above. If we want to see the value of the next successful execution, we can ask the interpreter to backtrack and attempt to generate a second non-failing execution. This is signaled by typing the symbol `try-again`. If any expression except `try-again` is given, the interpreter will start a new problem, discarding the unexplored alternatives in the previous problem. Here is a sample interaction:

```
;;; Amb-Eval input:
(prime-sum-pair '(1 3 5 8) '(20 35 110))
;;; Starting a new problem
;;; Amb-Eval value:
(3 20)

;;; Amb-Eval input:
try-again
;;; Amb-Eval value:
(3 110)

;;; Amb-Eval input:
try-again
;;; Amb-Eval value:
(8 35)

;;; Amb-Eval input:
```

sion of elegant ways to build truth-maintenance systems and applications using truth maintenance. Zabih et al. 1987 describes a nondeterministic extension to Scheme that is based on `amb`; it is similar to the interpreter described in this section, but more sophisticated, because it uses dependency-directed backtracking rather than chronological backtracking. Winston 1992 gives an introduction to both kinds of backtracking.

```
try-again
;;; There are no more values of
(prime-sum-pair (quote (1 3 5 8)) (quote (20 35 110)))

;;; Amb-Eval input:
(prime-sum-pair '(19 27 30) '(11 36 58))
;;; Starting a new problem
;;; Amb-Eval value:
(30 11)
```

Exercise 4.35: Write a procedure `an-integer-between` that returns an integer between two given bounds. This can be used to implement a procedure that finds Pythagorean triples, i.e., triples of integers (i, j, k) between the given bounds such that $i \leq j$ and $i^2 + j^2 = k^2$, as follows:

```
(define (a-pythagorean-triple-between low high)
  (let ((i (an-integer-between low high)))
    (let ((j (an-integer-between i high)))
      (let ((k (an-integer-between j high)))
        (require (= (+ (* i i) (* j j)) (* k k)))
        (list i j k)))))
```

Exercise 4.36: Exercise 3.69 discussed how to generate the stream of *all* Pythagorean triples, with no upper bound on the size of the integers to be searched. Explain why simply replacing `an-integer-between` by `an-integer-starting-from` in the procedure in Exercise 4.35 is not an adequate way to generate arbitrary Pythagorean triples. Write a procedure that actually will accomplish this. (That is, write a procedure for which repeatedly typing `try-again` would in principle eventually generate all Pythagorean triples.)

Exercise 4.37: Ben Bitdiddle claims that the following method for generating Pythagorean triples is more efficient than the one in Exercise 4.35. Is he correct? (Hint: Consider the number of possibilities that must be explored.)

```
(define (a-pythagorean-triple-between low high)
  (let ((i (an-integer-between low high))
        (hsq (* high high)))
    (let ((j (an-integer-between i high)))
      (let ((ksq (+ (* i i) (* j j))))
        (require (>= hsq ksq))
        (let ((k (sqrt ksq)))
          (require (integer? k))
          (list i j k))))))
```

4.3.2 Examples of Nondeterministic Programs

Section 4.3.3 describes the implementation of the `amb` evaluator. First, however, we give some examples of how it can be used. The advantage of nondeterministic programming is that we can suppress the details of how search is carried out, thereby expressing our programs at a higher level of abstraction.

Logic Puzzles

The following puzzle (taken from Dinesman 1968) is typical of a large class of simple logic puzzles:

> Baker, Cooper, Fletcher, Miller, and Smith live on different floors of an apartment house that contains only five floors. Baker does not live on the top floor. Cooper does not live on the bottom floor. Fletcher does not live on either the top or the bottom floor. Miller lives on a higher floor than does Cooper. Smith

does not live on a floor adjacent to Fletcher's. Fletcher does not live on a floor adjacent to Cooper's. Where does everyone live?

We can determine who lives on each floor in a straightforward way by enumerating all the possibilities and imposing the given restrictions:[48]

```
(define (multiple-dwelling)
  (let ((baker    (amb 1 2 3 4 5)) (cooper (amb 1 2 3 4 5))
        (fletcher (amb 1 2 3 4 5)) (miller (amb 1 2 3 4 5))
        (smith    (amb 1 2 3 4 5)))
    (require
     (distinct? (list baker cooper fletcher miller smith)))
    (require (not (= baker 5)))
    (require (not (= cooper 1)))
    (require (not (= fletcher 5)))
    (require (not (= fletcher 1)))
    (require (> miller cooper))
    (require (not (= (abs (- smith fletcher)) 1)))
    (require (not (= (abs (- fletcher cooper)) 1)))
    (list (list 'baker baker)       (list 'cooper cooper)
          (list 'fletcher fletcher) (list 'miller miller)
          (list 'smith smith))))
```

Evaluating the expression `(multiple-dwelling)` produces the result

```
((baker 3) (cooper 2) (fletcher 4) (miller 5) (smith 1))
```

[48] Our program uses the following procedure to determine if the elements of a list are distinct:

```
(define (distinct? items)
  (cond ((null? items) true)
        ((null? (cdr items)) true)
        ((member (car items) (cdr items)) false)
        (else (distinct? (cdr items)))))
```

`member` is like `memq` except that it uses `equal?` instead of `eq?` to test for equality.

Although this simple procedure works, it is very slow. Exercise 4.39 and Exercise 4.40 discuss some possible improvements.

Exercise 4.38: Modify the multiple-dwelling procedure to omit the requirement that Smith and Fletcher do not live on adjacent floors. How many solutions are there to this modified puzzle?

Exercise 4.39: Does the order of the restrictions in the multiple-dwelling procedure affect the answer? Does it affect the time to find an answer? If you think it matters, demonstrate a faster program obtained from the given one by reordering the restrictions. If you think it does not matter, argue your case.

Exercise 4.40: In the multiple dwelling problem, how many sets of assignments are there of people to floors, both before and after the requirement that floor assignments be distinct? It is very inefficient to generate all possible assignments of people to floors and then leave it to backtracking to eliminate them. For example, most of the restrictions depend on only one or two of the person-floor variables, and can thus be imposed before floors have been selected for all the people. Write and demonstrate a much more efficient nondeterministic procedure that solves this problem based upon generating only those possibilities that are not already ruled out by previous restrictions. (Hint: This will require a nest of `let` expressions.)

Exercise 4.41: Write an ordinary Scheme program to solve the multiple dwelling puzzle.

Exercise 4.42: Solve the following "Liars" puzzle (from Phillips 1934):

Five schoolgirls sat for an examination. Their parents—so they thought—showed an undue degree of interest in the result. They therefore agreed that, in writing home about the examination, each girl should make one true statement and one untrue one. The following are the relevant passages from their letters:

- Betty: "Kitty was second in the examination. I was only third."
- Ethel: "You'll be glad to hear that I was on top. Joan was 2nd."
- Joan: "I was third, and poor old Ethel was bottom."
- Kitty: "I came out second. Mary was only fourth."
- Mary: "I was fourth. Top place was taken by Betty."

What in fact was the order in which the five girls were placed?

Exercise 4.43: Use the `amb` evaluator to solve the following puzzle:[49]

Mary Ann Moore's father has a yacht and so has each of his four friends: Colonel Downing, Mr. Hall, Sir Barnacle Hood, and Dr. Parker. Each of the five also has one daughter and each has named his yacht after a daughter of one of the others. Sir Barnacle's yacht is the Gabrielle, Mr. Moore owns the Lorna; Mr. Hall the Rosalind. The Melissa, owned by Colonel Downing, is named after Sir Barnacle's daughter. Gabrielle's father owns the yacht that is named after Dr. Parker's daughter. Who is Lorna's father?

[49] This is taken from a booklet called "Problematical Recreations," published in the 1960s by Litton Industries, where it is attributed to the *Kansas State Engineer*.

Try to write the program so that it runs efficiently (see Exercise 4.40). Also determine how many solutions there are if we are not told that Mary Ann's last name is Moore.

Exercise 4.44: Exercise 2.42 described the "eight-queens puzzle" of placing queens on a chessboard so that no two attack each other. Write a nondeterministic program to solve this puzzle.

Parsing natural language

Programs designed to accept natural language as input usually start by attempting to *parse* the input, that is, to match the input against some grammatical structure. For example, we might try to recognize simple sentences consisting of an article followed by a noun followed by a verb, such as "The cat eats." To accomplish such an analysis, we must be able to identify the parts of speech of individual words. We could start with some lists that classify various words:[50]

```
(define nouns '(noun student professor cat class))
(define verbs '(verb studies lectures eats sleeps))
(define articles '(article the a))
```

We also need a *grammar*, that is, a set of rules describing how grammatical elements are composed from simpler elements. A very simple grammar might stipulate that a sentence always consists of two pieces—a noun phrase followed by a verb—and that a noun phrase consists of an article followed by a noun. With this grammar, the sentence "The cat eats" is parsed as follows:

```
(sentence (noun-phrase (article the) (noun cat))
          (verb eats))
```

[50] Here we use the convention that the first element of each list designates the part of speech for the rest of the words in the list.

We can generate such a parse with a simple program that has separate procedures for each of the grammatical rules. To parse a sentence, we identify its two constituent pieces and return a list of these two elements, tagged with the symbol `sentence`:

```
(define (parse-sentence)
  (list 'sentence
        (parse-noun-phrase)
        (parse-word verbs)))
```

A noun phrase, similarly, is parsed by finding an article followed by a noun:

```
(define (parse-noun-phrase)
  (list 'noun-phrase
        (parse-word articles)
        (parse-word nouns)))
```

At the lowest level, parsing boils down to repeatedly checking that the next unparsed word is a member of the list of words for the required part of speech. To implement this, we maintain a global variable `*unparsed*`, which is the input that has not yet been parsed. Each time we check a word, we require that `*unparsed*` must be non-empty and that it should begin with a word from the designated list. If so, we remove that word from `*unparsed*` and return the word together with its part of speech (which is found at the head of the list):[51]

```
(define (parse-word word-list)
  (require (not (null? *unparsed*)))
  (require (memq (car *unparsed*) (cdr word-list)))
  (let ((found-word (car *unparsed*)))
    (set! *unparsed* (cdr *unparsed*))
    (list (car word-list) found-word)))
```

[51] Notice that `parse-word` uses `set!` to modify the unparsed input list. For this to work, our `amb` evaluator must undo the effects of `set!` operations when it backtracks.

To start the parsing, all we need to do is set `*unparsed*` to be the entire input, try to parse a sentence, and check that nothing is left over:

```
(define *unparsed* '())
(define (parse input)
  (set! *unparsed* input)
  (let ((sent (parse-sentence)))
    (require (null? *unparsed*)) sent))
```

We can now try the parser and verify that it works for our simple test sentence:

```
;;; Amb-Eval input:
(parse '(the cat eats))
;;; Starting a new problem
;;; Amb-Eval value:

(sentence (noun-phrase (article the) (noun cat)) (verb eats))
```

The `amb` evaluator is useful here because it is convenient to express the parsing constraints with the aid of `require`. Automatic search and backtracking really pay off, however, when we consider more complex grammars where there are choices for how the units can be decomposed.

Let's add to our grammar a list of prepositions:

```
(define prepositions '(prep for to in by with))
```

and define a prepositional phrase (e.g., "for the cat") to be a preposition followed by a noun phrase:

```
(define (parse-prepositional-phrase)
  (list 'prep-phrase
        (parse-word prepositions)
        (parse-noun-phrase)))
```

Now we can define a sentence to be a noun phrase followed by a verb phrase, where a verb phrase can be either a verb or a verb phrase extended by a

prepositional phrase:[52]

```
(define (parse-sentence)
  (list 'sentence (parse-noun-phrase) (parse-verb-phrase)))
(define (parse-verb-phrase)
  (define (maybe-extend verb-phrase)
    (amb verb-phrase
         (maybe-extend
          (list 'verb-phrase
                verb-phrase
                (parse-prepositional-phrase)))))
  (maybe-extend (parse-word verbs)))
```

While we're at it, we can also elaborate the definition of noun phrases to permit such things as "a cat in the class." What we used to call a noun phrase, we'll now call a simple noun phrase, and a noun phrase will now be either a simple noun phrase or a noun phrase extended by a prepositional phrase:

```
(define (parse-simple-noun-phrase)
  (list 'simple-noun-phrase
        (parse-word articles)
        (parse-word nouns)))
(define (parse-noun-phrase)
  (define (maybe-extend noun-phrase)
    (amb noun-phrase
         (maybe-extend
          (list 'noun-phrase
                noun-phrase
                (parse-prepositional-phrase)))))
  (maybe-extend (parse-simple-noun-phrase)))
```

Our new grammar lets us parse more complex sentences. For example

[52] Observe that this definition is recursive—a verb may be followed by any number of prepositional phrases.

```
(parse '(the student with the cat sleeps in the class))
```

produces

```
(sentence
 (noun-phrase
  (simple-noun-phrase (article the) (noun student))
  (prep-phrase
   (prep with)
   (simple-noun-phrase (article the) (noun cat))))
 (verb-phrase
  (verb sleeps)
  (prep-phrase
   (prep in)
   (simple-noun-phrase (article the) (noun class)))))
```

Observe that a given input may have more than one legal parse. In the sentence "The professor lectures to the student with the cat," it may be that the professor is lecturing with the cat, or that the student has the cat. Our nondeterministic program finds both possibilities:

```
(parse '(the professor lectures to the student with the cat)
```

produces

```
(sentence
 (simple-noun-phrase (article the) (noun professor))
 (verb-phrase
  (verb-phrase
   (verb lectures)
   (prep-phrase
    (prep to)
    (simple-noun-phrase (article the) (noun student))))
  (prep-phrase
   (prep with)
   (simple-noun-phrase (article the) (noun cat)))))
```

Asking the evaluator to try again yields

```
(sentence
 (simple-noun-phrase (article the) (noun professor))
 (verb-phrase
  (verb lectures)
  (prep-phrase
   (prep to)
   (noun-phrase
    (simple-noun-phrase (article the) (noun student))
    (prep-phrase
     (prep with)
     (simple-noun-phrase (article the) (noun cat)))))))
```

Exercise 4.45: With the grammar given above, the following sentence can be parsed in five different ways: "The professor lectures to the student in the class with the cat." Give the five parses and explain the differences in shades of meaning among them.

Exercise 4.46: The evaluators in Section 4.1 and Section 4.2 do not determine what order operands are evaluated in. We will see that the `amb` evaluator evaluates them from left to right. Explain why our parsing program wouldn't work if the operands were evaluated in some other order.

Exercise 4.47: Louis Reasoner suggests that, since a verb phrase is either a verb or a verb phrase followed by a prepositional phrase, it would be much more straightforward to define the procedure `parse-verb-phrase` as follows (and similarly for noun phrases):

```
(define (parse-verb-phrase)
```

```
(amb (parse-word verbs)
     (list 'verb-phrase
           (parse-verb-phrase)
           (parse-prepositional-phrase))))
```

Does this work? Does the program's behavior change if we interchange the order of expressions in the `amb`?

Exercise 4.48: Extend the grammar given above to handle more complex sentences. For example, you could extend noun phrases and verb phrases to include adjectives and adverbs, or you could handle compound sentences.[53]

Exercise 4.49: Alyssa P. Hacker is more interested in generating interesting sentences than in parsing them. She reasons that by simply changing the procedure `parse-word` so that it ignores the "input sentence" and instead always succeeds and generates an appropriate word, we can use the programs we had built for parsing to do generation instead. Implement Alyssa's idea, and show the first half-dozen or so sentences generated.[54]

[53] This kind of grammar can become arbitrarily complex, but it is only a toy as far as real language understanding is concerned. Real natural-language understanding by computer requires an elaborate mixture of syntactic analysis and interpretation of meaning. On the other hand, even toy parsers can be useful in supporting flexible command languages for programs such as information-retrieval systems. Winston 1992 discusses computational approaches to real language understanding and also the applications of simple grammars to command languages.

[54] Although Alyssa's idea works just fine (and is surprisingly simple), the sentences that it generates are a bit boring—they don't sample the possible sentences of this language in a very interesting way. In fact, the grammar is highly recursive in many places, and Alyssa's technique "falls into" one of these recursions and gets stuck. See Exercise 4.50 for a way to deal with this.

4.3.3 Implementing the `amb` Evaluator

The evaluation of an ordinary Scheme expression may return a value, may never terminate, or may signal an error. In nondeterministic Scheme the evaluation of an expression may in addition result in the discovery of a dead end, in which case evaluation must backtrack to a previous choice point. The interpretation of nondeterministic Scheme is complicated by this extra case.

We will construct the `amb` evaluator for nondeterministic Scheme by modifying the analyzing evaluator of Section 4.1.7.[55] As in the analyzing evaluator, evaluation of an expression is accomplished by calling an execution procedure produced by analysis of that expression. The difference between the interpretation of ordinary Scheme and the interpretation of nondeterministic Scheme will be entirely in the execution procedures.

Execution procedures and continuations

Recall that the execution procedures for the ordinary evaluator take one argument: the environment of execution. In contrast, the execution procedures in the `amb` evaluator take three arguments: the environment, and two procedures called *continuation procedures*. The evaluation of an expression will finish by calling one of these two continuations: If the evaluation results in a value, the *success continuation* is called with that value; if the evaluation results in the discovery of a dead end, the *failure continuation* is called. Constructing and calling appropriate continuations is the mechanism by which the nondeterministic evaluator implements backtracking.

It is the job of the success continuation to receive a value and proceed with

[55] We chose to implement the lazy evaluator in Section 4.2 as a modification of the ordinary metacircular evaluator of Section 4.1.1. In contrast, we will base the `amb` evaluator on the analyzing evaluator of Section 4.1.7, because the execution procedures in that evaluator provide a convenient framework for implementing backtracking.

the computation. Along with that value, the success continuation is passed another failure continuation, which is to be called subsequently if the use of that value leads to a dead end.

It is the job of the failure continuation to try another branch of the nondeterministic process. The essence of the nondeterministic language is in the fact that expressions may represent choices among alternatives. The evaluation of such an expression must proceed with one of the indicated alternative choices, even though it is not known in advance which choices will lead to acceptable results. To deal with this, the evaluator picks one of the alternatives and passes this value to the success continuation. Together with this value, the evaluator constructs and passes along a failure continuation that can be called later to choose a different alternative.

A failure is triggered during evaluation (that is, a failure continuation is called) when a user program explicitly rejects the current line of attack (for example, a call to `require` may result in execution of `(amb)`, an expression that always fails—see Section 4.3.1). The failure continuation in hand at that point will cause the most recent choice point to choose another alternative. If there are no more alternatives to be considered at that choice point, a failure at an earlier choice point is triggered, and so on. Failure continuations are also invoked by the driver loop in response to a `try-again` request, to find another value of the expression.

In addition, if a side-effect operation (such as assignment to a variable) occurs on a branch of the process resulting from a choice, it may be necessary, when the process finds a dead end, to undo the side effect before making a new choice. This is accomplished by having the side-effect operation produce a failure continuation that undoes the side effect and propagates the failure.

In summary, failure continuations are constructed by

- `amb` expressions—to provide a mechanism to make alternative choices if the current choice made by the `amb` expression leads to a dead end;

- the top-level driver—to provide a mechanism to report failure when the choices are exhausted;
- assignments—to intercept failures and undo assignments during backtracking.

Failures are initiated only when a dead end is encountered. This occurs

- if the user program executes `(amb)`;
- if the user types `try-again` at the top-level driver.

Failure continuations are also called during processing of a failure:

- When the failure continuation created by an assignment finishes undoing a side effect, it calls the failure continuation it intercepted, in order to propagate the failure back to the choice point that led to this assignment or to the top level.
- When the failure continuation for an `amb` runs out of choices, it calls the failure continuation that was originally given to the `amb`, in order to propagate the failure back to the previous choice point or to the top level.

Structure of the evaluator

The syntax- and data-representation procedures for the `amb` evaluator, and also the basic `analyze` procedure, are identical to those in the evaluator of Section 4.1.7, except for the fact that we need additional syntax procedures to recognize the `amb` special form:[56]

[56] We assume that the evaluator supports `let` (see Exercise 4.22), which we have used in our nondeterministic programs.

```
(define (amb? exp) (tagged-list? exp 'amb))
(define (amb-choices exp) (cdr exp))
```

We must also add to the dispatch in `analyze` a clause that will recognize this special form and generate an appropriate execution procedure:

```
((amb? exp) (analyze-amb exp))
```

The top-level procedure `ambeval` (similar to the version of `eval` given in Section 4.1.7) analyzes the given expression and applies the resulting execution procedure to the given environment, together with two given continuations:

```
(define (ambeval exp env succeed fail)
  ((analyze exp) env succeed fail))
```

A success continuation is a procedure of two arguments: the value just obtained and another failure continuation to be used if that value leads to a subsequent failure. A failure continuation is a procedure of no arguments. So the general form of an execution procedure is

```
(lambda (env succeed fail)
  ;; succeed is (lambda (value fail) ...)
  ;; fail is (lambda () ...)
  ...)
```

For example, executing

```
(ambeval ⟨exp⟩
         the-global-environment
         (lambda (value fail) value)
         (lambda () 'failed))
```

will attempt to evaluate the given expression and will return either the expression's value (if the evaluation succeeds) or the symbol `failed` (if the evaluation fails). The call to `ambeval` in the driver loop shown below uses

much more complicated continuation procedures, which continue the loop and support the `try-again` request.

Most of the complexity of the `amb` evaluator results from the mechanics of passing the continuations around as the execution procedures call each other. In going through the following code, you should compare each of the execution procedures with the corresponding procedure for the ordinary evaluator given in Section 4.1.7.

Simple expressions

The execution procedures for the simplest kinds of expressions are essentially the same as those for the ordinary evaluator, except for the need to manage the continuations. The execution procedures simply succeed with the value of the expression, passing along the failure continuation that was passed to them.

```
(define (analyze-self-evaluating exp)
  (lambda (env succeed fail)
    (succeed exp fail)))
(define (analyze-quoted exp)
  (let ((qval (text-of-quotation exp)))
    (lambda (env succeed fail)
      (succeed qval fail))))
(define (analyze-variable exp)
  (lambda (env succeed fail)
    (succeed (lookup-variable-value exp env) fail)))
(define (analyze-lambda exp)
  (let ((vars (lambda-parameters exp))
        (bproc (analyze-sequence (lambda-body exp))))
    (lambda (env succeed fail)
      (succeed (make-procedure vars bproc env) fail))))
```

Notice that looking up a variable always 'succeeds.' If `lookup-variable-value` fails to find the variable, it signals an error, as usual. Such a "failure" indicates a program bug—a reference to an unbound variable; it is not an indication that we should try another nondeterministic choice instead of the one that is currently being tried.

Conditionals and sequences

Conditionals are also handled in a similar way as in the ordinary evaluator. The execution procedure generated by `analyze-if` invokes the predicate execution procedure `pproc` with a success continuation that checks whether the predicate value is true and goes on to execute either the consequent or the alternative. If the execution of `pproc` fails, the original failure continuation for the `if` expression is called.

```
(define (analyze-if exp)
  (let ((pproc (analyze (if-predicate exp)))
        (cproc (analyze (if-consequent exp)))
        (aproc (analyze (if-alternative exp))))
    (lambda (env succeed fail)
      (pproc env
             ;; success continuation for evaluating the predicate
             ;; to obtain pred-value
             (lambda (pred-value fail2)
               (if (true? pred-value)
                   (cproc env succeed fail2)
                   (aproc env succeed fail2)))
             ;; failure continuation for evaluating the predicate
             fail))))
```

Sequences are also handled in the same way as in the previous evaluator, except for the machinations in the subprocedure `sequentially` that are

required for passing the continuations. Namely, to sequentially execute `a` and then `b`, we call `a` with a success continuation that calls `b`.

```
(define (analyze-sequence exps)
  (define (sequentially a b)
    (lambda (env succeed fail)
      (a env
         ;; success continuation for calling a
         (lambda (a-value fail2)
           (b env succeed fail2))
         ;; failure continuation for calling a
         fail)))
  (define (loop first-proc rest-procs)
    (if (null? rest-procs)
        first-proc
        (loop (sequentially first-proc
                            (car rest-procs))
              (cdr rest-procs))))
  (let ((procs (map analyze exps)))
    (if (null? procs)
        (error "Empty sequence: ANALYZE"))
    (loop (car procs) (cdr procs))))
```

Definitions and assignments

Definitions are another case where we must go to some trouble to manage the continuations, because it is necessary to evaluate the definition-value expression before actually defining the new variable. To accomplish this, the definition-value execution procedure `vproc` is called with the environment, a success continuation, and the failure continuation. If the execution of `vproc` succeeds, obtaining a value `val` for the defined variable, the variable is defined and the success is propagated:

```
(define (analyze-definition exp)
  (let ((var (definition-variable exp))
        (vproc (analyze (definition-value exp))))
    (lambda (env succeed fail)
      (vproc env
             (lambda (val fail2)
               (define-variable! var val env)
               (succeed 'ok fail2))
             fail))))
```

Assignments are more interesting. This is the first place where we really use the continuations, rather than just passing them around. The execution procedure for assignments starts out like the one for definitions. It first attempts to obtain the new value to be assigned to the variable. If this evaluation of `vproc` fails, the assignment fails.

If `vproc` succeeds, however, and we go on to make the assignment, we must consider the possibility that this branch of the computation might later fail, which will require us to backtrack out of the assignment. Thus, we must arrange to undo the assignment as part of the backtracking process.[57]

This is accomplished by giving `vproc` a success continuation (marked with the comment "*1*" below) that saves the old value of the variable before assigning the new value to the variable and proceeding from the assignment. The failure continuation that is passed along with the value of the assignment (marked with the comment "*2*" below) restores the old value of the variable before continuing the failure. That is, a successful assignment provides a failure continuation that will intercept a subsequent failure; whatever failure would otherwise have called `fail2` calls this procedure instead, to undo the assignment before actually calling `fail2`.

[57] We didn't worry about undoing definitions, since we can assume that internal definitions are scanned out (Section 4.1.6).

```
(define (analyze-assignment exp)
  (let ((var (assignment-variable exp))
        (vproc (analyze (assignment-value exp))))
    (lambda (env succeed fail)
      (vproc env
             (lambda (val fail2)        ;*1*
               (let ((old-value
                      (lookup-variable-value var env)))
                 (set-variable-value! var val env)
                 (succeed 'ok
                          (lambda ()    ;*2*
                            (set-variable-value!
                             var old-value env)
                            (fail2)))))
             fail))))
```

Procedure applications

The execution procedure for applications contains no new ideas except for the technical complexity of managing the continuations. This complexity arises in `analyze-application`, due to the need to keep track of the success and failure continuations as we evaluate the operands. We use a procedure `get-args` to evaluate the list of operands, rather than a simple `map` as in the ordinary evaluator.

```
(define (analyze-application exp)
  (let ((fproc (analyze (operator exp)))
        (aprocs (map analyze (operands exp))))
    (lambda (env succeed fail)
      (fproc env
             (lambda (proc fail2)
               (get-args aprocs
                         env
```

```
                              (lambda (args fail3)
                                (execute-application
                                 proc args succeed fail3))
                              fail2))
                fail))))
```

In `get-args`, notice how `cdr`-ing down the list of `aproc` execution procedures and `cons`ing up the resulting list of `args` is accomplished by calling each `aproc` in the list with a success continuation that recursively calls `get-args`. Each of these recursive calls to `get-args` has a success continuation whose value is the `cons` of the newly obtained argument onto the list of accumulated arguments:

```
(define (get-args aprocs env succeed fail)
  (if (null? aprocs)
      (succeed '() fail)
      ((car aprocs)
       env
       ;; success continuation for this aproc
       (lambda (arg fail2)
         (get-args
          (cdr aprocs)
          env
          ;; success continuation for
          ;; recursive call to get-args
          (lambda (args fail3)
            (succeed (cons arg args) fail3))
          fail2))
       fail)))
```

The actual procedure application, which is performed by `execute-application`, is accomplished in the same way as for the ordinary evaluator, except for the need to manage the continuations.

```
(define (execute-application proc args succeed fail)
  (cond ((primitive-procedure? proc)
         (succeed (apply-primitive-procedure proc args)
                  fail))
        ((compound-procedure? proc)
         ((procedure-body proc)
          (extend-environment
           (procedure-parameters proc)
           args
           (procedure-environment proc))
          succeed
          fail))
        (else
         (error "Unknown procedure type: EXECUTE-APPLICATION
                proc))))
```

Evaluating `amb` expressions

The `amb` special form is the key element in the nondeterministic language. Here we see the essence of the interpretation process and the reason for keeping track of the continuations. The execution procedure for `amb` defines a loop `try-next` that cycles through the execution procedures for all the possible values of the `amb` expression. Each execution procedure is called with a failure continuation that will try the next one. When there are no more alternatives to try, the entire `amb` expression fails.

```
(define (analyze-amb exp)
  (let ((cprocs (map analyze (amb-choices exp))))
    (lambda (env succeed fail)
      (define (try-next choices)
        (if (null? choices)
            (fail)
            ((car choices)
```

```
            env
            succeed
            (lambda () (try-next (cdr choices))))))
      (try-next cprocs))))
```

Driver loop

The driver loop for the `amb` evaluator is complex, due to the mechanism that permits the user to try again in evaluating an expression. The driver uses a procedure called `internal-loop`, which takes as argument a procedure `try-again`. The intent is that calling `try-again` should go on to the next untried alternative in the nondeterministic evaluation. `internal-loop` either calls `try-again` in response to the user typing `try-again` at the driver loop, or else starts a new evaluation by calling `ambeval`.

The failure continuation for this call to `ambeval` informs the user that there are no more values and re-invokes the driver loop.

The success continuation for the call to `ambeval` is more subtle. We print the obtained value and then invoke the internal loop again with a `try-again` procedure that will be able to try the next alternative. This `next-alternative` procedure is the second argument that was passed to the success continuation. Ordinarily, we think of this second argument as a failure continuation to be used if the current evaluation branch later fails. In this case, however, we have completed a successful evaluation, so we can invoke the "failure" alternative branch in order to search for additional successful evaluations.

```
(define input-prompt  ";;; Amb-Eval input:")
(define output-prompt ";;; Amb-Eval value:")

(define (driver-loop)
  (define (internal-loop try-again)
```

```
    (prompt-for-input input-prompt)
    (let ((input (read)))
      (if (eq? input 'try-again)
          (try-again)
          (begin
            (newline) (display ";;; Starting a new problem "
            (ambeval
             input
             the-global-environment
             ;; ambeval success
             (lambda (val next-alternative)
               (announce-output output-prompt)
               (user-print val)
               (internal-loop next-alternative))
             ;; ambeval failure
             (lambda ()
               (announce-output
                ";;; There are no more values of")
               (user-print input)
               (driver-loop)))))))
  (internal-loop
   (lambda ()
     (newline) (display ";;; There is no current problem")
     (driver-loop))))
```

The initial call to `internal-loop` uses a `try-again` procedure that complains that there is no current problem and restarts the driver loop. This is the behavior that will happen if the user types `try-again` when there is no evaluation in progress.

> **Exercise 4.50:** Implement a new special form `ramb` that is like `amb` except that it searches alternatives in a random order, rather than from left to right. Show how this can help with Alyssa's

problem in Exercise 4.49.

Exercise 4.51: Implement a new kind of assignment called `permanent-set!` that is not undone upon failure. For example, we can choose two distinct elements from a list and count the number of trials required to make a successful choice as follows:

```
(define count 0)
(let ((x (an-element-of '(a b c)))
      (y (an-element-of '(a b c))))
  (permanent-set! count (+ count 1))
  (require (not (eq? x y)))
  (list x y count))
;;; Starting a new problem
;;; Amb-Eval value:
(a b 2)
;;; Amb-Eval input:
try-again
;;; Amb-Eval value:
(a c 3)
```

What values would have been displayed if we had used `set!` here rather than `permanent-set!` ?

Exercise 4.52: Implement a new construct called `if-fail` that permits the user to catch the failure of an expression. `if-fail` takes two expressions. It evaluates the first expression as usual and returns as usual if the evaluation succeeds. If the evaluation fails, however, the value of the second expression is returned, as in the following example:

```
;;; Amb-Eval input:
(if-fail (let ((x (an-element-of '(1 3 5))))
```

```
            (require (even? x))
            x)
          'all-odd)
;;; Starting a new problem
;;; Amb-Eval value:
all-odd

;;; Amb-Eval input:
(if-fail (let ((x (an-element-of '(1 3 5 8))))
            (require (even? x))
            x)
          'all-odd)
;;; Starting a new problem
;;; Amb-Eval value:
8
```

Exercise 4.53: With `permanent-set!` as described in Exercise 4.51 and `if-fail` as in Exercise 4.52, what will be the result of evaluating

```
(let ((pairs '()))
  (if-fail
   (let ((p (prime-sum-pair '(1 3 5 8)
                            '(20 35 110))))
     (permanent-set! pairs (cons p pairs))
     (amb))
   pairs))
```

Exercise 4.54: If we had not realized that `require` could be implemented as an ordinary procedure that uses `amb`, to be defined by the user as part of a nondeterministic program, we would have had to implement it as a special form. This would require syntax procedures

```
(define (require? exp)
  (tagged-list? exp 'require))
(define (require-predicate exp)
  (cadr exp))
```

and a new clause in the dispatch in `analyze`

```
((require? exp) (analyze-require exp))
```

as well the procedure `analyze-require` that handles `require` expressions. Complete the following definition of `analyze-require`.

```
(define (analyze-require exp)
  (let ((pproc (analyze (require-predicate exp))))
    (lambda (env succeed fail)
      (pproc env
             (lambda (pred-value fail2)
               (if ⟨??⟩
                   ⟨??⟩
                   (succeed 'ok fail2)))
             fail))))
```

4.4 Logic Programming

In Chapter 1 we stressed that computer science deals with imperative (how to) knowledge, whereas mathematics deals with declarative (what is) knowledge. Indeed, programming languages require that the programmer express knowledge in a form that indicates the step-by-step methods for solving particular problems. On the other hand, high-level languages provide, as part of the language implementation, a substantial amount of methodological knowledge that frees the user from concern with numerous details of how a specified computation will progress.

Most programming languages, including Lisp, are organized around computing the values of mathematical functions. Expression-oriented languages (such as Lisp, Fortran, and Algol) capitalize on the "pun" that an expression that describes the value of a function may also be interpreted as a means of computing that value. Because of this, most programming languages are strongly biased toward unidirectional computations (computations with well-defined inputs and outputs). There are, however, radically different programming languages that relax this bias. We saw one such example in Section 3.3.5, where the objects of computation were arithmetic constraints. In a constraint system the direction and the order of computation are not so well specified; in carrying out a computation the system must therefore provide more detailed "how to" knowledge than would be the case with an ordinary arithmetic computation. This does not mean, however, that the user is released altogether from the responsibility of providing imperative knowledge. There are many constraint networks that implement the same set of constraints, and the user must choose from the set of mathematically equivalent networks a suitable network to specify a particular computation.

The nondeterministic program evaluator of Section 4.3 also moves away from the view that programming is about constructing algorithms for computing unidirectional functions. In a nondeterministic language, expressions can have more than one value, and, as a result, the computation is dealing with relations rather than with single-valued functions. Logic programming extends this idea by combining a relational vision of programming with a powerful kind of symbolic pattern matching called *unification*.[58]

[58]Logic programming has grown out of a long history of research in automatic theorem proving. Early theorem-proving programs could accomplish very little, because they exhaustively searched the space of possible proofs. The major breakthrough that made such a search plausible was the discovery in the early 1960s of the *unification algorithm* and the *resolution principle* (Robinson 1965). Resolution was used, for example, by Green and Raphael (1968) (see also Green 1969) as the basis for a deductive question-answering system. During most of

This approach, when it works, can be a very powerful way to write programs. Part of the power comes from the fact that a single "what is" fact can be used to solve a number of different problems that would have different "how to" components. As an example, consider the `append` operation, which takes two lists as arguments and combines their elements to form a single list. In a procedural language such as Lisp, we could define `append` in terms of the basic list constructor `cons`, as we did in Section 2.2.1:

```
(define (append x y)
  (if (null? x) y (cons (car x) (append (cdr x) y))))
```

This procedure can be regarded as a translation into Lisp of the following two rules, the first of which covers the case where the first list is empty and the second of which handles the case of a nonempty list, which is a `cons` of two parts:

- For any list `y`, the empty list and `y` `append` to form `y`.

this period, researchers concentrated on algorithms that are guaranteed to find a proof if one exists. Such algorithms were difficult to control and to direct toward a proof. Hewitt (1969) recognized the possibility of merging the control structure of a programming language with the operations of a logic-manipulation system, leading to the work in automatic search mentioned in Section 4.3.1 (Footnote 4.47). At the same time that this was being done, Colmerauer, in Marseille, was developing rule-based systems for manipulating natural language (see Colmerauer et al. 1973). He invented a programming language called Prolog for representing those rules. Kowalski (1973; 1979), in Edinburgh, recognized that execution of a Prolog program could be interpreted as proving theorems (using a proof technique called linear Horn-clause resolution). The merging of the last two strands led to the logic-programming movement. Thus, in assigning credit for the development of logic programming, the French can point to Prolog's genesis at the University of Marseille, while the British can highlight the work at the University of Edinburgh. According to people at MIT, logic programming was developed by these groups in an attempt to figure out what Hewitt was talking about in his brilliant but impenetrable Ph.D. thesis. For a history of logic programming, see Robinson 1983.

- For any u, v, y, and z, (cons u v) and y append to form (cons u z) if v and y append to form z.[59]

Using the append procedure, we can answer questions such as

> Find the append of (a b) and (c d).

But the same two rules are also sufficient for answering the following sorts of questions, which the procedure can't answer:

> Find a list y that appends with (a b) to produce (a b c d).
>
> Find all x and y that append to form (a b c d).

In a logic programming language, the programmer writes an append "procedure" by stating the two rules about append given above. "How to" knowledge is provided automatically by the interpreter to allow this single pair of rules to be used to answer all three types of questions about append.[60]

Contemporary logic programming languages (including the one we implement here) have substantial deficiencies, in that their general "how to" methods can lead them into spurious infinite loops or other undesirable behavior.

[59] To see the correspondence between the rules and the procedure, let x in the procedure (where x is nonempty) correspond to (cons u v) in the rule. Then z in the rule corresponds to the append of (cdr x) and y.

[60] This certainly does not relieve the user of the entire problem of how to compute the answer. There are many different mathematically equivalent sets of rules for formulating the append relation, only some of which can be turned into effective devices for computing in any direction. In addition, sometimes "what is" information gives no clue "how to" compute an answer. For example, consider the problem of computing the y such that $y^2 = x$.

Logic programming is an active field of research in computer science.[61]

Earlier in this chapter we explored the technology of implementing interpreters and described the elements that are essential to an interpreter for a Lisp-like language (indeed, to an interpreter for any conventional language). Now we will apply these ideas to discuss an interpreter for a logic programming language. We call this language the *query language*, because it is very useful for retrieving information from data bases by formulating *queries*, or questions, expressed in the language. Even though the query language is very different from Lisp, we will find it convenient to describe the language in terms of the same general framework we have been using all along: as a collection of primitive elements, together with means of combination that enable us to combine simple elements to create more complex elements and means of abstraction that enable us to regard complex elements as single conceptual units. An interpreter for a logic programming language is considerably more complex than an interpreter for a language like Lisp. Nevertheless, we will see that our query-language interpreter contains many of the same elements found in the interpreter of Section 4.1. In particular, there will be an "eval" part that classifies expressions according to type and an "apply" part that implements the language's abstraction mechanism (procedures in the case of Lisp, and *rules* in the case of logic programming). Also, a central role is played in the implementation by a frame data structure, which determines

[61] Interest in logic programming peaked during the early 80s when the Japanese government began an ambitious project aimed at building superfast computers optimized to run logic programming languages. The speed of such computers was to be measured in LIPS (Logical Inferences Per Second) rather than the usual FLOPS (FLoating-point Operations Per Second). Although the project succeeded in developing hardware and software as originally planned, the international computer industry moved in a different direction. See Feigenbaum and Shrobe 1993 for an overview evaluation of the Japanese project. The logic programming community has also moved on to consider relational programming based on techniques other than simple pattern matching, such as the ability to deal with numerical constraints such as the ones illustrated in the constraint-propagation system of Section 3.3.5.

the correspondence between symbols and their associated values. One additional interesting aspect of our query-language implementation is that we make substantial use of streams, which were introduced in Chapter 3.

4.4.1 Deductive Information Retrieval

Logic programming excels in providing interfaces to data bases for information retrieval. The query language we shall implement in this chapter is designed to be used in this way.

In order to illustrate what the query system does, we will show how it can be used to manage the data base of personnel records for Microshaft, a thriving high-technology company in the Boston area. The language provides pattern-directed access to personnel information and can also take advantage of general rules in order to make logical deductions.

A sample data base

The personnel data base for Microshaft contains *assertions* about company personnel. Here is the information about Ben Bitdiddle, the resident computer wizard:

```
(address (Bitdiddle Ben) (Slumerville (Ridge Road) 10))
(job (Bitdiddle Ben) (computer wizard))
(salary (Bitdiddle Ben) 60000)
```

Each assertion is a list (in this case a triple) whose elements can themselves be lists.

As resident wizard, Ben is in charge of the company's computer division, and he supervises two programmers and one technician. Here is the information about them:

```
(address (Hacker Alyssa P) (Cambridge (Mass Ave) 78))
(job (Hacker Alyssa P) (computer programmer))
```

```
(salary (Hacker Alyssa P) 40000)
(supervisor (Hacker Alyssa P) (Bitdiddle Ben))

(address (Fect Cy D) (Cambridge (Ames Street) 3))
(job (Fect Cy D) (computer programmer))
(salary (Fect Cy D) 35000)
(supervisor (Fect Cy D) (Bitdiddle Ben))

(address (Tweakit Lem E) (Boston (Bay State Road) 22))
(job (Tweakit Lem E) (computer technician))
(salary (Tweakit Lem E) 25000)
(supervisor (Tweakit Lem E) (Bitdiddle Ben))
```

There is also a programmer trainee, who is supervised by Alyssa:

```
(address (Reasoner Louis) (Slumerville (Pine Tree Road) 80))
(job (Reasoner Louis) (computer programmer trainee))
(salary (Reasoner Louis) 30000)
(supervisor (Reasoner Louis) (Hacker Alyssa P))
```

All of these people are in the computer division, as indicated by the word `computer` as the first item in their job descriptions.

Ben is a high-level employee. His supervisor is the company's big wheel himself:

```
(supervisor (Bitdiddle Ben) (Warbucks Oliver))
(address (Warbucks Oliver) (Swellesley (Top Heap Road)))
(job (Warbucks Oliver) (administration big wheel))
(salary (Warbucks Oliver) 150000)
```

Besides the computer division supervised by Ben, the company has an accounting division, consisting of a chief accountant and his assistant:

```
(address (Scrooge Eben) (Weston (Shady Lane) 10))
(job (Scrooge Eben) (accounting chief accountant))
(salary (Scrooge Eben) 75000)
```

```
(supervisor (Scrooge Eben) (Warbucks Oliver))

(address (Cratchet Robert) (Allston (N Harvard Street) 16))
(job (Cratchet Robert) (accounting scrivener))
(salary (Cratchet Robert) 18000)
(supervisor (Cratchet Robert) (Scrooge Eben))
```

There is also a secretary for the big wheel:

```
(address (Aull DeWitt) (Slumerville (Onion Square) 5))
(job (Aull DeWitt) (administration secretary))
(salary (Aull DeWitt) 25000)
(supervisor (Aull DeWitt) (Warbucks Oliver))
```

The data base also contains assertions about which kinds of jobs can be done by people holding other kinds of jobs. For instance, a computer wizard can do the jobs of both a computer programmer and a computer technician:

```
(can-do-job (computer wizard) (computer programmer))
(can-do-job (computer wizard) (computer technician))
```

A computer programmer could fill in for a trainee:

```
(can-do-job (computer programmer)
            (computer programmer trainee))
```

Also, as is well known,

```
(can-do-job (administration secretary)
            (administration big wheel))
```

Simple queries

The query language allows users to retrieve information from the data base by posing queries in response to the system's prompt. For example, to find all computer programmers one can say

```
;;; Query input:
(job ?x (computer programmer))
```

The system will respond with the following items:

```
;;; Query results:
(job (Hacker Alyssa P) (computer programmer))
(job (Fect Cy D) (computer programmer))
```

The input query specifies that we are looking for entries in the data base that match a certain *pattern*. In this example, the pattern specifies entries consisting of three items, of which the first is the literal symbol `job`, the second can be anything, and the third is the literal list `(computer programmer)`. The "anything" that can be the second item in the matching list is specified by a *pattern variable*, `?x`. The general form of a pattern variable is a symbol, taken to be the name of the variable, preceded by a question mark. We will see below why it is useful to specify names for pattern variables rather than just putting `?` into patterns to represent "anything." The system responds to a simple query by showing all entries in the data base that match the specified pattern.

A pattern can have more than one variable. For example, the query

```
(address ?x ?y)
```

will list all the employees' addresses.

A pattern can have no variables, in which case the query simply determines whether that pattern is an entry in the data base. If so, there will be one match; if not, there will be no matches.

The same pattern variable can appear more than once in a query, specifying that the same "anything" must appear in each position. This is why variables have names. For example,

```
(supervisor ?x ?x)
```

finds all people who supervise themselves (though there are no such assertions in our sample data base).

The query

```
(job ?x (computer ?type))
```

matches all job entries whose third item is a two-element list whose first item is `computer`:

```
(job (Bitdiddle Ben) (computer wizard))
(job (Hacker Alyssa P) (computer programmer))
(job (Fect Cy D) (computer programmer))
(job (Tweakit Lem E) (computer technician))
```

This same pattern does *not* match

```
(job (Reasoner Louis) (computer programmer trainee))
```

because the third item in the entry is a list of three elements, and the pattern's third item specifies that there should be two elements. If we wanted to change the pattern so that the third item could be any list beginning with `computer`, we could specify[62]

```
(job ?x (computer . ?type))
```

For example,

```
(computer . ?type)
```

matches the data

```
(computer programmer trainee)
```

with `?type` as the list `(programmer trainee)`. It also matches the data

```
(computer programmer)
```

[62] This uses the dotted-tail notation introduced in Exercise 2.20.

with `?type` as the list `(programmer)`, and matches the data

`(computer)`

with `?type` as the empty list `()`.

We can describe the query language's processing of simple queries as follows:

- The system finds all assignments to variables in the query pattern that *satisfy* the pattern—that is, all sets of values for the variables such that if the pattern variables are *instantiated with* (replaced by) the values, the result is in the data base.
- The system responds to the query by listing all instantiations of the query pattern with the variable assignments that satisfy it.

Note that if the pattern has no variables, the query reduces to a determination of whether that pattern is in the data base. If so, the empty assignment, which assigns no values to variables, satisfies that pattern for that data base.

> **Exercise 4.55:** Give simple queries that retrieve the following information from the data base:
>
> 1. all people supervised by Ben Bitdiddle;
> 2. the names and jobs of all people in the accounting division;
> 3. the names and addresses of all people who live in Slumerville.

Compound queries

Simple queries form the primitive operations of the query language. In order to form compound operations, the query language provides means of combination. One thing that makes the query language a logic programming language is that the means of combination mirror the means of combination

used in forming logical expressions: `and`, `or`, and `not`. (Here `and`, `or`, and `not` are not the Lisp primitives, but rather operations built into the query language.)

We can use `and` as follows to find the addresses of all the computer programmers:

```
(and (job ?person (computer programmer))
     (address ?person ?where))
```

The resulting output is

```
(and (job (Hacker Alyssa P) (computer programmer))
     (address (Hacker Alyssa P) (Cambridge (Mass Ave) 78)))
(and (job (Fect Cy D) (computer programmer))
     (address (Fect Cy D) (Cambridge (Ames Street) 3)))
```

In general,

(**and** ⟨*query*$_1$⟩ ⟨*query*$_2$⟩ ... ⟨*query*$_n$⟩)

is satisfied by all sets of values for the pattern variables that simultaneously satisfy ⟨*query*$_1$⟩ ... ⟨*query*$_n$⟩.

As for simple queries, the system processes a compound query by finding all assignments to the pattern variables that satisfy the query, then displaying instantiations of the query with those values.

Another means of constructing compound queries is through `or`. For example,

```
(or (supervisor ?x (Bitdiddle Ben))
    (supervisor ?x (Hacker Alyssa P)))
```

will find all employees supervised by Ben Bitdiddle or Alyssa P. Hacker:

```
(or (supervisor (Hacker Alyssa P) (Bitdiddle Ben))
    (supervisor (Hacker Alyssa P) (Hacker Alyssa P)))
(or (supervisor (Fect Cy D) (Bitdiddle Ben))
```

```
    (supervisor (Fect Cy D) (Hacker Alyssa P)))
(or (supervisor (Tweakit Lem E) (Bitdiddle Ben))
    (supervisor (Tweakit Lem E) (Hacker Alyssa P)))
(or (supervisor (Reasoner Louis) (Bitdiddle Ben))
    (supervisor (Reasoner Louis) (Hacker Alyssa P)))
```

In general,

```
(or ⟨query1⟩ ⟨query2⟩ ... ⟨queryn⟩)
```

is satisfied by all sets of values for the pattern variables that satisfy at least one of $\langle query_1 \rangle \ldots \langle query_n \rangle$.

Compound queries can also be formed with `not`. For example,

```
(and (supervisor ?x (Bitdiddle Ben))
     (not (job ?x (computer programmer))))
```

finds all people supervised by Ben Bitdiddle who are not computer programmers. In general,

```
(not ⟨query1⟩)
```

is satisfied by all assignments to the pattern variables that do not satisfy $\langle query_1 \rangle$.[63]

The final combining form is called `lisp-value`. When `lisp-value` is the first element of a pattern, it specifies that the next element is a Lisp predicate to be applied to the rest of the (instantiated) elements as arguments. In general,

```
(lisp-value ⟨predicate⟩ ⟨arg1⟩ ... ⟨argn⟩)
```

will be satisfied by assignments to the pattern variables for which the $\langle predicate \rangle$ applied to the instantiated $\langle arg_1 \rangle \ldots \langle arg_n \rangle$ is true. For example, to find all

[63] Actually, this description of `not` is valid only for simple cases. The real behavior of `not` is more complex. We will examine `not`'s peculiarities in sections Section 4.4.2 and Section 4.4.3.

people whose salary is greater than $30,000 we could write[64]

```
(and (salary ?person ?amount) (lisp-value > ?amount 30000))
```

Exercise 4.56: Formulate compound queries that retrieve the following information:

a. the names of all people who are supervised by Ben Bitdiddle, together with their addresses;

b. all people whose salary is less than Ben Bitdiddle's, together with their salary and Ben Bitdiddle's salary;

c. all people who are supervised by someone who is not in the computer division, together with the supervisor's name and job.

Rules

In addition to primitive queries and compound queries, the query language provides means for abstracting queries. These are given by *rules*. The rule

```
(rule (lives-near ?person-1 ?person-2)
      (and (address ?person-1 (?town . ?rest-1))
           (address ?person-2 (?town . ?rest-2))
           (not (same ?person-1 ?person-2))))
```

[64] `lisp-value` should be used only to perform an operation not provided in the query language. In particular, it should not be used to test equality (since that is what the matching in the query language is designed to do) or inequality (since that can be done with the `same` rule shown below).

specifies that two people live near each other if they live in the same town. The final `not` clause prevents the rule from saying that all people live near themselves. The `same` relation is defined by a very simple rule:[65]

```
(rule (same ?x ?x))
```

The following rule declares that a person is a "wheel" in an organization if he supervises someone who is in turn a supervisor:

```
(rule (wheel ?person)
      (and (supervisor ?middle-manager ?person)
           (supervisor ?x ?middle-manager)))
```

The general form of a rule is

```
(rule ⟨conclusion⟩ ⟨body⟩)
```

where ⟨*conclusion*⟩ is a pattern and ⟨*body*⟩ is any query.[66] We can think of a rule as representing a large (even infinite) set of assertions, namely all instantiations of the rule conclusion with variable assignments that satisfy the rule body. When we described simple queries (patterns), we said that an assignment to variables satisfies a pattern if the instantiated pattern is in the data base. But the pattern needn't be explicitly in the data base as an assertion. It can be an implicit assertion implied by a rule. For example, the query

```
(lives-near ?x (Bitdiddle Ben))
```

[65] Notice that we do not need `same` in order to make two things be the same: We just use the same pattern variable for each—in effect, we have one thing instead of two things in the first place. For example, see `?town` in the `lives-near` rule and `?middle-manager` in the `wheel` rule below. `same` is useful when we want to force two things to be different, such as `?person-1` and `?person-2` in the `lives-near` rule. Although using the same pattern variable in two parts of a query forces the same value to appear in both places, using different pattern variables does not force different values to appear. (The values assigned to different pattern variables may be the same or different.)

[66] We will also allow rules without bodies, as in `same`, and we will interpret such a rule to mean that the rule conclusion is satisfied by any values of the variables.

results in

```
(lives-near (Reasoner Louis) (Bitdiddle Ben))
(lives-near (Aull DeWitt) (Bitdiddle Ben))
```

To find all computer programmers who live near Ben Bitdiddle, we can ask

```
(and (job ?x (computer programmer))
     (lives-near ?x (Bitdiddle Ben)))
```

As in the case of compound procedures, rules can be used as parts of other rules (as we saw with the `lives-near` rule above) or even be defined recursively. For instance, the rule

```
(rule (outranked-by ?staff-person ?boss)
      (or (supervisor ?staff-person ?boss)
          (and (supervisor ?staff-person ?middle-manager)
               (outranked-by ?middle-manager ?boss))))
```

says that a staff person is outranked by a boss in the organization if the boss is the person's supervisor or (recursively) if the person's supervisor is outranked by the boss.

Exercise 4.57: Define a rule that says that person 1 can replace person 2 if either person 1 does the same job as person 2 or someone who does person 1's job can also do person 2's job, and if person 1 and person 2 are not the same person. Using your rule, give queries that find the following:

a. all people who can replace Cy D. Fect;

b. all people who can replace someone who is being paid more than they are, together with the two salaries.

Exercise 4.58: Define a rule that says that a person is a "big shot" in a division if the person works in the division but does not have a supervisor who works in the division.

Exercise 4.59: Ben Bitdiddle has missed one meeting too many. Fearing that his habit of forgetting meetings could cost him his job, Ben decides to do something about it. He adds all the weekly meetings of the firm to the Microshaft data base by asserting the following:

```
(meeting accounting (Monday 9am))
(meeting administration (Monday 10am))
(meeting computer (Wednesday 3pm))
(meeting administration (Friday 1pm))
```

Each of the above assertions is for a meeting of an entire division. Ben also adds an entry for the company-wide meeting that spans all the divisions. All of the company's employees attend this meeting.

```
(meeting whole-company (Wednesday 4pm))
```

a. On Friday morning, Ben wants to query the data base for all the meetings that occur that day. What query should he use?

b. Alyssa P. Hacker is unimpressed. She thinks it would be much more useful to be able to ask for her meetings by specifying her name. So she designs a rule that says that a person's meetings include all `whole-company` meetings plus all meetings of that person's division. Fill in the body of Alyssa's rule.

```
(rule (meeting-time ?person ?day-and-time)
      ⟨rule-body⟩)
```

c. Alyssa arrives at work on Wednesday morning and wonders what meetings she has to attend that day. Having defined the above rule, what query should she make to find this out?

Exercise 4.60: By giving the query

```
(lives-near ?person (Hacker Alyssa P))
```

Alyssa P. Hacker is able to find people who live near her, with whom she can ride to work. On the other hand, when she tries to find all pairs of people who live near each other by querying

```
(lives-near ?person-1 ?person-2)
```

she notices that each pair of people who live near each other is listed twice; for example,

```
(lives-near (Hacker Alyssa P) (Fect Cy D))
(lives-near (Fect Cy D) (Hacker Alyssa P))
```

Why does this happen? Is there a way to find a list of people who live near each other, in which each pair appears only once? Explain.

Logic as programs

We can regard a rule as a kind of logical implication: *If* an assignment of values to pattern variables satisfies the body, *then* it satisfies the conclusion. Consequently, we can regard the query language as having the ability to perform *logical deductions* based upon the rules. As an example, consider the `append` operation described at the beginning of Section 4.4. As we said, `append` can be characterized by the following two rules:

- For any list `y`, the empty list and `y` `append` to form `y`.
- For any `u`, `v`, `y`, and `z`, `(cons u v)` and `y` `append` to form `(cons u z)` if `v` and `y` `append` to form `z`.

To express this in our query language, we define two rules for a relation

```
(append-to-form x y z)
```

which we can interpret to mean "`x` and `y` `append` to form `z`":

```
(rule (append-to-form () ?y ?y))
(rule (append-to-form (?u . ?v) ?y (?u . ?z))
      (append-to-form ?v ?y ?z))
```

The first rule has no body, which means that the conclusion holds for any value of `?y`. Note how the second rule makes use of dotted-tail notation to name the `car` and `cdr` of a list.

Given these two rules, we can formulate queries that compute the `append` of two lists:

```
;;; Query input:
(append-to-form (a b) (c d) ?z)
;;; Query results:
(append-to-form (a b) (c d) (a b c d))
```

What is more striking, we can use the same rules to ask the question "Which list, when `append`ed to `(a b)`, yields `(a b c d)`?" This is done as follows:

```
;;; Query input:
(append-to-form (a b) ?y (a b c d))
;;; Query results:
(append-to-form (a b) (c d) (a b c d))
```

We can also ask for all pairs of lists that `append` to form `(a b c d)`:

```
;;; Query input:
(append-to-form ?x ?y (a b c d))
;;; Query results:
(append-to-form () (a b c d) (a b c d))
(append-to-form (a) (b c d) (a b c d))
(append-to-form (a b) (c d) (a b c d))
(append-to-form (a b c) (d) (a b c d))
(append-to-form (a b c d) () (a b c d))
```

The query system may seem to exhibit quite a bit of intelligence in using the rules to deduce the answers to the queries above. Actually, as we will see in the next section, the system is following a well-determined algorithm in unraveling the rules. Unfortunately, although the system works impressively in the `append` case, the general methods may break down in more complex cases, as we will see in Section 4.4.3.

Exercise 4.61: The following rules implement a `next-to` relation that finds adjacent elements of a list:

```
(rule (?x next-to ?y in (?x ?y . ?u)))
(rule (?x next-to ?y in (?v . ?z))
      (?x next-to ?y in ?z))
```

What will the response be to the following queries?

```
(?x next-to ?y in (1 (2 3) 4))
(?x next-to  1 in (2 1 3 1))
```

Exercise 4.62: Define rules to implement the `last-pair` operation of Exercise 2.17, which returns a list containing the last element of a nonempty list. Check your rules on queries such as `(last-pair (3) ?x)`, `(last-pair (1 2 3) ?x)` and `(last-pair (2 ?x) (3))`. Do your rules

work correctly on queries such as `(last-pair ?x (3))` ?

Exercise 4.63: The following data base (see Genesis 4) traces the genealogy of the descendants of Ada back to Adam, by way of Cain:

```
(son Adam Cain)
(son Cain Enoch)
(son Enoch Irad)
(son Irad Mehujael)
(son Mehujael Methushael)
(son Methushael Lamech)
(wife Lamech Ada)
(son Ada Jabal)
(son Ada Jubal)
```

Formulate rules such as "If S is the son of f, and f is the son of G, then S is the grandson of G" and "If W is the wife of M, and S is the son of W, then S is the son of M" (which was supposedly more true in biblical times than today) that will enable the query system to find the grandson of Cain; the sons of Lamech; the grandsons of Methushael. (See Exercise 4.69 for some rules to deduce more complicated relationships.)

4.4.2 How the Query System Works

In Section 4.4.4 we will present an implementation of the query interpreter as a collection of procedures. In this section we give an overview that explains the general structure of the system independent of low-level implementation details. After describing the implementation of the interpreter, we will be in a position to understand some of its limitations and some of the subtle ways

in which the query language's logical operations differ from the operations of mathematical logic.

It should be apparent that the query evaluator must perform some kind of search in order to match queries against facts and rules in the data base. One way to do this would be to implement the query system as a nondeterministic program, using the `amb` evaluator of Section 4.3 (see Exercise 4.78). Another possibility is to manage the search with the aid of streams. Our implementation follows this second approach.

The query system is organized around two central operations called *pattern matching* and *unification*. We first describe pattern matching and explain how this operation, together with the organization of information in terms of streams of frames, enables us to implement both simple and compound queries. We next discuss unification, a generalization of pattern matching needed to implement rules. Finally, we show how the entire query interpreter fits together through a procedure that classifies expressions in a manner analogous to the way `eval` classifies expressions for the interpreter described in Section 4.1.

Pattern matching

A *pattern matcher* is a program that tests whether some datum fits a specified pattern. For example, the data list `((a b) c (a b))` matches the pattern `(?x c ?x)` with the pattern variable `?x` bound to `(a b)`. The same data list matches the pattern `(?x ?y ?z)` with `?x` and `?z` both bound to `(a b)` and `?y` bound to `c`. It also matches the pattern `((?x ?y) c (?x ?y))` with `?x` bound to `a` and `?y` bound to `b`. However, it does not match the pattern `(?x a ?y)`, since that pattern specifies a list whose second element is the symbol `a`.

The pattern matcher used by the query system takes as inputs a pattern, a datum, and a *frame* that specifies bindings for various pattern variables. It

checks whether the datum matches the pattern in a way that is consistent with the bindings already in the frame. If so, it returns the given frame augmented by any bindings that may have been determined by the match. Otherwise, it indicates that the match has failed.

For example, using the pattern `(?x ?y ?x)` to match `(a b a)` given an empty frame will return a frame specifying that `?x` is bound to `a` and `?y` is bound to `b`. Trying the match with the same pattern, the same datum, and a frame specifying that `?y` is bound to `a` will fail. Trying the match with the same pattern, the same datum, and a frame in which `?y` is bound to `b` and `?x` is unbound will return the given frame augmented by a binding of `?x` to `a`.

The pattern matcher is all the mechanism that is needed to process simple queries that don't involve rules. For instance, to process the query

```
(job ?x (computer programmer))
```

we scan through all assertions in the data base and select those that match the pattern with respect to an initially empty frame. For each match we find, we use the frame returned by the match to instantiate the pattern with a value for `?x`.

Streams of frames

The testing of patterns against frames is organized through the use of streams. Given a single frame, the matching process runs through the data-base entries one by one. For each data-base entry, the matcher generates either a special symbol indicating that the match has failed or an extension to the frame. The results for all the data-base entries are collected into a stream, which is passed through a filter to weed out the failures. The result is a stream of all the frames

that extend the given frame via a match to some assertion in the data base.[67]

In our system, a query takes an input stream of frames and performs the above matching operation for every frame in the stream, as indicated in Figure 4.4. That is, for each frame in the input stream, the query generates a new stream consisting of all extensions to that frame by matches to assertions in the data base. All these streams are then combined to form one huge stream, which contains all possible extensions of every frame in the input stream. This stream is the output of the query.

To answer a simple query, we use the query with an input stream consisting of a single empty frame. The resulting output stream contains all extensions to the empty frame (that is, all answers to our query). This stream of frames is then used to generate a stream of copies of the original query pattern with the variables instantiated by the values in each frame, and this is the stream that is finally printed.

Compound queries

The real elegance of the stream-of-frames implementation is evident when we deal with compound queries. The processing of compound queries makes use of the ability of our matcher to demand that a match be consistent with a specified frame. For example, to handle the `and` of two queries, such as

```
(and (can-do-job ?x (computer programmer trainee))
     (job ?person ?x))
```

[67] Because matching is generally very expensive, we would like to avoid applying the full matcher to every element of the data base. This is usually arranged by breaking up the process into a fast, coarse match and the final match. The coarse match filters the data base to produce a small set of candidates for the final match. With care, we can arrange our data base so that some of the work of coarse matching can be done when the data base is constructed rather then when we want to select the candidates. This is called *indexing* the data base. There is a vast technology built around data-base-indexing schemes. Our implementation, described in Section 4.4.4, contains a simple-minded form of such an optimization.




Figure 4.4: A query processes a stream of frames.

(informally, "Find all people who can do the job of a computer programmer trainee"), we first find all entries that match the pattern

```
(can-do-job ?x (computer programmer trainee))
```

This produces a stream of frames, each of which contains a binding for `?x`. Then for each frame in the stream we find all entries that match

```
(job ?person ?x)
```

in a way that is consistent with the given binding for `?x`. Each such match will produce a frame containing bindings for `?x` and `?person`. The `and` of two queries can be viewed as a series combination of the two component queries, as shown in Figure 4.5. The frames that pass through the first query filter are filtered and further extended by the second query.

Figure 4.6 shows the analogous method for computing the `or` of two queries as a parallel combination of the two component queries. The input stream of frames is extended separately by each query. The two resulting streams are then merged to produce the final output stream.

Even from this high-level description, it is apparent that the processing of compound queries can be slow. For example, since a query may produce




Figure 4.5: The `and` combination of two queries is produced by operating on the stream of frames in series.

more than one output frame for each input frame, and each query in an `and` gets its input frames from the previous query, an `and` query could, in the worst case, have to perform a number of matches that is exponential in the number of queries (see Exercise 4.76).[68] Though systems for handling only simple queries are quite practical, dealing with complex queries is extremely difficult.[69]

From the stream-of-frames viewpoint, the `not` of some query acts as a filter that removes all frames for which the query can be satisfied. For instance, given the pattern

```
(not (job ?x (computer programmer)))
```

we attempt, for each frame in the input stream, to produce extension frames that satisfy `(job ?x (computer programmer))`. We remove from the input stream all frames for which such extensions exist. The result

[68] But this kind of exponential explosion is not common in `and` queries because the added conditions tend to reduce rather than expand the number of frames produced.

[69] There is a large literature on data-base-management systems that is concerned with how to handle complex queries efficiently.




Figure 4.6: The `or` combination of two queries is produced by operating on the stream of frames in parallel and merging the results.

is a stream consisting of only those frames in which the binding for `?x` does not satisfy `(job ?x (computer programmer))`. For example, in processing the query

```
(and (supervisor ?x ?y)
     (not (job ?x (computer programmer))))
```

the first clause will generate frames with bindings for `?x` and `?y`. The `not` clause will then filter these by removing all frames in which the binding for `?x` satisfies the restriction that `?x` is a computer programmer.[70]

[70] There is a subtle difference between this filter implementation of `not` and the usual meaning of `not` in mathematical logic. See Section 4.4.3.

The `lisp-value` special form is implemented as a similar filter on frame streams. We use each frame in the stream to instantiate any variables in the pattern, then apply the Lisp predicate. We remove from the input stream all frames for which the predicate fails.

Unification

In order to handle rules in the query language, we must be able to find the rules whose conclusions match a given query pattern. Rule conclusions are like assertions except that they can contain variables, so we will need a generalization of pattern matching—called *unification*—in which both the "pattern" and the "datum" may contain variables.

A unifier takes two patterns, each containing constants and variables, and determines whether it is possible to assign values to the variables that will make the two patterns equal. If so, it returns a frame containing these bindings. For example, unifying `(?x a ?y)` and `(?y ?z a)` will specify a frame in which `?x`, `?y`, and `?z` must all be bound to `a`. On the other hand, unifying `(?x ?y a)` and `(?x b ?y)` will fail, because there is no value for `?y` that can make the two patterns equal. (For the second elements of the patterns to be equal, `?y` would have to be `b`; however, for the third elements to be equal, `?y` would have to be `a`.) The unifier used in the query system, like the pattern matcher, takes a frame as input and performs unifications that are consistent with this frame.

The unification algorithm is the most technically difficult part of the query system. With complex patterns, performing unification may seem to require deduction. To unify `(?x ?x)` and `((a ?y c) (a b ?z))`, for example, the algorithm must infer that `?x` should be `(a b c)`, `?y` should be `b`, and `?z` should be `c`. We may think of this process as solving a set of equations among the pattern components. In general, these are simultaneous

equations, which may require substantial manipulation to solve.[71] For example, unifying `(?x ?x)` and `((a ?y c) (a b ?z))` may be thought of as specifying the simultaneous equations

```
?x  =  (a ?y c)
?x  =  (a b ?z)
```

These equations imply that

```
(a ?y c)  =  (a b ?z)
```

which in turn implies that

```
 a  =  a,
?y  =  b,
 c  =  ?z,
```

and hence that

```
?x  =  (a b c)
```

In a successful pattern match, all pattern variables become bound, and the values to which they are bound contain only constants. This is also true of all the examples of unification we have seen so far. In general, however, a successful unification may not completely determine the variable values; some variables may remain unbound and others may be bound to values that contain variables.

Consider the unification of `(?x a)` and `((b ?y) ?z)`. We can deduce that `?x = (b ?y)` and `a = ?z`, but we cannot further solve for `?x` or `?y`. The unification doesn't fail, since it is certainly possible to make the two patterns equal by assigning values to `?x` and `?y`. Since this match in no way restricts the values `?y` can take on, no binding for `?y` is put into the result frame. The match does, however, restrict the value of `?x`. Whatever

[71] In one-sided pattern matching, all the equations that contain pattern variables are explicit and already solved for the unknown (the pattern variable).

value `?y` has, `?x` must be `(b ?y)`. A binding of `?x` to the pattern `(b ?y)` is thus put into the frame. If a value for `?y` is later determined and added to the frame (by a pattern match or unification that is required to be consistent with this frame), the previously bound `?x` will refer to this value.[72]

Applying rules

Unification is the key to the component of the query system that makes inferences from rules. To see how this is accomplished, consider processing a query that involves applying a rule, such as

```
(lives-near ?x (Hacker Alyssa P))
```

To process this query, we first use the ordinary pattern-match procedure described above to see if there are any assertions in the data base that match this pattern. (There will not be any in this case, since our data base includes no direct assertions about who lives near whom.) The next step is to attempt to unify the query pattern with the conclusion of each rule. We find that the pattern unifies with the conclusion of the rule

```
(rule (lives-near ?person-1 ?person-2)
      (and (address ?person-1 (?town . ?rest-1))
           (address ?person-2 (?town . ?rest-2))
           (not (same ?person-1 ?person-2))))
```

resulting in a frame specifying that `?person-2` is bound to `(Hacker Alyssa P)` and that `?x` should be bound to (have the same value as) `?person-1`. Now, relative to this frame, we evaluate the compound query

[72] Another way to think of unification is that it generates the most general pattern that is a specialization of the two input patterns. That is, the unification of `(?x a)` and `((b ?y) ?z)` is `((b ?y) a)`, and the unification of `(?x a ?y)` and `(?y ?z a)`, discussed above, is `(a a a)`. For our implementation, it is more convenient to think of the result of unification as a frame rather than a pattern.

given by the body of the rule. Successful matches will extend this frame by providing a binding for `?person-1`, and consequently a value for `?x`, which we can use to instantiate the original query pattern.

In general, the query evaluator uses the following method to apply a rule when trying to establish a query pattern in a frame that specifies bindings for some of the pattern variables:

- Unify the query with the conclusion of the rule to form, if successful, an extension of the original frame.
- Relative to the extended frame, evaluate the query formed by the body of the rule.

Notice how similar this is to the method for applying a procedure in the `eval/apply` evaluator for Lisp:

- Bind the procedure's parameters to its arguments to form a frame that extends the original procedure environment.
- Relative to the extended environment, evaluate the expression formed by the body of the procedure.

The similarity between the two evaluators should come as no surprise. Just as procedure definitions are the means of abstraction in Lisp, rule definitions are the means of abstraction in the query language. In each case, we unwind the abstraction by creating appropriate bindings and evaluating the rule or procedure body relative to these.

Simple queries

We saw earlier in this section how to evaluate simple queries in the absence of rules. Now that we have seen how to apply rules, we can describe how to evaluate simple queries by using both rules and assertions.

Given the query pattern and a stream of frames, we produce, for each frame in the input stream, two streams:

- a stream of extended frames obtained by matching the pattern against all assertions in the data base (using the pattern matcher), and
- a stream of extended frames obtained by applying all possible rules (using the unifier).[73]

Appending these two streams produces a stream that consists of all the ways that the given pattern can be satisfied consistent with the original frame. These streams (one for each frame in the input stream) are now all combined to form one large stream, which therefore consists of all the ways that any of the frames in the original input stream can be extended to produce a match with the given pattern.

The query evaluator and the driver loop

Despite the complexity of the underlying matching operations, the system is organized much like an evaluator for any language. The procedure that coordinates the matching operations is called `qeval`, and it plays a role analogous to that of the `eval` procedure for Lisp. `qeval` takes as inputs a query and a stream of frames. Its output is a stream of frames, corresponding to successful matches to the query pattern, that extend some frame in the input stream, as indicated in Figure 4.4. Like `eval`, `qeval` classifies the different types of expressions (queries) and dispatches to an appropriate procedure for each. There is a procedure for each special form (`and`, `or`, `not`, and `lisp-value`) and one for simple queries.

[73] Since unification is a generalization of matching, we could simplify the system by using the unifier to produce both streams. Treating the easy case with the simple matcher, however, illustrates how matching (as opposed to full-blown unification) can be useful in its own right.

The driver loop, which is analogous to the `driver-loop` procedure for the other evaluators in this chapter, reads queries from the terminal. For each query, it calls `qeval` with the query and a stream that consists of a single empty frame. This will produce the stream of all possible matches (all possible extensions to the empty frame). For each frame in the resulting stream, it instantiates the original query using the values of the variables found in the frame. This stream of instantiated queries is then printed.[74]

The driver also checks for the special command `assert!`, which signals that the input is not a query but rather an assertion or rule to be added to the data base. For instance,

```
(assert! (job (Bitdiddle Ben)
              (computer wizard)))
(assert! (rule (wheel ?person)
               (and (supervisor ?middle-manager ?person)
                    (supervisor ?x ?middle-manager))))
```

4.4.3 Is Logic Programming Mathematical Logic?

The means of combination used in the query language may at first seem identical to the operations `and`, `or`, and `not` of mathematical logic, and the application of query-language rules is in fact accomplished through a legitimate method of inference.[75] This identification of the query language with mathematical logic is not really valid, though, because the query language provides

[74] The reason we use streams (rather than lists) of frames is that the recursive application of rules can generate infinite numbers of values that satisfy a query. The delayed evaluation embodied in streams is crucial here: The system will print responses one by one as they are generated, regardless of whether there are a finite or infinite number of responses.

[75] That a particular method of inference is legitimate is not a trivial assertion. One must prove that if one starts with true premises, only true conclusions can be derived. The method of inference represented by rule applications is *modus ponens*, the familiar method of inference that says that if A is true and A *implies* B is true, then we may conclude that B is true.

a *control structure* that interprets the logical statements procedurally. We can often take advantage of this control structure. For example, to find all of the supervisors of programmers we could formulate a query in either of two logically equivalent forms:

```
(and (job ?x (computer programmer)) (supervisor ?x ?y))
```

or

```
(and (supervisor ?x ?y) (job ?x (computer programmer)))
```

If a company has many more supervisors than programmers (the usual case), it is better to use the first form rather than the second because the data base must be scanned for each intermediate result (frame) produced by the first clause of the `and`.

The aim of logic programming is to provide the programmer with techniques for decomposing a computational problem into two separate problems: "what" is to be computed, and "how" this should be computed. This is accomplished by selecting a subset of the statements of mathematical logic that is powerful enough to be able to describe anything one might want to compute, yet weak enough to have a controllable procedural interpretation. The intention here is that, on the one hand, a program specified in a logic programming language should be an effective program that can be carried out by a computer. Control ("how" to compute) is effected by using the order of evaluation of the language. We should be able to arrange the order of clauses and the order of subgoals within each clause so that the computation is done in an order deemed to be effective and efficient. At the same time, we should be able to view the result of the computation ("what" to compute) as a simple consequence of the laws of logic.

Our query language can be regarded as just such a procedurally interpretable subset of mathematical logic. An assertion represents a simple fact (an atomic proposition). A rule represents the implication that the rule con-

clusion holds for those cases where the rule body holds. A rule has a natural procedural interpretation: To establish the conclusion of the rule, establish the body of the rule. Rules, therefore, specify computations. However, because rules can also be regarded as statements of mathematical logic, we can justify any "inference" accomplished by a logic program by asserting that the same result could be obtained by working entirely within mathematical logic.[76]

Infinite loops

A consequence of the procedural interpretation of logic programs is that it is possible to construct hopelessly inefficient programs for solving certain problems. An extreme case of inefficiency occurs when the system falls into infinite loops in making deductions. As a simple example, suppose we are setting up a data base of famous marriages, including

```
(assert! (married Minnie Mickey))
```

If we now ask

```
(married Mickey ?who)
```

we will get no response, because the system doesn't know that if A is married to B, then B is married to A. So we assert the rule

[76] We must qualify this statement by agreeing that, in speaking of the "inference" accomplished by a logic program, we assume that the computation terminates. Unfortunately, even this qualified statement is false for our implementation of the query language (and also false for programs in Prolog and most other current logic programming languages) because of our use of `not` and `lisp-value`. As we will describe below, the `not` implemented in the query language is not always consistent with the `not` of mathematical logic, and `lisp-value` introduces additional complications. We could implement a language consistent with mathematical logic by simply removing `not` and `lisp-value` from the language and agreeing to write programs using only simple queries, `and`, and `or`. However, this would greatly restrict the expressive power of the language. One of the major concerns of research in logic programming is to find ways to achieve more consistency with mathematical logic without unduly sacrificing expressive power.

```
(assert! (rule (married ?x ?y) (married ?y ?x)))
```

and again query

```
(married Mickey ?who)
```

Unfortunately, this will drive the system into an infinite loop, as follows:

- The system finds that the `married` rule is applicable; that is, the rule conclusion `(married ?x ?y)` successfully unifies with the query pattern `(married Mickey ?who)` to produce a frame in which `?x` is bound to `Mickey` and `?y` is bound to `?who`. So the interpreter proceeds to evaluate the rule body `(married ?y ?x)` in this frame—in effect, to process the query `(married ?who Mickey)`.
- One answer appears directly as an assertion in the data base: `(married Minnie Mickey)`.
- The `married` rule is also applicable, so the interpreter again evaluates the rule body, which this time is equivalent to `(married Mickey ?who)`.

The system is now in an infinite loop. Indeed, whether the system will find the simple answer `(married Minnie Mickey)` before it goes into the loop depends on implementation details concerning the order in which the system checks the items in the data base. This is a very simple example of the kinds of loops that can occur. Collections of interrelated rules can lead to loops that are much harder to anticipate, and the appearance of a loop can depend on the order of clauses in an `and` (see Exercise 4.64) or on low-level details concerning the order in which the system processes queries.[77]

[77] This is not a problem of the logic but one of the procedural interpretation of the logic

Problems with `not`

Another quirk in the query system concerns `not`. Given the data base of Section 4.4.1, consider the following two queries:

```
(and (supervisor ?x ?y)
     (not (job ?x (computer programmer))))
(and (not (job ?x (computer programmer)))
     (supervisor ?x ?y))
```

These two queries do not produce the same result. The first query begins by finding all entries in the data base that match `(supervisor ?x ?y)`, and then filters the resulting frames by removing the ones in which the value of `?x` satisfies `(job ?x (computer programmer))`. The second query begins by filtering the incoming frames to remove those that can satisfy `(job ?x (computer programmer))`. Since the only incoming frame is empty, it checks the data base to see if there are any patterns that satisfy `(job ?x (computer programmer))`. Since there generally are entries of this form, the `not` clause filters out the empty frame and returns an empty stream of frames. Consequently, the entire compound query returns an empty stream.

The trouble is that our implementation of `not` really is meant to serve as a filter on values for the variables. If a `not` clause is processed with a frame

---

provided by our interpreter. We could write an interpreter that would not fall into a loop here. For example, we could enumerate all the proofs derivable from our assertions and our rules in a breadth-first rather than a depth-first order. However, such a system makes it more difficult to take advantage of the order of deductions in our programs. One attempt to build sophisticated control into such a program is described in deKleer et al. 1977. Another technique, which does not lead to such serious control problems, is to put in special knowledge, such as detectors for particular kinds of loops (Exercise 4.67). However, there can be no general scheme for reliably preventing a system from going down infinite paths in performing deductions. Imagine a diabolical rule of the form "To show $P(x)$ is true, show that $P(f(x))$ is true," for some suitably chosen function f.

in which some of the variables remain unbound (as does `?x` in the example above), the system will produce unexpected results. Similar problems occur with the use of `lisp-value`—the Lisp predicate can't work if some of its arguments are unbound. See Exercise 4.77.

There is also a much more serious way in which the `not` of the query language differs from the `not` of mathematical logic. In logic, we interpret the statement "not P" to mean that P is not true. In the query system, however, "not P" means that P is not deducible from the knowledge in the data base. For example, given the personnel data base of Section 4.4.1, the system would happily deduce all sorts of `not` statements, such as that Ben Bitdiddle is not a baseball fan, that it is not raining outside, and that 2 + 2 is not 4.[78] In other words, the `not` of logic programming languages reflects the so-called *closed world assumption* that all relevant information has been included in the data base.[79]

Exercise 4.64: Louis Reasoner mistakenly deletes the `outranked-by` rule (Section 4.4.1) from the data base. When he realizes this, he quickly reinstalls it. Unfortunately, he makes a slight change in the rule, and types it in as

```
(rule (outranked-by ?staff-person ?boss)
      (or (supervisor ?staff-person ?boss)
          (and (outranked-by ?middle-manager ?boss)
               (supervisor ?staff-person
                           ?middle-manager))))
```

[78] Consider the query `(not (baseball-fan (Bitdiddle Ben)))`. The system finds that `(baseball-fan (Bitdiddle Ben))` is not in the data base, so the empty frame does not satisfy the pattern and is not filtered out of the initial stream of frames. The result of the query is thus the empty frame, which is used to instantiate the input query to produce `(not (baseball-fan (Bitdiddle Ben)))`.

[79] A discussion and justification of this treatment of `not` can be found in the article by Clark (1978).

Just after Louis types this information into the system, DeWitt Aull comes by to find out who outranks Ben Bitdiddle. He issues the query

```
(outranked-by (Bitdiddle Ben) ?who)
```

After answering, the system goes into an infinite loop. Explain why.

Exercise 4.65: Cy D. Fect, looking forward to the day when he will rise in the organization, gives a query to find all the wheels (using the `wheel` rule of Section 4.4.1):

```
(wheel ?who)
```

To his surprise, the system responds

```
;;; Query results:
(wheel (Warbucks Oliver))
(wheel (Bitdiddle Ben))
(wheel (Warbucks Oliver))
(wheel (Warbucks Oliver))
(wheel (Warbucks Oliver))
```

Why is Oliver Warbucks listed four times?

Exercise 4.66: Ben has been generalizing the query system to provide statistics about the company. For example, to find the total salaries of all the computer programmers one will be able to say

```
(sum ?amount (and (job ?x (computer programmer))
                  (salary ?x ?amount)))
```

In general, Ben's new system allows expressions of the form

`(accumulation-function ⟨variable⟩ ⟨query pattern⟩)`

where `accumulation-function` can be things like `sum`, `average`, or `maximum`. Ben reasons that it should be a cinch to implement this. He will simply feed the query pattern to `qeval`. This will produce a stream of frames. He will then pass this stream through a mapping function that extracts the value of the designated variable from each frame in the stream and feed the resulting stream of values to the accumulation function. Just as Ben completes the implementation and is about to try it out, Cy walks by, still puzzling over the `wheel` query result in Exercise 4.65. When Cy shows Ben the system's response, Ben groans, "Oh, no, my simple accumulation scheme won't work!"

What has Ben just realized? Outline a method he can use to salvage the situation.

Exercise 4.67: Devise a way to install a loop detector in the query system so as to avoid the kinds of simple loops illustrated in the text and in Exercise 4.64. The general idea is that the system should maintain some sort of history of its current chain of deductions and should not begin processing a query that it is already working on. Describe what kind of information (patterns and frames) is included in this history, and how the check should be made. (After you study the details of the query-system implementation in Section 4.4.4, you may want to modify the system to include your loop detector.)

Exercise 4.68: Define rules to implement the `reverse` operation of Exercise 2.18, which returns a list containing the same

elements as a given list in reverse order. (Hint: Use `append-to-form`.) Can your rules answer both `(reverse (1 2 3) ?x)` and `(reverse ?x (1 2 3))`?

Exercise 4.69: Beginning with the data base and the rules you formulated in Exercise 4.63, devise a rule for adding "greats" to a grandson relationship. This should enable the system to deduce that Irad is the great-grandson of Adam, or that Jabal and Jubal are the great-great-great-great-great-grandsons of Adam. (Hint: Represent the fact about Irad, for example, as `((great grandson) Adam Irad)`. Write rules that determine if a list ends in the word `grandson`. Use this to express a rule that allows one to derive the relationship `((great . ?rel) ?x ?y)`, where `?rel` is a list ending in `grandson`.) Check your rules on queries such as `((great grandson) ?g ?ggs)` and `(?relationship Adam Irad)`.

4.4.4 Implementing the Query System

Section 4.4.2 described how the query system works. Now we fill in the details by presenting a complete implementation of the system.

4.4.4.1 The Driver Loop and Instantiation

The driver loop for the query system repeatedly reads input expressions. If the expression is a rule or assertion to be added to the data base, then the information is added. Otherwise the expression is assumed to be a query. The driver passes this query to the evaluator `qeval` together with an initial frame stream consisting of a single empty frame. The result of the evaluation is a stream of frames generated by satisfying the query with variable values found in the data base. These frames are used to form a new stream consisting

of copies of the original query in which the variables are instantiated with values supplied by the stream of frames, and this final stream is printed at the terminal:

```
(define input-prompt  ";;; Query input:")
(define output-prompt ";;; Query results:")

(define (query-driver-loop)
  (prompt-for-input input-prompt)
  (let ((q (query-syntax-process (read))))
    (cond ((assertion-to-be-added? q)
           (add-rule-or-assertion! (add-assertion-body q))
           (newline)
           (display "Assertion added to data base.")
           (query-driver-loop))
          (else
           (newline)
           (display output-prompt)
           (display-stream
            (stream-map
             (lambda (frame)
               (instantiate
                q
                frame
                (lambda (v f)
                  (contract-question-mark v))))
             (qeval q (singleton-stream '()))))
           (query-driver-loop)))))
```

Here, as in the other evaluators in this chapter, we use an abstract syntax for the expressions of the query language. The implementation of the expression syntax, including the predicate `assertion-to-be-added?` and the selector `add-assertion-body`, is given in Section 4.4.4.7. `add-`

`rule-or-assertion!` is defined in Section 4.4.4.5.

Before doing any processing on an input expression, the driver loop transforms it syntactically into a form that makes the processing more efficient. This involves changing the representation of pattern variables. When the query is instantiated, any variables that remain unbound are transformed back to the input representation before being printed. These transformations are performed by the two procedures `query-syntax-process` and `contract-question-mark` (Section 4.4.4.7).

To instantiate an expression, we copy it, replacing any variables in the expression by their values in a given frame. The values are themselves instantiated, since they could contain variables (for example, if `?x` in `exp` is bound to `?y` as the result of unification and `?y` is in turn bound to 5). The action to take if a variable cannot be instantiated is given by a procedural argument to `instantiate`.

```
(define (instantiate exp frame unbound-var-handler)
  (define (copy exp)
    (cond ((var? exp)
           (let ((binding (binding-in-frame exp frame)))
             (if binding
                 (copy (binding-value binding))
                 (unbound-var-handler exp frame))))
          ((pair? exp)
           (cons (copy (car exp)) (copy (cdr exp))))
          (else exp)))
  (copy exp))
```

The procedures that manipulate bindings are defined in Section 4.4.4.8.

4.4.4.2 The Evaluator

The `qeval` procedure, called by the `query-driver-loop`, is the basic evaluator of the query system. It takes as inputs a query and a stream of frames, and it returns a stream of extended frames. It identifies special forms by a data-directed dispatch using `get` and `put`, just as we did in implementing generic operations in Chapter 2. Any query that is not identified as a special form is assumed to be a simple query, to be processed by `simple-query`.

```
(define (qeval query frame-stream)
  (let ((qproc (get (type query) 'qeval)))
    (if qproc
        (qproc (contents query) frame-stream)
        (simple-query query frame-stream))))
```

`type` and `contents`, defined in Section 4.4.4.7, implement the abstract syntax of the special forms.

Simple queries

The `simple-query` procedure handles simple queries. It takes as arguments a simple query (a pattern) together with a stream of frames, and it returns the stream formed by extending each frame by all data-base matches of the query.

```
(define (simple-query query-pattern frame-stream)
  (stream-flatmap
   (lambda (frame)
     (stream-append-delayed
      (find-assertions query-pattern frame)
      (delay (apply-rules query-pattern frame))))
   frame-stream))
```

For each frame in the input stream, we use `find-assertions` (Section 4.4.4.3) to match the pattern against all assertions in the data base, producing a stream of extended frames, and we use `apply-rules` (Section 4.4.4.4) to apply all possible rules, producing another stream of extended frames. These two streams are combined (using `stream-append-delayed`, Section 4.4.4.6) to make a stream of all the ways that the given pattern can be satisfied consistent with the original frame (see Exercise 4.71). The streams for the individual input frames are combined using `stream-flatmap` (Section 4.4.4.6) to form one large stream of all the ways that any of the frames in the original input stream can be extended to produce a match with the given pattern.

Compound queries

`and` queries are handled as illustrated in Figure 4.5 by the `conjoin` procedure. `conjoin` takes as inputs the conjuncts and the frame stream and returns the stream of extended frames. First, `conjoin` processes the stream of frames to find the stream of all possible frame extensions that satisfy the first query in the conjunction. Then, using this as the new frame stream, it recursively applies `conjoin` to the rest of the queries.

```
(define (conjoin conjuncts frame-stream)
  (if (empty-conjunction? conjuncts)
      frame-stream
      (conjoin (rest-conjuncts conjuncts)
               (qeval (first-conjunct conjuncts) frame-strea
```

The expression

```
(put 'and 'qeval conjoin)
```

sets up `qeval` to dispatch to `conjoin` when an `and` form is encountered.

`or` queries are handled similarly, as shown in Figure 4.6. The output streams for the various disjuncts of the `or` are computed separately and merged using the `interleave-delayed` procedure from Section 4.4.4.6. (See Exercise 4.71 and Exercise 4.72.)

```
(define (disjoin disjuncts frame-stream)
  (if (empty-disjunction? disjuncts)
      the-empty-stream
      (interleave-delayed
       (qeval (first-disjunct disjuncts) frame-stream)
       (delay (disjoin (rest-disjuncts disjuncts) frame-stre
(put 'or 'qeval disjoin)
```

The predicates and selectors for the syntax of conjuncts and disjuncts are given in Section 4.4.4.7.

Filters

`not` is handled by the method outlined in Section 4.4.2. We attempt to extend each frame in the input stream to satisfy the query being negated, and we include a given frame in the output stream only if it cannot be extended.

```
(define (negate operands frame-stream)
  (stream-flatmap
   (lambda (frame)
     (if (stream-null?
          (qeval (negated-query operands)
                 (singleton-stream frame)))
         (singleton-stream frame)
         the-empty-stream))
   frame-stream))
(put 'not 'qeval negate)
```

`lisp-value` is a filter similar to `not`. Each frame in the stream is used to instantiate the variables in the pattern, the indicated predicate is applied, and

the frames for which the predicate returns false are filtered out of the input stream. An error results if there are unbound pattern variables.

```
(define (lisp-value call frame-stream)
  (stream-flatmap
   (lambda (frame)
     (if (execute
          (instantiate
           call
           frame
           (lambda (v f)
             (error "Unknown pat var: LISP-VALUE" v))))
         (singleton-stream frame)
         the-empty-stream))
   frame-stream))
(put 'lisp-value 'qeval lisp-value)
```

`execute`, which applies the predicate to the arguments, must `eval` the predicate expression to get the procedure to apply. However, it must not evaluate the arguments, since they are already the actual arguments, not expressions whose evaluation (in Lisp) will produce the arguments. Note that `execute` is implemented using `eval` and `apply` from the underlying Lisp system.

```
(define (execute exp)
  (apply (eval (predicate exp) user-initial-environment)
         (args exp)))
```

The `always-true` special form provides for a query that is always satisfied. It ignores its contents (normally empty) and simply passes through all the frames in the input stream. `always-true` is used by the `rule-body` selector (Section 4.4.4.7) to provide bodies for rules that were defined without bodies (that is, rules whose conclusions are always satisfied).

```
(define (always-true ignore frame-stream) frame-stream)
(put 'always-true 'qeval always-true)
```

The selectors that define the syntax of `not` and `lisp-value` are given in Section 4.4.4.7.

4.4.4.3 Finding Assertions by Pattern Matching

`find-assertions`, called by `simple-query` (Section 4.4.4.2), takes as input a pattern and a frame. It returns a stream of frames, each extending the given one by a data-base match of the given pattern. It uses `fetch-assertions` (Section 4.4.4.5) to get a stream of all the assertions in the data base that should be checked for a match against the pattern and the frame. The reason for `fetch-assertions` here is that we can often apply simple tests that will eliminate many of the entries in the data base from the pool of candidates for a successful match. The system would still work if we eliminated `fetch-assertions` and simply checked a stream of all assertions in the data base, but the computation would be less efficient because we would need to make many more calls to the matcher.

```
(define (find-assertions pattern frame)
  (stream-flatmap
   (lambda (datum) (check-an-assertion datum pattern frame))
   (fetch-assertions pattern frame)))
```

`check-an-assertion` takes as arguments a pattern, a data object (assertion), and a frame and returns either a one-element stream containing the extended frame or `the-empty-stream` if the match fails.

```
(define (check-an-assertion assertion query-pat query-frame)
  (let ((match-result
         (pattern-match query-pat assertion query-frame)))
```

```
    (if (eq? match-result 'failed)
        the-empty-stream
        (singleton-stream match-result))))
```

The basic pattern matcher returns either the symbol `failed` or an extension of the given frame. The basic idea of the matcher is to check the pattern against the data, element by element, accumulating bindings for the pattern variables. If the pattern and the data object are the same, the match succeeds and we return the frame of bindings accumulated so far. Otherwise, if the pattern is a variable we extend the current frame by binding the variable to the data, so long as this is consistent with the bindings already in the frame. If the pattern and the data are both pairs, we (recursively) match the `car` of the pattern against the `car` of the data to produce a frame; in this frame we then match the `cdr` of the pattern against the `cdr` of the data. If none of these cases are applicable, the match fails and we return the symbol `failed`.

```
(define (pattern-match pat dat frame)
  (cond ((eq? frame 'failed) 'failed)
        ((equal? pat dat) frame)
        ((var? pat) (extend-if-consistent pat dat frame))
        ((and (pair? pat) (pair? dat))
         (pattern-match
          (cdr pat)
          (cdr dat)
          (pattern-match (car pat) (car dat) frame)))
        (else 'failed)))
```

Here is the procedure that extends a frame by adding a new binding, if this is consistent with the bindings already in the frame:

```
(define (extend-if-consistent var dat frame)
  (let ((binding (binding-in-frame var frame)))
    (if binding
        (pattern-match (binding-value binding) dat frame)
```

```
        (extend var dat frame))))
```

If there is no binding for the variable in the frame, we simply add the binding of the variable to the data. Otherwise we match, in the frame, the data against the value of the variable in the frame. If the stored value contains only constants, as it must if it was stored during pattern matching by `extend-if-consistent`, then the match simply tests whether the stored and new values are the same. If so, it returns the unmodified frame; if not, it returns a failure indication. The stored value may, however, contain pattern variables if it was stored during unification (see Section 4.4.4.4). The recursive match of the stored pattern against the new data will add or check bindings for the variables in this pattern. For example, suppose we have a frame in which `?x` is bound to `(f ?y)` and `?y` is unbound, and we wish to augment this frame by a binding of `?x` to `(f b)`. We look up `?x` and find that it is bound to `(f ?y)`. This leads us to match `(f ?y)` against the proposed new value `(f b)` in the same frame. Eventually this match extends the frame by adding a binding of `?y` to `b`. `?X` remains bound to `(f ?y)`. We never modify a stored binding and we never store more than one binding for a given variable.

The procedures used by `extend-if-consistent` to manipulate bindings are defined in Section 4.4.4.8.

Patterns with dotted tails

If a pattern contains a dot followed by a pattern variable, the pattern variable matches the rest of the data list (rather than the next element of the data list), just as one would expect with the dotted-tail notation described in Exercise 2.20. Although the pattern matcher we have just implemented doesn't look for dots, it does behave as we want. This is because the Lisp `read` primitive, which is used by `query-driver-loop` to read the query and represent it as a list structure, treats dots in a special way.

When `read` sees a dot, instead of making the next item be the next element of a list (the `car` of a `cons` whose `cdr` will be the rest of the list) it makes the next item be the `cdr` of the list structure. For example, the list structure produced by `read` for the pattern `(computer ?type)` could be constructed by evaluating the expression `(cons 'computer (cons '?type '()))`, and that for `(computer . ?type)` could be constructed by evaluating the expression `(cons 'computer '?type)`.

Thus, as `pattern-match` recursively compares `cars` and `cdrs` of a data list and a pattern that had a dot, it eventually matches the variable after the dot (which is a `cdr` of the pattern) against a sublist of the data list, binding the variable to that list. For example, matching the pattern `(computer . ?type)` against `(computer programmer trainee)` will match `?type` against the list `(programmer trainee)`.

4.4.4.4 Rules and Unification

`apply-rules` is the rule analog of `find-assertions` (Section 4.4.4.3). It takes as input a pattern and a frame, and it forms a stream of extension frames by applying rules from the data base. `stream-flatmap` maps `apply-a-rule` down the stream of possibly applicable rules (selected by `fetch-rules`, Section 4.4.4.5) and combines the resulting streams of frames.

```
(define (apply-rules pattern frame)
  (stream-flatmap (lambda (rule)
                    (apply-a-rule rule pattern frame))
                  (fetch-rules pattern frame)))
```

`apply-a-rule` applies rules using the method outlined in Section 4.4.2. It first augments its argument frame by unifying the rule conclusion with the pattern in the given frame. If this succeeds, it evaluates the rule body in this new frame.

Before any of this happens, however, the program renames all the variables in the rule with unique new names. The reason for this is to prevent the variables for different rule applications from becoming confused with each other. For instance, if two rules both use a variable named `?x`, then each one may add a binding for `?x` to the frame when it is applied. These two `?x`'s have nothing to do with each other, and we should not be fooled into thinking that the two bindings must be consistent. Rather than rename variables, we could devise a more clever environment structure; however, the renaming approach we have chosen here is the most straightforward, even if not the most efficient. (See Exercise 4.79.) Here is the `apply-a-rule` procedure:

```
(define (apply-a-rule rule query-pattern query-frame)
  (let ((clean-rule (rename-variables-in rule)))
    (let ((unify-result (unify-match query-pattern
                                     (conclusion clean-rule)
                                     query-frame)))
      (if (eq? unify-result 'failed)
          the-empty-stream
          (qeval (rule-body clean-rule)
                 (singleton-stream unify-result))))))
```

The selectors `rule-body` and `conclusion` that extract parts of a rule are defined in Section 4.4.4.7.

We generate unique variable names by associating a unique identifier (such as a number) with each rule application and combining this identifier with the original variable names. For example, if the rule-application identifier is 7, we might change each `?x` in the rule to `?x-7` and each `?y` in the rule to `?y-7`. (`make-new-variable` and `new-rule-application-id` are included with the syntax procedures in Section 4.4.4.7.)

```
(define (rename-variables-in rule)
  (let ((rule-application-id (new-rule-application-id)))
```

```
    (define (tree-walk exp)
      (cond ((var? exp)
             (make-new-variable exp rule-application-id))
            ((pair? exp)
             (cons (tree-walk (car exp))
                   (tree-walk (cdr exp))))
            (else exp)))
    (tree-walk rule)))
```

The unification algorithm is implemented as a procedure that takes as inputs two patterns and a frame and returns either the extended frame or the symbol `failed`. The unifier is like the pattern matcher except that it is symmetrical —variables are allowed on both sides of the match. `unify-match` is basically the same as `pattern-match`, except that there is extra code (marked "`***`" below) to handle the case where the object on the right side of the match is a variable.

```
(define (unify-match p1 p2 frame)
  (cond ((eq? frame 'failed) 'failed)
        ((equal? p1 p2) frame)
        ((var? p1) (extend-if-possible p1 p2 frame))
        ((var? p2) (extend-if-possible p2 p1 frame))  ;
***
        ((and (pair? p1) (pair? p2))
         (unify-match (cdr p1)
                      (cdr p2)
                      (unify-match (car p1)
                                   (car p2)
                                   frame)))
        (else 'failed)))
```

In unification, as in one-sided pattern matching, we want to accept a proposed extension of the frame only if it is consistent with existing bindings. The procedure `extend-if-possible` used in unification is the same as

the `extend-if-consistent` used in pattern matching except for two special checks, marked "`***`" in the program below. In the first case, if the variable we are trying to match is not bound, but the value we are trying to match it with is itself a (different) variable, it is necessary to check to see if the value is bound, and if so, to match its value. If both parties to the match are unbound, we may bind either to the other.

The second check deals with attempts to bind a variable to a pattern that includes that variable. Such a situation can occur whenever a variable is repeated in both patterns. Consider, for example, unifying the two patterns `(?x ?x)` and `(?y` ⟨*expression involving ?y*⟩`)` in a frame where both `?x` and `?y` are unbound. First `?x` is matched against `?y`, making a binding of `?x` to `?y`. Next, the same `?x` is matched against the given expression involving `?y`. Since `?x` is already bound to `?y`, this results in matching `?y` against the expression. If we think of the unifier as finding a set of values for the pattern variables that make the patterns the same, then these patterns imply instructions to find a `?y` such that `?y` is equal to the expression involving `?y`. There is no general method for solving such equations, so we reject such bindings; these cases are recognized by the predicate `depends-on?`.[80] On the other hand, we do not want to reject attempts

[80] In general, unifying `?y` with an expression involving `?y` would require our being able to find a fixed point of the equation `?y` = ⟨*expression involving ?y*⟩. It is sometimes possible to syntactically form an expression that appears to be the solution. For example, `?y = (f ?y)` seems to have the fixed point `(f (f (f ... )))`, which we can produce by beginning with the expression `(f ?y)` and repeatedly substituting `(f ?y)` for `?y`. Unfortunately, not every such equation has a meaningful fixed point. The issues that arise here are similar to the issues of manipulating infinite series in mathematics. For example, we know that 2 is the solution to the equation $y = 1 + y/2$. Beginning with the expression $1 + y/2$ and repeatedly substituting $1 + y/2$ for y gives

$$2 = y = 1 + \frac{y}{2} = 1 + \frac{1}{2}\left(1 + \frac{y}{2}\right) = 1 + \frac{1}{2} + \frac{y}{4} = \ldots,$$

which leads to

to bind a variable to itself. For example, consider unifying `(?x ?x)` and `(?y ?y)`. The second attempt to bind `?x` to `?y` matches `?y` (the stored value of `?x`) against `?y` (the new value of `?x`). This is taken care of by the `equal?` clause of `unify-match`.

```
(define (extend-if-possible var val frame)
  (let ((binding (binding-in-frame var frame)))
    (cond (binding
           (unify-match (binding-value binding) val frame))
          ((var? val)                          ;***
           (let ((binding (binding-in-frame val frame)))
             (if binding
                 (unify-match
                  var (binding-value binding) frame)
                 (extend var val frame))))
          ((depends-on? val var frame)     ;***
           'failed)
          (else (extend var val frame)))))
```

`depends-on?` is a predicate that tests whether an expression proposed to be the value of a pattern variable depends on the variable. This must be done

---

$$2 = 1 + \frac{1}{2} + \frac{1}{4} + \frac{1}{8} + \ldots .$$

However, if we try the same manipulation beginning with the observation that -1 is the solution to the equation $y = 1 + 2y$, we obtain

$$-1 = y = 1 + 2y = 1 + 2(1 + 2y) = 1 + 2 + 4y = \ldots ,$$

which leads to

$$-1 = 1 + 2 + 4 + 8 + \ldots .$$

Although the formal manipulations used in deriving these two equations are identical, the first result is a valid assertion about infinite series but the second is not. Similarly, for our unification results, reasoning with an arbitrary syntactically constructed expression may lead to errors.

relative to the current frame because the expression may contain occurrences of a variable that already has a value that depends on our test variable. The structure of `depends-on?` is a simple recursive tree walk in which we substitute for the values of variables whenever necessary.

```
(define (depends-on? exp var frame)
  (define (tree-walk e)
    (cond ((var? e)
           (if (equal? var e)
               true
               (let ((b (binding-in-frame e frame)))
                 (if b
                     (tree-walk (binding-value b))
                     false))))
          ((pair? e)
           (or (tree-walk (car e))
               (tree-walk (cdr e))))
          (else false)))
  (tree-walk exp))
```

4.4.4.5 Maintaining the Data Base

One important problem in designing logic programming languages is that of arranging things so that as few irrelevant data-base entries as possible will be examined in checking a given pattern. In our system, in addition to storing all assertions in one big stream, we store all assertions whose `cars` are constant symbols in separate streams, in a table indexed by the symbol. To fetch an assertion that may match a pattern, we first check to see if the `car` of the pattern is a constant symbol. If so, we return (to be tested using the matcher) all the stored assertions that have the same `car`. If the pattern's `car` is not a constant symbol, we return all the stored assertions. Cleverer methods could also take advantage of information in the frame, or try also to optimize the

case where the `car` of the pattern is not a constant symbol. We avoid building our criteria for indexing (using the `car`, handling only the case of constant symbols) into the program; instead we call on predicates and selectors that embody our criteria.

```
(define THE-ASSERTIONS the-empty-stream)
(define (fetch-assertions pattern frame)
  (if (use-index? pattern)
      (get-indexed-assertions pattern)
      (get-all-assertions)))
(define (get-all-assertions) THE-ASSERTIONS)
(define (get-indexed-assertions pattern)
  (get-stream (index-key-of pattern) 'assertion-stream))
```

`get-stream` looks up a stream in the table and returns an empty stream if nothing is stored there.

```
(define (get-stream key1 key2)
  (let ((s (get key1 key2)))
    (if s s the-empty-stream)))
```

Rules are stored similarly, using the `car` of the rule conclusion. Rule conclusions are arbitrary patterns, however, so they differ from assertions in that they can contain variables. A pattern whose `car` is a constant symbol can match rules whose conclusions start with a variable as well as rules whose conclusions have the same `car`. Thus, when fetching rules that might match a pattern whose `car` is a constant symbol we fetch all rules whose conclusions start with a variable as well as those whose conclusions have the same `car` as the pattern. For this purpose we store all rules whose conclusions start with a variable in a separate stream in our table, indexed by the symbol `?`.

```
(define THE-RULES the-empty-stream)
(define (fetch-rules pattern frame)
  (if (use-index? pattern)
```

```
      (get-indexed-rules pattern)
      (get-all-rules)))
(define (get-all-rules) THE-RULES)
(define (get-indexed-rules pattern)
  (stream-append
   (get-stream (index-key-of pattern) 'rule-stream)
   (get-stream '? 'rule-stream)))
```

`add-rule-or-assertion!` is used by `query-driver-loop` to add assertions and rules to the data base. Each item is stored in the index, if appropriate, and in a stream of all assertions or rules in the data base.

```
(define (add-rule-or-assertion! assertion)
  (if (rule? assertion)
      (add-rule! assertion)
      (add-assertion! assertion)))
(define (add-assertion! assertion)
  (store-assertion-in-index assertion)
  (let ((old-assertions THE-ASSERTIONS))
    (set! THE-ASSERTIONS
          (cons-stream assertion old-assertions))
    'ok))
(define (add-rule! rule)
  (store-rule-in-index rule)
  (let ((old-rules THE-RULES))
    (set! THE-RULES (cons-stream rule old-rules))
    'ok))
```

To actually store an assertion or a rule, we check to see if it can be indexed. If so, we store it in the appropriate stream.

```
(define (store-assertion-in-index assertion)
  (if (indexable? assertion)
      (let ((key (index-key-of assertion)))
        (let ((current-assertion-stream
```

```
                (get-stream key 'assertion-stream)))
          (put key
               'assertion-stream
               (cons-stream
                assertion
                current-assertion-stream))))))
(define (store-rule-in-index rule)
  (let ((pattern (conclusion rule)))
    (if (indexable? pattern)
        (let ((key (index-key-of pattern)))
          (let ((current-rule-stream
                 (get-stream key 'rule-stream)))
            (put key
                 'rule-stream
                 (cons-stream rule
                              current-rule-stream)))))))
```

The following procedures define how the data-base index is used. A pattern (an assertion or a rule conclusion) will be stored in the table if it starts with a variable or a constant symbol.

```
(define (indexable? pat)
  (or (constant-symbol? (car pat))
      (var? (car pat))))
```

The key under which a pattern is stored in the table is either `?` (if it starts with a variable) or the constant symbol with which it starts.

```
(define (index-key-of pat)
  (let ((key (car pat)))
    (if (var? key) '? key)))
```

The index will be used to retrieve items that might match a pattern if the pattern starts with a constant symbol.

```
(define (use-index? pat) (constant-symbol? (car pat)))
```

Exercise 4.70: What is the purpose of the `let` bindings in the procedures `add-assertion!` and `add-rule!` ? What would be wrong with the following implementation of `add-assertion!` ? Hint: Recall the definition of the infinite stream of ones in Section 3.5.2: `(define ones (cons-stream 1 ones))`.

```
(define (add-assertion! assertion)
  (store-assertion-in-index assertion)
  (set! THE-ASSERTIONS
        (cons-stream assertion THE-ASSERTIONS))
  'ok)
```

4.4.4.6 Stream Operations

The query system uses a few stream operations that were not presented in Chapter 3.

`stream-append-delayed` and `interleave-delayed` are just like `stream-append` and `interleave` (Section 3.5.3), except that they take a delayed argument (like the `integral` procedure in Section 3.5.4). This postpones looping in some cases (see Exercise 4.71).

```
(define (stream-append-delayed s1 delayed-s2)
  (if (stream-null? s1)
      (force delayed-s2)
      (cons-stream
       (stream-car s1)
       (stream-append-delayed
        (stream-cdr s1)
        delayed-s2))))
(define (interleave-delayed s1 delayed-s2)
  (if (stream-null? s1)
      (force delayed-s2)
```

```
      (cons-stream
       (stream-car s1)
       (interleave-delayed
        (force delayed-s2)
        (delay (stream-cdr s1))))))
```

`stream-flatmap`, which is used throughout the query evaluator to map a procedure over a stream of frames and combine the resulting streams of frames, is the stream analog of the `flatmap` procedure introduced for ordinary lists in Section 2.2.3. Unlike ordinary `flatmap`, however, we accumulate the streams with an interleaving process, rather than simply appending them (see Exercise 4.72 and Exercise 4.73).

```
(define (stream-flatmap proc s)
  (flatten-stream (stream-map proc s)))

(define (flatten-stream stream)
  (if (stream-null? stream)
      the-empty-stream
      (interleave-delayed
       (stream-car stream)
       (delay (flatten-stream (stream-cdr stream))))))
```

The evaluator also uses the following simple procedure to generate a stream consisting of a single element:

```
(define (singleton-stream x)
  (cons-stream x the-empty-stream))
```

4.4.4.7 Query Syntax Procedures

`type` and `contents`, used by `qeval` (Section 4.4.4.2), specify that a special form is identified by the symbol in its `car`. They are the same as the

`type-tag` and `contents` procedures in Section 2.4.2, except for the error message.

```
(define (type exp)
  (if (pair? exp)
      (car exp)
      (error "Unknown expression TYPE" exp)))
(define (contents exp)
  (if (pair? exp)
      (cdr exp)
      (error "Unknown expression CONTENTS" exp)))
```

The following procedures, used by `query-driver-loop` (in Section 4.4.4.1), specify that rules and assertions are added to the data base by expressions of the form `(assert!` ⟨*rule-or-assertion*⟩`)`:

```
(define (assertion-to-be-added? exp)
  (eq? (type exp) 'assert!))
(define (add-assertion-body exp) (car (contents exp)))
```

Here are the syntax definitions for the `and`, `or`, `not`, and `lisp-value` special forms (Section 4.4.4.2):

```
(define (empty-conjunction? exps) (null? exps))
(define (first-conjunct exps) (car exps))
(define (rest-conjuncts exps) (cdr exps))
(define (empty-disjunction? exps) (null? exps))
(define (first-disjunct exps) (car exps))
(define (rest-disjuncts exps) (cdr exps))
(define (negated-query exps) (car exps))
(define (predicate exps) (car exps))
(define (args exps) (cdr exps))
```

The following three procedures define the syntax of rules:

```
(define (rule? statement)
```

```
  (tagged-list? statement 'rule))
(define (conclusion rule) (cadr rule))
(define (rule-body rule)
  (if (null? (cddr rule)) '(always-true) (caddr rule)))
```

`query-driver-loop` (Section 4.4.4.1) calls `query-syntax-process` to transform pattern variables in the expression, which have the form `?symbol`, into the internal format `(? symbol)`. That is to say, a pattern such as `(job ?x ?y)` is actually represented internally by the system as `(job (? x) (? y))`. This increases the efficiency of query processing, since it means that the system can check to see if an expression is a pattern variable by checking whether the `car` of the expression is the symbol `?`, rather than having to extract characters from the symbol. The syntax transformation is accomplished by the following procedure:[81]

```
(define (query-syntax-process exp)
  (map-over-symbols expand-question-mark exp))
(define (map-over-symbols proc exp)
  (cond ((pair? exp)
         (cons (map-over-symbols proc (car exp))
               (map-over-symbols proc (cdr exp))))
        ((symbol? exp) (proc exp))
        (else exp)))
(define (expand-question-mark symbol)
  (let ((chars (symbol->string symbol)))
```

[81] Most Lisp systems give the user the ability to modify the ordinary `read` procedure to perform such transformations by defining *reader macro characters*. Quoted expressions are already handled in this way: The reader automatically translates `'expression` into `(quote expression)` before the evaluator sees it. We could arrange for `?expression` to be transformed into `(? expression)` in the same way; however, for the sake of clarity we have included the transformation procedure here explicitly.

`expand-question-mark` and `contract-question-mark` use several procedures with `string` in their names. These are Scheme primitives.

```
    (if (string=? (substring chars 0 1) "?")
        (list '?
              (string->symbol
               (substring chars 1 (string-length chars))))
        symbol)))
```

Once the variables are transformed in this way, the variables in a pattern are lists starting with `?`, and the constant symbols (which need to be recognized for data-base indexing, Section 4.4.4.5) are just the symbols.

```
(define (var? exp) (tagged-list? exp '?))
(define (constant-symbol? exp) (symbol? exp))
```

Unique variables are constructed during rule application (in Section 4.4.4.4) by means of the following procedures. The unique identifier for a rule application is a number, which is incremented each time a rule is applied.

```
(define rule-counter 0)
(define (new-rule-application-id)
  (set! rule-counter (+ 1 rule-counter))
  rule-counter)
(define (make-new-variable var rule-application-id)
  (cons '? (cons rule-application-id (cdr var))))
```

When `query-driver-loop` instantiates the query to print the answer, it converts any unbound pattern variables back to the right form for printing, using

```
(define (contract-question-mark variable)
  (string->symbol
   (string-append "?"
     (if (number? (cadr variable))
         (string-append (symbol->string (caddr variable))
                        "-"
                        (number->string (cadr variable)))
         (symbol->string (cadr variable))))))
```

4.4.4.8 Frames and Bindings

Frames are represented as lists of bindings, which are variable-value pairs:

```
(define (make-binding variable value)
  (cons variable value))
(define (binding-variable binding) (car binding))
(define (binding-value binding) (cdr binding))
(define (binding-in-frame variable frame)
  (assoc variable frame))
(define (extend variable value frame)
  (cons (make-binding variable value) frame))
```

Exercise 4.71: Louis Reasoner wonders why the `simple-query` and `disjoin` procedures (Section 4.4.4.2) are implemented using explicit `delay` operations, rather than being defined as follows:

```
(define (simple-query query-pattern frame-stream)
  (stream-flatmap
   (lambda (frame)
     (stream-append
      (find-assertions query-pattern frame)
      (apply-rules query-pattern frame)))
   frame-stream))
(define (disjoin disjuncts frame-stream)
  (if (empty-disjunction? disjuncts)
      the-empty-stream
      (interleave
       (qeval (first-disjunct disjuncts)
              frame-stream)
       (disjoin (rest-disjuncts disjuncts)
                frame-stream))))
```

Can you give examples of queries where these simpler definitions would lead to undesirable behavior?

Exercise 4.72: Why do `disjoin` and `stream-flatmap` interleave the streams rather than simply append them? Give examples that illustrate why interleaving works better. (Hint: Why did we use `interleave` in Section 3.5.3?)

Exercise 4.73: Why does `flatten-stream` use `delay` explicitly? What would be wrong with defining it as follows:

```
(define (flatten-stream stream)
  (if (stream-null? stream)
      the-empty-stream
      (interleave
       (stream-car stream)
       (flatten-stream (stream-cdr stream)))))
```

Exercise 4.74: Alyssa P. Hacker proposes to use a simpler version of `stream-flatmap` in `negate`, `lisp-value`, and `find-assertions`. She observes that the procedure that is mapped over the frame stream in these cases always produces either the empty stream or a singleton stream, so no interleaving is needed when combining these streams.

a. Fill in the missing expressions in Alyssa's program.

```
(define (simple-stream-flatmap proc s)
  (simple-flatten (stream-map proc s)))
(define (simple-flatten stream)
  (stream-map ⟨??⟩
              (stream-filter ⟨??⟩ stream)))
```

b. Does the query system's behavior change if we change it in this way?

Exercise 4.75: Implement for the query language a new special form called `unique`. `unique` should succeed if there is precisely one item in the data base satisfying a specified query. For example,

```
(unique (job ?x (computer wizard)))
```

should print the one-item stream

```
(unique (job (Bitdiddle Ben) (computer wizard)))
```

since Ben is the only computer wizard, and

```
(unique (job ?x (computer programmer)))
```

should print the empty stream, since there is more than one computer programmer. Moreover,

```
(and (job ?x ?j) (unique (job ?anyone ?j)))
```

should list all the jobs that are filled by only one person, and the people who fill them.

There are two parts to implementing `unique`. The first is to write a procedure that handles this special form, and the second is to make `qeval` dispatch to that procedure. The second part is trivial, since `qeval` does its dispatching in a data-directed way. If your procedure is called `uniquely-asserted`, all you need to do is

```
(put 'unique 'qeval uniquely-asserted)
```

and `qeval` will dispatch to this procedure for every query whose `type` (`car`) is the symbol `unique`.

The real problem is to write the procedure `uniquely-asserted`. This should take as input the `contents` (`cdr`) of the `unique` query, together with a stream of frames. For each frame in the stream, it should use `qeval` to find the stream of all extensions to the frame that satisfy the given query. Any stream that does not have exactly one item in it should be eliminated. The remaining streams should be passed back to be accumulated into one big stream that is the result of the `unique` query. This is similar to the implementation of the `not` special form.

Test your implementation by forming a query that lists all people who supervise precisely one person.

Exercise 4.76: Our implementation of `and` as a series combination of queries (Figure 4.5) is elegant, but it is inefficient because in processing the second query of the `and` we must scan the data base for each frame produced by the first query. If the data base has n elements, and a typical query produces a number of output frames proportional to n (say n/k), then scanning the data base for each frame produced by the first query will require n^2/k calls to the pattern matcher. Another approach would be to process the two clauses of the `and` separately, then look for all pairs of output frames that are compatible. If each query produces n/k output frames, then this means that we must perform n^2/k^2 compatibility checks—a factor of k fewer than the number of matches required in our current method.

Devise an implementation of `and` that uses this strategy. You must implement a procedure that takes two frames as inputs,

checks whether the bindings in the frames are compatible, and, if so, produces a frame that merges the two sets of bindings. This operation is similar to unification.

Exercise 4.77: In Section 4.4.3 we saw that `not` and `lisp-value` can cause the query language to give "wrong" answers if these filtering operations are applied to frames in which variables are unbound. Devise a way to fix this shortcoming. One idea is to perform the filtering in a "delayed" manner by appending to the frame a "promise" to filter that is fulfilled only when enough variables have been bound to make the operation possible. We could wait to perform filtering until all other operations have been performed. However, for efficiency's sake, we would like to perform filtering as soon as possible so as to cut down on the number of intermediate frames generated.

Exercise 4.78: Redesign the query language as a nondeterministic program to be implemented using the evaluator of Section 4.3, rather than as a stream process. In this approach, each query will produce a single answer (rather than the stream of all answers) and the user can type `try-again` to see more answers. You should find that much of the mechanism we built in this section is subsumed by nondeterministic search and backtracking. You will probably also find, however, that your new query language has subtle differences in behavior from the one implemented here. Can you find examples that illustrate this difference?

Exercise 4.79: When we implemented the Lisp evaluator in Section 4.1, we saw how to use local environments to avoid name

conflicts between the parameters of procedures. For example, in evaluating

```
(define (square x) (* x x))
(define (sum-of-squares x y)
  (+ (square x) (square y)))
(sum-of-squares 3 4)
```

there is no confusion between the `x` in `square` and the `x` in `sum-of-squares`, because we evaluate the body of each procedure in an environment that is specially constructed to contain bindings for the local variables. In the query system, we used a different strategy to avoid name conflicts in applying rules. Each time we apply a rule we rename the variables with new names that are guaranteed to be unique. The analogous strategy for the Lisp evaluator would be to do away with local environments and simply rename the variables in the body of a procedure each time we apply the procedure.

Implement for the query language a rule-application method that uses environments rather than renaming. See if you can build on your environment structure to create constructs in the query language for dealing with large systems, such as the rule analog of block-structured procedures. Can you relate any of this to the problem of making deductions in a context (e.g., "If I supposed that P were true, then I would be able to deduce A and B.") as a method of problem solving? (This problem is open-ended. A good answer is probably worth a Ph.D.)

5

Computing with Register Machines

> My aim is to show that the heavenly machine is not a kind of divine, live being, but a kind of clockwork (and he who believes that a clock has soul attributes the maker's glory to the work), insofar as nearly all the manifold motions are caused by a most simple and material force, just as all motions of the clock are caused by a single weight.
>
> —Johannes Kepler (letter to Herwart von Hohenburg, 1605)

WE BEGAN THIS BOOK by studying processes and by describing processes in terms of procedures written in Lisp. To explain the meanings of these procedures, we used a succession of models of evaluation: the substitution model of Chapter 1, the environment model of Chapter 3, and the metacircular evaluator of Chapter 4. Our examination of the metacircular evaluator, in particular, dispelled much of the mystery of how Lisp-like languages are interpreted. But even the metacircular evaluator leaves important questions unanswered, because it fails to elucidate the mechanisms of control in a Lisp

system. For instance, the evaluator does not explain how the evaluation of a subexpression manages to return a value to the expression that uses this value, nor does the evaluator explain how some recursive procedures generate iterative processes (that is, are evaluated using constant space) whereas other recursive procedures generate recursive processes. These questions remain unanswered because the metacircular evaluator is itself a Lisp program and hence inherits the control structure of the underlying Lisp system. In order to provide a more complete description of the control structure of the Lisp evaluator, we must work at a more primitive level than Lisp itself.

In this chapter we will describe processes in terms of the step-by-step operation of a traditional computer. Such a computer, or *register machine*, sequentially executes *instructions* that manipulate the contents of a fixed set of storage elements called *registers*. A typical register-machine instruction applies a primitive operation to the contents of some registers and assigns the result to another register. Our descriptions of processes executed by register machines will look very much like "machine-language" programs for traditional computers. However, instead of focusing on the machine language of any particular computer, we will examine several Lisp procedures and design a specific register machine to execute each procedure. Thus, we will approach our task from the perspective of a hardware architect rather than that of a machine-language computer programmer. In designing register machines, we will develop mechanisms for implementing important programming constructs such as recursion. We will also present a language for describing designs for register machines. In Section 5.2 we will implement a Lisp program that uses these descriptions to simulate the machines we design.

Most of the primitive operations of our register machines are very simple. For example, an operation might add the numbers fetched from two registers, producing a result to be stored into a third register. Such an operation can be performed by easily described hardware. In order to deal with list structure,

however, we will also use the memory operations `car`, `cdr`, and `cons`, which require an elaborate storage-allocation mechanism. In Section 5.3 we study their implementation in terms of more elementary operations.

In Section 5.4, after we have accumulated experience formulating simple procedures as register machines, we will design a machine that carries out the algorithm described by the metacircular evaluator of Section 4.1. This will fill in the gap in our understanding of how Scheme expressions are interpreted, by providing an explicit model for the mechanisms of control in the evaluator. In Section 5.5 we will study a simple compiler that translates Scheme programs into sequences of instructions that can be executed directly with the registers and operations of the evaluator register machine.

5.1 Designing Register Machines

To design a register machine, we must design its *data paths* (registers and operations) and the *controller* that sequences these operations. To illustrate the design of a simple register machine, let us examine Euclid's Algorithm, which is used to compute the greatest common divisor (GCD) of two integers. As we saw in Section 1.2.5, Euclid's Algorithm can be carried out by an iterative process, as specified by the following procedure:

```
(define (gcd a b)
  (if (= b 0)
      a
      (gcd b (remainder a b))))
```

A machine to carry out this algorithm must keep track of two numbers, a and b, so let us assume that these numbers are stored in two registers with those names. The basic operations required are testing whether the contents of register `b` is zero and computing the remainder of the contents of register

a divided by the contents of register b. The remainder operation is a complex process, but assume for the moment that we have a primitive device that computes remainders. On each cycle of the GCD algorithm, the contents of register a must be replaced by the contents of register b, and the contents of b must be replaced by the remainder of the old contents of a divided by the old contents of b. It would be convenient if these replacements could be done simultaneously, but in our model of register machines we will assume that only one register can be assigned a new value at each step. To accomplish the replacements, our machine will use a third "temporary" register, which we call t. (First the remainder will be placed in t, then the contents of b will be placed in a, and finally the remainder stored in t will be placed in b.)

We can illustrate the registers and operations required for this machine by using the data-path diagram shown in Figure 5.1. In this diagram, the registers (a, b, and t) are represented by rectangles. Each way to assign a value to a register is indicated by an arrow with an X behind the head, pointing from the source of data to the register. We can think of the X as a button that, when pushed, allows the value at the source to "flow" into the designated register. The label next to each button is the name we will use to refer to the button. The names are arbitrary, and can be chosen to have mnemonic value (for example, a←b denotes pushing the button that assigns the contents of register b to register a). The source of data for a register can be another register (as in the a←b assignment), an operation result (as in the t←r assignment), or a constant (a built-in value that cannot be changed, represented in a data-path diagram by a triangle containing the constant).

An operation that computes a value from constants and the contents of registers is represented in a data-path diagram by a trapezoid containing a name for the operation. For example, the box marked rem in Figure 5.1 represents an operation that computes the remainder of the contents of the registers a and b to which it is attached. Arrows (without buttons) point




Figure 5.1: Data paths for a GCD machine.

from the input registers and constants to the box, and arrows connect the operation's output value to registers. A test is represented by a circle containing a name for the test. For example, our GCD machine has an operation that tests whether the contents of register `b` is zero. A test also has arrows from its input registers and constants, but it has no output arrows; its value is used by the controller rather than by the data paths. Overall, the data-path diagram shows the registers and operations that are required for the machine and how they must be connected. If we view the arrows as wires and the `X` buttons as switches, the data-path diagram is very like the wiring diagram for a machine that could be constructed from electrical components.

In order for the data paths to actually compute GCDs, the buttons must be pushed in the correct sequence. We will describe this sequence in terms of a controller diagram, as illustrated in Figure 5.2. The elements of the controller diagram indicate how the data-path components should be operated. The rectangular boxes in the controller diagram identify data-path buttons to be pushed, and the arrows describe the sequencing from one step to the next. The diamond in the diagram represents a decision. One of the two sequencing arrows will be followed, depending on the value of the data-path test identified




Figure 5.2: Controller for a GCD machine.

in the diamond. We can interpret the controller in terms of a physical analogy: Think of the diagram as a maze in which a marble is rolling. When the marble rolls into a box, it pushes the data-path button that is named by the box. When the marble rolls into a decision node (such as the test for `b` = 0), it leaves the node on the path determined by the result of the indicated test. Taken together, the data paths and the controller completely describe a machine for computing GCDs. We start the controller (the rolling marble) at the place marked `start`, after placing numbers in registers `a` and `b`. When the controller reaches `done`, we will find the value of the GCD in register `a`.

Exercise 5.1: Design a register machine to compute factorials using the iterative algorithm specified by the following procedure. Draw data-path and controller diagrams for this machine.

```
(define (factorial n)
  (define (iter product counter)
    (if (> counter n)
        product
```

```
        (iter (* counter product)
              (+ counter 1))))
  (iter 1 1))
```

5.1.1 A Language for Describing Register Machines

Data-path and controller diagrams are adequate for representing simple machines such as GCD, but they are unwieldy for describing large machines such as a Lisp interpreter. To make it possible to deal with complex machines, we will create a language that presents, in textual form, all the information given by the data-path and controller diagrams. We will start with a notation that directly mirrors the diagrams.

We define the data paths of a machine by describing the registers and the operations. To describe a register, we give it a name and specify the buttons that control assignment to it. We give each of these buttons a name and specify the source of the data that enters the register under the button's control. (The source is a register, a constant, or an operation.) To describe an operation, we give it a name and specify its inputs (registers or constants).

We define the controller of a machine as a sequence of *instructions* together with *labels* that identify *entry points* in the sequence. An instruction is one of the following:

- The name of a data-path button to push to assign a value to a register. (This corresponds to a box in the controller diagram.)
- A `test` instruction, that performs a specified test.
- A conditional branch (`branch` instruction) to a location indicated by a controller label, based on the result of the previous test. (The test and branch together correspond to a diamond in the controller diagram.) If the test is false, the controller should continue with the next instruction

in the sequence. Otherwise, the controller should continue with the instruction after the label.

- An unconditional branch (`goto` instruction) naming a controller label at which to continue execution.

The machine starts at the beginning of the controller instruction sequence and stops when execution reaches the end of the sequence. Except when a branch changes the flow of control, instructions are executed in the order in which they are listed.

Figure 5.3: ↓ A specification of the GCD machine.

```
(data-paths
 (registers
  ((name a)
   (buttons ((name a<-b) (source (register b)))))
  ((name b)
   (buttons ((name b<-t) (source (register t)))))
  ((name t)
   (buttons ((name t<-r) (source (operation rem))))))
 (operations
  ((name rem) (inputs (register a) (register b)))
  ((name =) (inputs (register b) (constant 0)))))
(controller
 test-b                                  ; label
   (test =)                              ; test
   (branch (label gcd-done))             ; conditional branch
   (t<-r)                                ; button push
   (a<-b)                                ; button push
   (b<-t)                                ; button push
   (goto (label test-b))                 ; unconditional
branch
 gcd-done)                               ; label
```

Figure 5.3 shows the GCD machine described in this way. This example only hints at the generality of these descriptions, since the GCD machine is a very simple case: Each register has only one button, and each button and test is used only once in the controller.

Unfortunately, it is difficult to read such a description. In order to understand the controller instructions we must constantly refer back to the definitions of the button names and the operation names, and to understand what the buttons do we may have to refer to the definitions of the operation names. We will thus transform our notation to combine the information from the data-path and controller descriptions so that we see it all together.

To obtain this form of description, we will replace the arbitrary button and operation names by the definitions of their behavior. That is, instead of saying (in the controller) "Push button `t←r`" and separately saying (in the data paths) "Button `t←r` assigns the value of the `rem` operation to register `t`" and "The `rem` operation's inputs are the contents of registers `a` and `b`," we will say (in the controller) "Push the button that assigns to register `t` the value of the `rem` operation on the contents of registers `a` and `b`." Similarly, instead of saying (in the controller) "Perform the = test" and separately saying (in the data paths) "The = test operates on the contents of register `b` and the constant 0," we will say "Perform the = test on the contents of register `b` and the constant 0." We will omit the data-path description, leaving only the controller sequence. Thus, the GCD machine is described as follows:

```
(controller
 test-b
   (test (op =) (reg b) (const 0))
   (branch (label gcd-done))
   (assign t (op rem) (reg a) (reg b))
   (assign a (reg b))
   (assign b (reg t))
   (goto (label test-b))
```

```
gcd-done)
```

This form of description is easier to read than the kind illustrated in Figure 5.3, but it also has disadvantages:


- It is more verbose for large machines, because complete descriptions of the data-path elements are repeated whenever the elements are mentioned in the controller instruction sequence. (This is not a problem in the GCD example, because each operation and button is used only once.) Moreover, repeating the data-path descriptions obscures the actual data-path structure of the machine; it is not obvious for a large machine how many registers, operations, and buttons there are and how they are interconnected.
- Because the controller instructions in a machine definition look like Lisp expressions, it is easy to forget that they are not arbitrary Lisp expressions. They can notate only legal machine operations. For example, operations can operate directly only on constants and the contents of registers, not on the results of other operations.

In spite of these disadvantages, we will use this register-machine language throughout this chapter, because we will be more concerned with understanding controllers than with understanding the elements and connections in data paths. We should keep in mind, however, that data-path design is crucial in designing real machines.

> **Exercise 5.2:** Use the register-machine language to describe the iterative factorial machine of Exercise 5.1.

Actions

Let us modify the GCD machine so that we can type in the numbers whose GCD we want and get the answer printed at our terminal. We will not discuss how




```
(controller
 gcd-loop
  (assign a (op read))
  (assign b (op read))
 test-b
  (test (op =)
      (reg b)
      (const 0))
  (branch (label gcd-done))
  (assign t
       (op rem)
       (reg a)
       (reg b))
  (assign a (reg b))
  (assign b (reg t))
  (goto (label test-b))
 gcd-done
  (perform (op print)
        (reg a))
  (goto (label gcd-loop)))
```

Figure 5.4: A GCD machine that reads inputs and prints results.

to make a machine that can read and print, but will assume (as we do when we use `read` and `display` in Scheme) that they are available as primitive operations.[1]

`read` is like the operations we have been using in that it produces a value that can be stored in a register. But `read` does not take inputs from any registers; its value depends on something that happens outside the parts of the machine we are designing. We will allow our machine's operations to have such behavior, and thus will draw and notate the use of `read` just as we do any other operation that computes a value.

[1]This assumption glosses over a great deal of complexity. Usually a large portion of the implementation of a Lisp system is dedicated to making reading and printing work.

`print`, on the other hand, differs from the operations we have been using in a fundamental way: It does not produce an output value to be stored in a register. Though it has an effect, this effect is not on a part of the machine we are designing. We will refer to this kind of operation as an *action*. We will represent an action in a data-path diagram just as we represent an operation that computes a value—as a trapezoid that contains the name of the action. Arrows point to the action box from any inputs (registers or constants). We also associate a button with the action. Pushing the button makes the action happen. To make a controller push an action button we use a new kind of instruction called `perform`. Thus, the action of printing the contents of register `a` is represented in a controller sequence by the instruction

```
(perform (op print) (reg a))
```

Figure 5.4 shows the data paths and controller for the new GCD machine. Instead of having the machine stop after printing the answer, we have made it start over, so that it repeatedly reads a pair of numbers, computes their GCD, and prints the result. This structure is like the driver loops we used in the interpreters of Chapter 4.

5.1.2 Abstraction in Machine Design

We will often define a machine to include "primitive" operations that are actually very complex. For example, in Section 5.4 and Section 5.5 we will treat Scheme's environment manipulations as primitive. Such abstraction is valuable because it allows us to ignore the details of parts of a machine so that we can concentrate on other aspects of the design. The fact that we have swept a lot of complexity under the rug, however, does not mean that a machine design is unrealistic. We can always replace the complex "primitives" by simpler primitive operations.

Consider the GCD machine. The machine has an instruction that computes

the remainder of the contents of registers `a` and `b` and assigns the result to register `t`. If we want to construct the GCD machine without using a primitive remainder operation, we must specify how to compute remainders in terms of simpler operations, such as subtraction. Indeed, we can write a Scheme procedure that finds remainders in this way:

```
(define (remainder n d)
  (if (< n d)
      n
      (remainder (- n d) d)))
```

We can thus replace the remainder operation in the GCD machine's data paths with a subtraction operation and a comparison test. Figure 5.5 shows the data paths and controller for the elaborated machine. The instruction

```
(assign t (op rem) (reg a) (reg b))
```

in the GCD controller definition is replaced by a sequence of instructions that contains a loop, as shown in Figure 5.6.

Figure 5.6: ↓ Controller instruction sequence for the GCD machine in Figure 5.5.

```
(controller test-b
              (test (op =) (reg b) (const 0))
              (branch (label gcd-done))
              (assign t (reg a))
            rem-loop
              (test (op <) (reg t) (reg b))
              (branch (label rem-done))
              (assign t (op -) (reg t) (reg b))
              (goto (label rem-loop))
            rem-done
```




Figure 5.5: Data paths and controller for the elaborated GCD machine.

```
      (assign a (reg b))
      (assign b (reg t))
      (goto (label test-b))
    gcd-done)
```


Exercise 5.3: Design a machine to compute square roots using Newton's method, as described in Section 1.1.7:

```
(define (sqrt x)
  (define (good-enough? guess)
    (< (abs (- (square guess) x)) 0.001))
  (define (improve guess)
    (average guess (/ x guess)))
  (define (sqrt-iter guess)
    (if (good-enough? guess)
        guess
        (sqrt-iter (improve guess))))
  (sqrt-iter 1.0))
```

Begin by assuming that `good-enough?` and `improve` operations are available as primitives. Then show how to expand these in terms of arithmetic operations. Describe each version of the `sqrt` machine design by drawing a data-path diagram and writing a controller definition in the register-machine language.

5.1.3 Subroutines

When designing a machine to perform a computation, we would often prefer to arrange for components to be shared by different parts of the computation rather than duplicate the components. Consider a machine that includes two GCD computations—one that finds the GCD of the contents of registers `a` and




```
gcd-1
(test (op =) (reg b) (const 0))
(branch (label after-gcd-1))
(assign t (op rem) (reg a) (reg b))
(assign a (reg b))
(assign b (reg t))
(goto (label gcd-1))
after-gcd-1
```

```
gcd-2
(test (op =) (reg d) (const 0))
(branch (label after-gcd-2))
(assign s (op rem) (reg c) (reg d))
(assign c (reg d))
(assign d (reg s))
(goto (label gcd-2))
after-gcd-2
```

Figure 5.7: Portions of the data paths and controller sequence for a machine with two GCD computations.

`b` and one that finds the GCD of the contents of registers `c` and `d`. We might start by assuming we have a primitive `gcd` operation, then expand the two instances of `gcd` in terms of more primitive operations. Figure 5.7 shows just the GCD portions of the resulting machine's data paths, without showing how they connect to the rest of the machine. The figure also shows the corresponding portions of the machine's controller sequence.

This machine has two remainder operation boxes and two boxes for testing equality. If the duplicated components are complicated, as is the remainder box, this will not be an economical way to build the machine. We can avoid duplicating the data-path components by using the same components for both

GCD computations, provided that doing so will not affect the rest of the larger machine's computation. If the values in registers `a` and `b` are not needed by the time the controller gets to `gcd-2` (or if these values can be moved to other registers for safekeeping), we can change the machine so that it uses registers `a` and `b`, rather than registers `c` and `d`, in computing the second GCD as well as the first. If we do this, we obtain the controller sequence shown in Figure 5.8.

Figure 5.8: ↓ Portions of the controller sequence for a machine that uses the same data-path components for two different GCD computations.

```
gcd-1
  (test (op =) (reg b) (const 0))
  (branch (label after-gcd-1))
  (assign t (op rem) (reg a) (reg b))
  (assign a (reg b))
  (assign b (reg t))
  (goto (label gcd-1))
after-gcd-1
   ...
gcd-2
  (test (op =) (reg b) (const 0))
  (branch (label after-gcd-2))
  (assign t (op rem) (reg a) (reg b))
  (assign a (reg b))
  (assign b (reg t))
  (goto (label gcd-2))
after-gcd-2
```

We have removed the duplicate data-path components (so that the data paths are again as in Figure 5.1), but the controller now has two GCD sequences that

differ only in their entry-point labels. It would be better to replace these two sequences by branches to a single sequence—a `gcd` *subroutine*—at the end of which we branch back to the correct place in the main instruction sequence. We can accomplish this as follows: Before branching to `gcd`, we place a distinguishing value (such as 0 or 1) into a special register, `continue`. At the end of the `gcd` subroutine we return either to `after-gcd-1` or to `after-gcd-2`, depending on the value of the `continue` register. Figure 5.9 shows the relevant portion of the resulting controller sequence, which includes only a single copy of the `gcd` instructions.

Figure 5.9: ↓ Using a `continue` register to avoid the duplicate controller sequence in Figure 5.8.

```
gcd
  (test (op =) (reg b) (const 0))
  (branch (label gcd-done))
  (assign t (op rem) (reg a) (reg b))
  (assign a (reg b))
  (assign b (reg t))
  (goto (label gcd))
gcd-done
  (test (op =) (reg continue) (const 0))
  (branch (label after-gcd-1))
  (goto (label after-gcd-2))
   ...
  ;; Before branching to gcd from the first place where
  ;; it is needed, we place 0 in the continue register
  (assign continue (const 0))
  (goto (label gcd))
after-gcd-1
   ...

  ;; Before the second use of gcd, we place 1
```

```
  ;; in the continue register
  (assign continue (const 1))
  (goto (label gcd))
after-gcd-2
```

This is a reasonable approach for handling small problems, but it would be awkward if there were many instances of GCD computations in the controller sequence. To decide where to continue executing after the `gcd` subroutine, we would need tests in the data paths and branch instructions in the controller for all the places that use `gcd`. A more powerful method for implementing subroutines is to have the `continue` register hold the label of the entry point in the controller sequence at which execution should continue when the subroutine is finished. Implementing this strategy requires a new kind of connection between the data paths and the controller of a register machine: There must be a way to assign to a register a label in the controller sequence in such a way that this value can be fetched from the register and used to continue execution at the designated entry point.

To reflect this ability, we will extend the `assign` instruction of the register-machine language to allow a register to be assigned as value a label from the controller sequence (as a special kind of constant). We will also extend the `goto` instruction to allow execution to continue at the entry point described by the contents of a register rather than only at an entry point described by a constant label. Using these new constructs we can terminate the `gcd` subroutine with a branch to the location stored in the `continue` register. This leads to the controller sequence shown in Figure 5.10.

Figure 5.10: ↓ Assigning labels to the `continue` register simplifies and generalizes the strategy shown in Figure 5.9.

```
gcd
  (test (op =) (reg b) (const 0))
```

```
  (branch (label gcd-done))
  (assign t (op rem) (reg a) (reg b))
  (assign a (reg b))
  (assign b (reg t))
  (goto (label gcd))
gcd-done
  (goto (reg continue))
    ...
  ;; Before calling gcd, we assign to continue
  ;; the label to which gcd should return.
  (assign continue (label after-gcd-1))
  (goto (label gcd))
after-gcd-1
    ...
  ;; Here is the second call to gcd,
  ;; with a different continuation.
  (assign continue (label after-gcd-2))
  (goto (label gcd))
after-gcd-2
```

A machine with more than one subroutine could use multiple continuation registers (e.g., `gcd-continue`, `factorial-continue`) or we could have all subroutines share a single `continue` register. Sharing is more economical, but we must be careful if we have a subroutine (`sub1`) that calls another subroutine (`sub2`). Unless `sub1` saves the contents of `continue` in some other register before setting up `continue` for the call to `sub2`, `sub1` will not know where to go when it is finished. The mechanism developed in the next section to handle recursion also provides a better solution to this problem of nested subroutine calls.

5.1.4 Using a Stack to Implement Recursion

With the ideas illustrated so far, we can implement any iterative process by specifying a register machine that has a register corresponding to each state variable of the process. The machine repeatedly executes a controller loop, changing the contents of the registers, until some termination condition is satisfied. At each point in the controller sequence, the state of the machine (representing the state of the iterative process) is completely determined by the contents of the registers (the values of the state variables).

Implementing recursive processes, however, requires an additional mechanism. Consider the following recursive method for computing factorials, which we first examined in Section 1.2.1:

```
(define (factorial n)
  (if (= n 1) 1 (* (factorial (- n 1)) n)))
```

As we see from the procedure, computing $n!$ requires computing $(n-1)!$. Our GCD machine, modeled on the procedure

```
(define (gcd a b)
  (if (= b 0) a (gcd b (remainder a b))))
```

similarly had to compute another GCD. But there is an important difference between the `gcd` procedure, which reduces the original computation to a new GCD computation, and `factorial`, which requires computing another factorial as a subproblem. In GCD, the answer to the new GCD computation is the answer to the original problem. To compute the next GCD, we simply place the new arguments in the input registers of the GCD machine and reuse the machine's data paths by executing the same controller sequence. When the machine is finished solving the final GCD problem, it has completed the entire computation.

In the case of factorial (or any recursive process) the answer to the new factorial subproblem is not the answer to the original problem. The value ob-

tained for $(n-1)!$ must be multiplied by n to get the final answer. If we try to imitate the GCD design, and solve the factorial subproblem by decrementing the `n` register and rerunning the factorial machine, we will no longer have available the old value of `n` by which to multiply the result. We thus need a second factorial machine to work on the subproblem. This second factorial computation itself has a factorial subproblem, which requires a third factorial machine, and so on. Since each factorial machine contains another factorial machine within it, the total machine contains an infinite nest of similar machines and hence cannot be constructed from a fixed, finite number of parts.

Nevertheless, we can implement the factorial process as a register machine if we can arrange to use the same components for each nested instance of the machine. Specifically, the machine that computes $n!$ should use the same components to work on the subproblem of computing $(n-1)!$, on the subproblem for $(n-2)!$, and so on. This is plausible because, although the factorial process dictates that an unbounded number of copies of the same machine are needed to perform a computation, only one of these copies needs to be active at any given time. When the machine encounters a recursive subproblem, it can suspend work on the main problem, reuse the same physical parts to work on the subproblem, then continue the suspended computation.

In the subproblem, the contents of the registers will be different than they were in the main problem. (In this case the `n` register is decremented.) In order to be able to continue the suspended computation, the machine must save the contents of any registers that will be needed after the subproblem is solved so that these can be restored to continue the suspended computation. In the case of factorial, we will save the old value of `n`, to be restored when we are finished computing the factorial of the decremented `n` register.[2]

[2] One might argue that we don't need to save the old `n`; after we decrement it and solve the subproblem, we could simply increment it to recover the old value. Although this strategy works for factorial, it cannot work in general, since the old value of a register cannot always

Since there is no *a priori* limit on the depth of nested recursive calls, we may need to save an arbitrary number of register values. These values must be restored in the reverse of the order in which they were saved, since in a nest of recursions the last subproblem to be entered is the first to be finished. This dictates the use of a *stack*, or "last in, first out" data structure, to save register values. We can extend the register-machine language to include a stack by adding two kinds of instructions: Values are placed on the stack using a `save` instruction and restored from the stack using a `restore` instruction. After a sequence of values has been `saved` on the stack, a sequence of `restores` will retrieve these values in reverse order.[3]

With the aid of the stack, we can reuse a single copy of the factorial machine's data paths for each factorial subproblem. There is a similar design issue in reusing the controller sequence that operates the data paths. To reexecute the factorial computation, the controller cannot simply loop back to the beginning, as with an iterative process, because after solving the $(n-1)!$ subproblem the machine must still multiply the result by n. The controller must suspend its computation of $n!$, solve the $(n-1)!$ subproblem, then continue its computation of $n!$. This view of the factorial computation suggests the use of the subroutine mechanism described in Section 5.1.3, which has the controller use a `continue` register to transfer to the part of the sequence that solves a subproblem and then continue where it left off on the main problem. We can thus make a factorial subroutine that returns to the entry point stored in the `continue` register. Around each subroutine call, we save and restore `continue` just as we do the `n` register, since each "level" of the factorial computation will use the same `continue` register. That is, the factorial subroutine must put a new value in `continue` when it calls itself for a subproblem, but it will need the old value in order to return to the place


be computed from the new one.

[3] In Section 5.3 we will see how to implement a stack in terms of more primitive operations.

that called it to solve a subproblem.

Figure 5.11 shows the data paths and controller for a machine that implements the recursive `factorial` procedure. The machine has a stack and three registers, called `n`, `val`, and `continue`. To simplify the data-path diagram, we have not named the register-assignment buttons, only the stack-operation buttons (`sc` and `sn` to save registers, `rc` and `rn` to restore registers). To operate the machine, we put in register `n` the number whose factorial we wish to compute and start the machine. When the machine reaches `fact-done`, the computation is finished and the answer will be found in the `val` register. In the controller sequence, `n` and `continue` are saved before each recursive call and restored upon return from the call. Returning from a call is accomplished by branching to the location stored in `continue`. `continue` is initialized when the machine starts so that the last return will go to `fact-done`. The `val` register, which holds the result of the factorial computation, is not saved before the recursive call, because the old contents of `val` is not useful after the subroutine returns. Only the new value, which is the value produced by the subcomputation, is needed.

Although in principle the factorial computation requires an infinite machine, the machine in Figure 5.11 is actually finite except for the stack, which is potentially unbounded. Any particular physical implementation of a stack, however, will be of finite size, and this will limit the depth of recursive calls that can be handled by the machine. This implementation of factorial illustrates the general strategy for realizing recursive algorithms as ordinary register machines augmented by stacks. When a recursive subproblem is encountered, we save on the stack the registers whose current values will be required after the subproblem is solved, solve the recursive subproblem, then restore the saved registers and continue execution on the main problem. The `continue` register must always be saved. Whether there are other registers that need to be saved depends on the particular machine, since not all




```
(controller
  (assign continue (label fact-done))   ;set up final return address
 fact-loop
  (test (op =) (reg n) (const 1))
  (branch (label base-case))
  ;; Set up for the recursive call by saving n and continue.
  ;; Set up continue so that the computation will continue
  ;; at after-fact when the subroutine returns.
  (save continue)
  (save n)
  (assign n (op -) (reg n) (const 1))
  (assign continue (label after-fact))
  (goto (label fact-loop))
 after-fact
  (restore n)
  (restore continue)
  (assign val (op *) (reg n) (reg val))  ;val now contains n(n - 1)!
  (goto (reg continue))                  ;return to caller
 base-case
  (assign val (const 1))                 ;base case: 1! = 1
  (goto (reg continue))                  ;return to caller
 fact-done)
```

Figure 5.11: A recursive factorial machine.

recursive computations need the original values of registers that are modified during solution of the subproblem (see Exercise 5.4).

A double recursion

Let us examine a more complex recursive process, the tree-recursive computation of the Fibonacci numbers, which we introduced in Section 1.2.2:

```
(define (fib n)
  (if (< n 2)
      n
      (+ (fib (- n 1)) (fib (- n 2)))))
```

Just as with factorial, we can implement the recursive Fibonacci computation as a register machine with registers `n`, `val`, and `continue`. The machine is more complex than the one for factorial, because there are two places in the controller sequence where we need to perform recursive calls—once to compute $\mathrm{Fib}(n-1)$ and once to compute $\mathrm{Fib}(n-2)$. To set up for each of these calls, we save the registers whose values will be needed later, set the `n` register to the number whose Fib we need to compute recursively ($n-1$ or $n-2$), and assign to `continue` the entry point in the main sequence to which to return (`afterfib-n-1` or `afterfib-n-2`, respectively). We then go to `fib-loop`. When we return from the recursive call, the answer is in `val`. Figure 5.12 shows the controller sequence for this machine.

Figure 5.12: ↓ Controller for a machine to compute Fibonacci numbers.

```
(controller
   (assign continue (label fib-done))
 fib-loop
   (test (op <) (reg n) (const 2))
   (branch (label immediate-answer))
```

```
    ;; set up to compute Fib(n − 1)
    (save continue)
    (assign continue (label afterfib-n-1))
    (save n)                          ; save old value of n
    (assign n (op -) (reg n) (const 1)) ; clobber n to n-1
    (goto (label fib-loop))           ; perform recursive call
  afterfib-n-1                        ; upon return, val contains Fib(n − 1)
    (restore n)
    (restore continue)
    ;; set up to compute Fib(n − 2)
    (assign n (op -) (reg n) (const 2))
    (save continue)
    (assign continue (label afterfib-n-2))
    (save val)                        ; save Fib(n − 1)
    (goto (label fib-loop))
  afterfib-n-2                        ; upon return, val contains Fib(n − 2)
    (assign n (reg val))              ; n now contains Fib(n−
2)
    (restore val)                     ; val now contains Fib(n−
1)
    (restore continue)
    (assign val                       ; Fib(n − 1) + Fib(n −
2)
            (op +) (reg val) (reg n))
    (goto (reg continue))             ; return to caller, answer
is in val
  immediate-answer
    (assign val (reg n))              ; base case: Fib(n) =
n
    (goto (reg continue))
  fib-done)
```

Exercise 5.4: Specify register machines that implement each of the following procedures. For each machine, write a controller instruction sequence and draw a diagram showing the data paths.

a. Recursive exponentiation:

```
(define (expt b n)
  (if (= n 0)
      1
      (* b (expt b (- n 1)))))
```

b. Iterative exponentiation:

```
(define (expt b n)
  (define (expt-iter counter product)
    (if (= counter 0)
        product
        (expt-iter (- counter 1)
                   (* b product))))
  (expt-iter n 1))
```

Exercise 5.5: Hand-simulate the factorial and Fibonacci machines, using some nontrivial input (requiring execution of at least one recursive call). Show the contents of the stack at each significant point in the execution.

Exercise 5.6: Ben Bitdiddle observes that the Fibonacci machine's controller sequence has an extra `save` and an extra `restore`, which can be removed to make a faster machine. Where are these instructions?

5.1.5 Instruction Summary

A controller instruction in our register-machine language has one of the following forms, where each ⟨*input*$_i$⟩ is either `(reg ⟨register-name⟩)` or `(const ⟨constant-value⟩)`. These instructions were introduced in Section 5.1.1:

```
(assign ⟨register-name⟩ (reg ⟨register-name⟩))
(assign ⟨register-name⟩ (const ⟨constant-value⟩))
(assign ⟨register-name⟩
        (op ⟨operation-name⟩)
        ⟨input1⟩ ... ⟨inputn⟩)
(perform (op ⟨operation-name⟩) ⟨input1⟩ ... ⟨inputn⟩)
(test (op ⟨operation-name⟩) ⟨input1⟩ ... ⟨inputn⟩)
(branch (label ⟨label-name⟩))
(goto (label ⟨label-name⟩))
```

The use of registers to hold labels was introduced in Section 5.1.3:

```
(assign ⟨register-name⟩ (label ⟨label-name⟩))
(goto (reg ⟨register-name⟩))
```

Instructions to use the stack were introduced in Section 5.1.4:

```
(save ⟨register-name⟩)
(restore ⟨register-name⟩)
```

The only kind of ⟨*constant-value*⟩ we have seen so far is a number, but later we will use strings, symbols, and lists. For example,

`(const "abc")` is the string `"abc"`,
`(const abc)` is the symbol `abc`,
`(const (a b c))` is the list `(a b c)`,
and `(const ())` is the empty list.

5.2 A Register-Machine Simulator

In order to gain a good understanding of the design of register machines, we must test the machines we design to see if they perform as expected. One way to test a design is to hand-simulate the operation of the controller, as in Exercise 5.5. But this is extremely tedious for all but the simplest machines. In this section we construct a simulator for machines described in the register-machine language. The simulator is a Scheme program with four interface procedures. The first uses a description of a register machine to construct a model of the machine (a data structure whose parts correspond to the parts of the machine to be simulated), and the other three allow us to simulate the machine by manipulating the model:

`(make-machine ⟨register-names⟩ ⟨operations⟩ ⟨controller⟩)`

constructs and returns a model of the machine with the given registers, operations, and controller.

`(set-register-contents! ⟨machine-model⟩ ⟨register-name⟩ ⟨value⟩)`

stores a value in a simulated register in the given machine.

`(get-register-contents ⟨machine-model⟩ ⟨register-name⟩)`

returns the contents of a simulated register in the given machine.

`(start ⟨machine-model⟩)`

simulates the execution of the given machine, starting from the beginning of the controller sequence and stopping when it reaches the end of the sequence.

As an example of how these procedures are used, we can define `gcd-machine` to be a model of the GCD machine of Section 5.1.1 as follows:

```
(define gcd-machine
  (make-machine
   '(a b t)
   (list (list 'rem remainder) (list '= =))
   '(test-b (test (op =) (reg b) (const 0))
            (branch (label gcd-done))
            (assign t (op rem) (reg a) (reg b))
            (assign a (reg b))
            (assign b (reg t))
            (goto (label test-b))
           gcd-done)))
```

The first argument to `make-machine` is a list of register names. The next argument is a table (a list of two-element lists) that pairs each operation name with a Scheme procedure that implements the operation (that is, produces the same output value given the same input values). The last argument specifies the controller as a list of labels and machine instructions, as in Section 5.1.

To compute GCDs with this machine, we set the input registers, start the machine, and examine the result when the simulation terminates:

```
(set-register-contents! gcd-machine 'a 206)
done
(set-register-contents! gcd-machine 'b 40)
done
(start gcd-machine)
done
(get-register-contents gcd-machine 'a)
2
```

This computation will run much more slowly than a `gcd` procedure written in Scheme, because we will simulate low-level machine instructions, such as

`assign`, by much more complex operations.

> **Exercise 5.7:** Use the simulator to test the machines you designed in Exercise 5.4.

5.2.1 The Machine Model

The machine model generated by `make-machine` is represented as a procedure with local state using the message-passing techniques developed in Chapter 3. To build this model, `make-machine` begins by calling the procedure `make-new-machine` to construct the parts of the machine model that are common to all register machines. This basic machine model constructed by `make-new-machine` is essentially a container for some registers and a stack, together with an execution mechanism that processes the controller instructions one by one.

`make-machine` then extends this basic model (by sending it messages) to include the registers, operations, and controller of the particular machine being defined. First it allocates a register in the new machine for each of the supplied register names and installs the designated operations in the machine. Then it uses an *assembler* (described below in Section 5.2.2) to transform the controller list into instructions for the new machine and installs these as the machine's instruction sequence. `make-machine` returns as its value the modified machine model.

```
(define (make-machine register-names ops controller-text)
  (let ((machine (make-new-machine)))
    (for-each
     (lambda (register-name)
       ((machine 'allocate-register) register-name))
     register-names)
    ((machine 'install-operations) ops)
    ((machine 'install-instruction-sequence)
```

```
     (assemble controller-text machine))
    machine))
```

Registers

We will represent a register as a procedure with local state, as in Chapter 3. The procedure `make-register` creates a register that holds a value that can be accessed or changed:

```
(define (make-register name)
  (let ((contents '*unassigned*))
    (define (dispatch message)
      (cond ((eq? message 'get) contents)
            ((eq? message 'set)
             (lambda (value) (set! contents value)))
            (else
             (error "Unknown request: REGISTER" message))))
    dispatch))
```

The following procedures are used to access registers:

```
(define (get-contents register) (register 'get))
(define (set-contents! register value)
  ((register 'set) value))
```

The stack

We can also represent a stack as a procedure with local state. The procedure `make-stack` creates a stack whose local state consists of a list of the items on the stack. A stack accepts requests to `push` an item onto the stack, to `pop` the top item off the stack and return it, and to `initialize` the stack to empty.

```
(define (make-stack)
  (let ((s '()))
    (define (push x) (set! s (cons x s)))
    (define (pop)
      (if (null? s)
          (error "Empty stack: POP")
          (let ((top (car s)))
            (set! s (cdr s))
            top)))
    (define (initialize)
      (set! s '())
      'done)
    (define (dispatch message)
      (cond ((eq? message 'push) push)
            ((eq? message 'pop) (pop))
            ((eq? message 'initialize) (initialize))
            (else (error "Unknown request: STACK" message))))
    dispatch))
```

The following procedures are used to access stacks:

```
(define (pop stack) (stack 'pop))
(define (push stack value) ((stack 'push) value))
```

The basic machine

The `make-new-machine` procedure, shown in Figure 5.13, constructs an object whose local state consists of a stack, an initially empty instruction sequence, a list of operations that initially contains an operation to initialize the stack, and a *register table* that initially contains two registers, named `flag` and `pc` (for "program counter"). The internal procedure `allocate-register` adds new entries to the register table, and the internal procedure `lookup-register` looks up registers in the table.

The `flag` register is used to control branching in the simulated machine. `test` instructions set the contents of `flag` to the result of the test (true or false). `branch` instructions decide whether or not to branch by examining the contents of `flag`.

The `pc` register determines the sequencing of instructions as the machine runs. This sequencing is implemented by the internal procedure `execute`. In the simulation model, each machine instruction is a data structure that includes a procedure of no arguments, called the *instruction execution procedure*, such that calling this procedure simulates executing the instruction. As the simulation runs, `pc` points to the place in the instruction sequence beginning with the next instruction to be executed. `execute` gets that instruction, executes it by calling the instruction execution procedure, and repeats this cycle until there are no more instructions to execute (i.e., until `pc` points to the end of the instruction sequence).

Figure 5.13: ↓ The `make-new-machine` procedure, which implements the basic machine model.

```
(define (make-new-machine)
  (let ((pc (make-register 'pc))
        (flag (make-register 'flag))
        (stack (make-stack))
        (the-instruction-sequence '()))
    (let ((the-ops
           (list (list 'initialize-stack
                       (lambda () (stack 'initialize)))
          (register-table
           (list (list 'pc pc) (list 'flag flag))))
      (define (allocate-register name)
        (if (assoc name register-table)
            (error "Multiply defined register: " name)
            (set! register-table
```

```
            (cons (list name (make-register name)
                        register-table)))
  'register-allocated)
(define (lookup-register name)
  (let ((val (assoc name register-table)))
    (if val
        (cadr val)
        (error "Unknown register:" name))))
(define (execute)
  (let ((insts (get-contents pc)))
    (if (null? insts)
        'done
        (begin
          ((instruction-execution-proc (car insts
          (execute))))))
(define (dispatch message)
  (cond ((eq? message 'start)
         (set-contents! pc the-instruction-sequen
         (execute))
        ((eq? message 'install-instruction-sequen
         (lambda (seq)
           (set! the-instruction-sequence seq)))
        ((eq? message 'allocate-register)
         allocate-register)
        ((eq? message 'get-register)
         lookup-register)
        ((eq? message 'install-operations)
         (lambda (ops)
           (set! the-ops (append the-ops ops))))
        ((eq? message 'stack) stack)
        ((eq? message 'operations) the-ops)
        (else (error "Unknown request: MACHINE"
                     message))))
```

```
          dispatch)))
```

As part of its operation, each instruction execution procedure modifies `pc` to indicate the next instruction to be executed. `branch` and `goto` instructions change `pc` to point to the new destination. All other instructions simply advance `pc`, making it point to the next instruction in the sequence. Observe that each call to `execute` calls `execute` again, but this does not produce an infinite loop because running the instruction execution procedure changes the contents of `pc`.

`make-new-machine` returns a `dispatch` procedure that implements message-passing access to the internal state. Notice that starting the machine is accomplished by setting `pc` to the beginning of the instruction sequence and calling `execute`.

For convenience, we provide an alternate procedural interface to a machine's `start` operation, as well as procedures to set and examine register contents, as specified at the beginning of Section 5.2:

```
(define (start machine) (machine 'start))
(define (get-register-contents machine register-name)
  (get-contents (get-register machine register-name)))
(define (set-register-contents! machine register-name value)
  (set-contents! (get-register machine register-name)
                 value)
  'done)
```

These procedures (and many procedures in Section 5.2.2 and Section 5.2.3) use the following to look up the register with a given name in a given machine:

```
(define (get-register machine reg-name)
  ((machine 'get-register) reg-name))
```

5.2.2 The Assembler

The assembler transforms the sequence of controller expressions for a machine into a corresponding list of machine instructions, each with its execution procedure. Overall, the assembler is much like the evaluators we studied in Chapter 4—there is an input language (in this case, the register-machine language) and we must perform an appropriate action for each type of expression in the language.

The technique of producing an execution procedure for each instruction is just what we used in Section 4.1.7 to speed up the evaluator by separating analysis from runtime execution. As we saw in Chapter 4, much useful analysis of Scheme expressions could be performed without knowing the actual values of variables. Here, analogously, much useful analysis of register-machine-language expressions can be performed without knowing the actual contents of machine registers. For example, we can replace references to registers by pointers to the register objects, and we can replace references to labels by pointers to the place in the instruction sequence that the label designates.

Before it can generate the instruction execution procedures, the assembler must know what all the labels refer to, so it begins by scanning the controller text to separate the labels from the instructions. As it scans the text, it constructs both a list of instructions and a table that associates each label with a pointer into that list. Then the assembler augments the instruction list by inserting the execution procedure for each instruction.

The `assemble` procedure is the main entry to the assembler. It takes the controller text and the machine model as arguments and returns the instruction sequence to be stored in the model. `assemble` calls `extract-labels` to build the initial instruction list and label table from the supplied controller text. The second argument to `extract-labels` is a procedure to be called to process these results: This procedure uses `update-`

`insts!` to generate the instruction execution procedures and insert them into the instruction list, and returns the modified list.

```
(define (assemble controller-text machine)
  (extract-labels
   controller-text
   (lambda (insts labels)
     (update-insts! insts labels machine)
     insts)))
```

`extract-labels` takes as arguments a list `text` (the sequence of controller instruction expressions) and a `receive` procedure. `receive` will be called with two values: (1) a list `insts` of instruction data structures, each containing an instruction from `text`; and (2) a table called `labels`, which associates each label from `text` with the position in the list `insts` that the label designates.

```
(define (extract-labels text receive)
  (if (null? text)
      (receive '() '())
      (extract-labels
       (cdr text)
       (lambda (insts labels)
         (let ((next-inst (car text)))
           (if (symbol? next-inst)
               (receive insts
                        (cons (make-label-entry next-inst
                                                insts)
                              labels))
               (receive (cons (make-instruction next-inst)
                              insts)
                        labels)))))))
```

`extract-labels` works by sequentially scanning the elements of the `text` and accumulating the `insts` and the `labels`. If an element is a

symbol (and thus a label) an appropriate entry is added to the `labels` table. Otherwise the element is accumulated onto the `insts` list.[4]

`update-insts!` modifies the instruction list, which initially contains only the text of the instructions, to include the corresponding execution procedures:

[4] Using the `receive` procedure here is a way to get `extract-labels` to effectively return two values—`labels` and `insts`—without explicitly making a compound data structure to hold them. An alternative implementation, which returns an explicit pair of values, is

```
(define (extract-labels text)
  (if (null? text)
      (cons '() '())
      (let ((result (extract-labels (cdr text))))
        (let ((insts (car result)) (labels (cdr result)))
          (let ((next-inst (car text)))
            (if (symbol? next-inst)
                (cons insts
                      (cons (make-label-entry next-inst insts)
                            labels))
                (cons (cons (make-instruction next-inst) insts)
                      labels)))))))
```

which would be called by `assemble` as follows:

```
(define (assemble controller-text machine)
  (let ((result (extract-labels controller-text)))
    (let ((insts (car result)) (labels (cdr result)))
      (update-insts! insts labels machine)
      insts)))
```

You can consider our use of `receive` as demonstrating an elegant way to return multiple values, or simply an excuse to show off a programming trick. An argument like `receive` that is the next procedure to be invoked is called a "continuation." Recall that we also used continuations to implement the backtracking control structure in the `amb` evaluator in Section 4.3.3.

```
(define (update-insts! insts labels machine)
  (let ((pc (get-register machine 'pc))
        (flag (get-register machine 'flag))
        (stack (machine 'stack))
        (ops (machine 'operations)))
    (for-each
     (lambda (inst)
       (set-instruction-execution-proc!
        inst
        (make-execution-procedure
         (instruction-text inst)
         labels machine pc flag stack ops)))
     insts)))
```

The machine instruction data structure simply pairs the instruction text with the corresponding execution procedure. The execution procedure is not yet available when `extract-labels` constructs the instruction, and is inserted later by `update-insts!`.

```
(define (make-instruction text) (cons text '()))
(define (instruction-text inst) (car inst))
(define (instruction-execution-proc inst) (cdr inst))
(define (set-instruction-execution-proc! inst proc)
  (set-cdr! inst proc))
```

The instruction text is not used by our simulator, but it is handy to keep around for debugging (see Exercise 5.16).

Elements of the label table are pairs:

```
(define (make-label-entry label-name insts)
  (cons label-name insts))
```

Entries will be looked up in the table with

```
(define (lookup-label labels label-name)
  (let ((val (assoc label-name labels)))
```

```
(if val
    (cdr val)
    (error "Undefined label: ASSEMBLE"
           label-name))))
```

Exercise 5.8: The following register-machine code is ambiguous, because the label `here` is defined more than once:

```
start
  (goto (label here))
here
  (assign a (const 3))
  (goto (label there))
here
  (assign a (const 4))
  (goto (label there))
there
```

With the simulator as written, what will the contents of register `a` be when control reaches `there`? Modify the `extract-labels` procedure so that the assembler will signal an error if the same label name is used to indicate two different locations.

5.2.3 Generating Execution Procedures for Instructions

The assembler calls `make-execution-procedure` to generate the execution procedure for an instruction. Like the `analyze` procedure in the evaluator of Section 4.1.7, this dispatches on the type of instruction to generate the appropriate execution procedure.

```
(define (make-execution-procedure
         inst labels machine pc flag stack ops)
```

```
(cond ((eq? (car inst) 'assign)
       (make-assign inst machine labels ops pc))
      ((eq? (car inst) 'test)
       (make-test inst machine labels ops flag pc))
      ((eq? (car inst) 'branch)
       (make-branch inst machine labels flag pc))
      ((eq? (car inst) 'goto)
       (make-goto inst machine labels pc))
      ((eq? (car inst) 'save)
       (make-save inst machine stack pc))
      ((eq? (car inst) 'restore)
       (make-restore inst machine stack pc))
      ((eq? (car inst) 'perform)
       (make-perform inst machine labels ops pc))
      (else
       (error "Unknown instruction type: ASSEMBLE"
              inst))))
```

For each type of instruction in the register-machine language, there is a generator that builds an appropriate execution procedure. The details of these procedures determine both the syntax and meaning of the individual instructions in the register-machine language. We use data abstraction to isolate the detailed syntax of register-machine expressions from the general execution mechanism, as we did for evaluators in Section 4.1.2, by using syntax procedures to extract and classify the parts of an instruction.

`assign` instructions

The `make-assign` procedure handles `assign` instructions:

```
(define (make-assign inst machine labels operations pc)
  (let ((target
         (get-register machine (assign-reg-name inst)))
```

```
        (value-exp (assign-value-exp inst)))
    (let ((value-proc
           (if (operation-exp? value-exp)
               (make-operation-exp
                value-exp machine labels operations)
               (make-primitive-exp
                (car value-exp) machine labels))))
      (lambda ()    ; execution procedure for assign
        (set-contents! target (value-proc))
        (advance-pc pc)))))
```

`make-assign` extracts the target register name (the second element of the instruction) and the value expression (the rest of the list that forms the instruction) from the `assign` instruction using the selectors

```
(define (assign-reg-name assign-instruction)
  (cadr assign-instruction))
(define (assign-value-exp assign-instruction)
  (cddr assign-instruction))
```

The register name is looked up with `get-register` to produce the target register object. The value expression is passed to `make-operation-exp` if the value is the result of an operation, and to `make-primitive-exp` otherwise. These procedures (shown below) parse the value expression and produce an execution procedure for the value. This is a procedure of no arguments, called `value-proc`, which will be evaluated during the simulation to produce the actual value to be assigned to the register. Notice that the work of looking up the register name and parsing the value expression is performed just once, at assembly time, not every time the instruction is simulated. This saving of work is the reason we use execution procedures, and corresponds directly to the saving in work we obtained by separating program analysis from execution in the evaluator of Section 4.1.7.

The result returned by `make-assign` is the execution procedure for

the `assign` instruction. When this procedure is called (by the machine model's `execute` procedure), it sets the contents of the target register to the result obtained by executing `value-proc`. Then it advances the `pc` to the next instruction by running the procedure

```
(define (advance-pc pc)
  (set-contents! pc (cdr (get-contents pc))))
```

`advance-pc` is the normal termination for all instructions except `branch` and `goto`.

`test`, `branch`, and `goto` instructions

`make-test` handles `test` instructions in a similar way. It extracts the expression that specifies the condition to be tested and generates an execution procedure for it. At simulation time, the procedure for the condition is called, the result is assigned to the `flag` register, and the `pc` is advanced:

```
(define (make-test inst machine labels operations flag pc)
  (let ((condition (test-condition inst)))
    (if (operation-exp? condition)
        (let ((condition-proc
               (make-operation-exp
                condition machine labels operations)))
          (lambda ()
            (set-contents! flag (condition-proc))
            (advance-pc pc)))
        (error "Bad TEST instruction: ASSEMBLE" inst))))
(define (test-condition test-instruction)
  (cdr test-instruction))
```

The execution procedure for a `branch` instruction checks the contents of the `flag` register and either sets the contents of the `pc` to the branch destination

(if the branch is taken) or else just advances the `pc` (if the branch is not taken). Notice that the indicated destination in a `branch` instruction must be a label, and the `make-branch` procedure enforces this. Notice also that the label is looked up at assembly time, not each time the `branch` instruction is simulated.

```
(define (make-branch inst machine labels flag pc)
  (let ((dest (branch-dest inst)))
    (if (label-exp? dest)
        (let ((insts
               (lookup-label
                labels
                (label-exp-label dest))))
          (lambda ()
            (if (get-contents flag)
                (set-contents! pc insts)
                (advance-pc pc))))
        (error "Bad BRANCH instruction: ASSEMBLE" inst))))
(define (branch-dest branch-instruction)
  (cadr branch-instruction))
```

A `goto` instruction is similar to a branch, except that the destination may be specified either as a label or as a register, and there is no condition to check —the `pc` is always set to the new destination.

```
(define (make-goto inst machine labels pc)
  (let ((dest (goto-dest inst)))
    (cond ((label-exp? dest)
           (let ((insts (lookup-label
                         labels
                         (label-exp-label dest))))
             (lambda () (set-contents! pc insts))))
          ((register-exp? dest)
           (let ((reg (get-register
```

```
                        machine
                        (register-exp-reg dest))))
                (lambda ()
                  (set-contents! pc (get-contents reg)))))
            (else (error "Bad GOTO instruction: ASSEMBLE" inst
(define (goto-dest goto-instruction)
  (cadr goto-instruction))
```

Other instructions

The stack instructions `save` and `restore` simply use the stack with the designated register and advance the `pc`:

```
(define (make-save inst machine stack pc)
  (let ((reg (get-register machine
                           (stack-inst-reg-name inst))))
    (lambda ()
      (push stack (get-contents reg))
      (advance-pc pc))))
(define (make-restore inst machine stack pc)
  (let ((reg (get-register machine
                           (stack-inst-reg-name inst))))
    (lambda ()
      (set-contents! reg (pop stack))
      (advance-pc pc))))
(define (stack-inst-reg-name stack-instruction)
  (cadr stack-instruction))
```

The final instruction type, handled by `make-perform`, generates an execution procedure for the action to be performed. At simulation time, the action procedure is executed and the `pc` advanced.

```
(define (make-perform inst machine labels operations pc)
  (let ((action (perform-action inst)))
```

```
    (if (operation-exp? action)
        (let ((action-proc
               (make-operation-exp
                action machine labels operations)))
          (lambda () (action-proc) (advance-pc pc)))
        (error "Bad PERFORM instruction: ASSEMBLE" inst))))
(define (perform-action inst) (cdr inst))
```

Execution procedures for subexpressions

The value of a `reg`, `label`, or `const` expression may be needed for assignment to a register (`make-assign`) or for input to an operation (`make-operation-exp`, below). The following procedure generates execution procedures to produce values for these expressions during the simulation:

```
(define (make-primitive-exp exp machine labels)
  (cond ((constant-exp? exp)
         (let ((c (constant-exp-value exp)))
           (lambda () c)))
        ((label-exp? exp)
         (let ((insts (lookup-label
                       labels
                       (label-exp-label exp))))
           (lambda () insts)))
        ((register-exp? exp)
         (let ((r (get-register machine (register-exp-reg ex
           (lambda () (get-contents r))))
        (else (error "Unknown expression type: ASSEMBLE" exp
```

The syntax of `reg`, `label`, and `const` expressions is determined by

```
(define (register-exp? exp) (tagged-list? exp 'reg))
(define (register-exp-reg exp) (cadr exp))
(define (constant-exp? exp) (tagged-list? exp 'const))
```

```
(define (constant-exp-value exp) (cadr exp))
(define (label-exp? exp) (tagged-list? exp 'label))
(define (label-exp-label exp) (cadr exp))
```

`assign`, `perform`, and `test` instructions may include the application of a machine operation (specified by an `op` expression) to some operands (specified by `reg` and `const` expressions). The following procedure produces an execution procedure for an "operation expression"—a list containing the operation and operand expressions from the instruction:

```
(define (make-operation-exp exp machine labels operations)
  (let ((op (lookup-prim (operation-exp-op exp)
                         operations))
        (aprocs
         (map (lambda (e)
                (make-primitive-exp e machine labels))
              (operation-exp-operands exp))))
    (lambda ()
      (apply op (map (lambda (p) (p)) aprocs)))))
```

The syntax of operation expressions is determined by

```
(define (operation-exp? exp)
  (and (pair? exp) (tagged-list? (car exp) 'op)))
(define (operation-exp-op operation-exp)
  (cadr (car operation-exp)))
(define (operation-exp-operands operation-exp)
  (cdr operation-exp))
```

Observe that the treatment of operation expressions is very much like the treatment of procedure applications by the `analyze-application` procedure in the evaluator of Section 4.1.7 in that we generate an execution procedure for each operand. At simulation time, we call the operand procedures and apply the Scheme procedure that simulates the operation to

the resulting values. The simulation procedure is found by looking up the operation name in the operation table for the machine:

```
(define (lookup-prim symbol operations)
  (let ((val (assoc symbol operations)))
    (if val
        (cadr val)
        (error "Unknown operation: ASSEMBLE"
               symbol))))
```

Exercise 5.9: The treatment of machine operations above permits them to operate on labels as well as on constants and the contents of registers. Modify the expression-processing procedures to enforce the condition that operations can be used only with registers and constants.

Exercise 5.10: Design a new syntax for register-machine instructions and modify the simulator to use your new syntax. Can you implement your new syntax without changing any part of the simulator except the syntax procedures in this section?

Exercise 5.11: When we introduced `save` and `restore` in Section 5.1.4, we didn't specify what would happen if you tried to restore a register that was not the last one saved, as in the sequence

```
(save y)   (save x)   (restore y)
```

There are several reasonable possibilities for the meaning of `restore`:

a. `(restore y)` puts into `y` the last value saved on the stack, regardless of what register that value came from.

This is the way our simulator behaves. Show how to take advantage of this behavior to eliminate one instruction from the Fibonacci machine of Section 5.1.4 (Figure 5.12).

b. `(restore y)` puts into `y` the last value saved on the stack, but only if that value was saved from `y`; otherwise, it signals an error. Modify the simulator to behave this way. You will have to change `save` to put the register name on the stack along with the value.

c. `(restore y)` puts into `y` the last value saved from `y` regardless of what other registers were saved after `y` and not restored. Modify the simulator to behave this way. You will have to associate a separate stack with each register. You should make the `initialize-stack` operation initialize all the register stacks.

Exercise 5.12: The simulator can be used to help determine the data paths required for implementing a machine with a given controller. Extend the assembler to store the following information in the machine model:

- a list of all instructions, with duplicates removed, sorted by instruction type (`assign`, `goto`, and so on);
- a list (without duplicates) of the registers used to hold entry points (these are the registers referenced by `goto` instructions);
- a list (without duplicates) of the registers that are `saved` or `restored`;
- for each register, a list (without duplicates) of the sources from which it is assigned (for example, the sources for

register `val` in the factorial machine of Figure 5.11 are `(const 1)` and `((op *) (reg n) (reg val))`.

Extend the message-passing interface to the machine to provide access to this new information. To test your analyzer, define the Fibonacci machine from Figure 5.12 and examine the lists you constructed.

Exercise 5.13: Modify the simulator so that it uses the controller sequence to determine what registers the machine has rather than requiring a list of registers as an argument to `make-machine`. Instead of pre-allocating the registers in `make-machine`, you can allocate them one at a time when they are first seen during assembly of the instructions.

5.2.4 Monitoring Machine Performance

Simulation is useful not only for verifying the correctness of a proposed machine design but also for measuring the machine's performance. For example, we can install in our simulation program a "meter" that measures the number of stack operations used in a computation. To do this, we modify our simulated stack to keep track of the number of times registers are saved on the stack and the maximum depth reached by the stack, and add a message to the stack's interface that prints the statistics, as shown below. We also add an operation to the basic machine model to print the stack statistics, by initializing `the-ops` in `make-new-machine` to

```
(list (list 'initialize-stack
            (lambda () (stack 'initialize)))
      (list 'print-stack-statistics
            (lambda () (stack 'print-statistics))))
```

Here is the new version of `make-stack`:

```
(define (make-stack)
  (let ((s '())
        (number-pushes 0)
        (max-depth 0)
        (current-depth 0))
    (define (push x)
      (set! s (cons x s))
      (set! number-pushes (+ 1 number-pushes))
      (set! current-depth (+ 1 current-depth))
      (set! max-depth (max current-depth max-depth)))
    (define (pop)
      (if (null? s)
          (error "Empty stack: POP")
          (let ((top (car s)))
            (set! s (cdr s))
            (set! current-depth (- current-depth 1))
            top)))
    (define (initialize)
      (set! s '())
      (set! number-pushes 0)
      (set! max-depth 0)
      (set! current-depth 0)
      'done)
    (define (print-statistics)
      (newline)
      (display (list 'total-pushes  '= number-pushes
                     'maximum-depth '= max-depth)))
    (define (dispatch message)
      (cond ((eq? message 'push) push)
            ((eq? message 'pop) (pop))
            ((eq? message 'initialize) (initialize))
            ((eq? message 'print-statistics)
```

```
            (print-statistics))
           (else (error "Unknown request: STACK" message))))
  dispatch))
```

Exercise 5.15 through Exercise 5.19 describe other useful monitoring and debugging features that can be added to the register-machine simulator.

Exercise 5.14: Measure the number of pushes and the maximum stack depth required to compute $n!$ for various small values of n using the factorial machine shown in Figure 5.11. From your data determine formulas in terms of n for the total number of push operations and the maximum stack depth used in computing $n!$ for any $n > 1$. Note that each of these is a linear function of n and is thus determined by two constants. In order to get the statistics printed, you will have to augment the factorial machine with instructions to initialize the stack and print the statistics. You may want to also modify the machine so that it repeatedly reads a value for n, computes the factorial, and prints the result (as we did for the GCD machine in Figure 5.4), so that you will not have to repeatedly invoke `get-register-contents`, `set-register-contents!`, and `start`.

Exercise 5.15: Add *instruction counting* to the register machine simulation. That is, have the machine model keep track of the number of instructions executed. Extend the machine model's interface to accept a new message that prints the value of the instruction count and resets the count to zero.

Exercise 5.16: Augment the simulator to provide for *instruction tracing*. That is, before each instruction is executed, the simulator should print the text of the instruction. Make the machine

model accept `trace-on` and `trace-off` messages to turn tracing on and off.

Exercise 5.17: Extend the instruction tracing of Exercise 5.16 so that before printing an instruction, the simulator prints any labels that immediately precede that instruction in the controller sequence. Be careful to do this in a way that does not interfere with instruction counting (Exercise 5.15). You will have to make the simulator retain the necessary label information.

Exercise 5.18: Modify the `make-register` procedure of Section 5.2.1 so that registers can be traced. Registers should accept messages that turn tracing on and off. When a register is traced, assigning a value to the register should print the name of the register, the old contents of the register, and the new contents being assigned. Extend the interface to the machine model to permit you to turn tracing on and off for designated machine registers.

Exercise 5.19: Alyssa P. Hacker wants a *breakpoint* feature in the simulator to help her debug her machine designs. You have been hired to install this feature for her. She wants to be able to specify a place in the controller sequence where the simulator will stop and allow her to examine the state of the machine. You are to implement a procedure

```
(set-breakpoint ⟨machine⟩ ⟨label⟩ ⟨n⟩)
```

that sets a breakpoint just before the nth instruction after the given label. For example,

```
(set-breakpoint gcd-machine 'test-b 4)
```

installs a breakpoint in `gcd-machine` just before the assignment to register `a`. When the simulator reaches the breakpoint it should print the label and the offset of the breakpoint and stop executing instructions. Alyssa can then use `get-register-contents` and `set-register-contents!` to manipulate the state of the simulated machine. She should then be able to continue execution by saying

```
(proceed-machine ⟨machine⟩)
```

She should also be able to remove a specific breakpoint by means of

```
(cancel-breakpoint ⟨machine⟩ ⟨label⟩ ⟨n⟩)
```

or to remove all breakpoints by means of

```
(cancel-all-breakpoints ⟨machine⟩)
```

5.3 Storage Allocation and Garbage Collection

In Section 5.4, we will show how to implement a Scheme evaluator as a register machine. In order to simplify the discussion, we will assume that our register machines can be equipped with a *list-structured memory*, in which the basic operations for manipulating list-structured data are primitive. Postulating the existence of such a memory is a useful abstraction when one is focusing on the mechanisms of control in a Scheme interpreter, but this does not reflect a realistic view of the actual primitive data operations of contemporary computers. To obtain a more complete picture of how a Lisp system operates, we must investigate how list structure can be represented in a way that is compatible with conventional computer memories.

There are two considerations in implementing list structure. The first is purely an issue of representation: how to represent the "box-and-pointer" structure of Lisp pairs, using only the storage and addressing capabilities of typical computer memories. The second issue concerns the management of memory as a computation proceeds. The operation of a Lisp system depends crucially on the ability to continually create new data objects. These include objects that are explicitly created by the Lisp procedures being interpreted as well as structures created by the interpreter itself, such as environments and argument lists. Although the constant creation of new data objects would pose no problem on a computer with an infinite amount of rapidly addressable memory, computer memories are available only in finite sizes (more's the pity). Lisp systems thus provide an *automatic storage allocation* facility to support the illusion of an infinite memory. When a data object is no longer needed, the memory allocated to it is automatically recycled and used to construct new data objects. There are various techniques for providing such automatic storage allocation. The method we shall discuss in this section is called *garbage collection*.

5.3.1 Memory as Vectors

A conventional computer memory can be thought of as an array of cubbyholes, each of which can contain a piece of information. Each cubbyhole has a unique name, called its *address* or *location*. Typical memory systems provide two primitive operations: one that fetches the data stored in a specified location and one that assigns new data to a specified location. Memory addresses can be incremented to support sequential access to some set of the cubbyholes. More generally, many important data operations require that memory addresses be treated as data, which can be stored in memory locations and manipulated in machine registers. The representation of list structure is one application of such *address arithmetic*.

To model computer memory, we use a new kind of data structure called a *vector*. Abstractly, a vector is a compound data object whose individual elements can be accessed by means of an integer index in an amount of time that is independent of the index.[5] In order to describe memory operations, we use two primitive Scheme procedures for manipulating vectors:

- `(vector-ref` ⟨*vector*⟩ ⟨*n*⟩`)` returns the nth element of the vector.
- `(vector-set!` ⟨*vector*⟩ ⟨*n*⟩ ⟨*value*⟩`)` sets the nth element of the vector to the designated value.

For example, if `v` is a vector, then `(vector-ref v 5)` gets the fifth entry in the vector `v` and `(vector-set! v 5 7)` changes the value of the fifth entry of the vector `v` to 7.[6] For computer memory, this access can be implemented through the use of address arithmetic to combine a *base address* that specifies the beginning location of a vector in memory with an *index* that specifies the offset of a particular element of the vector.

Representing Lisp data

We can use vectors to implement the basic pair structures required for a list-structured memory. Let us imagine that computer memory is divided into two vectors: `the-cars` and `the-cdrs`. We will represent list structure as follows: A pointer to a pair is an index into the two vectors. The `car` of the

[5] We could represent memory as lists of items. However, the access time would then not be independent of the index, since accessing the nth element of a list requires $n - 1$ `cdr` operations.

[6] For completeness, we should specify a `make-vector` operation that constructs vectors. However, in the present application we will use vectors only to model fixed divisions of the computer memory.

pair is the entry in `the-cars` with the designated index, and the `cdr` of the pair is the entry in `the-cdrs` with the designated index. We also need a representation for objects other than pairs (such as numbers and symbols) and a way to distinguish one kind of data from another. There are many methods of accomplishing this, but they all reduce to using *typed pointers*, that is, to extending the notion of "pointer" to include information on data type.[7] The data type enables the system to distinguish a pointer to a pair (which consists of the "pair" data type and an index into the memory vectors) from pointers to other kinds of data (which consist of some other data type and whatever is being used to represent data of that type). Two data objects are considered to be the same (`eq?`) if their pointers are identical.[8] Figure 5.14 illustrates the use of this method to represent the list `((1 2) 3 4)`, whose box-and-pointer diagram is also shown. We use letter prefixes to denote the data-type information. Thus, a pointer to the pair with index 5 is denoted `p5`, the empty list is denoted by the pointer `e0`, and a pointer to the number 4 is denoted `n4`. In the box-and-pointer diagram, we have indicated at the lower left of each pair the vector index that specifies where the `car` and `cdr` of the pair are stored. The blank locations in `the-cars` and `the-cdrs` may contain

[7] This is precisely the same "tagged data" idea we introduced in Chapter 2 for dealing with generic operations. Here, however, the data types are included at the primitive machine level rather than constructed through the use of lists.

[8] Type information may be encoded in a variety of ways, depending on the details of the machine on which the Lisp system is to be implemented. The execution efficiency of Lisp programs will be strongly dependent on how cleverly this choice is made, but it is difficult to formulate general design rules for good choices. The most straightforward way to implement typed pointers is to allocate a fixed set of bits in each pointer to be a *type field* that encodes the data type. Important questions to be addressed in designing such a representation include the following: How many type bits are required? How large must the vector indices be? How efficiently can the primitive machine instructions be used to manipulate the type fields of pointers? Machines that include special hardware for the efficient handling of type fields are said to have *tagged architectures*.

parts of other list structures (not of interest here).

A pointer to a number, such as `n4`, might consist of a type indicating numeric data together with the actual representation of the number 4.[9] To deal with numbers that are too large to be represented in the fixed amount of space allocated for a single pointer, we could use a distinct *bignum* data type, for which the pointer designates a list in which the parts of the number are stored.[10]

A symbol might be represented as a typed pointer that designates a sequence of the characters that form the symbol's printed representation. This sequence is constructed by the Lisp reader when the character string is initially encountered in input. Since we want two instances of a symbol to be recognized as the "same" symbol by `eq?` and we want `eq?` to be a simple test for equality of pointers, we must ensure that if the reader sees the same character string twice, it will use the same pointer (to the same sequence of characters) to represent both occurrences. To accomplish this, the reader maintains a table, traditionally called the *obarray*, of all the symbols it has ever encountered. When the reader encounters a character string and is about to construct a symbol, it checks the obarray to see if it has ever before seen the same character string. If it has not, it uses the characters to construct a new symbol (a typed pointer to a new character sequence) and enters this pointer in the obarray. If the reader has seen the string before, it returns the symbol pointer stored in the obarray. This process of replacing character strings by unique pointers is called *interning* symbols.

[9] This decision on the representation of numbers determines whether `eq?`, which tests equality of pointers, can be used to test for equality of numbers. If the pointer contains the number itself, then equal numbers will have the same pointer. But if the pointer contains the index of a location where the number is stored, equal numbers will be guaranteed to have equal pointers only if we are careful never to store the same number in more than one location.

[10] This is just like writing a number as a sequence of digits, except that each "digit" is a number between 0 and the largest number that can be stored in a single pointer.




Figure 5.14: Box-and-pointer and memory-vector representations of the list `((1 2) 3 4)`.

Implementing the primitive list operations

Given the above representation scheme, we can replace each "primitive" list operation of a register machine with one or more primitive vector operations. We will use two registers, `the-cars` and `the-cdrs`, to identify the memory vectors, and will assume that `vector-ref` and `vector-set!` are available as primitive operations. We also assume that numeric operations on pointers (such as incrementing a pointer, using a pair pointer to index a vector, or adding two numbers) use only the index portion of the typed pointer.

For example, we can make a register machine support the instructions

```
(assign ⟨reg1⟩ (op car) (reg ⟨reg2⟩))
(assign ⟨reg1⟩ (op cdr) (reg ⟨reg2⟩))
```

if we implement these, respectively, as

```
(assign ⟨reg1⟩ (op vector-ref) (reg the-cars) (reg ⟨reg2⟩))
(assign ⟨reg1⟩ (op vector-ref) (reg the-cdrs) (reg ⟨reg2⟩))
```

The instructions

```
(perform (op set-car!) (reg ⟨reg1⟩) (reg ⟨reg2⟩))
(perform (op set-cdr!) (reg ⟨reg1⟩) (reg ⟨reg2⟩))
```

are implemented as

```
(perform
 (op vector-set!) (reg the-cars) (reg ⟨reg1⟩) (reg ⟨reg2⟩))
(perform
 (op vector-set!) (reg the-cdrs) (reg ⟨reg1⟩) (reg ⟨reg2⟩))
```

`cons` is performed by allocating an unused index and storing the arguments to `cons` in `the-cars` and `the-cdrs` at that indexed vector position. We presume that there is a special register, `free`, that always holds a pair pointer containing the next available index, and that we can increment the index part of that pointer to find the next free location.[11] For example, the instruction

```
(assign ⟨reg1⟩ (op cons) (reg ⟨reg2⟩) (reg ⟨reg3⟩))
```

is implemented as the following sequence of vector operations:[12]

```
(perform
 (op vector-set!) (reg the-cars) (reg free) (reg ⟨reg2⟩))
(perform
```

[11] There are other ways of finding free storage. For example, we could link together all the unused pairs into a *free list*. Our free locations are consecutive (and hence can be accessed by incrementing a pointer) because we are using a compacting garbage collector, as we will see in Section 5.3.2.

[12] This is essentially the implementation of `cons` in terms of `set-car!` and `set-cdr!`, as described in Section 3.3.1. The operation `get-new-pair` used in that implementation is realized here by the `free` pointer.

```
 (op vector-set!) (reg the-cdrs) (reg free) (reg ⟨reg3⟩)))
(assign ⟨reg1⟩ (reg free))
(assign free (op +) (reg free) (const 1))
```

The `eq?` operation

```
(op eq?) (reg ⟨reg1⟩) (reg ⟨reg2⟩)
```

simply tests the equality of all fields in the registers, and predicates such as `pair?`, `null?`, `symbol?`, and `number?` need only check the type field.

Implementing stacks

Although our register machines use stacks, we need do nothing special here, since stacks can be modeled in terms of lists. The stack can be a list of the saved values, pointed to by a special register `the-stack`. Thus, `(save` ⟨*reg*⟩`)` can be implemented as

```
(assign the-stack (op cons) (reg ⟨reg⟩) (reg the-stack))
```

Similarly, `(restore` ⟨*reg*⟩`)` can be implemented as

```
(assign ⟨reg⟩ (op car) (reg the-stack))
(assign the-stack (op cdr) (reg the-stack))
```

and `(perform (op initialize-stack))` can be implemented as

```
(assign the-stack (const ()))
```

These operations can be further expanded in terms of the vector operations given above. In conventional computer architectures, however, it is usually advantageous to allocate the stack as a separate vector. Then pushing and popping the stack can be accomplished by incrementing or decrementing an index into that vector.

Exercise 5.20: Draw the box-and-pointer representation and the memory-vector representation (as in Figure 5.14) of the list structure produced by

```
(define x (cons 1 2))
(define y (list x x))
```

with the `free` pointer initially `p1`. What is the final value of `free` ? What pointers represent the values of `x` and `y` ?

Exercise 5.21: Implement register machines for the following procedures. Assume that the list-structure memory operations are available as machine primitives.

a. Recursive `count-leaves`:

```
(define (count-leaves tree)
  (cond ((null? tree) 0)
        ((not (pair? tree)) 1)
        (else (+ (count-leaves (car tree))
                 (count-leaves (cdr tree))))))
```

b. Recursive `count-leaves` with explicit counter:

```
(define (count-leaves tree)
  (define (count-iter tree n)
    (cond ((null? tree) n)
          ((not (pair? tree)) (+ n 1))
          (else
           (count-iter (cdr tree)
                       (count-iter (car tree)
                                   n)))))
  (count-iter tree 0))
```

Exercise 5.22: Exercise 3.12 of Section 3.3.1 presented an `append` procedure that appends two lists to form a new list and an `append!` procedure that splices two lists together. Design a register machine to implement each of these procedures. Assume that the list-structure memory operations are available as primitive operations.

5.3.2 Maintaining the Illusion of Infinite Memory

The representation method outlined in Section 5.3.1 solves the problem of implementing list structure, provided that we have an infinite amount of memory. With a real computer we will eventually run out of free space in which to construct new pairs.[13] However, most of the pairs generated in a typical computation are used only to hold intermediate results. After these results are accessed, the pairs are no longer needed—they are *garbage*. For instance, the computation

```
(accumulate + 0 (filter odd? (enumerate-interval 0 n)))
```

constructs two lists: the enumeration and the result of filtering the enumeration. When the accumulation is complete, these lists are no longer needed, and the allocated memory can be reclaimed. If we can arrange to collect all the garbage periodically, and if this turns out to recycle memory at about the

[13] This may not be true eventually, because memories may get large enough so that it would be impossible to run out of free memory in the lifetime of the computer. For example, there are about $3 \cdot 10^{13}$ microseconds in a year, so if we were to `cons` once per microsecond we would need about 10^{15} cells of memory to build a machine that could operate for 30 years without running out of memory. That much memory seems absurdly large by today's standards, but it is not physically impossible. On the other hand, processors are getting faster and a future computer may have large numbers of processors operating in parallel on a single memory, so it may be possible to use up memory much faster than we have postulated.

same rate at which we construct new pairs, we will have preserved the illusion that there is an infinite amount of memory.

In order to recycle pairs, we must have a way to determine which allocated pairs are not needed (in the sense that their contents can no longer influence the future of the computation). The method we shall examine for accomplishing this is known as *garbage collection*. Garbage collection is based on the observation that, at any moment in a Lisp interpretation, the only objects that can affect the future of the computation are those that can be reached by some succession of `car` and `cdr` operations starting from the pointers that are currently in the machine registers.[14] Any memory cell that is not so accessible may be recycled.

There are many ways to perform garbage collection. The method we shall examine here is called *stop-and-copy*. The basic idea is to divide memory into two halves: "working memory" and "free memory." When `cons` constructs pairs, it allocates these in working memory. When working memory is full, we perform garbage collection by locating all the useful pairs in working memory and copying these into consecutive locations in free memory. (The useful pairs are located by tracing all the `car` and `cdr` pointers, starting with the machine registers.) Since we do not copy the garbage, there will presumably be additional free memory that we can use to allocate new pairs. In addition, nothing in the working memory is needed, since all the useful pairs in it have been copied. Thus, if we interchange the roles of working memory and free memory, we can continue processing; new pairs will be allocated in the new working memory (which was the old free memory). When this is full, we can copy the useful pairs into the new free memory (which was the old working memory).[15]

[14] We assume here that the stack is represented as a list as described in Section 5.3.1, so that items on the stack are accessible via the pointer in the stack register.

[15] This idea was invented and first implemented by Minsky, as part of the implementation

Implementation of a stop-and-copy garbage collector

We now use our register-machine language to describe the stop-and-copy algorithm in more detail. We will assume that there is a register called `root` that contains a pointer to a structure that eventually points at all accessible data. This can be arranged by storing the contents of all the machine registers in a pre-allocated list pointed at by `root` just before starting garbage collection.[16] We also assume that, in addition to the current working memory, there is free memory available into which we can copy the useful data. The current working memory consists of vectors whose base addresses are in registers called `the-cars` and `the-cdrs`, and the free memory is in

---

of Lisp for the PDP-1 at the MIT Research Laboratory of Electronics. It was further developed by Fenichel and Yochelson (1969) for use in the Lisp implementation for the Multics time-sharing system. Later, Baker (1978) developed a "real-time" version of the method, which does not require the computation to stop during garbage collection. Baker's idea was extended by Hewitt, Lieberman, and Moon (see Lieberman and Hewitt 1983) to take advantage of the fact that some structure is more volatile and other structure is more permanent.

An alternative commonly used garbage-collection technique is the *mark-sweep* method. This consists of tracing all the structure accessible from the machine registers and marking each pair we reach. We then scan all of memory, and any location that is unmarked is "swept up" as garbage and made available for reuse. A full discussion of the mark-sweep method can be found in Allen 1978.

The Minsky-Fenichel-Yochelson algorithm is the dominant algorithm in use for large-memory systems because it examines only the useful part of memory. This is in contrast to mark-sweep, in which the sweep phase must check all of memory. A second advantage of stop-and-copy is that it is a *compacting* garbage collector. That is, at the end of the garbage-collection phase the useful data will have been moved to consecutive memory locations, with all garbage pairs compressed out. This can be an extremely important performance consideration in machines with virtual memory, in which accesses to widely separated memory addresses may require extra paging operations.

[16] This list of registers does not include the registers used by the storage-allocation system —`root`, `the-cars`, `the-cdrs`, and the other registers that will be introduced in this section.

registers called `new-cars` and `new-cdrs`.

Garbage collection is triggered when we exhaust the free cells in the current working memory, that is, when a `cons` operation attempts to increment the `free` pointer beyond the end of the memory vector. When the garbage-collection process is complete, the `root` pointer will point into the new memory, all objects accessible from the `root` will have been moved to the new memory, and the `free` pointer will indicate the next place in the new memory where a new pair can be allocated. In addition, the roles of working memory and new memory will have been interchanged—new pairs will be constructed in the new memory, beginning at the place indicated by `free`, and the (previous) working memory will be available as the new memory for the next garbage collection. Figure 5.15 shows the arrangement of memory just before and just after garbage collection.

The state of the garbage-collection process is controlled by maintaining two pointers: `free` and `scan`. These are initialized to point to the beginning of the new memory. The algorithm begins by relocating the pair pointed at by `root` to the beginning of the new memory. The pair is copied, the `root` pointer is adjusted to point to the new location, and the `free` pointer is incremented. In addition, the old location of the pair is marked to show that its contents have been moved. This marking is done as follows: In the `car` position, we place a special tag that signals that this is an already-moved object. (Such an object is traditionally called a *broken heart*.)[17] In the `cdr` position we place a *forwarding address* that points at the location to which the object has been moved.

After relocating the root, the garbage collector enters its basic cycle. At each step in the algorithm, the `scan` pointer (initially pointing at the relocated root) points at a pair that has been moved to the new memory but whose

[17] The term *broken heart* was coined by David Cressey, who wrote a garbage collector for MDL, a dialect of Lisp developed at MIT during the early 1970s.




Figure 5.15: Reconfiguration of memory by the garbage-collection process.

car and cdr pointers still refer to objects in the old memory. These objects are each relocated, and the scan pointer is incremented. To relocate an object (for example, the object indicated by the car pointer of the pair we are scanning) we check to see if the object has already been moved (as indicated by the presence of a broken-heart tag in the car position of the object). If the object has not already been moved, we copy it to the place indicated by free, update free, set up a broken heart at the object's old location, and update the pointer to the object (in this example, the car pointer of the pair we are scanning) to point to the new location. If the object has already been moved, its forwarding address (found in the cdr position of the broken heart) is substituted for the pointer in the pair being scanned. Eventually, all accessible objects will have been moved and scanned, at which point the scan pointer will overtake the free pointer and the process will terminate.

We can specify the stop-and-copy algorithm as a sequence of instructions for a register machine. The basic step of relocating an object is accomplished by a subroutine called relocate-old-result-in-new. This subroutine gets its argument, a pointer to the object to be relocated, from a register named old. It relocates the designated object (incrementing free in the process), puts a pointer to the relocated object into a register called new, and returns by branching to the entry point stored in the register relocate-continue. To begin garbage collection, we invoke this subroutine to relocate the root pointer, after initializing free and scan. When the relocation of root has been accomplished, we install the new pointer as the new root and enter the main loop of the garbage collector.

```
begin-garbage-collection
  (assign free (const 0))
  (assign scan (const 0))
  (assign old (reg root))
  (assign relocate-continue (label reassign-root))
  (goto (label relocate-old-result-in-new))
```

```
reassign-root
  (assign root (reg new))
  (goto (label gc-loop))
```

In the main loop of the garbage collector we must determine whether there are any more objects to be scanned. We do this by testing whether the `scan` pointer is coincident with the `free` pointer. If the pointers are equal, then all accessible objects have been relocated, and we branch to `gc-flip`, which cleans things up so that we can continue the interrupted computation. If there are still pairs to be scanned, we call the relocate subroutine to relocate the `car` of the next pair (by placing the `car` pointer in `old`). The `relocate-continue` register is set up so that the subroutine will return to update the `car` pointer.

```
gc-loop
  (test (op =) (reg scan) (reg free))
  (branch (label gc-flip))
  (assign old (op vector-ref) (reg new-cars) (reg scan))
  (assign relocate-continue (label update-car))
  (goto (label relocate-old-result-in-new))
```

At `update-car`, we modify the `car` pointer of the pair being scanned, then proceed to relocate the `cdr` of the pair. We return to `update-cdr` when that relocation has been accomplished. After relocating and updating the `cdr`, we are finished scanning that pair, so we continue with the main loop.

```
update-car
  (perform (op vector-set!)
           (reg new-cars)
           (reg scan)
           (reg new))
  (assign old (op vector-ref) (reg new-cdrs) (reg scan))
  (assign relocate-continue (label update-cdr))
```

```
  (goto (label relocate-old-result-in-new))
update-cdr
  (perform (op vector-set!)
           (reg new-cdrs)
           (reg scan)
           (reg new))
  (assign scan (op +) (reg scan) (const 1))
  (goto (label gc-loop))
```

The subroutine `relocate-old-result-in-new` relocates objects as follows: If the object to be relocated (pointed at by `old`) is not a pair, then we return the same pointer to the object unchanged (in `new`). (For example, we may be scanning a pair whose `car` is the number 4. If we represent the `car` by `n4`, as described in Section 5.3.1, then we want the "relocated" `car` pointer to still be `n4`.) Otherwise, we must perform the relocation. If the `car` position of the pair to be relocated contains a broken-heart tag, then the pair has in fact already been moved, so we retrieve the forwarding address (from the `cdr` position of the broken heart) and return this in `new`. If the pointer in `old` points at a yet-unmoved pair, then we move the pair to the first free cell in new memory (pointed at by `free`) and set up the broken heart by storing a broken-heart tag and forwarding address at the old location. `relocate-old-result-in-new` uses a register `oldcr` to hold the `car` or the `cdr` of the object pointed at by `old`.[18]

```
relocate-old-result-in-new
  (test (op pointer-to-pair?) (reg old))
```

[18]The garbage collector uses the low-level predicate `pointer-to-pair?` instead of the list-structure `pair?` operation because in a real system there might be various things that are treated as pairs for garbage-collection purposes. For example, in a Scheme system that conforms to the IEEE standard a procedure object may be implemented as a special kind of "pair" that doesn't satisfy the `pair?` predicate. For simulation purposes, `pointer-to-pair?` can be implemented as `pair?`.

```
  (branch (label pair))
  (assign new (reg old))
  (goto (reg relocate-continue))
pair
  (assign oldcr (op vector-ref) (reg the-cars) (reg old))
  (test (op broken-heart?) (reg oldcr))
  (branch (label already-moved))
  (assign new (reg free)) ; new location for pair
  ;; Update free pointer.
  (assign free (op +) (reg free) (const 1))
  ;; Copy the car and cdr to new memory.
  (perform (op vector-set!)
           (reg new-cars) (reg new) (reg oldcr))
  (assign oldcr (op vector-ref) (reg the-cdrs) (reg old))
  (perform (op vector-set!)
           (reg new-cdrs) (reg new) (reg oldcr))
  ;; Construct the broken heart.
  (perform (op vector-set!)
           (reg the-cars) (reg old) (const broken-heart))
  (perform
   (op vector-set!) (reg the-cdrs) (reg old) (reg new))
  (goto (reg relocate-continue))
already-moved
  (assign new (op vector-ref) (reg the-cdrs) (reg old))
  (goto (reg relocate-continue))
```

At the very end of the garbage-collection process, we interchange the role of old and new memories by interchanging pointers: interchanging `the-cars` with `new-cars`, and `the-cdrs` with `new-cdrs`. We will then be ready to perform another garbage collection the next time memory runs out.

```
gc-flip
  (assign temp (reg the-cdrs))
  (assign the-cdrs (reg new-cdrs))
```

```
(assign new-cdrs (reg temp))
(assign temp (reg the-cars))
(assign the-cars (reg new-cars))
(assign new-cars (reg temp))
```

5.4 The Explicit-Control Evaluator

In Section 5.1 we saw how to transform simple Scheme programs into descriptions of register machines. We will now perform this transformation on a more complex program, the metacircular evaluator of Section 4.1.1–Section 4.1.4, which shows how the behavior of a Scheme interpreter can be described in terms of the procedures `eval` and `apply`. The *explicit-control evaluator* that we develop in this section shows how the underlying procedure-calling and argument-passing mechanisms used in the evaluation process can be described in terms of operations on registers and stacks. In addition, the explicit-control evaluator can serve as an implementation of a Scheme interpreter, written in a language that is very similar to the native machine language of conventional computers. The evaluator can be executed by the register-machine simulator of Section 5.2. Alternatively, it can be used as a starting point for building a machine-language implementation of a Scheme evaluator, or even a special-purpose machine for evaluating Scheme expressions. Figure 5.16 shows such a hardware implementation: a silicon chip that acts as an evaluator for Scheme. The chip designers started with the data-path and controller specifications for a register machine similar to the evaluator described in this section and used design automation programs to construct the integrated-circuit layout.[19]

[19] See Batali et al. 1982 for more information on the chip and the method by which it was designed.




Figure 5.16: A silicon-chip implementation of an evaluator for Scheme.

Registers and operations

In designing the explicit-control evaluator, we must specify the operations to be used in our register machine. We described the metacircular evaluator in terms of abstract syntax, using procedures such as `quoted?` and `make-procedure`. In implementing the register machine, we could expand these procedures into sequences of elementary list-structure memory operations, and implement these operations on our register machine. However, this would make our evaluator very long, obscuring the basic structure with details. To clarify the presentation, we will include as primitive operations of the register

machine the syntax procedures given in Section 4.1.2 and the procedures for representing environments and other run-time data given in sections Section 4.1.3 and Section 4.1.4. In order to completely specify an evaluator that could be programmed in a low-level machine language or implemented in hardware, we would replace these operations by more elementary operations, using the list-structure implementation we described in Section 5.3.

Our Scheme evaluator register machine includes a stack and seven registers: `exp`, `env`, `val`, `continue`, `proc`, `argl`, and `unev`. `exp` is used to hold the expression to be evaluated, and `env` contains the environment in which the evaluation is to be performed. At the end of an evaluation, `val` contains the value obtained by evaluating the expression in the designated environment. The `continue` register is used to implement recursion, as explained in Section 5.1.4. (The evaluator needs to call itself recursively, since evaluating an expression requires evaluating its subexpressions.) The registers `proc`, `argl`, and `unev` are used in evaluating combinations.

We will not provide a data-path diagram to show how the registers and operations of the evaluator are connected, nor will we give the complete list of machine operations. These are implicit in the evaluator's controller, which will be presented in detail.

5.4.1 The Core of the Explicit-Control Evaluator

The central element in the evaluator is the sequence of instructions beginning at `eval-dispatch`. This corresponds to the `eval` procedure of the metacircular evaluator described in Section 4.1.1. When the controller starts at `eval-dispatch`, it evaluates the expression specified by `exp` in the environment specified by `env`. When evaluation is complete, the controller will go to the entry point stored in `continue`, and the `val` register will hold the value of the expression. As with the metacircular `eval`, the structure of `eval-dispatch` is a case analysis on the syntactic type of

the expression to be evaluated.[20]

```
eval-dispatch
  (test (op self-evaluating?) (reg exp))
  (branch (label ev-self-eval))
  (test (op variable?) (reg exp))
  (branch (label ev-variable))
  (test (op quoted?) (reg exp))
  (branch (label ev-quoted))
  (test (op assignment?) (reg exp))
  (branch (label ev-assignment))
  (test (op definition?) (reg exp))
  (branch (label ev-definition))
  (test (op if?) (reg exp))
  (branch (label ev-if))
  (test (op lambda?) (reg exp))
  (branch (label ev-lambda))
  (test (op begin?) (reg exp))
  (branch (label ev-begin))
  (test (op application?) (reg exp))
  (branch (label ev-application))
  (goto (label unknown-expression-type))
```

Evaluating simple expressions

Numbers and strings (which are self-evaluating), variables, quotations, and `lambda` expressions have no subexpressions to be evaluated. For these, the

[20] In our controller, the dispatch is written as a sequence of `test` and `branch` instructions. Alternatively, it could have been written in a data-directed style (and in a real system it probably would have been) to avoid the need to perform sequential tests and to facilitate the definition of new expression types. A machine designed to run Lisp would probably include a `dispatch-on-type` instruction that would efficiently execute such data-directed dispatches.

evaluator simply places the correct value in the `val` register and continues execution at the entry point specified by `continue`. Evaluation of simple expressions is performed by the following controller code:

```
ev-self-eval
  (assign val (reg exp))
  (goto (reg continue))
ev-variable
  (assign val (op lookup-variable-value) (reg exp) (reg env)
  (goto (reg continue))
ev-quoted
  (assign val (op text-of-quotation) (reg exp))
  (goto (reg continue))
ev-lambda
  (assign unev (op lambda-parameters) (reg exp))
  (assign exp (op lambda-body) (reg exp))
  (assign val (op make-procedure) (reg unev) (reg exp) (reg
  (goto (reg continue))
```

Observe how `ev-lambda` uses the `unev` and `exp` registers to hold the parameters and body of the lambda expression so that they can be passed to the `make-procedure` operation, along with the environment in `env`.

Evaluating procedure applications

A procedure application is specified by a combination containing an operator and operands. The operator is a subexpression whose value is a procedure, and the operands are subexpressions whose values are the arguments to which the procedure should be applied. The metacircular `eval` handles applications by calling itself recursively to evaluate each element of the combination, and then passing the results to `apply`, which performs the actual procedure application. The explicit-control evaluator does the same thing; these recursive calls are implemented by `goto` instructions, together with use of the

stack to save registers that will be restored after the recursive call returns. Before each call we will be careful to identify which registers must be saved (because their values will be needed later).[21]

We begin the evaluation of an application by evaluating the operator to produce a procedure, which will later be applied to the evaluated operands. To evaluate the operator, we move it to the `exp` register and go to `eval-dispatch`. The environment in the `env` register is already the correct one in which to evaluate the operator. However, we save `env` because we will need it later to evaluate the operands. We also extract the operands into `unev` and save this on the stack. We set up `continue` so that `eval-dispatch` will resume at `ev-appl-did-operator` after the operator has been evaluated. First, however, we save the old value of `continue`, which tells the controller where to continue after the application.

```
ev-application
  (save continue)
  (save env)
  (assign unev (op operands) (reg exp))
  (save unev)
  (assign exp (op operator) (reg exp))
  (assign continue (label ev-appl-did-operator))
  (goto (label eval-dispatch))
```

Upon returning from evaluating the operator subexpression, we proceed to evaluate the operands of the combination and to accumulate the resulting arguments in a list, held in `argl`. First we restore the unevaluated operands and

[21] This is an important but subtle point in translating algorithms from a procedural language, such as Lisp, to a register-machine language. As an alternative to saving only what is needed, we could save all the registers (except `val`) before each recursive call. This is called a *framed-stack* discipline. This would work but might save more registers than necessary; this could be an important consideration in a system where stack operations are expensive. Saving registers whose contents will not be needed later may also hold onto useless data that could otherwise be garbage-collected, freeing space to be reused.

the environment. We initialize `argl` to an empty list. Then we assign to the `proc` register the procedure that was produced by evaluating the operator. If there are no operands, we go directly to `apply-dispatch`. Otherwise we save `proc` on the stack and start the argument-evaluation loop:[22]

```
ev-appl-did-operator
  (restore unev)                          ; the operands
  (restore env)
  (assign argl (op empty-arglist))
  (assign proc (reg val))                 ; the operator
  (test (op no-operands?) (reg unev))
  (branch (label apply-dispatch))
  (save proc)
```

Each cycle of the argument-evaluation loop evaluates an operand from the list in `unev` and accumulates the result into `argl`. To evaluate an operand, we place it in the `exp` register and go to `eval-dispatch`, after setting `continue` so that execution will resume with the argument-accumulation phase. But first we save the arguments accumulated so far (held in `argl`), the environment (held in `env`), and the remaining operands to be evaluated (held in `unev`). A special case is made for the evaluation of the last operand, which is handled at `ev-appl-last-arg`.

```
ev-appl-operand-loop
```

[22] We add to the evaluator data-structure procedures in Section 4.1.3 the following two procedures for manipulating argument lists:

```
(define (empty-arglist) '())
(define (adjoin-arg arg arglist) (append arglist (list arg)))
```

We also use an additional syntax procedure to test for the last operand in a combination:

```
(define (last-operand? ops) (null? (cdr ops)))
```

```
  (save argl)
  (assign exp (op first-operand) (reg unev))
  (test (op last-operand?) (reg unev))
  (branch (label ev-appl-last-arg))
  (save env)
  (save unev)
  (assign continue (label ev-appl-accumulate-arg))
  (goto (label eval-dispatch))
```

When an operand has been evaluated, the value is accumulated into the list held in `argl`. The operand is then removed from the list of unevaluated operands in `unev`, and the argument-evaluation continues.

```
ev-appl-accumulate-arg
  (restore unev)
  (restore env)
  (restore argl)
  (assign argl (op adjoin-arg) (reg val) (reg argl))
  (assign unev (op rest-operands) (reg unev))
  (goto (label ev-appl-operand-loop))
```

Evaluation of the last argument is handled differently. There is no need to save the environment or the list of unevaluated operands before going to `eval-dispatch`, since they will not be required after the last operand is evaluated. Thus, we return from the evaluation to a special entry point `ev-appl-accum-last-arg`, which restores the argument list, accumulates the new argument, restores the saved procedure, and goes off to perform the application.[23]

[23] The optimization of treating the last operand specially is known as *evlis tail recursion* (see Wand 1980). We could be somewhat more efficient in the argument evaluation loop if we made evaluation of the first operand a special case too. This would permit us to postpone initializing `argl` until after evaluating the first operand, so as to avoid saving `argl` in this case. The compiler in Section 5.5 performs this optimization. (Compare the `construct-`

```
ev-appl-last-arg
  (assign continue (label ev-appl-accum-last-arg))
  (goto (label eval-dispatch))
ev-appl-accum-last-arg
  (restore argl)
  (assign argl (op adjoin-arg) (reg val) (reg argl))
  (restore proc)
  (goto (label apply-dispatch))
```

The details of the argument-evaluation loop determine the order in which the interpreter evaluates the operands of a combination (e.g., left to right or right to left—see Exercise 3.8). This order is not determined by the metacircular evaluator, which inherits its control structure from the underlying Scheme in which it is implemented.[24] Because the `first-operand` selector (used in `ev-appl-operand-loop` to extract successive operands from `unev`) is implemented as `car` and the `rest-operands` selector is implemented as `cdr`, the explicit-control evaluator will evaluate the operands of a combination in left-to-right order.

Procedure application

The entry point `apply-dispatch` corresponds to the `apply` procedure of the metacircular evaluator. By the time we get to `apply-dispatch`, the `proc` register contains the procedure to apply and `argl` contains the list of evaluated arguments to which it must be applied. The saved value of `continue` (originally passed to `eval-dispatch` and saved at `ev-application`), which tells where to return with the result of the proce-

`arglist` procedure of Section 5.5.3.)

[24] The order of operand evaluation in the metacircular evaluator is determined by the order of evaluation of the arguments to `cons` in the procedure `list-of-values` of Section 4.1.1 (see Exercise 4.1).

dure application, is on the stack. When the application is complete, the controller transfers to the entry point specified by the saved `continue`, with the result of the application in `val`. As with the metacircular `apply`, there are two cases to consider. Either the procedure to be applied is a primitive or it is a compound procedure.

```
apply-dispatch
  (test (op primitive-procedure?) (reg proc))
  (branch (label primitive-apply))
  (test (op compound-procedure?) (reg proc))
  (branch (label compound-apply))
  (goto (label unknown-procedure-type))
```

We assume that each primitive is implemented so as to obtain its arguments from `argl` and place its result in `val`. To specify how the machine handles primitives, we would have to provide a sequence of controller instructions to implement each primitive and arrange for `primitive-apply` to dispatch to the instructions for the primitive identified by the contents of `proc`. Since we are interested in the structure of the evaluation process rather than the details of the primitives, we will instead just use an `apply-primitive-procedure` operation that applies the procedure in `proc` to the arguments in `argl`. For the purpose of simulating the evaluator with the simulator of Section 5.2 we use the procedure `apply-primitive-procedure`, which calls on the underlying Scheme system to perform the application, just as we did for the metacircular evaluator in Section 4.1.4. After computing the value of the primitive application, we restore `continue` and go to the designated entry point.

```
primitive-apply
  (assign val (op apply-primitive-procedure)
              (reg proc)
              (reg argl))
```

```
  (restore continue)
  (goto (reg continue))
```

To apply a compound procedure, we proceed just as with the metacircular evaluator. We construct a frame that binds the procedure's parameters to the arguments, use this frame to extend the environment carried by the procedure, and evaluate in this extended environment the sequence of expressions that forms the body of the procedure. `ev-sequence`, described below in Section 5.4.2, handles the evaluation of the sequence.

```
compound-apply
  (assign unev (op procedure-parameters) (reg proc))
  (assign env (op procedure-environment) (reg proc))
  (assign env (op extend-environment)
              (reg unev) (reg argl) (reg env))
  (assign unev (op procedure-body) (reg proc))
  (goto (label ev-sequence))
```

`compound-apply` is the only place in the interpreter where the `env` register is ever assigned a new value. Just as in the metacircular evaluator, the new environment is constructed from the environment carried by the procedure, together with the argument list and the corresponding list of variables to be bound.

5.4.2 Sequence Evaluation and Tail Recursion

The portion of the explicit-control evaluator at `ev-sequence` is analogous to the metacircular evaluator's `eval-sequence` procedure. It handles sequences of expressions in procedure bodies or in explicit `begin` expressions.

Explicit `begin` expressions are evaluated by placing the sequence of expressions to be evaluated in `unev`, saving `continue` on the stack, and jumping to `ev-sequence`.

```
ev-begin
  (assign unev (op begin-actions) (reg exp))
  (save continue)
  (goto (label ev-sequence))
```

The implicit sequences in procedure bodies are handled by jumping to `ev-sequence` from `compound-apply`, at which point `continue` is already on the stack, having been saved at `ev-application`.

The entries at `ev-sequence` and `ev-sequence-continue` form a loop that successively evaluates each expression in a sequence. The list of unevaluated expressions is kept in `unev`. Before evaluating each expression, we check to see if there are additional expressions to be evaluated in the sequence. If so, we save the rest of the unevaluated expressions (held in `unev`) and the environment in which these must be evaluated (held in `env`) and call `eval-dispatch` to evaluate the expression. The two saved registers are restored upon the return from this evaluation, at `ev-sequence-continue`.

The final expression in the sequence is handled differently, at the entry point `ev-sequence-last-exp`. Since there are no more expressions to be evaluated after this one, we need not save `unev` or `env` before going to `eval-dispatch`. The value of the whole sequence is the value of the last expression, so after the evaluation of the last expression there is nothing left to do except continue at the entry point currently held on the stack (which was saved by `ev-application` or `ev-begin`.) Rather than setting up `continue` to arrange for `eval-dispatch` to return here and then restoring `continue` from the stack and continuing at that entry point, we restore `continue` from the stack before going to `eval-dispatch`, so that `eval-dispatch` will continue at that entry point after evaluating the expression.

```
ev-sequence
```

```
  (assign exp (op first-exp) (reg unev))
  (test (op last-exp?) (reg unev))
  (branch (label ev-sequence-last-exp))
  (save unev)
  (save env)
  (assign continue (label ev-sequence-continue))
  (goto (label eval-dispatch))
ev-sequence-continue
  (restore env)
  (restore unev)
  (assign unev (op rest-exps) (reg unev))
  (goto (label ev-sequence))
ev-sequence-last-exp
  (restore continue)
  (goto (label eval-dispatch))
```

Tail recursion

In Chapter 1 we said that the process described by a procedure such as

```
(define (sqrt-iter guess x)
  (if (good-enough? guess x)
      guess
      (sqrt-iter (improve guess x) x)))
```

is an iterative process. Even though the procedure is syntactically recursive (defined in terms of itself), it is not logically necessary for an evaluator to save information in passing from one call to `sqrt-iter` to the next.[25] An evaluator that can execute a procedure such as `sqrt-iter` without requiring increasing storage as the procedure continues to call itself is called a *tail-recursive* evaluator. The metacircular implementation of the evaluator in

[25] We saw in Section 5.1 how to implement such a process with a register machine that had no stack; the state of the process was stored in a fixed set of registers.

Chapter 4 does not specify whether the evaluator is tail-recursive, because that evaluator inherits its mechanism for saving state from the underlying Scheme. With the explicit-control evaluator, however, we can trace through the evaluation process to see when procedure calls cause a net accumulation of information on the stack.

Our evaluator is tail-recursive, because in order to evaluate the final expression of a sequence we transfer directly to `eval-dispatch` without saving any information on the stack. Hence, evaluating the final expression in a sequence—even if it is a procedure call (as in `sqrt-iter`, where the `if` expression, which is the last expression in the procedure body, reduces to a call to `sqrt-iter`)—will not cause any information to be accumulated on the stack.[26]

If we did not think to take advantage of the fact that it was unnecessary to save information in this case, we might have implemented `eval-sequence` by treating all the expressions in a sequence in the same way —saving the registers, evaluating the expression, returning to restore the registers, and repeating this until all the expressions have been evaluated:[27]

```
ev-sequence
   (test (op no-more-exps?) (reg unev))
   (branch (label ev-sequence-end))
   (assign exp (op first-exp) (reg unev))
   (save unev)
   (save env)
```

[26] This implementation of tail recursion in `ev-sequence` is one variety of a well-known optimization technique used by many compilers. In compiling a procedure that ends with a procedure call, one can replace the call by a jump to the called procedure's entry point. Building this strategy into the interpreter, as we have done in this section, provides the optimization uniformly throughout the language.

[27] We can define `no-more-exps?` as follows:

```
(define (no-more-exps? seq) (null? seq))
```

```
  (assign continue (label ev-sequence-continue))
  (goto (label eval-dispatch))
ev-sequence-continue
  (restore env)
  (restore unev)
  (assign unev (op rest-exps) (reg unev))
  (goto (label ev-sequence))
ev-sequence-end
  (restore continue)
  (goto (reg continue))
```

This may seem like a minor change to our previous code for evaluation of a sequence: The only difference is that we go through the save-restore cycle for the last expression in a sequence as well as for the others. The interpreter will still give the same value for any expression. But this change is fatal to the tail-recursive implementation, because we must now return after evaluating the final expression in a sequence in order to undo the (useless) register saves. These extra saves will accumulate during a nest of procedure calls. Consequently, processes such as `sqrt-iter` will require space proportional to the number of iterations rather than requiring constant space. This difference can be significant. For example, with tail recursion, an infinite loop can be expressed using only the procedure-call mechanism:

```
(define (count n)
  (newline) (display n) (count (+ n 1)))
```

Without tail recursion, such a procedure would eventually run out of stack space, and expressing a true iteration would require some control mechanism other than procedure call.

5.4.3 Conditionals, Assignments, and Definitions

As with the metacircular evaluator, special forms are handled by selectively evaluating fragments of the expression. For an `if` expression, we must eval-

uate the predicate and decide, based on the value of predicate, whether to evaluate the consequent or the alternative.

Before evaluating the predicate, we save the `if` expression itself so that we can later extract the consequent or alternative. We also save the environment, which we will need later in order to evaluate the consequent or the alternative, and we save `continue`, which we will need later in order to return to the evaluation of the expression that is waiting for the value of the `if`.

```
ev-if
  (save exp)                          ; save expression for later
  (save env)
  (save continue)
  (assign continue (label ev-if-decide))
  (assign exp (op if-predicate) (reg exp))
  (goto (label eval-dispatch))        ; evaluate the predicate
```

When we return from evaluating the predicate, we test whether it was true or false and, depending on the result, place either the consequent or the alternative in `exp` before going to `eval-dispatch`. Notice that restoring `env` and `continue` here sets up `eval-dispatch` to have the correct environment and to continue at the right place to receive the value of the `if` expression.

```
ev-if-decide
  (restore continue)
  (restore env)
  (restore exp)
  (test (op true?) (reg val))
  (branch (label ev-if-consequent))
ev-if-alternative
  (assign exp (op if-alternative) (reg exp))
```

```
  (goto (label eval-dispatch))
ev-if-consequent
  (assign exp (op if-consequent) (reg exp))
  (goto (label eval-dispatch))
```

Assignments and definitions

Assignments are handled by `ev-assignment`, which is reached from `eval-dispatch` with the assignment expression in `exp`. The code at `ev-assignment` first evaluates the value part of the expression and then installs the new value in the environment. `set-variable-value!` is assumed to be available as a machine operation.

```
ev-assignment
  (assign unev (op assignment-variable) (reg exp))
  (save unev)                          ; save variable for later
  (assign exp (op assignment-value) (reg exp))
  (save env)
  (save continue)
  (assign continue (label ev-assignment-1))
  (goto (label eval-dispatch))   ; evaluate the assignment value
ev-assignment-1
  (restore continue)
  (restore env)
  (restore unev)
  (perform
   (op set-variable-value!) (reg unev) (reg val) (reg env))
  (assign val (const ok))
  (goto (reg continue))
```

Definitions are handled in a similar way:

```
ev-definition
  (assign unev (op definition-variable) (reg exp))
  (save unev)                          ; save variable for later
```

```
  (assign exp (op definition-value) (reg exp))
  (save env)
  (save continue)
  (assign continue (label ev-definition-1))
  (goto (label eval-dispatch))   ; evaluate the definition value
ev-definition-1
  (restore continue)
  (restore env)
  (restore unev)
  (perform
   (op define-variable!) (reg unev) (reg val) (reg env))
  (assign val (const ok))
  (goto (reg continue))
```

Exercise 5.23: Extend the evaluator to handle derived expressions such as `cond`, `let`, and so on (Section 4.1.2). You may "cheat" and assume that the syntax transformers such as `cond->if` are available as machine operations.[28]

Exercise 5.24: Implement `cond` as a new basic special form without reducing it to `if`. You will have to construct a loop that tests the predicates of successive `cond` clauses until you find one that is true, and then use `ev-sequence` to evaluate the actions of the clause.

Exercise 5.25: Modify the evaluator so that it uses normal-order evaluation, based on the lazy evaluator of Section 4.2.

[28] This isn't really cheating. In an actual implementation built from scratch, we would use our explicit-control evaluator to interpret a Scheme program that performs source-level transformations like `cond->if` in a syntax phase that runs before execution.

5.4.4 Running the Evaluator

With the implementation of the explicit-control evaluator we come to the end of a development, begun in Chapter 1, in which we have explored successively more precise models of the evaluation process. We started with the relatively informal substitution model, then extended this in Chapter 3 to the environment model, which enabled us to deal with state and change. In the metacircular evaluator of Chapter 4, we used Scheme itself as a language for making more explicit the environment structure constructed during evaluation of an expression. Now, with register machines, we have taken a close look at the evaluator's mechanisms for storage management, argument passing, and control. At each new level of description, we have had to raise issues and resolve ambiguities that were not apparent at the previous, less precise treatment of evaluation. To understand the behavior of the explicit-control evaluator, we can simulate it and monitor its performance.

We will install a driver loop in our evaluator machine. This plays the role of the `driver-loop` procedure of Section 4.1.4. The evaluator will repeatedly print a prompt, read an expression, evaluate the expression by going to `eval-dispatch`, and print the result. The following instructions form the beginning of the explicit-control evaluator's controller sequence:[29]

```
read-eval-print-loop
```

[29] We assume here that `read` and the various printing operations are available as primitive machine operations, which is useful for our simulation, but completely unrealistic in practice. These are actually extremely complex operations. In practice, they would be implemented using low-level input-output operations such as transferring single characters to and from a device.

To support the `get-global-environment` operation we define

```
(define the-global-environment (setup-environment))
(define (get-global-environment) the-global-environment)
```

```
  (perform (op initialize-stack))
  (perform
   (op prompt-for-input) (const ";;EC-Eval input:"))
  (assign exp (op read))
  (assign env (op get-global-environment))
  (assign continue (label print-result))
  (goto (label eval-dispatch))
print-result
  (perform (op announce-output) (const ";;EC-Eval value:"))
  (perform (op user-print) (reg val))
  (goto (label read-eval-print-loop))
```

When we encounter an error in a procedure (such as the "unknown procedure type error" indicated at `apply-dispatch`), we print an error message and return to the driver loop.[30]

```
unknown-expression-type
  (assign val (const unknown-expression-type-error))
  (goto (label signal-error))
unknown-procedure-type
  (restore continue)      ; clean up stack (from apply-dispatch)
  (assign val (const unknown-procedure-type-error))
  (goto (label signal-error))
signal-error
  (perform (op user-print) (reg val))
  (goto (label read-eval-print-loop))
```

For the purposes of the simulation, we initialize the stack each time through the driver loop, since it might not be empty after an error (such as an undefined variable) interrupts an evaluation.[31]

[30] There are other errors that we would like the interpreter to handle, but these are not so simple. See Exercise 5.30.

[31] We could perform the stack initialization only after errors, but doing it in the driver loop will be convenient for monitoring the evaluator's performance, as described below.

If we combine all the code fragments presented in Section 5.4.1–Section 5.4.4, we can create an evaluator machine model that we can run using the register-machine simulator of Section 5.2.

```
(define eceval
  (make-machine
   '(exp env val proc argl continue unev)
   eceval-operations
   '(read-eval-print-loop
     ⟨entire machine controller as given above⟩ )))
```

We must define Scheme procedures to simulate the operations used as primitives by the evaluator. These are the same procedures we used for the metacircular evaluator in Section 4.1, together with the few additional ones defined in footnotes throughout Section 5.4.

```
(define eceval-operations
  (list (list 'self-evaluating? self-evaluating)
        ⟨complete list of operations for eceval machine⟩))
```

Finally, we can initialize the global environment and run the evaluator:

```
(define the-global-environment (setup-environment))
(start eceval)
;;; EC-Eval input:
(define (append x y)
  (if (null? x) y (cons (car x) (append (cdr x) y))))
;;; EC-Eval value:
ok
;;; EC-Eval input:
(append '(a b c) '(d e f))
;;; EC-Eval value:
(a b c d e f)
```

Of course, evaluating expressions in this way will take much longer than if we had directly typed them into Scheme, because of the multiple levels of

simulation involved. Our expressions are evaluated by the explicit-control-evaluator machine, which is being simulated by a Scheme program, which is itself being evaluated by the Scheme interpreter.

Monitoring the performance of the evaluator

Simulation can be a powerful tool to guide the implementation of evaluators. Simulations make it easy not only to explore variations of the register-machine design but also to monitor the performance of the simulated evaluator. For example, one important factor in performance is how efficiently the evaluator uses the stack. We can observe the number of stack operations required to evaluate various expressions by defining the evaluator register machine with the version of the simulator that collects statistics on stack use (Section 5.2.4), and adding an instruction at the evaluator's `print-result` entry point to print the statistics:

```
print-result
  (perform (op print-stack-statistics))    ; added instruction
  (perform
   (op announce-output) (const ";;; EC-Eval value:"))
  ... ; same as before
```

Interactions with the evaluator now look like this:

```
;;; EC-Eval input:
(define (factorial n)
  (if (= n 1) 1 (* (factorial (- n 1)) n)))
(total-pushes = 3 maximum-depth = 3)
;;; EC-Eval value:
ok
;;; EC-Eval input:
(factorial 5)
```

```
(total-pushes = 144 maximum-depth = 28)
;;; EC-Eval value:
120
```

Note that the driver loop of the evaluator reinitializes the stack at the start of each interaction, so that the statistics printed will refer only to stack operations used to evaluate the previous expression.

Exercise 5.26: Use the monitored stack to explore the tail-recursive property of the evaluator (Section 5.4.2). Start the evaluator and define the iterative `factorial` procedure from Section 1.2.1:

```
(define (factorial n)
  (define (iter product counter)
    (if (> counter n)
        product
        (iter (* counter product) (+ counter 1))))
  (iter 1 1))
```

Run the procedure with some small values of n. Record the maximum stack depth and the number of pushes required to compute $n!$ for each of these values.

a. You will find that the maximum depth required to evaluate $n!$ is independent of n. What is that depth?

b. Determine from your data a formula in terms of n for the total number of push operations used in evaluating $n!$ for any $n \geq 1$. Note that the number of operations used is a linear function of n and is thus determined by two constants.

Exercise 5.27: For comparison with Exercise 5.26, explore the behavior of the following procedure for computing factorials recursively:

```
(define (factorial n)
  (if (= n 1) 1 (* (factorial (- n 1)) n)))
```

By running this procedure with the monitored stack, determine, as a function of n, the maximum depth of the stack and the total number of pushes used in evaluating $n!$ for $n \geq 1$. (Again, these functions will be linear.) Summarize your experiments by filling in the following table with the appropriate expressions in terms of n:

	Maximum depth	Number of pushes
Recursive factorial		
Iterative factorial		

The maximum depth is a measure of the amount of space used by the evaluator in carrying out the computation, and the number of pushes correlates well with the time required.

Exercise 5.28: Modify the definition of the evaluator by changing `eval-sequence` as described in Section 5.4.2 so that the evaluator is no longer tail-recursive. Rerun your experiments from Exercise 5.26 and Exercise 5.27 to demonstrate that both versions of the `factorial` procedure now require space that grows linearly with their input.

Exercise 5.29: Monitor the stack operations in the tree-recursive Fibonacci computation:

```
(define (fib n)
  (if (< n 2)
      n
      (+ (fib (- n 1)) (fib (- n 2)))))
```

a. Give a formula in terms of n for the maximum depth of the stack required to compute $\mathrm{Fib}(n)$ for $n \geq 2$. Hint: In Section 1.2.2 we argued that the space used by this process grows linearly with n.

b. Give a formula for the total number of pushes used to compute $\mathrm{Fib}(n)$ for $n \geq 2$. You should find that the number of pushes (which correlates well with the time used) grows exponentially with n. Hint: Let $S(n)$ be the number of pushes used in computing $\mathrm{Fib}(n)$. You should be able to argue that there is a formula that expresses $S(n)$ in terms of $S(n-1)$, $S(n-2)$, and some fixed "overhead" constant k that is independent of n. Give the formula, and say what k is. Then show that $S(n)$ can be expressed as $a \cdot \mathrm{Fib}(n+1) + b$ and give the values of a and b.

Exercise 5.30: Our evaluator currently catches and signals only two kinds of errors—unknown expression types and unknown procedure types. Other errors will take us out of the evaluator read-eval-print loop. When we run the evaluator using the register-machine simulator, these errors are caught by the underlying Scheme system. This is analogous to the computer crash-

ing when a user program makes an error.[32] It is a large project to make a real error system work, but it is well worth the effort to understand what is involved here.

a. Errors that occur in the evaluation process, such as an attempt to access an unbound variable, could be caught by changing the lookup operation to make it return a distinguished condition code, which cannot be a possible value of any user variable. The evaluator can test for this condition code and then do what is necessary to go to `signal-error`. Find all of the places in the evaluator where such a change is necessary and fix them. This is lots of work.

b. Much worse is the problem of handling errors that are signaled by applying primitive procedures, such as an attempt to divide by zero or an attempt to extract the `car` of a symbol. In a professionally written high-quality system, each primitive application is checked for safety as part of the primitive. For example, every call to `car` could first check that the argument is a pair. If the argument is not a pair, the application would return a distinguished condition code to the evaluator, which would then report the failure. We could arrange for this in our register-machine simulator by making each primitive procedure check for applicability and returning an appropriate distinguished condition code on failure. Then the `primitive-apply` code in the evaluator can check for the condition code and

[32] Regrettably, this is the normal state of affairs in conventional compiler-based language systems such as C. In UNIX(tm) the system "dumps core," and in DOS/Windows(tm) it becomes catatonic. The Macintosh(tm) displays a picture of an exploding bomb and offers you the opportunity to reboot the computer—if you're lucky.

go to `signal-error` if necessary. Build this structure and make it work. This is a major project.

5.5 Compilation

The explicit-control evaluator of Section 5.4 is a register machine whose controller interprets Scheme programs. In this section we will see how to run Scheme programs on a register machine whose controller is not a Scheme interpreter.

The explicit-control evaluator machine is universal—it can carry out any computational process that can be described in Scheme. The evaluator's controller orchestrates the use of its data paths to perform the desired computation. Thus, the evaluator's data paths are universal: They are sufficient to perform any computation we desire, given an appropriate controller.[33]

Commercial general-purpose computers are register machines organized around a collection of registers and operations that constitute an efficient and convenient universal set of data paths. The controller for a general-purpose machine is an interpreter for a register-machine language like the one we have been using. This language is called the *native language* of the machine, or simply *machine language*. Programs written in machine language are sequences of instructions that use the machine's data paths. For example, the explicit-control evaluator's instruction sequence can be thought of as a machine-language program for a general-purpose computer rather than as the controller for a specialized interpreter machine.

There are two common strategies for bridging the gap between higher-

[33] This is a theoretical statement. We are not claiming that the evaluator's data paths are a particularly convenient or efficient set of data paths for a general-purpose computer. For example, they are not very good for implementing high-performance floating-point calculations or calculations that intensively manipulate bit vectors.

level languages and register-machine languages. The explicit-control evaluator illustrates the strategy of interpretation. An interpreter written in the native language of a machine configures the machine to execute programs written in a language (called the *source language*) that may differ from the native language of the machine performing the evaluation. The primitive procedures of the source language are implemented as a library of subroutines written in the native language of the given machine. A program to be interpreted (called the *source program*) is represented as a data structure. The interpreter traverses this data structure, analyzing the source program. As it does so, it simulates the intended behavior of the source program by calling appropriate primitive subroutines from the library.

In this section, we explore the alternative strategy of *compilation*. A compiler for a given source language and machine translates a source program into an equivalent program (called the *object program*) written in the machine's native language. The compiler that we implement in this section translates programs written in Scheme into sequences of instructions to be executed using the explicit-control evaluator machine's data paths.[34]

Compared with interpretation, compilation can provide a great increase in the efficiency of program execution, as we will explain below in the overview of the compiler. On the other hand, an interpreter provides a more powerful environment for interactive program development and debugging, because the source program being executed is available at run time to be examined and modified. In addition, because the entire library of primitives is present, new

[34] Actually, the machine that runs compiled code can be simpler than the interpreter machine, because we won't use the `exp` and `unev` registers. The interpreter used these to hold pieces of unevaluated expressions. With the compiler, however, these expressions get built into the compiled code that the register machine will run. For the same reason, we don't need the machine operations that deal with expression syntax. But compiled code will use a few additional machine operations (to represent compiled procedure objects) that didn't appear in the explicit-control evaluator machine.

programs can be constructed and added to the system during debugging.

In view of the complementary advantages of compilation and interpretation, modern program-development environments pursue a mixed strategy. Lisp interpreters are generally organized so that interpreted procedures and compiled procedures can call each other. This enables a programmer to compile those parts of a program that are assumed to be debugged, thus gaining the efficiency advantage of compilation, while retaining the interpretive mode of execution for those parts of the program that are in the flux of interactive development and debugging. In Section 5.5.7, after we have implemented the compiler, we will show how to interface it with our interpreter to produce an integrated interpreter-compiler development system.

An overview of the compiler

Our compiler is much like our interpreter, both in its structure and in the function it performs. Accordingly, the mechanisms used by the compiler for analyzing expressions will be similar to those used by the interpreter. Moreover, to make it easy to interface compiled and interpreted code, we will design the compiler to generate code that obeys the same conventions of register usage as the interpreter: The environment will be kept in the `env` register, argument lists will be accumulated in `argl`, a procedure to be applied will be in `proc`, procedures will return their answers in `val`, and the location to which a procedure should return will be kept in `continue`. In general, the compiler translates a source program into an object program that performs essentially the same register operations as would the interpreter in evaluating the same source program.

This description suggests a strategy for implementing a rudimentary compiler: We traverse the expression in the same way the interpreter does. When we encounter a register instruction that the interpreter would perform in evaluating the expression, we do not execute the instruction but instead accumu-

late it into a sequence. The resulting sequence of instructions will be the object code. Observe the efficiency advantage of compilation over interpretation. Each time the interpreter evaluates an expression—for example, `(f 84 96)`—it performs the work of classifying the expression (discovering that this is a procedure application) and testing for the end of the operand list (discovering that there are two operands). With a compiler, the expression is analyzed only once, when the instruction sequence is generated at compile time. The object code produced by the compiler contains only the instructions that evaluate the operator and the two operands, assemble the argument list, and apply the procedure (in `proc`) to the arguments (in `argl`).

This is the same kind of optimization we implemented in the analyzing evaluator of Section 4.1.7. But there are further opportunities to gain efficiency in compiled code. As the interpreter runs, it follows a process that must be applicable to any expression in the language. In contrast, a given segment of compiled code is meant to execute some particular expression. This can make a big difference, for example in the use of the stack to save registers. When the interpreter evaluates an expression, it must be prepared for any contingency. Before evaluating a subexpression, the interpreter saves all registers that will be needed later, because the subexpression might require an arbitrary evaluation. A compiler, on the other hand, can exploit the structure of the particular expression it is processing to generate code that avoids unnecessary stack operations.

As a case in point, consider the combination `(f 84 96)`. Before the interpreter evaluates the operator of the combination, it prepares for this evaluation by saving the registers containing the operands and the environment, whose values will be needed later. The interpreter then evaluates the operator to obtain the result in `val`, restores the saved registers, and finally moves the result from `val` to `proc`. However, in the particular expression we are dealing with, the operator is the symbol `f`, whose evaluation is accomplished

by the machine operation `lookup-variable-value`, which does not alter any registers. The compiler that we implement in this section will take advantage of this fact and generate code that evaluates the operator using the instruction

```
(assign proc (op lookup-variable-value)
             (const f)
             (reg env))
```

This code not only avoids the unnecessary saves and restores but also assigns the value of the lookup directly to `proc`, whereas the interpreter would obtain the result in `val` and then move this to `proc`.

A compiler can also optimize access to the environment. Having analyzed the code, the compiler can in many cases know in which frame a particular variable will be located and access that frame directly, rather than performing the `lookup-variable-value` search. We will discuss how to implement such variable access in Section 5.5.6. Until then, however, we will focus on the kind of register and stack optimizations described above. There are many other optimizations that can be performed by a compiler, such as coding primitive operations "in line" instead of using a general `apply` mechanism (see Exercise 5.38); but we will not emphasize these here. Our main goal in this section is to illustrate the compilation process in a simplified (but still interesting) context.

5.5.1 Structure of the Compiler

In Section 4.1.7 we modified our original metacircular interpreter to separate analysis from execution. We analyzed each expression to produce an execution procedure that took an environment as argument and performed the required operations. In our compiler, we will do essentially the same analysis. Instead of producing execution procedures, however, we will generate

sequences of instructions to be run by our register machine.

The procedure `compile` is the top-level dispatch in the compiler. It corresponds to the `eval` procedure of Section 4.1.1, the `analyze` procedure of Section 4.1.7, and the `eval-dispatch` entry point of the explicit-control-evaluator in Section 5.4.1. The compiler, like the interpreters, uses the expression-syntax procedures defined in Section 4.1.2.[35] `compile` performs a case analysis on the syntactic type of the expression to be compiled. For each type of expression, it dispatches to a specialized *code generator*:

```
(define (compile exp target linkage)
  (cond ((self-evaluating? exp)
         (compile-self-evaluating exp target linkage))
        ((quoted? exp) (compile-quoted exp target linkage))
        ((variable? exp)
         (compile-variable exp target linkage))
        ((assignment? exp)
         (compile-assignment exp target linkage))
        ((definition? exp)
         (compile-definition exp target linkage))
        ((if? exp) (compile-if exp target linkage))
        ((lambda? exp) (compile-lambda exp target linkage))
        ((begin? exp)
         (compile-sequence
          (begin-actions exp) target linkage))
        ((cond? exp)
         (compile (cond->if exp) target linkage))
```

[35] Notice, however, that our compiler is a Scheme program, and the syntax procedures that it uses to manipulate expressions are the actual Scheme procedures used with the metacircular evaluator. For the explicit-control evaluator, in contrast, we assumed that equivalent syntax operations were available as operations for the register machine. (Of course, when we simulated the register machine in Scheme, we used the actual Scheme procedures in our register machine simulation.)

```
        ((application? exp)
         (compile-application exp target linkage))
        (else
         (error "Unknown expression type: COMPILE" exp))))
```

Targets and linkages

`compile` and the code generators that it calls take two arguments in addition to the expression to compile. There is a *target*, which specifies the register in which the compiled code is to return the value of the expression. There is also a *linkage descriptor*, which describes how the code resulting from the compilation of the expression should proceed when it has finished its execution. The linkage descriptor can require that the code do one of the following three things:

- continue at the next instruction in sequence (this is specified by the linkage descriptor `next`),
- return from the procedure being compiled (this is specified by the linkage descriptor `return`), or
- jump to a named entry point (this is specified by using the designated label as the linkage descriptor).

For example, compiling the expression `5` (which is self-evaluating) with a target of the `val` register and a linkage of `next` should produce the instruction

```
(assign val (const 5))
```

Compiling the same expression with a linkage of `return` should produce the instructions

```
(assign val (const 5))
(goto (reg continue))
```

In the first case, execution will continue with the next instruction in the sequence. In the second case, we will return from a procedure call. In both cases, the value of the expression will be placed into the target `val` register.

Instruction sequences and stack usage

Each code generator returns an *instruction sequence* containing the object code it has generated for the expression. Code generation for a compound expression is accomplished by combining the output from simpler code generators for component expressions, just as evaluation of a compound expression is accomplished by evaluating the component expressions.

The simplest method for combining instruction sequences is a procedure called `append-instruction-sequences`. It takes as arguments any number of instruction sequences that are to be executed sequentially; it appends them and returns the combined sequence. That is, if $\langle seq_1 \rangle$ and $\langle seq_2 \rangle$ are sequences of instructions, then evaluating

`(append-instruction-sequences` $\langle seq_1 \rangle$ $\langle seq_2 \rangle$`)`

produces the sequence

$\langle seq_1 \rangle$
$\langle seq_2 \rangle$

Whenever registers might need to be saved, the compiler's code generators use `preserving`, which is a more subtle method for combining instruction sequences. `preserving` takes three arguments: a set of registers and two instruction sequences that are to be executed sequentially. It appends the sequences in such a way that the contents of each register in the set is preserved over the execution of the first sequence, if this is needed for the execution of the second sequence. That is, if the first sequence modifies the register and the second sequence actually needs the register's original contents, then `preserving` wraps a `save` and a `restore` of the register around the

first sequence before appending the sequences. Otherwise, `preserving` simply returns the appended instruction sequences. Thus, for example,

`(preserving (list` ⟨*reg*$_1$⟩ ⟨*reg*$_2$⟩`)` ⟨*seq*$_1$⟩ ⟨*seq*$_2$⟩`)`

produces one of the following four sequences of instructions, depending on how ⟨*seq*$_1$⟩ and ⟨*seq*$_2$⟩ use ⟨*reg*$_1$⟩ and ⟨*reg*$_2$⟩:

⟨*seq*$_1$⟩
⟨*seq*$_2$⟩
	`(save` ⟨*reg*$_1$⟩`)`
	⟨*seq*$_1$⟩
	`(restore` ⟨*reg*$_1$⟩`)`
	⟨*seq*$_2$⟩
		`(save` ⟨*reg*$_2$⟩`)`
		⟨*seq*$_1$⟩
		`(restore` ⟨*reg*$_2$⟩`)`
		⟨*seq*$_2$⟩
			`(save` ⟨*reg*$_2$⟩`)`
			`(save` ⟨*reg*$_1$⟩`)`
			⟨*seq*$_1$⟩
			`(restore` ⟨*reg*$_1$⟩`)`
			`(restore` ⟨*reg*$_2$⟩`)`
			⟨*seq*$_2$⟩

By using `preserving` to combine instruction sequences the compiler avoids unnecessary stack operations. This also isolates the details of whether or not to generate `save` and `restore` instructions within the `preserving` procedure, separating them from the concerns that arise in writing each of the individual code generators. In fact no `save` or `restore` instructions are explicitly produced by the code generators.

In principle, we could represent an instruction sequence simply as a list of instructions. `append-instruction-sequences` could then combine instruction sequences by performing an ordinary list `append`. However, `preserving` would then be a complex operation, because it would have to analyze each instruction sequence to determine how the sequence uses its registers. `preserving` would be inefficient as well as complex, because it would have to analyze each of its instruction sequence arguments, even though these sequences might themselves have been constructed by calls to `preserving`, in which case their parts would have already been analyzed. To avoid such repetitious analysis we will associate with each instruc-

tion sequence some information about its register use. When we construct a basic instruction sequence we will provide this information explicitly, and the procedures that combine instruction sequences will derive register-use information for the combined sequence from the information associated with the component sequences.

An instruction sequence will contain three pieces of information:

- the set of registers that must be initialized before the instructions in the sequence are executed (these registers are said to be *needed* by the sequence),
- the set of registers whose values are modified by the instructions in the sequence, and
- the actual instructions (also called *statements*) in the sequence.

We will represent an instruction sequence as a list of its three parts. The constructor for instruction sequences is thus

```
(define (make-instruction-sequence
         needs modifies statements)
  (list needs modifies statements))
```

For example, the two-instruction sequence that looks up the value of the variable `x` in the current environment, assigns the result to `val`, and then returns, requires registers `env` and `continue` to have been initialized, and modifies register `val`. This sequence would therefore be constructed as

```
(make-instruction-sequence
 '(env continue)
 '(val)
 '((assign val
           (op lookup-variable-value) (const x) (reg env))
   (goto (reg continue))))
```

We sometimes need to construct an instruction sequence with no statements:

```
(define (empty-instruction-sequence)
  (make-instruction-sequence '() '() '()))
```

The procedures for combining instruction sequences are shown in Section 5.5.4.

Exercise 5.31: In evaluating a procedure application, the explicit-control evaluator always saves and restores the `env` register around the evaluation of the operator, saves and restores `env` around the evaluation of each operand (except the final one), saves and restores `argl` around the evaluation of each operand, and saves and restores `proc` around the evaluation of the operand sequence. For each of the following combinations, say which of these `save` and `restore` operations are superfluous and thus could be eliminated by the compiler's `preserving` mechanism:

```
(f 'x 'y)
((f) 'x 'y)
(f (g 'x) y)
(f (g 'x) 'y)
```

Exercise 5.32: Using the `preserving` mechanism, the compiler will avoid saving and restoring `env` around the evaluation of the operator of a combination in the case where the operator is a symbol. We could also build such optimizations into the evaluator. Indeed, the explicit-control evaluator of Section 5.4 already performs a similar optimization, by treating combinations with no operands as a special case.

a. Extend the explicit-control evaluator to recognize as a separate class of expressions combinations whose operator is a symbol, and to take advantage of this fact in evaluating such expressions.

b. Alyssa P. Hacker suggests that by extending the evaluator to recognize more and more special cases we could incorporate all the compiler's optimizations, and that this would eliminate the advantage of compilation altogether. What do you think of this idea?

5.5.2 Compiling Expressions

In this section and the next we implement the code generators to which the `compile` procedure dispatches.

Compiling linkage code

In general, the output of each code generator will end with instructions—generated by the procedure `compile-linkage`—that implement the required linkage. If the linkage is `return` then we must generate the instruction `(goto (reg continue))`. This needs the `continue` register and does not modify any registers. If the linkage is `next`, then we needn't include any additional instructions. Otherwise, the linkage is a label, and we generate a `goto` to that label, an instruction that does not need or modify any registers.[36]

[36] This procedure uses a feature of Lisp called *backquote* (or *quasiquote*) that is handy for constructing lists. Preceding a list with a backquote symbol is much like quoting it, except that anything in the list that is flagged with a comma is evaluated.

For example, if the value of `linkage` is the symbol `branch25`, then the expression

```
`((goto (label ,linkage)))
```

```
(define (compile-linkage linkage)
  (cond ((eq? linkage 'return)
         (make-instruction-sequence '(continue) '()
          '((goto (reg continue)))))
        ((eq? linkage 'next)
         (empty-instruction-sequence))
        (else
         (make-instruction-sequence '() '()
          `((goto (label ,linkage)))))))
```

The linkage code is appended to an instruction sequence by `preserving` the `continue` register, since a `return` linkage will require the `continue` register: If the given instruction sequence modifies `continue` and the linkage code needs it, `continue` will be saved and restored.

```
(define (end-with-linkage linkage instruction-sequence)
  (preserving '(continue)
   instruction-sequence
   (compile-linkage linkage)))
```

Compiling simple expressions

The code generators for self-evaluating expressions, quotations, and variables construct instruction sequences that assign the required value to the target

---

evaluates to the list

```
((goto (label branch25)))
```

Similarly, if the value of `x` is the list `(a b c)`, then

```
`(1 2 ,(car x))
```

evaluates to the list

```
(1 2 a).
```

register and then proceed as specified by the linkage descriptor.

```
(define (compile-self-evaluating exp target linkage)
  (end-with-linkage linkage
   (make-instruction-sequence '() (list target)
    `((assign ,target (const ,exp))))))
(define (compile-quoted exp target linkage)
  (end-with-linkage linkage
   (make-instruction-sequence '() (list target)
    `((assign ,target (const ,(text-of-quotation exp)))))))
(define (compile-variable exp target linkage)
  (end-with-linkage linkage
   (make-instruction-sequence '(env) (list target)
    `((assign ,target
              (op lookup-variable-value)
              (const ,exp)
              (reg env))))))
```

All these assignment instructions modify the target register, and the one that looks up a variable needs the `env` register.

Assignments and definitions are handled much as they are in the interpreter. We recursively generate code that computes the value to be assigned to the variable, and append to it a two-instruction sequence that actually sets or defines the variable and assigns the value of the whole expression (the symbol `ok`) to the target register. The recursive compilation has target `val` and linkage `next` so that the code will put its result into `val` and continue with the code that is appended after it. The appending is done preserving `env`, since the environment is needed for setting or defining the variable and the code for the variable value could be the compilation of a complex expression that might modify the registers in arbitrary ways.

```
(define (compile-assignment exp target linkage)
  (let ((var (assignment-variable exp))
```

```
        (get-value-code
         (compile (assignment-value exp) 'val 'next)))
    (end-with-linkage linkage
     (preserving '(env)
      get-value-code
      (make-instruction-sequence '(env val) (list target)
       `((perform (op set-variable-value!)
                  (const ,var)
                  (reg val)
                  (reg env))
         (assign ,target (const ok)))))))))
(define (compile-definition exp target linkage)
  (let ((var (definition-variable exp))
        (get-value-code
         (compile (definition-value exp) 'val 'next)))
    (end-with-linkage linkage
     (preserving '(env)
      get-value-code
      (make-instruction-sequence '(env val) (list target)
       `((perform (op define-variable!)
                  (const ,var)
                  (reg val)
                  (reg env))
         (assign ,target (const ok)))))))))
```

The appended two-instruction sequence requires `env` and `val` and modifies the target. Note that although we preserve `env` for this sequence, we do not preserve `val`, because the `get-value-code` is designed to explicitly place its result in `val` for use by this sequence. (In fact, if we did preserve `val`, we would have a bug, because this would cause the previous contents of `val` to be restored right after the `get-value-code` is run.)

Compiling conditional expressions

The code for an `if` expression compiled with a given target and linkage has the form

```
⟨compilation of predicate, target val, linkage next⟩
 (test (op false?) (reg val))
 (branch (label false-branch))
true-branch
 ⟨compilation of consequent with given target
  and given linkage or after-if⟩
false-branch
 ⟨compilation of alternative with given target and linkage⟩
after-if
```

To generate this code, we compile the predicate, consequent, and alternative, and combine the resulting code with instructions to test the predicate result and with newly generated labels to mark the true and false branches and the end of the conditional.[37] In this arrangement of code, we must branch around

[37] We can't just use the labels `true-branch`, `false-branch`, and `after-if` as shown above, because there might be more than one `if` in the program. The compiler uses the procedure `make-label` to generate labels. `make-label` takes a symbol as argument and returns a new symbol that begins with the given symbol. For example, successive calls to `(make-label 'a)` would return `a1`, `a2`, and so on. `make-label` can be implemented similarly to the generation of unique variable names in the query language, as follows:

```
(define label-counter 0)
(define (new-label-number)
  (set! label-counter (+ 1 label-counter))
  label-counter)
(define (make-label name)
  (string->symbol
    (string-append (symbol->string name)
                   (number->string (new-label-number)))))
```

the true branch if the test is false. The only slight complication is in how the linkage for the true branch should be handled. If the linkage for the conditional is `return` or a label, then the true and false branches will both use this same linkage. If the linkage is `next`, the true branch ends with a jump around the code for the false branch to the label at the end of the conditional.

```
(define (compile-if exp target linkage)
  (let ((t-branch (make-label 'true-branch))
        (f-branch (make-label 'false-branch))
        (after-if (make-label 'after-if)))
    (let ((consequent-linkage
           (if (eq? linkage 'next) after-if linkage)))
      (let ((p-code (compile (if-predicate exp) 'val 'next))
            (c-code
             (compile
              (if-consequent exp) target
                                  consequent-linkage))
            (a-code
             (compile (if-alternative exp) target linkage)))
        (preserving '(env continue)
         p-code
         (append-instruction-sequences
          (make-instruction-sequence '(val) '()
           `((test (op false?) (reg val))
             (branch (label ,f-branch))))
          (parallel-instruction-sequences
           (append-instruction-sequences t-branch c-code)
           (append-instruction-sequences f-branch a-code))
          after-if))))))
```

`env` is preserved around the predicate code because it could be needed by the true and false branches, and `continue` is preserved because it could

be needed by the linkage code in those branches. The code for the true and false branches (which are not executed sequentially) is appended using a special combiner `parallel-instruction-sequences` described in Section 5.5.4.

Note that `cond` is a derived expression, so all that the compiler needs to do handle it is to apply the `cond->if` transformer (from Section 4.1.2) and compile the resulting `if` expression.

Compiling sequences

The compilation of sequences (from procedure bodies or explicit `begin` expressions) parallels their evaluation. Each expression of the sequence is compiled—the last expression with the linkage specified for the sequence, and the other expressions with linkage `next` (to execute the rest of the sequence). The instruction sequences for the individual expressions are appended to form a single instruction sequence, such that `env` (needed for the rest of the sequence) and `continue` (possibly needed for the linkage at the end of the sequence) are preserved.

```
(define (compile-sequence seq target linkage)
  (if (last-exp? seq)
      (compile (first-exp seq) target linkage)
      (preserving
       '(env continue)
       (compile (first-exp seq) target 'next)
       (compile-sequence (rest-exps seq) target linkage))))
```

Compiling `lambda` expressions

`lambda` expressions construct procedures. The object code for a `lambda` expression must have the form

```
⟨construct procedure object and assign it to target register
⟨linkage⟩
```

When we compile the `lambda` expression, we also generate the code for the procedure body. Although the body won't be executed at the time of procedure construction, it is convenient to insert it into the object code right after the code for the `lambda`. If the linkage for the `lambda` expression is a label or `return`, this is fine. But if the linkage is `next`, we will need to skip around the code for the procedure body by using a linkage that jumps to a label that is inserted after the body. The object code thus has the form

```
⟨construct procedure object and assign it to target register
 ⟨code for given linkage⟩ or (goto (label after-lambda))
 ⟨compilation of procedure body⟩
after-lambda
```

`compile-lambda` generates the code for constructing the procedure object followed by the code for the procedure body. The procedure object will be constructed at run time by combining the current environment (the environment at the point of definition) with the entry point to the compiled procedure body (a newly generated label).[38]

```
(define (compile-lambda exp target linkage)
  (let ((proc-entry (make-label 'entry))
```

[38] We need machine operations to implement a data structure for representing compiled procedures, analogous to the structure for compound procedures described in Section 4.1.3:

```
(define (make-compiled-procedure entry env)
  (list 'compiled-procedure entry env))
(define (compiled-procedure? proc)
  (tagged-list? proc 'compiled-procedure))
(define (compiled-procedure-entry c-proc) (cadr c-proc))
(define (compiled-procedure-env c-proc) (caddr c-proc))
```

```
      (after-lambda (make-label 'after-lambda)))
  (let ((lambda-linkage
         (if (eq? linkage 'next) after-lambda linkage)))
    (append-instruction-sequences
     (tack-on-instruction-sequence
      (end-with-linkage lambda-linkage
       (make-instruction-sequence '(env) (list target)
        `((assign ,target
                  (op make-compiled-procedure)
                  (label ,proc-entry)
                  (reg env)))))
      (compile-lambda-body exp proc-entry))
     after-lambda))))
```

`compile-lambda` uses the special combiner `tack-on-instruction-sequence` rather than `append-instruction-sequences` (Section 5.5.4) to append the procedure body to the `lambda` expression code, because the body is not part of the sequence of instructions that will be executed when the combined sequence is entered; rather, it is in the sequence only because that was a convenient place to put it.

`compile-lambda-body` constructs the code for the body of the procedure. This code begins with a label for the entry point. Next come instructions that will cause the run-time evaluation environment to switch to the correct environment for evaluating the procedure body—namely, the definition environment of the procedure, extended to include the bindings of the formal parameters to the arguments with which the procedure is called. After this comes the code for the sequence of expressions that makes up the procedure body. The sequence is compiled with linkage `return` and target `val` so that it will end by returning from the procedure with the procedure result in `val`.

```
(define (compile-lambda-body exp proc-entry)
  (let ((formals (lambda-parameters exp)))
```

```
(append-instruction-sequences
 (make-instruction-sequence '(env proc argl) '(env)
  `(,proc-entry
    (assign env
            (op compiled-procedure-env)
            (reg proc))
    (assign env
            (op extend-environment)
            (const ,formals)
            (reg argl)
            (reg env))))
 (compile-sequence (lambda-body exp) 'val 'return))))
```

5.5.3 Compiling Combinations

The essence of the compilation process is the compilation of procedure applications. The code for a combination compiled with a given target and linkage has the form

⟨*compilation of operator, target* proc, *linkage* next⟩
⟨*evaluate operands and construct argument list in* argl⟩
⟨*compilation of procedure call with given target and linkage*⟩

The registers `env`, `proc`, and `argl` may have to be saved and restored during evaluation of the operator and operands. Note that this is the only place in the compiler where a target other than `val` is specified.

The required code is generated by `compile-application`. This recursively compiles the operator, to produce code that puts the procedure to be applied into `proc`, and compiles the operands, to produce code that evaluates the individual operands of the application. The instruction sequences for the operands are combined (by `construct-arglist`) with code

that constructs the list of arguments in `argl`, and the resulting argument-list code is combined with the procedure code and the code that performs the procedure call (produced by `compile-procedure-call`). In appending the code sequences, the `env` register must be preserved around the evaluation of the operator (since evaluating the operator might modify `env`, which will be needed to evaluate the operands), and the `proc` register must be preserved around the construction of the argument list (since evaluating the operands might modify `proc`, which will be needed for the actual procedure application). `continue` must also be preserved throughout, since it is needed for the linkage in the procedure call.

```
(define (compile-application exp target linkage)
  (let ((proc-code (compile (operator exp) 'proc 'next))
        (operand-codes
         (map (lambda
                (operand) (compile operand 'val 'next))
              (operands exp))))
    (preserving '(env continue)
     proc-code
     (preserving '(proc continue)
      (construct-arglist operand-codes)
      (compile-procedure-call target linkage)))))
```

The code to construct the argument list will evaluate each operand into `val` and then `cons` that value onto the argument list being accumulated in `argl`. Since we `cons` the arguments onto `argl` in sequence, we must start with the last argument and end with the first, so that the arguments will appear in order from first to last in the resulting list. Rather than waste an instruction by initializing `argl` to the empty list to set up for this sequence of evaluations, we make the first code sequence construct the initial `argl`. The general form of the argument-list construction is thus as follows:

⟨*compilation of last operand, targeted to* val⟩

```
(assign argl (op list) (reg val))
⟨compilation of next operand, targeted to val⟩
(assign argl (op cons) (reg val) (reg argl))
...
⟨compilation of first operand, targeted to val⟩
(assign argl (op cons) (reg val) (reg argl))
```

`argl` must be preserved around each operand evaluation except the first (so that arguments accumulated so far won't be lost), and `env` must be preserved around each operand evaluation except the last (for use by subsequent operand evaluations).

Compiling this argument code is a bit tricky, because of the special treatment of the first operand to be evaluated and the need to preserve `argl` and `env` in different places. The `construct-arglist` procedure takes as arguments the code that evaluates the individual operands. If there are no operands at all, it simply emits the instruction

```
(assign argl (const ()))
```

Otherwise, `construct-arglist` creates code that initializes `argl` with the last argument, and appends code that evaluates the rest of the arguments and adjoins them to `argl` in succession. In order to process the arguments from last to first, we must reverse the list of operand code sequences from the order supplied by `compile-application`.

```
(define (construct-arglist operand-codes)
  (let ((operand-codes (reverse operand-codes)))
    (if (null? operand-codes)
        (make-instruction-sequence '() '(argl)
         '((assign argl (const ()))))
        (let ((code-to-get-last-arg
               (append-instruction-sequences
                (car operand-codes)
                (make-instruction-sequence '(val) '(argl)
```

```
                '((assign argl (op list) (reg val)))))))
          (if (null? (cdr operand-codes))
              code-to-get-last-arg
              (preserving '(env)
               code-to-get-last-arg
               (code-to-get-rest-args
                (cdr operand-codes))))))))

(define (code-to-get-rest-args operand-codes)
  (let ((code-for-next-arg
         (preserving '(argl)
          (car operand-codes)
          (make-instruction-sequence '(val argl) '(argl)
           '((assign argl
              (op cons) (reg val) (reg argl)))))))
    (if (null? (cdr operand-codes))
        code-for-next-arg
        (preserving '(env)
         code-for-next-arg
         (code-to-get-rest-args (cdr operand-codes))))))
```

Applying procedures

After evaluating the elements of a combination, the compiled code must apply the procedure in `proc` to the arguments in `argl`. The code performs essentially the same dispatch as the `apply` procedure in the metacircular evaluator of Section 4.1.1 or the `apply-dispatch` entry point in the explicit-control evaluator of Section 5.4.1. It checks whether the procedure to be applied is a primitive procedure or a compiled procedure. For a primitive procedure, it uses `apply-primitive-procedure`; we will see shortly how it handles compiled procedures. The procedure-application code has the following form:

```
(test (op primitive-procedure?) (reg proc))
 (branch (label primitive-branch))
compiled-branch
 ⟨code to apply compiled procedure with given target
  and appropriate linkage⟩
primitive-branch
 (assign ⟨target⟩
         (op apply-primitive-procedure)
         (reg proc)
         (reg argl))
 ⟨linkage⟩
after-call
```

Observe that the compiled branch must skip around the primitive branch. Therefore, if the linkage for the original procedure call was `next`, the compound branch must use a linkage that jumps to a label that is inserted after the primitive branch. (This is similar to the linkage used for the true branch in `compile-if`.)

```
(define (compile-procedure-call target linkage)
  (let ((primitive-branch (make-label 'primitive-branch))
        (compiled-branch (make-label 'compiled-branch))
        (after-call (make-label 'after-call)))

    (let ((compiled-linkage
           (if (eq? linkage 'next) after-call linkage)))
      (append-instruction-sequences
       (make-instruction-sequence '(proc) '()
        `((test (op primitive-procedure?) (reg proc))
          (branch (label ,primitive-branch))))
       (parallel-instruction-sequences
        (append-instruction-sequences
         compiled-branch
         (compile-proc-appl target compiled-linkage))
```

```
      (append-instruction-sequences
       primitive-branch
       (end-with-linkage linkage
        (make-instruction-sequence '(proc argl)
                                   (list target)
         `((assign ,target
                   (op apply-primitive-procedure)
                   (reg proc)
                   (reg argl)))))))
    after-call))))
```

The primitive and compound branches, like the true and false branches in `compile-if`, are appended using `parallel-instruction-sequences` rather than the ordinary `append-instruction-sequences`, because they will not be executed sequentially.

Applying compiled procedures

The code that handles procedure application is the most subtle part of the compiler, even though the instruction sequences it generates are very short. A compiled procedure (as constructed by `compile-lambda`) has an entry point, which is a label that designates where the code for the procedure starts. The code at this entry point computes a result in `val` and returns by executing the instruction `(goto (reg continue))`. Thus, we might expect the code for a compiled-procedure application (to be generated by `compile-proc-appl`) with a given target and linkage to look like this if the linkage is a label

```
(assign continue (label proc-return))
 (assign val (op compiled-procedure-entry) (reg proc))
 (goto (reg val))
proc-return
 (assign ⟨target⟩ (reg val))    ; included if target is not val
```

```
 (goto (label ⟨linkage⟩))        ; linkage code
```

or like this if the linkage is `return`.

```
(save continue)
 (assign continue (label proc-return))
 (assign val (op compiled-procedure-entry) (reg proc))
 (goto (reg val))
proc-return
 (assign ⟨target⟩ (reg val))    ; included if target is not val
 (restore continue)
 (goto (reg continue))           ; linkage code
```

This code sets up `continue` so that the procedure will return to a label `proc-return` and jumps to the procedure's entry point. The code at `proc-return` transfers the procedure's result from `val` to the target register (if necessary) and then jumps to the location specified by the linkage. (The linkage is always `return` or a label, because `compile-procedure-call` replaces a `next` linkage for the compound-procedure branch by an `after-call` label.)

In fact, if the target is not `val`, that is exactly the code our compiler will generate.[39] Usually, however, the target is `val` (the only time the compiler specifies a different register is when targeting the evaluation of an operator to `proc`), so the procedure result is put directly into the target register and there is no need to return to a special location that copies it. Instead, we simplify the code by setting up `continue` so that the procedure will "return" directly to the place specified by the caller's linkage:

```
⟨set up continue for linkage⟩
(assign val (op compiled-procedure-entry) (reg proc))
```

[39] Actually, we signal an error when the target is not `val` and the linkage is `return`, since the only place we request `return` linkages is in compiling procedures, and our convention is that procedures return their values in `val`.

```
(goto (reg val))
```

If the linkage is a label, we set up `continue` so that the procedure will return to that label. (That is, the `(goto (reg continue))` the procedure ends with becomes equivalent to the `(goto (label ⟨linkage⟩))` at `proc-return` above.)

```
(assign continue (label ⟨linkage⟩))
(assign val (op compiled-procedure-entry) (reg proc))
(goto (reg val))
```

If the linkage is `return`, we don't need to set up `continue` at all: It already holds the desired location. (That is, the `(goto (reg continue))` the procedure ends with goes directly to the place where the `(goto (reg continue))` at `proc-return` would have gone.)

```
(assign val (op compiled-procedure-entry) (reg proc))
(goto (reg val))
```

With this implementation of the `return` linkage, the compiler generates tail-recursive code. Calling a procedure as the final step in a procedure body does a direct transfer, without saving any information on the stack.

Suppose instead that we had handled the case of a procedure call with a linkage of `return` and a target of `val` as shown above for a non-`val` target. This would destroy tail recursion. Our system would still give the same value for any expression. But each time we called a procedure, we would save `continue` and return after the call to undo the (useless) save. These extra saves would accumulate during a nest of procedure calls.[40]

[40] Making a compiler generate tail-recursive code might seem like a straightforward idea. But most compilers for common languages, including C and Pascal, do not do this, and therefore these languages cannot represent iterative processes in terms of procedure call alone. The difficulty with tail recursion in these languages is that their implementations use the stack to store procedure arguments and local variables as well as return addresses. The Scheme im-

`compile-proc-appl` generates the above procedure-application code by considering four cases, depending on whether the target for the call is `val` and whether the linkage is `return`. Observe that the instruction sequences are declared to modify all the registers, since executing the procedure body can change the registers in arbitrary ways.[41] Also note that the code sequence for the case with target `val` and linkage `return` is declared to need `continue`: Even though `continue` is not explicitly used in the two-instruction sequence, we must be sure that `continue` will have the correct value when we enter the compiled procedure.

```
(define (compile-proc-appl target linkage)
  (cond ((and (eq? target 'val) (not (eq? linkage 'return)))
         (make-instruction-sequence '(proc) all-regs
           `((assign continue (label ,linkage))
             (assign val (op compiled-procedure-entry)
                         (reg proc))
             (goto (reg val)))))
        ((and (not (eq? target 'val))
              (not (eq? linkage 'return)))
         (let ((proc-return (make-label 'proc-return)))
           (make-instruction-sequence '(proc) all-regs
```

plementations described in this book store arguments and variables in memory to be garbage-collected. The reason for using the stack for variables and arguments is that it avoids the need for garbage collection in languages that would not otherwise require it, and is generally believed to be more efficient. Sophisticated Lisp compilers can, in fact, use the stack for arguments without destroying tail recursion. (See Hanson 1990 for a description.) There is also some debate about whether stack allocation is actually more efficient than garbage collection in the first place, but the details seem to hinge on fine points of computer architecture. (See Appel 1987 and Miller and Rozas 1994 for opposing views on this issue.)

[41] The variable `all-regs` is bound to the list of names of all the registers:

```
(define all-regs '(env proc val argl continue))
```

```
        `((assign continue (label ,proc-return))
          (assign val (op compiled-procedure-entry)
                      (reg proc))
          (goto (reg val))
          ,proc-return
          (assign ,target (reg val))
          (goto (label ,linkage))))))
    ((and (eq? target 'val) (eq? linkage 'return))
     (make-instruction-sequence
      '(proc continue)
      all-regs
      '((assign val (op compiled-procedure-entry)
                    (reg proc))
        (goto (reg val)))))
    ((and (not (eq? target 'val))
          (eq? linkage 'return))
     (error "return linkage, target not val: COMPILE"
            target))))
```

5.5.4 Combining Instruction Sequences

This section describes the details on how instruction sequences are represented and combined. Recall from Section 5.5.1 that an instruction sequence is represented as a list of the registers needed, the registers modified, and the actual instructions. We will also consider a label (symbol) to be a degenerate case of an instruction sequence, which doesn't need or modify any registers. So to determine the registers needed and modified by instruction sequences we use the selectors

```
(define (registers-needed s)
  (if (symbol? s) '() (car s)))
(define (registers-modified s)
  (if (symbol? s) '() (cadr s)))
```

```
(define (statements s)
  (if (symbol? s) (list s) (caddr s)))
```

and to determine whether a given sequence needs or modifies a given register we use the predicates

```
(define (needs-register? seq reg)
  (memq reg (registers-needed seq)))
(define (modifies-register? seq reg)
  (memq reg (registers-modified seq)))
```

In terms of these predicates and selectors, we can implement the various instruction sequence combiners used throughout the compiler.

The basic combiner is `append-instruction-sequences`. This takes as arguments an arbitrary number of instruction sequences that are to be executed sequentially and returns an instruction sequence whose statements are the statements of all the sequences appended together. The subtle point is to determine the registers that are needed and modified by the resulting sequence. It modifies those registers that are modified by any of the sequences; it needs those registers that must be initialized before the first sequence can be run (the registers needed by the first sequence), together with those registers needed by any of the other sequences that are not initialized (modified) by sequences preceding it.

The sequences are appended two at a time by `append-2-sequences`. This takes two instruction sequences `seq1` and `seq2` and returns the instruction sequence whose statements are the statements of `seq1` followed by the statements of `seq2`, whose modified registers are those registers that are modified by either `seq1` or `seq2`, and whose needed registers are the registers needed by `seq1` together with those registers needed by `seq2` that are not modified by `seq1`. (In terms of set operations, the new set of needed registers is the union of the set of registers needed by `seq1` with the set difference of the registers needed by `seq2` and the registers modi-

fied by `seq1`.) Thus, `append-instruction-sequences` is implemented as follows:

```
(define (append-instruction-sequences . seqs)
  (define (append-2-sequences seq1 seq2)
    (make-instruction-sequence
     (list-union
      (registers-needed seq1)
      (list-difference (registers-needed seq2)
                       (registers-modified seq1)))
     (list-union (registers-modified seq1)
                 (registers-modified seq2))
     (append (statements seq1) (statements seq2))))
  (define (append-seq-list seqs)
    (if (null? seqs)
        (empty-instruction-sequence)
        (append-2-sequences
         (car seqs)
         (append-seq-list (cdr seqs)))))
  (append-seq-list seqs))
```

This procedure uses some simple operations for manipulating sets represented as lists, similar to the (unordered) set representation described in Section 2.3.3:

```
(define (list-union s1 s2)
  (cond ((null? s1) s2)
        ((memq (car s1) s2) (list-union (cdr s1) s2))
        (else (cons (car s1) (list-union (cdr s1) s2)))))
(define (list-difference s1 s2)
  (cond ((null? s1) '())
        ((memq (car s1) s2) (list-difference (cdr s1) s2))
        (else (cons (car s1)
                    (list-difference (cdr s1) s2)))))
```

preserving, the second major instruction sequence combiner, takes a list of registers regs and two instruction sequences seq1 and seq2 that are to be executed sequentially. It returns an instruction sequence whose statements are the statements of seq1 followed by the statements of seq2, with appropriate save and restore instructions around seq1 to protect the registers in regs that are modified by seq1 but needed by seq2. To accomplish this, preserving first creates a sequence that has the required saves followed by the statements of seq1 followed by the required restores. This sequence needs the registers being saved and restored in addition to the registers needed by seq1, and modifies the registers modified by seq1 except for the ones being saved and restored. This augmented sequence and seq2 are then appended in the usual way. The following procedure implements this strategy recursively, walking down the list of registers to be preserved:[42]

```
(define (preserving regs seq1 seq2)
  (if (null? regs)
      (append-instruction-sequences seq1 seq2)
      (let ((first-reg (car regs)))
        (if (and (needs-register? seq2 first-reg)
                 (modifies-register? seq1 first-reg))
            (preserving (cdr regs)
             (make-instruction-sequence
              (list-union (list first-reg)
                          (registers-needed seq1))
              (list-difference (registers-modified seq1)
                               (list first-reg))
              (append `((save ,first-reg))
                      (statements seq1)
```

[42]Note that preserving calls append with three arguments. Though the definition of append shown in this book accepts only two arguments, Scheme standardly provides an append procedure that takes an arbitrary number of arguments.

```
                    `((restore ,first-reg))))
             seq2)
            (preserving (cdr regs) seq1 seq2)))))
```

Another sequence combiner, `tack-on-instruction-sequence`, is used by `compile-lambda` to append a procedure body to another sequence. Because the procedure body is not "in line" to be executed as part of the combined sequence, its register use has no impact on the register use of the sequence in which it is embedded. We thus ignore the procedure body's sets of needed and modified registers when we tack it onto the other sequence.

```
(define (tack-on-instruction-sequence seq body-seq)
  (make-instruction-sequence
   (registers-needed seq)
   (registers-modified seq)
   (append (statements seq)
           (statements body-seq))))
```

`compile-if` and `compile-procedure-call` use a special combiner called `parallel-instruction-sequences` to append the two alternative branches that follow a test. The two branches will never be executed sequentially; for any particular evaluation of the test, one branch or the other will be entered. Because of this, the registers needed by the second branch are still needed by the combined sequence, even if these are modified by the first branch.

```
(define (parallel-instruction-sequences seq1 seq2)
  (make-instruction-sequence
   (list-union (registers-needed seq1)
               (registers-needed seq2))
   (list-union (registers-modified seq1)
               (registers-modified seq2))
   (append (statements seq1)
           (statements seq2))))
```

5.5.5 An Example of Compiled Code

Now that we have seen all the elements of the compiler, let us examine an example of compiled code to see how things fit together. We will compile the definition of a recursive `factorial` procedure by calling `compile`:

```
(compile
 '(define (factorial n)
    (if (= n 1)
        1
        (* (factorial (- n 1)) n)))
 'val
 'next)
```

We have specified that the value of the `define` expression should be placed in the `val` register. We don't care what the compiled code does after executing the `define`, so our choice of `next` as the linkage descriptor is arbitrary.

`compile` determines that the expression is a definition, so it calls `compile-definition` to compile code to compute the value to be assigned (targeted to `val`), followed by code to install the definition, followed by code to put the value of the `define` (which is the symbol `ok`) into the target register, followed finally by the linkage code. `env` is preserved around the computation of the value, because it is needed in order to install the definition. Because the linkage is `next`, there is no linkage code in this case. The skeleton of the compiled code is thus

```
⟨save env if modified by code to compute value⟩
  ⟨compilation of definition value, target val, linkage
next⟩
  ⟨restore env if saved above⟩
  (perform (op define-variable!)
           (const factorial)
```

```
            (reg val)
            (reg env))
  (assign val (const ok))
```

The expression that is to be compiled to produce the value for the variable `factorial` is a `lambda` expression whose value is the procedure that computes factorials. `compile` handles this by calling `compile-lambda`, which compiles the procedure body, labels it as a new entry point, and generates the instruction that will combine the procedure body at the new entry point with the run-time environment and assign the result to `val`. The sequence then skips around the compiled procedure code, which is inserted at this point. The procedure code itself begins by extending the procedure's definition environment by a frame that binds the formal parameter `n` to the procedure argument. Then comes the actual procedure body. Since this code for the value of the variable doesn't modify the `env` register, the optional `save` and `restore` shown above aren't generated. (The procedure code at `entry2` isn't executed at this point, so its use of `env` is irrelevant.) Therefore, the skeleton for the compiled code becomes

```
  (assign val
          (op make-compiled-procedure)
          (label entry2)
          (reg env))
  (goto (label after-lambda1))
entry2
  (assign env (op compiled-procedure-env) (reg proc))
  (assign env
          (op extend-environment)
          (const (n))
          (reg argl)
          (reg env))
  ⟨compilation of procedure body⟩
after-lambda1
```

```
  (perform (op define-variable!)
           (const factorial)
           (reg val)
           (reg env))
  (assign val (const ok))
```

A procedure body is always compiled (by `compile-lambda-body`) as a sequence with target `val` and linkage `return`. The sequence in this case consists of a single `if` expression:

```
(if (= n 1)
    1
    (* (factorial (- n 1)) n))
```

`compile-if` generates code that first computes the predicate (targeted to `val`), then checks the result and branches around the true branch if the predicate is false. `env` and `continue` are preserved around the predicate code, since they may be needed for the rest of the `if` expression. Since the `if` expression is the final expression (and only expression) in the sequence making up the procedure body, its target is `val` and its linkage is `return`, so the true and false branches are both compiled with target `val` and linkage `return`. (That is, the value of the conditional, which is the value computed by either of its branches, is the value of the procedure.)

```
⟨save continue, env if modified by predicate and needed
by branches⟩
  ⟨compilation of predicate, target val, linkage next⟩
  ⟨restore continue, env if saved above⟩
  (test (op false?) (reg val))
  (branch (label false-branch4))
true-branch5
  ⟨compilation of true branch, target val, linkage return⟩
false-branch4
  ⟨compilation of false branch, target val, linkage return⟩
```

```
after-if3
```

The predicate `(= n 1)` is a procedure call. This looks up the operator (the symbol =) and places this value in `proc`. It then assembles the arguments `1` and the value of `n` into `argl`. Then it tests whether `proc` contains a primitive or a compound procedure, and dispatches to a primitive branch or a compound branch accordingly. Both branches resume at the `after-call` label. The requirements to preserve registers around the evaluation of the operator and operands don't result in any saving of registers, because in this case those evaluations don't modify the registers in question.

```
  (assign proc
          (op lookup-variable-value) (const =) (reg env))
  (assign val (const 1))
  (assign argl (op list) (reg val))
  (assign val
          (op lookup-variable-value) (const n) (reg env))
  (assign argl (op cons) (reg val) (reg argl))
  (test (op primitive-procedure?) (reg proc))
  (branch (label primitive-branch17))
compiled-branch16
  (assign continue (label after-call15))
  (assign val (op compiled-procedure-entry) (reg proc))
  (goto (reg val))
primitive-branch17
  (assign val
          (op apply-primitive-procedure)
          (reg proc)
          (reg argl))
after-call15
```

The true branch, which is the constant 1, compiles (with target `val` and linkage `return`) to

```
(assign val (const 1))
(goto (reg continue))
```

The code for the false branch is another procedure call, where the procedure is the value of the symbol `*`, and the arguments are `n` and the result of another procedure call (a call to `factorial`). Each of these calls sets up `proc` and `argl` and its own primitive and compound branches. Figure 5.17 shows the complete compilation of the definition of the `factorial` procedure. Notice that the possible `save` and `restore` of `continue` and `env` around the predicate, shown above, are in fact generated, because these registers are modified by the procedure call in the predicate and needed for the procedure call and the `return` linkage in the branches.

Exercise 5.33: Consider the following definition of a factorial procedure, which is slightly different from the one given above:

```
(define (factorial-alt n)
  (if (= n 1)
      1
      (* n (factorial-alt (- n 1)))))
```

Compile this procedure and compare the resulting code with that produced for `factorial`. Explain any differences you find. Does either program execute more efficiently than the other?

Exercise 5.34: Compile the iterative factorial procedure

```
(define (factorial n)
  (define (iter product counter)
    (if (> counter n)
        product
        (iter (* counter product)
              (+ counter 1))))
  (iter 1 1))
```

Annotate the resulting code, showing the essential difference between the code for iterative and recursive versions of `factorial` that makes one process build up stack space and the other run in constant stack space.

Figure 5.17: ↓ Compilation of the definition of the `factorial` procedure.

```
;; construct the procedure and skip over code for the procedure body
   (assign val
           (op make-compiled-procedure)
           (label entry2)
           (reg env))
   (goto (label after-lambda1))
entry2      ; calls to factorial will enter here
   (assign env (op compiled-procedure-env) (reg proc))
   (assign env
           (op extend-environment)
           (const (n))
           (reg argl)
           (reg env))
;; begin actual procedure body
   (save continue)
   (save env)
;; compute (= n 1)
   (assign proc
           (op lookup-variable-value)
           (const =)
           (reg env))
   (assign val (const 1))
   (assign argl (op list) (reg val))
   (assign val
           (op lookup-variable-value)
           (const n)
           (reg env))
   (assign argl (op cons) (reg val) (reg argl))
```

```
  (test (op primitive-procedure?) (reg proc))
  (branch (label primitive-branch17))
compiled-branch16
  (assign continue (label after-call15))
  (assign val (op compiled-procedure-entry) (reg proc))
  (goto (reg val))
primitive-branch17
  (assign val
          (op apply-primitive-procedure)
          (reg proc)
          (reg argl))
after-call15   ; val now contains result of (= n 1)
  (restore env)
  (restore continue)
  (test (op false?) (reg val))
  (branch (label false-branch4))
true-branch5  ; return 1
  (assign val (const 1))
  (goto (reg continue))
false-branch4
;; compute and return (* (factorial (- n 1)) n)
  (assign proc
          (op lookup-variable-value)
          (const *)
          (reg env))
  (save continue)
  (save proc)   ; save * procedure
  (assign val
          (op lookup-variable-value)
          (const n)
          (reg env))
  (assign argl (op list) (reg val))
  (save argl)   ; save partial argument list for *
;; compute (factorial (- n 1)), which is the other argument for *
  (assign proc
          (op lookup-variable-value)
```

```
            (const factorial)
            (reg env))
   (save proc)   ; save factorial procedure
;; compute (- n 1), which is the argument for factorial
   (assign proc
            (op lookup-variable-value)
            (const -)
            (reg env))
   (assign val (const 1))
   (assign argl (op list) (reg val))
   (assign val
            (op lookup-variable-value)
            (const n)
            (reg env))
   (assign argl (op cons) (reg val) (reg argl))
   (test (op primitive-procedure?) (reg proc))
   (branch (label primitive-branch8))
compiled-branch7
   (assign continue (label after-call6))
   (assign val (op compiled-procedure-entry) (reg proc))
   (goto (reg val))
primitive-branch8
   (assign val
            (op apply-primitive-procedure)
            (reg proc)
            (reg argl))
after-call6    ; val now contains result of (- n 1)
   (assign argl (op list) (reg val))
   (restore proc) ; restore factorial
;; apply factorial
   (test (op primitive-procedure?) (reg proc))
   (branch (label primitive-branch11))
compiled-branch10
   (assign continue (label after-call9))
   (assign val (op compiled-procedure-entry) (reg proc))
   (goto (reg val))
```

```
primitive-branch11
  (assign val
          (op apply-primitive-procedure)
          (reg proc)
          (reg argl))
after-call9       ; val now contains result of (factorial (-
n 1))
  (restore argl)  ; restore partial argument list for *
  (assign argl (op cons) (reg val) (reg argl))
  (restore proc)  ; restore *
  (restore continue)
;; apply * and return its value
  (test (op primitive-procedure?) (reg proc))
  (branch (label primitive-branch14))
compiled-branch13
;; note that a compound procedure here is called tail-recursively
  (assign val (op compiled-procedure-entry) (reg proc))
  (goto (reg val))
primitive-branch14
  (assign val
          (op apply-primitive-procedure)
          (reg proc)
          (reg argl))
  (goto (reg continue))
after-call12
after-if3
after-lambda1
;; assign the procedure to the variable factorial
  (perform (op define-variable!)
           (const factorial)
           (reg val)
           (reg env))
  (assign val (const ok))
```

Exercise 5.35: What expression was compiled to produce the code shown in Figure 5.18?

Figure 5.18: ↓ An example of compiler output. See Exercise 5.35.

```
(assign val
        (op make-compiled-procedure)
        (label entry16)
        (reg env))
  (goto (label after-lambda15))
entry16
  (assign env (op compiled-procedure-env) (reg proc))
  (assign env
          (op extend-environment)
          (const (x))
          (reg argl)
          (reg env))
  (assign proc
          (op lookup-variable-value)
          (const +)
          (reg env))
  (save continue)
  (save proc)
  (save env)
  (assign proc
          (op lookup-variable-value)
          (const g)
          (reg env))
  (save proc)
  (assign proc
          (op lookup-variable-value)
          (const +)
          (reg env))
  (assign val (const 2))
  (assign argl (op list) (reg val))
  (assign val
          (op lookup-variable-value)
          (const x)
```

```
          (reg env))
  (assign argl (op cons) (reg val) (reg argl))
  (test (op primitive-procedure?) (reg proc))
  (branch (label primitive-branch19))
compiled-branch18
  (assign continue (label after-call17))
  (assign val (op compiled-procedure-entry) (reg proc))
  (goto (reg val))
primitive-branch19
  (assign val
          (op apply-primitive-procedure)
          (reg proc)
          (reg argl))
after-call17
  (assign argl (op list) (reg val))
  (restore proc)
  (test (op primitive-procedure?) (reg proc))
  (branch (label primitive-branch22))
compiled-branch21
  (assign continue (label after-call20))
  (assign val (op compiled-procedure-entry) (reg proc))
  (goto (reg val))
primitive-branch22
  (assign val
          (op apply-primitive-procedure)
          (reg proc)
          (reg argl))
after-call20
  (assign argl (op list) (reg val))
  (restore env)
  (assign val
          (op lookup-variable-value)
          (const x)
          (reg env))
  (assign argl (op cons) (reg val) (reg argl))
  (restore proc)
```

```
  (restore continue)
  (test (op primitive-procedure?) (reg proc))
  (branch (label primitive-branch25))
compiled-branch24
  (assign val
          (op compiled-procedure-entry)
          (reg proc))
  (goto (reg val))
primitive-branch25
  (assign val
          (op apply-primitive-procedure)
          (reg proc)
          (reg argl))
  (goto (reg continue))
after-call23
after-lambda15
  (perform (op define-variable!)
           (const f)
           (reg val)
           (reg env))
  (assign val (const ok))
```

Exercise 5.36: What order of evaluation does our compiler produce for operands of a combination? Is it left-to-right, right-to-left, or some other order? Where in the compiler is this order determined? Modify the compiler so that it produces some other order of evaluation. (See the discussion of order of evaluation for the explicit-control evaluator in Section 5.4.1.) How does changing the order of operand evaluation affect the efficiency of the code that constructs the argument list?

Exercise 5.37: One way to understand the compiler's `preserving` mechanism for optimizing stack usage is to see what extra operations would be generated if we did not use this idea. Mod-

ify `preserving` so that it always generates the `save` and `restore` operations. Compile some simple expressions and identify the unnecessary stack operations that are generated. Compare the code to that generated with the `preserving` mechanism intact.

Exercise 5.38: Our compiler is clever about avoiding unnecessary stack operations, but it is not clever at all when it comes to compiling calls to the primitive procedures of the language in terms of the primitive operations supplied by the machine. For example, consider how much code is compiled to compute `(+ a 1)`: The code sets up an argument list in `argl`, puts the primitive addition procedure (which it finds by looking up the symbol + in the environment) into `proc`, and tests whether the procedure is primitive or compound. The compiler always generates code to perform the test, as well as code for primitive and compound branches (only one of which will be executed). We have not shown the part of the controller that implements primitives, but we presume that these instructions make use of primitive arithmetic operations in the machine's data paths. Consider how much less code would be generated if the compiler could *open-code* primitives—that is, if it could generate code to directly use these primitive machine operations. The expression `(+ a 1)` might be compiled into something as simple as[43]

```
(assign
 val (op lookup-variable-value) (const a) (reg env))
(assign val (op +) (reg val) (const 1))
```

[43] We have used the same symbol + here to denote both the source-language procedure and the machine operation. In general there will not be a one-to-one correspondence between primitives of the source language and primitives of the machine.

In this exercise we will extend our compiler to support open coding of selected primitives. Special-purpose code will be generated for calls to these primitive procedures instead of the general procedure-application code. In order to support this, we will augment our machine with special argument registers `arg1` and `arg2`. The primitive arithmetic operations of the machine will take their inputs from `arg1` and `arg2`. The results may be put into `val`, `arg1`, or `arg2`.

The compiler must be able to recognize the application of an open-coded primitive in the source program. We will augment the dispatch in the `compile` procedure to recognize the names of these primitives in addition to the reserved words (the special forms) it currently recognizes.[44] For each special form our compiler has a code generator. In this exercise we will construct a family of code generators for the open-coded primitives.

a. The open-coded primitives, unlike the special forms, all need their operands evaluated. Write a code generator `spread-arguments` for use by all the open-coding code generators. `spread-arguments` should take an operand list and compile the given operands targeted to successive argument registers. Note that an operand may contain a call to an open-coded primitive, so argument registers will have to be preserved during operand evaluation.

[44] Making the primitives into reserved words is in general a bad idea, since a user cannot then rebind these names to different procedures. Moreover, if we add reserved words to a compiler that is in use, existing programs that define procedures with these names will stop working. See Exercise 5.44 for ideas on how to avoid this problem.

b. For each of the primitive procedures =, *, −, and +, write a code generator that takes a combination with that operator, together with a target and a linkage descriptor, and produces code to spread the arguments into the registers and then perform the operation targeted to the given target with the given linkage. You need only handle expressions with two operands. Make `compile` dispatch to these code generators.

c. Try your new compiler on the `factorial` example. Compare the resulting code with the result produced without open coding.

d. Extend your code generators for + and * so that they can handle expressions with arbitrary numbers of operands. An expression with more than two operands will have to be compiled into a sequence of operations, each with only two inputs.

5.5.6 Lexical Addressing

One of the most common optimizations performed by compilers is the optimization of variable lookup. Our compiler, as we have implemented it so far, generates code that uses the `lookup-variable-value` operation of the evaluator machine. This searches for a variable by comparing it with each variable that is currently bound, working frame by frame outward through the run-time environment. This search can be expensive if the frames are deeply nested or if there are many variables. For example, consider the problem of looking up the value of `x` while evaluating the expression `(* x y z)` in an application of the procedure that is returned by

```
(let ((x 3) (y 4))
  (lambda (a b c d e)
```

```
    (let ((y (* a b x)) (z (+ c d x)))
      (* x y z))))
```

Since a `let` expression is just syntactic sugar for a `lambda` combination, this expression is equivalent to

```
((lambda (x y)
   (lambda (a b c d e)
     ((lambda (y z) (* x y z))
      (* a b x)
      (+ c d x))))
 3
 4)
```

Each time `lookup-variable-value` searches for `x`, it must determine that the symbol `x` is not `eq?` to `y` or `z` (in the first frame), nor to `a`, `b`, `c`, `d`, or `e` (in the second frame). We will assume, for the moment, that our programs do not use `define`—that variables are bound only with `lambda`. Because our language is lexically scoped, the run-time environment for any expression will have a structure that parallels the lexical structure of the program in which the expression appears.[45] Thus, the compiler can know, when it analyzes the above expression, that each time the procedure is applied the variable `x` in `(* x y z)` will be found two frames out from the current frame and will be the first variable in that frame.

We can exploit this fact by inventing a new kind of variable-lookup operation, `lexical-address-lookup`, that takes as arguments an environment and a *lexical address* that consists of two numbers: a *frame number*, which specifies how many frames to pass over, and a *displacement number*, which specifies how many variables to pass over in that frame. `lexical-address-lookup` will produce the value of the variable stored at that

[45] This is not true if we allow internal definitions, unless we scan them out. See Exercise 5.43.

lexical address relative to the current environment. If we add the `lexical-address-lookup` operation to our machine, we can make the compiler generate code that references variables using this operation, rather than `lookup-variable-value`. Similarly, our compiled code can use a new `lexical-address-set!` operation instead of `set-variable-value!`.

In order to generate such code, the compiler must be able to determine the lexical address of a variable it is about to compile a reference to. The lexical address of a variable in a program depends on where one is in the code. For example, in the following program, the address of `x` in expression ⟨*e1*⟩ is (2, 0)—two frames back and the first variable in the frame. At that point `y` is at address (0, 0) and `c` is at address (1, 2). In expression ⟨*e2*⟩, `x` is at (1, 0), `y` is at (1, 1), and `c` is at (0, 2).

```
((lambda (x y)
   (lambda (a b c d e)
     ((lambda (y z) ⟨e1⟩)
      ⟨e2⟩
      (+ c d x))))
 3
 4)
```

One way for the compiler to produce code that uses lexical addressing is to maintain a data structure called a *compile-time environment*. This keeps track of which variables will be at which positions in which frames in the run-time environment when a particular variable-access operation is executed. The compile-time environment is a list of frames, each containing a list of variables. (There will of course be no values bound to the variables, since values are not computed at compile time.) The compile-time environment becomes an additional argument to `compile` and is passed along to each code generator. The top-level call to `compile` uses an empty compile-time environ-

ment. When a `lambda` body is compiled, `compile-lambda-body` extends the compile-time environment by a frame containing the procedure's parameters, so that the sequence making up the body is compiled with that extended environment. At each point in the compilation, `compile-variable` and `compile-assignment` use the compile-time environment in order to generate the appropriate lexical addresses.

Exercise 5.39 through Exercise 5.43 describe how to complete this sketch of the lexical-addressing strategy in order to incorporate lexical lookup into the compiler. Exercise 5.44 describes another use for the compile-time environment.

> **Exercise 5.39:** Write a procedure `lexical-address-lookup` that implements the new lookup operation. It should take two arguments—a lexical address and a run-time environment—and return the value of the variable stored at the specified lexical address. `lexical-address-lookup` should signal an error if the value of the variable is the symbol `*unassigned*`.[46] Also write a procedure `lexical-address-set!` that implements the operation that changes the value of the variable at a specified lexical address.
>
> **Exercise 5.40:** Modify the compiler to maintain the compile-time environment as described above. That is, add a compile-time-environment argument to `compile` and the various code generators, and extend it in `compile-lambda-body`.
>
> **Exercise 5.41:** Write a procedure `find-variable` that takes as arguments a variable and a compile-time environment and re-

[46] This is the modification to variable lookup required if we implement the scanning method to eliminate internal definitions (Exercise 5.43). We will need to eliminate these definitions in order for lexical addressing to work.

turns the lexical address of the variable with respect to that environment. For example, in the program fragment that is shown above, the compile-time environment during the compilation of expression ⟨*e1*⟩ is `((y z) (a b c d e) (x y))`. `find-variable` should produce

```
(find-variable 'c '((y z) (a b c d e) (x y)))
(1 2)
(find-variable 'x '((y z) (a b c d e) (x y)))
(2 0)
(find-variable 'w '((y z) (a b c d e) (x y)))
not-found
```

Exercise 5.42: Using `find-variable` from Exercise 5.41, rewrite `compile-variable` and `compile-assignment` to output lexical-address instructions. In cases where `find-variable` returns `not-found` (that is, where the variable is not in the compile-time environment), you should have the code generators use the evaluator operations, as before, to search for the binding. (The only place a variable that is not found at compile time can be is in the global environment, which is part of the run-time environment but is not part of the compile-time environment.[47] Thus, if you wish, you may have the evaluator operations look directly in the global environment, which can be obtained with the operation `(op get-global-environment)`, instead of having them search the whole run-time environment

[47] Lexical addresses cannot be used to access variables in the global environment, because these names can be defined and redefined interactively at any time. With internal definitions scanned out, as in Exercise 5.43, the only definitions the compiler sees are those at top level, which act on the global environment. Compilation of a definition does not cause the defined name to be entered in the compile-time environment.

found in `env`.) Test the modified compiler on a few simple cases, such as the nested `lambda` combination at the beginning of this section.

Exercise 5.43: We argued in Section 4.1.6 that internal definitions for block structure should not be considered "real" `define`s. Rather, a procedure body should be interpreted as if the internal variables being defined were installed as ordinary `lambda` variables initialized to their correct values using `set!`. Section 4.1.6 and Exercise 4.16 showed how to modify the metacircular interpreter to accomplish this by scanning out internal definitions. Modify the compiler to perform the same transformation before it compiles a procedure body.

Exercise 5.44: In this section we have focused on the use of the compile-time environment to produce lexical addresses. But there are other uses for compile-time environments. For instance, in Exercise 5.38 we increased the efficiency of compiled code by open-coding primitive procedures. Our implementation treated the names of open-coded procedures as reserved words. If a program were to rebind such a name, the mechanism described in Exercise 5.38 would still open-code it as a primitive, ignoring the new binding. For example, consider the procedure

```
(lambda (+ * a b x y)
  (+ (* a x) (* b y)))
```

which computes a linear combination of `x` and `y`. We might call it with arguments `+matrix`, `*matrix`, and four matrices, but the open-coding compiler would still open-code the `+` and the `*` in `(+ (* a x) (* b y))` as primitive `+` and `*`.

Modify the open-coding compiler to consult the compile-time environment in order to compile the correct code for expressions involving the names of primitive procedures. (The code will work correctly as long as the program does not `define` or `set!` these names.)

5.5.7 Interfacing Compiled Code to the Evaluator

We have not yet explained how to load compiled code into the evaluator machine or how to run it. We will assume that the explicit-control-evaluator machine has been defined as in Section 5.4.4, with the additional operations specified in Footnote 38. We will implement a procedure `compile-and-go` that compiles a Scheme expression, loads the resulting object code into the evaluator machine, and causes the machine to run the code in the evaluator global environment, print the result, and enter the evaluator's driver loop. We will also modify the evaluator so that interpreted expressions can call compiled procedures as well as interpreted ones. We can then put a compiled procedure into the machine and use the evaluator to call it:

```
(compile-and-go
 '(define (factorial n)
    (if (= n 1)
        1
        (* (factorial (- n 1)) n))))
;;; EC-Eval value:
ok
;;; EC-Eval input:
(factorial 5)
;;; EC-Eval value:
120
```

To allow the evaluator to handle compiled procedures (for example, to evalu-

ate the call to `factorial` above), we need to change the code at `apply-dispatch` (Section 5.4.1) so that it recognizes compiled procedures (as distinct from compound or primitive procedures) and transfers control directly to the entry point of the compiled code:[48]

```
apply-dispatch
  (test (op primitive-procedure?) (reg proc))
  (branch (label primitive-apply))
  (test (op compound-procedure?) (reg proc))
  (branch (label compound-apply))
  (test (op compiled-procedure?) (reg proc))
  (branch (label compiled-apply))
  (goto (label unknown-procedure-type))
compiled-apply
  (restore continue)
  (assign val (op compiled-procedure-entry) (reg proc))
  (goto (reg val))
```

Note the restore of `continue` at `compiled-apply`. Recall that the evaluator was arranged so that at `apply-dispatch`, the continuation would be at the top of the stack. The compiled code entry point, on the other hand, expects the continuation to be in `continue`, so `continue` must be restored before the compiled code is executed.

To enable us to run some compiled code when we start the evaluator machine, we add a `branch` instruction at the beginning of the evaluator machine, which causes the machine to go to a new entry point if the `flag` register is set.[49]

[48] Of course, compiled procedures as well as interpreted procedures are compound (non-primitive). For compatibility with the terminology used in the explicit-control evaluator, in this section we will use "compound" to mean interpreted (as opposed to compiled).

[49] Now that the evaluator machine starts with a `branch`, we must always initialize the `flag` register before starting the evaluator machine. To start the machine at its ordinary

```
(branch (label external-entry))        ; branches if flag is
set
read-eval-print-loop
  (perform (op initialize-stack))
  ...
```

`external-entry` assumes that the machine is started with `val` containing the location of an instruction sequence that puts a result into `val` and ends with `(goto (reg continue))`. Starting at this entry point jumps to the location designated by `val`, but first assigns `continue` so that execution will return to `print-result`, which prints the value in `val` and then goes to the beginning of the evaluator's read-eval-print loop.[50]

```
external-entry
  (perform (op initialize-stack))
```

---

read-eval-print loop, we could use

```
(define (start-eceval)
  (set! the-global-environment (setup-environment))
  (set-register-contents! eceval 'flag false)
  (start eceval))
```

[50] Since a compiled procedure is an object that the system may try to print, we also modify the system print operation `user-print` (from Section 4.1.4) so that it will not attempt to print the components of a compiled procedure:

```
(define (user-print object)
  (cond ((compound-procedure? object)
         (display (list 'compound-procedure
                        (procedure-parameters object)
                        (procedure-body object)
                        '<procedure-env>)))
        ((compiled-procedure? object)
         (display '<compiled-procedure>))
        (else (display object))))
```

```
  (assign env (op get-global-environment))
  (assign continue (label print-result))
  (goto (reg val))
```

Now we can use the following procedure to compile a procedure definition, execute the compiled code, and run the read-eval-print loop so we can try the procedure. Because we want the compiled code to return to the location in `continue` with its result in `val`, we compile the expression with a target of `val` and a linkage of `return`. In order to transform the object code produced by the compiler into executable instructions for the evaluator register machine, we use the procedure `assemble` from the register-machine simulator (Section 5.2.2). We then initialize the `val` register to point to the list of instructions, set the `flag` so that the evaluator will go to `external-entry`, and start the evaluator.

```
(define (compile-and-go expression)
  (let ((instructions
         (assemble
          (statements
           (compile expression 'val 'return))
          eceval)))
    (set! the-global-environment (setup-environment))
    (set-register-contents! eceval 'val instructions)
    (set-register-contents! eceval 'flag true)
    (start eceval)))
```

If we have set up stack monitoring, as at the end of Section 5.4.4, we can examine the stack usage of compiled code:

```
(compile-and-go
 '(define (factorial n)
    (if (= n 1)
        1
        (* (factorial (- n 1)) n))))
```

```
(total-pushes = 0 maximum-depth = 0)
;;; EC-Eval value:
ok
;;; EC-Eval input:
(factorial 5)
(total-pushes = 31 maximum-depth = 14)
;;; EC-Eval value:
120
```

Compare this example with the evaluation of `(factorial 5)` using the interpreted version of the same procedure, shown at the end of Section 5.4.4. The interpreted version required 144 pushes and a maximum stack depth of 28. This illustrates the optimization that results from our compilation strategy.

Interpretation and compilation

With the programs in this section, we can now experiment with the alternative execution strategies of interpretation and compilation.[51] An interpreter raises the machine to the level of the user program; a compiler lowers the user program to the level of the machine language. We can regard the Scheme language (or any programming language) as a coherent family of abstractions erected on the machine language. Interpreters are good for interactive program development and debugging because the steps of program execution are organized in terms of these abstractions, and are therefore more intelligible to the programmer. Compiled code can execute faster, because the steps of program execution are organized in terms of the machine language, and the compiler is free to make optimizations that cut across the higher-level abstractions.[52]

[51] We can do even better by extending the compiler to allow compiled code to call interpreted procedures. See Exercise 5.47.

[52] Independent of the strategy of execution, we incur significant overhead if we insist that errors encountered in execution of a user program be detected and signaled, rather than be-

The alternatives of interpretation and compilation also lead to different strategies for porting languages to new computers. Suppose that we wish to implement Lisp for a new machine. One strategy is to begin with the explicit-control evaluator of Section 5.4 and translate its instructions to instructions for the new machine. A different strategy is to begin with the compiler and change the code generators so that they generate code for the new machine. The second strategy allows us to run any Lisp program on the new machine by first compiling it with the compiler running on our original Lisp system, and linking it with a compiled version of the run-time library.[53] Better yet, we can compile the compiler itself, and run this on the new machine to compile other Lisp programs.[54] Or we can compile one of the interpreters of Section

ing allowed to kill the system or produce wrong answers. For example, an out-of-bounds array reference can be detected by checking the validity of the reference before performing it. The overhead of checking, however, can be many times the cost of the array reference itself, and a programmer should weigh speed against safety in determining whether such a check is desirable. A good compiler should be able to produce code with such checks, should avoid redundant checks, and should allow programmers to control the extent and type of error checking in the compiled code.

Compilers for popular languages, such as C and C++, put hardly any error-checking operations into running code, so as to make things run as fast as possible. As a result, it falls to programmers to explicitly provide error checking. Unfortunately, people often neglect to do this, even in critical applications where speed is not a constraint. Their programs lead fast and dangerous lives. For example, the notorious "Worm" that paralyzed the Internet in 1988 exploited the UNIX(tm) operating system's failure to check whether the input buffer has overflowed in the finger daemon. (See Spafford 1989.)

[53] Of course, with either the interpretation or the compilation strategy we must also implement for the new machine storage allocation, input and output, and all the various operations that we took as "primitive" in our discussion of the evaluator and compiler. One strategy for minimizing work here is to write as many of these operations as possible in Lisp and then compile them for the new machine. Ultimately, everything reduces to a small kernel (such as garbage collection and the mechanism for applying actual machine primitives) that is hand-coded for the new machine.

[54] This strategy leads to amusing tests of correctness of the compiler, such as checking

4.1 to produce an interpreter that runs on the new machine.

Exercise 5.45: By comparing the stack operations used by compiled code to the stack operations used by the evaluator for the same computation, we can determine the extent to which the compiler optimizes use of the stack, both in speed (reducing the total number of stack operations) and in space (reducing the maximum stack depth). Comparing this optimized stack use to the performance of a special-purpose machine for the same computation gives some indication of the quality of the compiler.

a. Exercise 5.27 asked you to determine, as a function of n, the number of pushes and the maximum stack depth needed by the evaluator to compute $n!$ using the recursive factorial procedure given above. Exercise 5.14 asked you to do the same measurements for the special-purpose factorial machine shown in Figure 5.11. Now perform the same analysis using the compiled `factorial` procedure.

   Take the ratio of the number of pushes in the compiled version to the number of pushes in the interpreted version, and do the same for the maximum stack depth. Since the number of operations and the stack depth used to compute $n!$ are linear in n, these ratios should approach constants as n becomes large. What are these constants? Similarly,

whether the compilation of a program on the new machine, using the compiled compiler, is identical with the compilation of the program on the original Lisp system. Tracking down the source of differences is fun but often frustrating, because the results are extremely sensitive to minuscule details.

find the ratios of the stack usage in the special-purpose machine to the usage in the interpreted version.

Compare the ratios for special-purpose versus interpreted code to the ratios for compiled versus interpreted code. You should find that the special-purpose machine does much better than the compiled code, since the hand-tailored controller code should be much better than what is produced by our rudimentary general-purpose compiler.

b. Can you suggest improvements to the compiler that would help it generate code that would come closer in performance to the hand-tailored version?

Exercise 5.46: Carry out an analysis like the one in Exercise 5.45 to determine the effectiveness of compiling the tree-recursive Fibonacci procedure

```
(define (fib n)
  (if (< n 2)
      n
      (+ (fib (- n 1))
         (fib (- n 2)))))
```

compared to the effectiveness of using the special-purpose Fibonacci machine of Figure 5.12. (For measurement of the interpreted performance, see Exercise 5.29.) For Fibonacci, the time resource used is not linear in n; hence the ratios of stack operations will not approach a limiting value that is independent of n.

Exercise 5.47: This section described how to modify the explicit-control evaluator so that interpreted code can call compiled procedures. Show how to modify the compiler so that compiled

procedures can call not only primitive procedures and compiled procedures, but interpreted procedures as well. This requires modifying `compile-procedure-call` to handle the case of compound (interpreted) procedures. Be sure to handle all the same `target` and `linkage` combinations as in `compile-proc-appl`. To do the actual procedure application, the code needs to jump to the evaluator's `compound-apply` entry point. This label cannot be directly referenced in object code (since the assembler requires that all labels referenced by the code it is assembling be defined there), so we will add a register called `compapp` to the evaluator machine to hold this entry point, and add an instruction to initialize it:

```
 (assign compapp (label compound-apply))
 (branch (label external-entry)) ; branches if flag
is set
read-eval-print-loop ...
```

To test your code, start by defining a procedure `f` that calls a procedure `g`. Use `compile-and-go` to compile the definition of `f` and start the evaluator. Now, typing at the evaluator, define `g` and try to call `f`.

Exercise 5.48: The `compile-and-go` interface implemented in this section is awkward, since the compiler can be called only once (when the evaluator machine is started). Augment the compiler-interpreter interface by providing a `compile-and-run` primitive that can be called from within the explicit-control evaluator as follows:

```
;;; EC-Eval input:
(compile-and-run
```

```
 '(define (factorial n)
    (if (= n 1) 1 (* (factorial (- n 1)) n))))
;;; EC-Eval value:
ok
;;; EC-Eval input:
(factorial 5)
;;; EC-Eval value:
120
```

Exercise 5.49: As an alternative to using the explicit-control evaluator's read-eval-print loop, design a register machine that performs a read-compile-execute-print loop. That is, the machine should run a loop that reads an expression, compiles it, assembles and executes the resulting code, and prints the result. This is easy to run in our simulated setup, since we can arrange to call the procedures `compile` and `assemble` as "register-machine operations."

Exercise 5.50: Use the compiler to compile the metacircular evaluator of Section 4.1 and run this program using the register-machine simulator. (To compile more than one definition at a time, you can package the definitions in a `begin`.) The resulting interpreter will run very slowly because of the multiple levels of interpretation, but getting all the details to work is an instructive exercise.

Exercise 5.51: Develop a rudimentary implementation of Scheme in C (or some other low-level language of your choice) by translating the explicit-control evaluator of Section 5.4 into C. In order to run this code you will need to also provide appropriate storage-allocation routines and other run-time support.

Exercise 5.52: As a counterpoint to Exercise 5.51, modify the compiler so that it compiles Scheme procedures into sequences of C instructions. Compile the metacircular evaluator of Section 4.1 to produce a Scheme interpreter written in C.

References

Abelson, Harold, Andrew Berlin, Jacob Katzenelson, William McAllister, Guillermo Rozas, Gerald Jay Sussman, and Jack Wisdom. 1992. The Supercomputer Toolkit: A general framework for special-purpose computing. *International Journal of High-Speed Electronics* 3(3): 337-361. →

Allen, John. 1978. *Anatomy of Lisp*. New York: McGraw-Hill.

ANSI X3.226-1994. *American National Standard for Information Systems —Programming Language—Common Lisp*.

Appel, Andrew W. 1987. Garbage collection can be faster than stack allocation. *Information Processing Letters* 25(4): 275-279. →

Backus, John. 1978. Can programming be liberated from the von Neumann style? *Communications of the ACM* 21(8): 613-641. →

Baker, Henry G., Jr. 1978. List processing in real time on a serial computer. *Communications of the ACM* 21(4): 280-293. →

Batali, John, Neil Mayle, Howard Shrobe, Gerald Jay Sussman, and Daniel Weise. 1982. The Scheme-81 architecture—System and chip. In *Proceedings of the MIT Conference on Advanced Research in VLSI*, edited by Paul Penfield, Jr. Dedham, MA: Artech House.

Borning, Alan. 1977. ThingLab—An object-oriented system for building simulations using constraints. In *Proceedings of the 5th International Joint Conference on Artificial Intelligence*. →

Borodin, Alan, and Ian Munro. 1975. *The Computational Complexity of Algebraic and Numeric Problems*. New York: American Elsevier.

Chaitin, Gregory J. 1975. Randomness and mathematical proof. *Scientific American* 232(5): 47-52. →

Church, Alonzo. 1941. *The Calculi of Lambda-Conversion*. Princeton, N.J.: Princeton University Press.

Clark, Keith L. 1978. Negation as failure. In *Logic and Data Bases*. New York: Plenum Press, pp. 293-322. →

Clinger, William. 1982. Nondeterministic call by need is neither lazy nor by name. In *Proceedings of the ACM Symposium on Lisp and Functional Programming*, pp. 226-234.

Clinger, William, and Jonathan Rees. 1991. Macros that work. In *Proceedings of the 1991 ACM Conference on Principles of Programming Languages*, pp. 155-162. →

Colmerauer A., H. Kanoui, R. Pasero, and P. Roussel. 1973. Un système de communication homme-machine en français. Technical report, Groupe Intelligence Artificielle, Université d'Aix Marseille, Luminy. →

Cormen, Thomas, Charles Leiserson, and Ronald Rivest. 1990. *Introduction to Algorithms*. Cambridge, MA: MIT Press.

Darlington, John, Peter Henderson, and David Turner. 1982. *Functional Programming and Its Applications*. New York: Cambridge University Press.

Dijkstra, Edsger W. 1968a. The structure of the "THE" multiprogramming system. *Communications of the ACM* 11(5): 341-346. →

Dijkstra, Edsger W. 1968b. Cooperating sequential processes. In *Programming Languages*, edited by F. Genuys. New York: Academic Press, pp. 43-112. →

Dinesman, Howard P. 1968. *Superior Mathematical Puzzles*. New York: Simon and Schuster.

deKleer, Johan, Jon Doyle, Guy Steele, and Gerald J. Sussman. 1977.

AMORD: Explicit control of reasoning. In *Proceedings of the ACM Symposium on Artificial Intelligence and Programming Languages*, pp. 116-125. →

Doyle, Jon. 1979. A truth maintenance system. *Artificial Intelligence* 12: 231-272. →

Feigenbaum, Edward, and Howard Shrobe. 1993. The Japanese National Fifth Generation Project: Introduction, survey, and evaluation. In *Future Generation Computer Systems*, vol. 9, pp. 105-117. →

Feeley, Marc. 1986. Deux approches à l'implantation du language Scheme. Masters thesis, Université de Montréal. →

Feeley, Marc and Guy Lapalme. 1987. Using closures for code generation. *Journal of Computer Languages* 12(1): 47-66. →

Feller, William. 1957. *An Introduction to Probability Theory and Its Applications*, volume 1. New York: John Wiley & Sons.

Fenichel, R., and J. Yochelson. 1969. A Lisp garbage collector for virtual memory computer systems. *Communications of the ACM* 12(11): 611-612. →

Floyd, Robert. 1967. Nondeterministic algorithms. *JACM*, 14(4): 636-644. →

Forbus, Kenneth D., and Johan deKleer. 1993. *Building Problem Solvers*. Cambridge, MA: MIT Press.

Friedman, Daniel P., and David S. Wise. 1976. CONS should not evaluate its arguments. In *Automata, Languages, and Programming: Third International Colloquium*, edited by S. Michaelson and R. Milner, pp. 257-284. →

Friedman, Daniel P., Mitchell Wand, and Christopher T. Haynes. 1992. *Essentials of Programming Languages*. Cambridge, MA: MIT Press/ McGraw-Hill.

Gabriel, Richard P. 1988. The Why of *Y*. *Lisp Pointers* 2(2): 15-25. →

Goldberg, Adele, and David Robson. 1983. *Smalltalk-80: The Lan-*

guage and Its Implementation. Reading, MA: Addison-Wesley. →

Gordon, Michael, Robin Milner, and Christopher Wadsworth. 1979. *Edinburgh LCF*. Lecture Notes in Computer Science, volume 78. New York: Springer-Verlag.

Gray, Jim, and Andreas Reuter. 1993. *Transaction Processing: Concepts and Models*. San Mateo, CA: Morgan-Kaufman.

Green, Cordell. 1969. Application of theorem proving to problem solving. In *Proceedings of the International Joint Conference on Artificial Intelligence*, pp. 219-240. →

Green, Cordell, and Bertram Raphael. 1968. The use of theorem-proving techniques in question-answering systems. In *Proceedings of the ACM National Conference*, pp. 169-181. →

Griss, Martin L. 1981. Portable Standard Lisp, a brief overview. Utah Symbolic Computation Group Operating Note 58, University of Utah.

Guttag, John V. 1977. Abstract data types and the development of data structures. *Communications of the ACM* 20(6): 396-404. →

Hamming, Richard W. 1980. *Coding and Information Theory*. Englewood Cliffs, N.J.: Prentice-Hall.

Hanson, Christopher P. 1990. Efficient stack allocation for tail-recursive languages. In *Proceedings of ACM Conference on Lisp and Functional Programming*, pp. 106-118. →

Hanson, Christopher P. 1991. A syntactic closures macro facility. *Lisp Pointers*, 4(3). →

Hardy, Godfrey H. 1921. Srinivasa Ramanujan. *Proceedings of the London Mathematical Society* XIX(2).

Hardy, Godfrey H., and E. M. Wright. 1960. *An Introduction to the Theory of Numbers*. 4th edition. New York: Oxford University Press. →

Havender, J. 1968. Avoiding deadlocks in multi-tasking systems. *IBM Systems Journal* 7(2): 74-84.

Hearn, Anthony C. 1969. Standard Lisp. Technical report AIM-90, Artificial Intelligence Project, Stanford University. →

Henderson, Peter. 1980. *Functional Programming: Application and Implementation*. Englewood Cliffs, N.J.: Prentice-Hall.

Henderson, Peter. 1982. Functional Geometry. In *Conference Record of the 1982 ACM Symposium on Lisp and Functional Programming*, pp. 179-187. →, 2002 version →

Hewitt, Carl E. 1969. PLANNER: A language for proving theorems in robots. In *Proceedings of the International Joint Conference on Artificial Intelligence*, pp. 295-301. →

Hewitt, Carl E. 1977. Viewing control structures as patterns of passing messages. *Journal of Artificial Intelligence* 8(3): 323-364. →

Hoare, C. A. R. 1972. Proof of correctness of data representations. *Acta Informatica* 1(1).

Hodges, Andrew. 1983. *Alan Turing: The Enigma*. New York: Simon and Schuster.

Hofstadter, Douglas R. 1979. *Gödel, Escher, Bach: An Eternal Golden Braid*. New York: Basic Books.

Hughes, R. J. M. 1990. Why functional programming matters. In *Research Topics in Functional Programming*, edited by David Turner. Reading, MA: Addison-Wesley, pp. 17-42. →

IEEE Std 1178-1990. 1990. *IEEE Standard for the Scheme Programming Language*.

Ingerman, Peter, Edgar Irons, Kirk Sattley, and Wallace Feurzeig; assisted by M. Lind, Herbert Kanner, and Robert Floyd. 1960. THUNKS: A way of compiling procedure statements, with some comments on procedure declarations. Unpublished manuscript. (Also, private communication from Wallace Feurzeig.)

Kaldewaij, Anne. 1990. *Programming: The Derivation of Algorithms*. New York: Prentice-Hall.

Knuth, Donald E. 1973. *Fundamental Algorithms*. Volume 1 of *The Art of Computer Programming*. 2nd edition. Reading, MA: Addison-Wesley.

Knuth, Donald E. 1981. *Seminumerical Algorithms*. Volume 2 of *The Art of Computer Programming*. 2nd edition. Reading, MA: Addison-Wesley.

Kohlbecker, Eugene Edmund, Jr. 1986. Syntactic extensions in the programming language Lisp. Ph.D. thesis, Indiana University. →

Konopasek, Milos, and Sundaresan Jayaraman. 1984. *The TK!Solver Book: A Guide to Problem-Solving in Science, Engineering, Business, and Education*. Berkeley, CA: Osborne/McGraw-Hill.

Kowalski, Robert. 1973. Predicate logic as a programming language. Technical report 70, Department of Computational Logic, School of Artificial Intelligence, University of Edinburgh. →

Kowalski, Robert. 1979. *Logic for Problem Solving*. New York: North-Holland. →

Lamport, Leslie. 1978. Time, clocks, and the ordering of events in a distributed system. *Communications of the ACM* 21(7): 558-565. →

Lampson, Butler, J. J. Horning, R. London, J. G. Mitchell, and G. K. Popek. 1981. Report on the programming language Euclid. Technical report, Computer Systems Research Group, University of Toronto. →

Landin, Peter. 1965. A correspondence between Algol 60 and Church's lambda notation: Part I. *Communications of the ACM* 8(2): 89-101.

Lieberman, Henry, and Carl E. Hewitt. 1983. A real-time garbage collector based on the lifetimes of objects. *Communications of the ACM* 26(6): 419-429. →

Liskov, Barbara H., and Stephen N. Zilles. 1975. Specification techniques for data abstractions. *IEEE Transactions on Software Engineering* 1(1): 7-19. →

McAllester, David Allen. 1978. A three-valued truth-maintenance system. Memo 473, MIT Artificial Intelligence Laboratory. →

McAllester, David Allen. 1980. An outlook on truth maintenance. Memo 551, MIT Artificial Intelligence Laboratory. →

McCarthy, John. 1960. Recursive functions of symbolic expressions and their computation by machine. *Communications of the ACM* 3(4): 184-195. →

McCarthy, John. 1963. A basis for a mathematical theory of computation. In *Computer Programming and Formal Systems*, edited by P. Braffort and D. Hirschberg. North-Holland. →

McCarthy, John. 1978. The history of Lisp. In *Proceedings of the ACM SIGPLAN Conference on the History of Programming Languages*. →

McCarthy, John, P. W. Abrahams, D. J. Edwards, T. P. Hart, and M. I. Levin. 1965. *Lisp 1.5 Programmer's Manual*. 2nd edition. Cambridge, MA: MIT Press. →

McDermott, Drew, and Gerald Jay Sussman. 1972. Conniver reference manual. Memo 259, MIT Artificial Intelligence Laboratory. →

Miller, Gary L. 1976. Riemann's Hypothesis and tests for primality. *Journal of Computer and System Sciences* 13(3): 300-317. →

Miller, James S., and Guillermo J. Rozas. 1994. Garbage collection is fast, but a stack is faster. Memo 1462, MIT Artificial Intelligence Laboratory. →

Moon, David. 1978. MacLisp reference manual, Version 0. Technical report, MIT Laboratory for Computer Science. →

Moon, David, and Daniel Weinreb. 1981. Lisp machine manual. Technical report, MIT Artificial Intelligence Laboratory. →

Morris, J. H., Eric Schmidt, and Philip Wadler. 1980. Experience with an applicative string processing language. In *Proceedings of the 7th Annual ACM SIGACT/SIGPLAN Symposium on the Principles of Programming Languages*.

Phillips, Hubert. 1934. *The Sphinx Problem Book*. London: Faber and Faber.

Pitman, Kent. 1983. The revised MacLisp Manual (Saturday evening

edition). Technical report 295, MIT Laboratory for Computer Science. →

Rabin, Michael O. 1980. Probabilistic algorithm for testing primality. *Journal of Number Theory* 12: 128-138.

Raymond, Eric. 1993. *The New Hacker's Dictionary*. 2nd edition. Cambridge, MA: MIT Press. →

Raynal, Michel. 1986. *Algorithms for Mutual Exclusion*. Cambridge, MA: MIT Press.

Rees, Jonathan A., and Norman I. Adams IV. 1982. T: A dialect of Lisp or, lambda: The ultimate software tool. In *Conference Record of the 1982 ACM Symposium on Lisp and Functional Programming*, pp. 114-122. →

Rees, Jonathan, and William Clinger (eds). 1991. The revised^4 report on the algorithmic language Scheme. *Lisp Pointers*, 4(3). →

Rivest, Ronald, Adi Shamir, and Leonard Adleman. 1977. A method for obtaining digital signatures and public-key cryptosystems. Technical memo LCS/TM82, MIT Laboratory for Computer Science. →

Robinson, J. A. 1965. A machine-oriented logic based on the resolution principle. *Journal of the ACM* 12(1): 23.

Robinson, J. A. 1983. Logic programming—Past, present, and future. *New Generation Computing* 1: 107-124.

Spafford, Eugene H. 1989. The Internet Worm: Crisis and aftermath. *Communications of the ACM* 32(6): 678-688. →

Steele, Guy Lewis, Jr. 1977. Debunking the "expensive procedure call" myth. In *Proceedings of the National Conference of the ACM*, pp. 153-62. →

Steele, Guy Lewis, Jr. 1982. An overview of Common Lisp. In *Proceedings of the ACM Symposium on Lisp and Functional Programming*, pp. 98-107.

Steele, Guy Lewis, Jr. 1990. *Common Lisp: The Language*. 2nd edition. Digital Press. →

Steele, Guy Lewis, Jr., and Gerald Jay Sussman. 1975. Scheme: An interpreter for the extended lambda calculus. Memo 349, MIT Artificial Intelligence Laboratory. →

Steele, Guy Lewis, Jr., Donald R. Woods, Raphael A. Finkel, Mark R. Crispin, Richard M. Stallman, and Geoffrey S. Goodfellow. 1983. *The Hacker's Dictionary*. New York: Harper & Row. →

Stoy, Joseph E. 1977. *Denotational Semantics*. Cambridge, MA: MIT Press.

Sussman, Gerald Jay, and Richard M. Stallman. 1975. Heuristic techniques in computer-aided circuit analysis. *IEEE Transactions on Circuits and Systems* CAS-22(11): 857-865. →

Sussman, Gerald Jay, and Guy Lewis Steele Jr. 1980. Constraints—A language for expressing almost-hierachical descriptions. *AI Journal* 14: 1-39. →

Sussman, Gerald Jay, and Jack Wisdom. 1992. Chaotic evolution of the solar system. *Science* 257: 256-262. →

Sussman, Gerald Jay, Terry Winograd, and Eugene Charniak. 1971. Microplanner reference manual. Memo 203A, MIT Artificial Intelligence Laboratory. →

Sutherland, Ivan E. 1963. SKETCHPAD: A man-machine graphical communication system. Technical report 296, MIT Lincoln Laboratory. →

Teitelman, Warren. 1974. Interlisp reference manual. Technical report, Xerox Palo Alto Research Center. →

Thatcher, James W., Eric G. Wagner, and Jesse B. Wright. 1978. Data

type specification: Parameterization and the power of specification techniques. In *Conference Record of the Tenth Annual ACM Symposium on Theory of Computing*, pp. 119-132.

Turner, David. 1981. The future of applicative languages. In *Proceedings of the 3rd European Conference on Informatics*, Lecture Notes in Computer Science, volume 123. New York: Springer-Verlag, pp. 334-348.

Wand, Mitchell. 1980. Continuation-based program transformation strategies. *Journal of the ACM* 27(1): 164-180. →

Waters, Richard C. 1979. A method for analyzing loop programs. *IEEE Transactions on Software Engineering* 5(3): 237-247.

Winograd, Terry. 1971. Procedures as a representation for data in a computer program for understanding natural language. Technical report AI TR-17, MIT Artificial Intelligence Laboratory. →

Winston, Patrick. 1992. *Artificial Intelligence*. 3rd edition. Reading, MA: Addison-Wesley.

Zabih, Ramin, David McAllester, and David Chapman. 1987. Nondeterministic Lisp with dependency-directed backtracking. *AAAI-87*, pp. 59-64. →

Zippel, Richard. 1979. Probabilistic algorithms for sparse polynomials. Ph.D. dissertation, Department of Electrical Engineering and Computer Science, MIT.

Zippel, Richard. 1993. *Effective Polynomial Computation*. Boston, MA: Kluwer Academic Publishers.

List of Exercises 練習 ê 列單

Chapter 1

1.1 1.2 1.3 1.4 1.5 1.6 1.7 1.8 1.9 1.10
1.11 1.12 1.13 1.14 1.15 1.16 1.17 1.18 1.19 1.20
1.21 1.22 1.23 1.24 1.25 1.26 1.27 1.28 1.29 1.30
1.31 1.32 1.33 1.34 1.35 1.36 1.37 1.38 1.39 1.40
1.41 1.42 1.43 1.44 1.45 1.46

Chapter 2

2.1 2.2 2.3 2.4 2.5 2.6 2.7 2.8 2.9 2.10
2.11 2.12 2.13 2.14 2.15 2.16 2.17 2.18 2.19 2.20
2.21 2.22 2.23 2.24 2.25 2.26 2.27 2.28 2.29 2.30
2.31 2.32 2.33 2.34 2.35 2.36 2.37 2.38 2.39 2.40
2.41 2.42 2.43 2.44 2.45 2.46 2.47 2.48 2.49 2.50
2.51 2.52 2.53 2.54 2.55 2.56 2.57 2.58 2.59 2.60
2.61 2.62 2.63 2.64 2.65 2.66 2.67 2.68 2.69 2.70
2.71 2.72 2.73 2.74 2.75 2.76 2.77 2.78 2.79 2.80
2.81 2.82 2.83 2.84 2.85 2.86 2.87 2.88 2.89 2.90
2.91 2.92 2.93 2.94 2.95 2.96 2.97

Chapter 3

3.1	3.2	3.3	3.4	3.5	3.6	3.7	3.8	3.9	3.10
3.11	3.12	3.13	3.14	3.15	3.16	3.17	3.18	3.19	3.20
3.21	3.22	3.23	3.24	3.25	3.26	3.27	3.28	3.29	3.30
3.31	3.32	3.33	3.34	3.35	3.36	3.37	3.38	3.39	3.40
3.41	3.42	3.43	3.44	3.45	3.46	3.47	3.48	3.49	3.50
3.51	3.52	3.53	3.54	3.55	3.56	3.57	3.58	3.59	3.60
3.61	3.62	3.63	3.64	3.65	3.66	3.67	3.68	3.69	3.70
3.71	3.72	3.73	3.74	3.75	3.76	3.77	3.78	3.79	3.80
3.81	3.82								

Chapter 4

4.1	4.2	4.3	4.4	4.5	4.6	4.7	4.8	4.9	4.10
4.11	4.12	4.13	4.14	4.15	4.16	4.17	4.18	4.19	4.20
4.21	4.22	4.23	4.24	4.25	4.26	4.27	4.28	4.29	4.30
4.31	4.32	4.33	4.34	4.35	4.36	4.37	4.38	4.39	4.40
4.41	4.42	4.43	4.44	4.45	4.46	4.47	4.48	4.49	4.50
4.51	4.52	4.53	4.54	4.55	4.56	4.57	4.58	4.59	4.60
4.61	4.62	4.63	4.64	4.65	4.66	4.67	4.68	4.69	4.70
4.71	4.72	4.73	4.74	4.75	4.76	4.77	4.78	4.79	

Chapter 5

5.1 5.2 5.3 5.4 5.5 5.6 5.7 5.8 5.9 5.10
5.11 5.12 5.13 5.14 5.15 5.16 5.17 5.18 5.19 5.20
5.21 5.22 5.23 5.24 5.25 5.26 5.27 5.28 5.29 5.30
5.31 5.32 5.33 5.34 5.35 5.36 5.37 5.38 5.39 5.40
5.41 5.42 5.43 5.44 5.45 5.46 5.47 5.48 5.49 5.50
5.51 5.52

List of Figures 圖片 ê 列單

Chapter 1

1.1 1.2 1.3 1.4 1.5

Chapter 2

2.1 2.2 2.3 2.4 2.5 2.6 2.7 2.8 2.9 2.10
2.11 2.12 2.13 2.14 2.15 2.16 2.17 2.18 2.19 2.20
2.21 2.22 2.23 2.24 2.25 2.26

Chapter 3

3.1 3.2 3.3 3.4 3.5 3.6 3.7 3.8 3.9 3.10
3.11 3.12 3.13 3.14 3.15 3.16 3.17 3.18 3.19 3.20
3.21 3.22 3.23 3.24 3.25 3.26 3.27 3.28 3.29 3.30
3.31 3.32 3.33 3.34 3.35 3.36 3.37 3.38

Chapter 4

4.1 4.2 4.3 4.4 4.5 4.6

Chapter 5

5.1 5.2 5.3 5.4 5.5 5.6 5.7 5.8 5.9 5.10
5.11 5.12 5.13 5.14 5.15 5.16 5.17 5.18

Index

Any inaccuracies in this index may be explained by the fact that it has been prepared with the help of a computer.

佇 chit 篇索引，任何無正確 ê 所在，會當解說是因為伊受電腦協助。

—Donald E. Knuth, *Fundamental Algorithms*
(Volume 1 of *The Art of Computer Programming*)

Symbols

k-term finite continued fraction 138
n-fold smoothed function 152
1873 年 ê 經濟懍 neh 252

A

abstract models 178
abstract syntax 573
abstraction barriers 160, 172
accumulator 226, 387
acquired 502
action 751
additive 328
additively 162, 316
address 796
address arithmetic 796
agenda 461
algebraic specification 178
aliasing 400
and-gate 452
AND 門 274
applicative-order 619
applicative-order evaluation 31
arbiter 505
arguments 12
assembler 771
assertions 675
assignment operator 381
atomically 504
automatic storage allocation 796

average damping 136

B

B-trees 299
backbone 443
backquote 850
backtracks 641
balanced 219
barrier synchronization 507
base address 797
Bertrand's hypothesis 527
bignum 799
bindings 404
binds 53
binomial coefficients 77
block structure 55
bound variable 52
box-and-pointer notation 192
breakpoint 794
broken heart 807
bugs 3

C

cache-coherence 487
call-by-name 519, 623
call-by-name thunks 519
call-by-need 519, 623
call-by-need thunks 519
capturing 53
Carmichael numbers 100
Carmichael 數 100
case analysis 33
cell 503
chhoàh 體 11
chronological backtracking 641
Church numerals 183
Church-Turing thesis 601
Church 數 183
clauses 33
closed world assumption 707
closure 161
closure property 193
code generator 844
coerce 355
coercion 348
combinations 12
comments 242
compacting 806
compilation 840
compile-time environment 889
composition 150
compound data 156
compound data object 157
compound procedure 23
computability 601
computational process 2
concurrently 483
congruent modulo 97
connectors 468
consequent expression 34
constraint networks 468
constructors 164
continuation procedures 655
continued fraction 137
control structure 703
controller 742
conventional interfaces 161, 223
current time 465

D

data 2, 177
data abstraction 158, 163

data paths 742
data-directed 316
data-directed programming 162, 328
deadlock 506
deadlock-recovery 506
debug 3
deep binding 595
deferred operations 63
delayed argument 551
delayed evaluation 380, 510
delayed object 514
dense 365
dependency-directed backtracking . . 641
depth-first search 641
deque 442
derived expressions 585
digital signals 452
dispatching on type 327
displacement number 888
dotted-tail notation 205
driver loop 598

E

empty list 199
encapsulated 384
enclosing environment 404
entry points 746
enumerator 226
environment 17
environment model 379
environments 404
Euclid ê 演算法 91
Euclid's Algorithm 91
Euclidean ring 372
evaluating 11
evaluator 568
event-driven simulation 451
evlis tail recursion 820
execution procedure 613
explicit-control evaluator 813
expression 11

F

failure continuation 655
FIFO 436
filter 119, 226
first-class 148
fixed point 133
fixed-length 304
forcing 622
forwarding address 807
frame 691
frame coordinate map 262
frame number 888
framed-stack 818
frames 404
free 53
free list 801
front 436
full-adder 454
function boxes 452
functional programming 395
functional programming languages . . 563

G

garbage 804
garbage collection 796, 805
garbage collector 425
garbage-collected 627
generic operations 162
generic procedures 309, 316
glitches 3

global 58, 404
global environment 17
golden ratio 70
grammar 648

H

half-adder 453
half-interval method 129
Halting Theorem 604
headed list 444
hiding principle 384
hierarchical 193
hierarchy of types 351
higher-order procedures 110
Horner's rule 233
Horner 法則 233

I

imperative programming 401
indeterminates 359
index 797
indexing 693
instantiated with 680
instruction counting 793
instruction execution procedure 774
instruction sequence 846
instruction tracing 793
instructions 741, 746
integerizing factor 374
integers 10
integrator 545
interning 799
interpreter 4, 568
invariant quantity 86
inverter 452
iterative improvement 153
iterative process 64

K

key 302
k 項有限連分數 138

L

labels 746
lazy evaluation 619
lexical address 888
lexical addressing 595
lexical scoping 56
linear iterative process 64
linear recursive process 63
linkage descriptor 845
list 196, 205
list structure 197
list-structured 168
list-structured memory 795
local evolution 58
local state variables 380
location 796
logic-programming 570
logical and 452
logical deductions 687
logical or 452

M

machine language 839
macro 585
map 226
mark-sweep 806
Memoization 450
memoization 76
memoize 623
merge 563

message passing 181, 338
message-passing 386
metacircular 571
Metalinguistic abstraction 568
Miller-Rabin test 107
Miller-Rabin ê 測試 108
modular 378
module 化 157
modulo 97
modus ponens 702
moments in time 483
Monte Carlo integration 393
Monte Carlo simulation 390
mutable data objects 424
mutators 424
mutex 502
mutual exclusion 502

N

native language 839
needed 848
networks 567
Newton ê 方法 143
Newton's method 143
nil 199
non-computable 604
non-strict 620
nondeterministic 490
nondeterministic choice point 640
nondeterministic computing . . . 570, 636
normal-order 619
normal-order evaluation 31, 570

O

obarray 799
object program 840
objects 379
open-code 885
operands 12
operator 12, 611
or-gate 452
order of growth 78
ordinary 341
OR 門 274
output prompt 598

P

package 330
painter 249
pair 167, 168
parse 648
Pascal's triangle 77
Pascal 三角形 77
pattern 678
pattern matcher 691
pattern matching 691
pattern variable 678
phú 色層 267
pipelining 484
pointer 192
poly 360
power series 530
predicate 33, 34
prefix 305
prefix code 305
prefix notation 12
pretty-printing 14
primitive constraints 468
probabilistic algorithms 101
procedural abstraction 50
procedural epistemology xxvi
procedure 65

procedure definitions 23
procedures 7
process 65
program 2
programming languages 2
prompt 598
pseudo-random 390
pseudodivision 374
pseudoremainder 374

Q

quasiquote 850
queries 674
query language 674
queue 436
quote 277

R

Ramanujan numbers 544
rational functions 371
RC circuit 545
read-eval-print loop 14
reader macro characters 732
real numbers 10
rear 436
recursion equations 4
Recursion theory 602
recursive 18, 48
recursive process 63
red-black trees 299
referentially transparent 399
register machine 741
register table 773
registers 741
released 502
remainder of 97
resolution principle 671
ripple-carry adder 457
robust 274
RSA algorithm 102
RSA 演算法 102
rules 674, 683

S

satisfy 680
scope 53
selectors 164
semaphore 502
separator code 305
sequence 195
sequence accelerator 535
sequences 117
serializer 492
serializers 493
series RLC circuit 554
shadow 405
shared 430
side-effect bugs 400
sieve of Eratosthenes 522
smoothing 151
source language 840
source program 840
sparse 365
special forms 21
stack 64, 65, 762
state variables 64, 380
statements 848
stop-and-copy 805
stratified design 273
stream processing 32
streams 379, 509, 510
strict 620

subroutine 757
substitution 29
substitution model 28
subtype 351
success continuation 655
summation of a series 112
summer 545
supertype 352
symbolic expressions 161
syntactic sugar 21
syntax 572
systematically search 641
systems 567
súi 氣輸出 14

T

tableau 536
tabulation 76, 450
tagged architectures 798
tail-recursive 66, 825
target 845
thrashing x
thunk 622
thunks 622
time 483
time segments 464
tower 352
tree accumulation 19
tree recursion 68
trees 213
truth maintenance 641
Turing machine 601
type field 798
type tag 323
type tags 316
type-inferencing 557
typed pointers 798

U

unbound 404
unification 671, 691, 697
unification algorithm 671
univariate polynomials 359
universal machine 600
upward-compatible extension 631

V

value 15
value of a variable 404
values 277
variable 15
variable-length 304
vector 797

W

width 187
wires 452
wishful thinking 165

Z

zero crossings 546

λ 運算 123

三元組 240
不動點 133
不變量 87
並列 184
串 278
二元平衡裝飾 218

二項係數 78
代數規範 179
作用範圍 53

倒數 121
值 15, 277
全域 ê 59
全域環境 17
分層設計 273
切斷誤差 10
列 118, 196
列—行位置 247
列單 197, 205
列單結構 168, 197
列舉器 226
前置表示法 13
助程序 121
包裹 163
區域展開 59
區間運算 185
半區間法 130
印刷器 269
原油線 252
原點向量 261
反覆改善 153
反覆過程 64
取代模型 28
句 278
合成 150
向望 ê 觀察 165
向量 236
基礎要件 273
塊結構 56
子句 33
實數 10

封閉 ê 194
專門形式 22
對 167, 168
導函數 143
尾 liu 有點 ê 表示法 205
尾遞迴 66
幅度 187
平均減衰 136
平滑化 152
延遲運算 63
建構器 164
引數 12
引用 277
弧度 134

慣例介面 161, 223
應用序算值 31
成長率 79
所倚靠 ê 232
抽象化障礙 161, 173
抽象模型 179
括弧 12
指標 192
捨入誤差 10
掠 54
接近使用 174
揀選器 164
整數 10
暗碼學 102
有 kâng 款 ê 餘數 97
束縛 53
束縛變數 53
枋模 112, 234
框殼座標地圖 262
案例分析 33

模範 232
樹 á 213
樹累積 19
樹遞迴 68
機率演算法 102
正規序算值 31
流處理 32

狀態變數 64
環境 17
畫圖器 251
盒仔—指標表示法 192
直譯器 5
相連 sòa ê 230
矩陣 79
確定地址 167
程序 8, 65
程序定義 23
程序抽象化 50
程式 2
程式語言 3
空 ê 列單 199
符號 276
符號表達式 162
第 *n* 改平滑化 ê 函數 152
等價 191
算值 11
粗勇 275
純量 264
級數和 112
累積器 226
終端機 11
組合 12
結果表達式 34
線性反覆過程 64
線性遞迴過程 63

自由 ê 53
表化 76
表明 179
表達式 11
複合程序 24
複合資料 156
複合資料物件 158
計算過程 2
訊號流圖 225
記持化 76
註 kha 242
詞法使用範圍 56
語法糖 22
謂詞 34
讀算印 loop 15
變換器 226
變數 15
資料 2, 178
資料引 chhōa 程式設計 162
資料抽象化 158, 163
起造模型 181

通用操作 162
通用目的 168
連分數 137
運算子 12
運算數 12
過濾器 120, 226
過程 65
遞減 167
遞迴 18, 48
遞迴方程式 4

邊向量 261
閉包 161
閉包性 194
附加 163
陣列 195
除去錯誤 4
階層 194
電阻器 184
項 278
順序對 239
頭等 148
餘數 97
高階程序 110
麻芳 chhoâh 268
黃金比例 70

教會白話字 kap 教育部台羅拼音 ê 比較

Chit 本 chheh 是 kā 聖經巴克禮譯本使用 ê 教會白話字 (Pe̍h-ōe-jī; POJ) 規範，當做書寫 ê 羅馬字 (Romanization) 原則，伊是 chit-má koh teh 用 ê 歷史上久長 ê 臺語羅馬字系統。因為教育部訂 ê 台羅拼音 (Tâi-lô; TL) 標準有參考 che，所以有真 chē 相 siâng ê 所在。但是為著予對教育部拼音較熟 ê 讀者較快讀，下 kha 列出 2 款羅馬字 ê 差別：

1. 白話字 ê「ch」就是台羅 ê「ts」;「chh」就是「tsh」。比論：chū-iû^{POJ} = tsū-iû^{TL}、chhia^{POJ} = tshia^{TL}。

2. 白話字 ê「o͘」就是台羅 ê「oo」，其中「o͘」ê 調號標佇台羅頭一个「o」。比論：o͘ ^{POJ} = oo^{TL}、hō ^{POJ} = hōo^{TL}

3. 白話字 ê 鼻化母音標記「ⁿ」，就是台羅 ê「nn」。比論：saⁿ ^{POJ} = sann^{TL}、kiàⁿ ^{POJ} = kiànn^{TL}。毋 koh 白話字 ê「hⁿ」，寫做台羅「nnh」。比論：hiahⁿ ^{POJ} = hiannh^{TL}。

4. 白話字 ê「oa」就是台羅 ê「ua」。Kap 台羅 kā 調號 lóng 寫佇「a」面頂無 kâng，白話字 ê「oa」，kā 調號寫佇「o」面頂，除非後壁 koh 有字母，chiah 寫佇「a」面頂。比論：góa^{POJ} = guá^{TL}、joa̍h^{POJ} = jua̍h^{TL}、hoâiⁿ ^{POJ} = huâinn^{TL}、koân^{POJ} = kuân^{TL}。

5. 白話字 ê「oe」就是台羅 ê「ue」。比論：koe^{POJ} = kue^{TL}、goe̍h^{POJ} = gue̍h^{TL}。

6. 白話字 ê「ui」，Kap 台羅 kā 調號 lóng 寫佇「i」面頂無 kâng，白話字 ê「ui」，kā 調號 lóng 寫佇「u」面頂。比論：súi^{POJ} = suí^{TL}。

7. 雖 bóng 聖經巴克禮譯本無記載第九調（高升調，用佇疊字、外來語等特殊 ê 詞），但是使用白話字 ê，有 lâng 使用撇音符號 (diacritic) ê “breve” (◌̆)，soah 無用教育部台羅 ê “double acute” (◌̋) 代表第九調。本冊用 breve 標示。比如：hŏng^{POJ}（「予 lâng」ê 合音）= hőng^{TL}。

Colophon 版權頁

On the cover page is Agostino Ramelli's bookwheel mechanism from 1588. It could be seen as an early hypertext navigation aid. This image of the engraving is hosted by J. E. Johnson of New Gottland.

The typefaces are Linux Libertine for body text and Linux Biolinum for headings, both by Philipp H. Poll. Typewriter face is Inconsolata created by Raph Levien and supplemented by Dimosthenis Kaponis and Takashi Tanigawa in the form of Inconsolata LGC. The cover page typeface is Alegreya, designed by Juan Pablo del Peral.

Graphic design and typography are done by Andres Raba. Texinfo source is converted to LaTeX by a Perl script and compiled to PDF by XeLaTeX. Diagrams are drawn with Inkscape.

佇封面是 Agostino Ramelli 佇 1588 年畫 ê 冊 lián-á。伊會當掠做是較早 ê 超文字 (hypertext) 導覽 ê 協助。Chit pak 版畫由 J. E. Johnson（New Gottland）收藏。

臺文版 ê 內文羅馬字(包含英語)ê 字型是 FreeSans、FreeSerif、FreeMono，是 GNU FreeFont 計畫（設計師：Primož Peterlin kap Steve White）所出。封面 ê 字型是 Noto Sans CJK TC，內文 ê 漢字字型，是 Noto Sans CJK TC kap Noto Serif CJK TC，是 Adobe kap Google 所推出。

圖形設計 kap 排版由 Andres Raba 完成。Texinfo ê 原始碼是由 Perl ê script 轉做 LaTeX，koh 用 XeLaTeX 編譯做 PDF。圖表用 Inkscape 畫。